



AFTER THE COMPLETION OF THE FINAL FLUSHING THE CONTRACTOR SHALL REMOVE THE TEMPORARY FLUSHING CONNECTION AND INSTALL A CAP WITH MEGALUGS AND A THRUST BLOCK