

**CLEAN WATER INFRASTRUCTURE
REPLACEMENT PLAN UPDATE
for the
KENT COUNTY WATER AUTHORITY**

DECEMBER 13, 2019



Table of Contents

Section 1
Inventory

Section 2
Infrastructure Adequacy

Section 3
Infrastructure Adequacy (Water Main Details)

Section 4
Cost Summary

Section 5
Financial Adequacy



System Information	
System Name	Kent County Water Authority
PWSID	RI1559511
System Type	CWS
Contact Name	David L. Simmons
Contact Phone	401-821-9300
Contact E-mail	dsimmons@kentcountywater.org
Fiscal Year Used	July 1- June 30
Current System Information	
Retail Population	88,779
Consecutive Population	Wholesale to Warwck
Consecutive Population	Retail Sale to Center of New England
Consecutive Population	Retail Sale to Coventry School
Total Population	
# of Service Connections	27,230
Type of Source Water	Blended: Purchased SW and Produced GW
Purchaser or Wholesaler	Both
Annual Usage (Million Gallons)	2,303 million gallons

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Source	Well	Mishnock Well #3, Gravel Packed Well 67.5', Developed March 2000, Cleaned in 2013, 18" Steel Cased 10' SS Screen	1	20	Excellent	40-50	Yes	Yes	Yes	\$10,000	Clean and Redevelopment	(Water Treatment Plant Online Dec 2013) Recuring
Source	Well	Mishnock Well #4, Gravel Packed Well 72', Developed 2001, Cleaned in 2013, 18" Steel Cased 10' SS Screen	1	19	Excellent	40-50	Yes	Yes	Yes	\$10,000	Clean and Redevelopment	(Water Treatment Plant Online Dec 2013) Recuring
Source	Well	Mishnock Well #5, Gravel Packed Well 85', Developed 2001, Cleaned in 2013, 18" Steel Cased 10' SS Screen	1	19	Excellent	40-50	Yes	Yes	Yes	\$10,000	Clean and Redevelopment	(Water Treatment Plant Online Dec 2013) Recuring
Treatment	Treatment Building	Mishnock Treatment Facility	1	6	Excellent	40-50	Yes	Yes	Yes	\$30,000	Inspect tank coating and recost as needed, Overhaul aeration blowers and chemical pumps	Water Treatment Plant Online Dec 2013
Treatment	Treatment Building	Mishnock Treatment Facility	5	6	Excellent	4	Yes	Yes	Yes	\$1,000,000	Remove Replace membranes	Water Treatment Plant Online Dec 2013
Treatment	Generator	Mishnock Treatment Facility 600 kW GenSet with ATS	1	6	Excellent	30-35	No	No	Yes	\$0	0	Water Treatment Plant Online Dec 2013

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Treatment	Finished Water Pumps	Low Lift Pumps. 50 HP Multistate Turbines.	2	6	Good	15-20	Yes	Yes	Yes	\$7,000	Remove Inspect Rebuild 1 Pump and Motor	(Water Treatment Plant Online Dec 2013. Replace motor & pump.) Recurring
Treatment	Finished Water Pumps	High Lift Pumps. 100 HP Multistate Turbines.	3	6	Good	15-20	Yes	Yes	Yes	\$7,000	Remove Inspect Rebuild 1 Pump and Motor	(Water Treatment Plant Online Dec 2013. Replace Motor & Pump.) Recurring
Source	Well	Ground Water, Gravel-Packed, Well Spring Lake, Offline	1	59	Poor (offline)	>10 with repairs	Yes	Yes	No	\$2,000,000	Budgeted \$50,000 for Cleaning and Inspection. Requires replacement of well building wit treatment and/or transmission main to mishnock plant	Facility Replacement within 5yr and Complete well Redevelopment in.
Source	Well Pump	Mishnock Well Pump # 3, 25 HP Submersible Vertical Turbine Pump	1	6	Good	10-15	Yes	Yes	Yes	\$15,000	Remove pump Inspect and overhaul Clean and redevelop well	(Water Treatment Plant Online Dec 2013.) As Part of Well Redevelopment Recurring
Source	Well Pump	Mishnock Well Pump # 4, 30 HP Submersible Vertical Turbine Pump	1	6	Good	10-15	Yes	Yes	Yes	\$15,000	Remove pump Inspect and overhaul Clean and redevelop well	(Water Treatment Plant Online Dec 2013.) As Part of Well Redevelopment Recurring
Source	Well Pump	Mishnock Well Pump #5, 20 HP Submersible Vertical Turbine Pump	1	6	Good	10-15	Yes	Yes	Yes	\$15,000	Remove pump Inspect and overhaul Clean and redevelop well	(Water Treatment Plant Online Dec 2013) Recurring

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Source	Well	Ground Water, Gravel-Packed Well, East Greenwich	1	55	Excellent	10-15	no	No	Yes	\$0	\$0	Redeveloped 2017
Treatment	Treatment Building	East Greenwich Well Treatment Facility	1	2	Excellent	40-50	No	Yes	No	\$6,000,000	CIP or IFR Construction Contract for Pressure Filter & Finished Water Tank 4 Log Removal	Construction new wellfield facility 2017. May fit IFR requirements for compliance with SDWA or becomes CIP Addition to Include Pressure Filter & Finished Water
Treatment	Generator	East Greenwich Well Treatment Facility 250 kW LG	1	1	Excellent	30-35	No	No	Yes	\$0	0	Construction new wellfield facility 2017.
Transmission_Distribution	Transmission Pump Station	Clinton Ave. Pump Station	1	14	Excellent	35-40	No	No	Yes	\$0	0	Rehabilitated in 2006
Transmission_Distribution	Booster Pumps	3,800 gpm Vertical Turbine Pumps at Clinton Ave. Pump Station	5	14	Good	10-15	Yes	Yes	Yes	\$10,000	Overhaul 1 Pump & Motor per year over 5 yr period	New 2006
Transmission_Distribution	Booster Pumps	2,100 gpm Vertical Turbine Pumps at Clinton Ave. Pump Station	2	14	Good	10-15	Yes	Yes	Yes	\$10,000	Overhaul 1 pump per year over 5 yr period	New in 2006

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Transmission_Distribution	Water Meters	12 inch Master Meter at Oaklawn Ave for Interconnection with Providence Water Supply Board, Underground Station.	1	15	Functional	30	Yes	No	Yes	\$0	0	Rehabilitated in 2004
Transmission_Distribution	Transmission Pump Station	Bald Hill Road Pump Station	1	5	Excellent	35-40	No	yes	Yes	\$2,000,000	Complete installation of high service 500 foot gradient pumps and transmission main	Rehabilitated 2014 low service pumping
Storage	Reservoir	3,000,000 Gallon Setian Lane Steel Tank, No Cathodic Protection	1	50	Good	20	Yes	Yes	Yes	\$400,000	Blast and Coat Exterior	Rehabilitate Coating System Fails.
Storage	Reservoir	Frenchtown Tank. 1,500,000 Gallon Concrete Tank, No Cathodic Protection	1	42	Good	20-50	Yes	No	Yes	\$25,000	0	Costs for Cleaning and Inspecting (20yr). Blast The Outer Surfaces When Coating System Fails
Storage	Reservoir	Wakefield Street Tank. 2,000,000 Gallon Concrete Reservoir. No Cathodic Protection. OUT OF SERVICE.	1	29	N/A	0	Yes	Yes	No	\$25,000	Hydraulic Model Study Evaluate Tank unable to cycle due to pump head influence	Out Of Service. \$100,000 to Demolish
Storage	Standpipe	West Street Tank. 1,000,000 Gallon Steel Standpipe. No Cathodic Protection. OUT OF SERVICE.	Enter Number of Components Included in The Infrastructure if More Than 1	63	N/A	0	Yes	Yes	No	\$100,000	Demolition Contract unable to cycle due to pump head influence	Out Of Service. \$100,000 to Demolish

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Storage	Standpipe	Read School House Road Tank. 1,500,000 Gallon Concrete Tank. No Cathodic Protection	1	10	Good	50+	No	Yes	Yes	\$0	\$5,000 for Cleaning and Inspection	Constructed at 500ft elevation in 2009. Recoat Exterior As Coating System Fails.
Storage	Elevated Water Storage	Technology Park Elevated Tank. 1,500,000 Spheroid Steel Tank With Cathodic Protection	1	31	Very good	50+	Yes	No	Yes	\$1,000,000	\$5,000 for Cleaning and Inspection	Costs for Complete Recoating, Cleaning, and Inspection. \$1 million Expense for Complete Rehabilitation At The End of Coating System Life Cycle.
Storage	Reservoir	Carr Pond Road Tank. 3,000,000 Gallon Concrete Reservoir. No Cathodic Protection	1	18	Very good	50+	Yes	No	Yes	\$0	Unable to cycle per RIDOH requirements due to reduced demand and hydraulic influences	Recoat Exterior When Coating System Fails. Offline
Transmission_Distribution	Booster Pump Station Building	Knotty Oak Rd.	1	19	Poor Offline	10	No	No	No	\$100,000	No longer serviceable. Infrastructure shifted to 500 foot gradient making this pum station obsolete	Demolish Building
Transmission_Distribution	Booster Pumps	1,200 gpm pump at Johnson Blvd. pumping station	1	28	Good	10	Yes	No	Yes	\$50,000	Obsolete	Removed From Service since Mishnock Treatment Plant High Service Capacity is Online
Transmission_Distribution	Booster Pump Station	West Warwick Industrial Park	1	15	Excellent	20+	Yes	Yes	Yes	\$10,000	Overhaul 1 Pump & Motor	Structure Consists Of A Prefabricated Buried Steel Vault With Ladder Access.

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Transmission_Distribution	Booster Pump Station	Seitan Lane Booster Pump Station	1	15	Excellent	10	Yes	Yes	Yes	\$5,000	Overhaul 1 Pump & Motor	Structure Consists Of A Prefabricated Buried Steel Vault With Ladder Access.
Transmission_Distribution	Pressure reducing station	Middle Road	1	21	Good	10	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ Years With Proper Maintenance. A Mechanical/Electric Upgrade is Recommended at 16-20 Years at A Cost Of \$75,000.
Transmission_Distribution	Pressure reducing station	Cowesett Road	1	21	Good	10	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ Years With Proper Maintenance. A Mechanical/Electric Upgrade is Recommended at 20-25 Years at A Cost Of \$75,000.
Transmission_Distribution	Pressure reducing station	Love Lane	1	21	Good	10	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ Years With Proper Maintenance. A Mechanical/Electric Upgrade is Recommended at 20-25 Years at A Cost Of \$75,000.
Transmission_Distribution	Pressure reducing station	Post Road	1	21	Good	10	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ Years With Proper Maintenance. A Mechanical/Electric Upgrade is Recommended at 20-25 Years at A Cost Of \$75,000.
Transmission_Distribution	Pressure reducing station	Centerville Road	1	21	Good	10	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ Years With Proper Maintenance. A Mechanical/Electric Upgrade is Recommended at 20-25 Years at A Cost Of \$75,000.

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Transmission_Distribution	Pressure reducing station	Division Road	1	21	Excellent	20	Yes	No	Yes	\$75,000	0	Installed in 1999. 20+ Years With Proper Maintenance. A Mechanical/Electric Upgrade is Recommended at 16-20 Years at A Cost Of \$75,000.
Transmission_Distribution	Pressure reducing station	Helen Street	1	28	Poor	5	Yes	Yes	Yes	\$300,000	This Facility Should Be Replaced With A Modern, Buried Capsule-Type Valve Vault With Confined Space Entry Provisions At The Estimated Cost Of \$300,000.	Requires relocation of station and infrastructure. Relocate to Johnsons BLV site or may require aquisition of property if this location is not usable
Transmission_Distribution	Pressure reducing station	Mishnock Road	1	28	Poor	5	Yes	Yes	Yes	\$300,000	This Facility Should Be Replaced With A Modern, Buried Capsule-Type Valve Vault With Confined Space Entry Provisions At The Estimated Cost Of \$300,000.	Can be replaced on current property under control of KCWA
Transmission_Distribution	Pressure reducing station	Tiogoe Avenue	1	10	Excellent	15	Yes	Yes	Yes	\$0	This Facility Should Be Replaced With A Modern, Buried Capsule-Type Valve Vault With Confined Space Entry Provisions At The Estimated Cost Of \$300,000.	Installed in 2009. 20+ Years With Proper Maintenance. A Mechanical/Electric Upgrade is Recommended at 20-25 Years at A Cost Of \$75,000.
Transmission_Distribution	Generator	Quaker Lane 600 kW GenSet with ATS	1	5	Excellent	30-35	No	No	Yes	\$0	0	40+ Years With Proper Maintenance. No upgrades needed.
Transmission_Distribution	Generator	Setien Lane Booster Pump Station 725 kW Generator	1	15	Excellent	30-35	No	No	Yes	\$0	0	40+ Years With Proper Maintenance. No upgrades needed.

Infrastructure Type	Infrastructure Subtype	Brief Infrastructure Description	Number of Infrastructure Subtype	Age (in years)	Condition (poor, fair, good, excellent; or rating scale)	Remaining Useful Life (in years)	Need for Rehabilitation or Replacement (20-year timeframe) (Yes/No)	Evaluation/Prioritization for Rehabilitation or Replacement (5-year intervals) (Yes/No)	Infrastructure Supports SDWA Compliance (Yes/No)	Financial Forecast (in dollars)	O&M Notes	Other Notes
Transmission_Distribution	Generator	Clinton Ave. Pump Station 725 kW Generator	1	13	Excellent	30-35	No	No	Yes	\$0	0	40+ Years With Proper Maintenance. No upgrades needed.
Other	Office Building	Main Street Administrative and Maintenance Building	1	100 years	Poor-Fair	Reached end of useful life	Yes	Yes	Yes	\$8,000,000	Purchase property and construct new facilities	Complete Replacement Using IFR and CIP Funds At A Cost Of \$8,000,000.
Other	Other (describe)	Hydraulic Model Update	1	10	Fair	1	Yes	No	Yes	\$125,000	2019 Update	Ongoing; Provides Guidance On Implementing System Improvements
Other	Other (describe)	GIS For The System	1	10	Ongoing	20	Yes	Yes	Meets SDWA Requirements (Yes/No)	\$12,000	continuous reoccurring cost	Update, Licenses & Software

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5941	P-7253	COV	Abbotts Crossing Rd	6	Asbestos Cement	476	69	2 out of 5	\$442	210,191
Distribution Main	5942	P-7253	COV	Abbotts Crossing Rd	6	Asbestos Cement	204	69	2 out of 5	\$442	90,243
Distribution Main	5943	P-7253	COV	Abbotts Crossing Rd	6	Asbestos Cement	598	69	2 out of 5	\$442	264,097
Distribution Main	7848	P-7252	COV	Abbotts Crossing Rd	6	Asbestos Cement	51	69	2 out of 5	\$442	22,718
Distribution Main	7849	P-7252	COV	Abbotts Crossing Rd	6	Asbestos Cement	6	69	2 out of 5	\$442	2,648
Distribution Main	11973	P-7253	COV	Abbotts Crossing Rd	6	Asbestos Cement	396	69	2 out of 5	\$442	174,934
Distribution Main	6314	P-7145	COV	Acacia Ct	8	Asbestos Cement	59	39	1 out of 5	\$442	26,081
Distribution Main	7278	P-7145	COV	Acacia Ct	8	Asbestos Cement	522	39	1 out of 5	\$442	230,794
Distribution Main	1086		COV	Acorn St	6	Asbestos Cement	17	53	1.85 out of 5	\$442	7,694
Distribution Main	2471	P-8302	COV	Acorn St	6	Asbestos Cement	109	53	1.85 out of 5	\$442	48,256
Distribution Main	2472	P-8302	COV	Acorn St	6	Asbestos Cement	196	53	1.85 out of 5	\$442	86,528
Distribution Main	2642	P-8982	COV	Acorn St	6	Asbestos Cement	25	53	1.85 out of 5	\$442	10,872
Distribution Main	2643	P-8982	COV	Acorn St	6	Asbestos Cement	418	53	1.85 out of 5	\$442	184,791
Distribution Main	11174	P-8302	COV	Acorn St	6	Asbestos Cement	16	53	1.85 out of 5	\$442	7,269
Distribution Main	1854	P-7604	COV	Ada Ct	6	Asbestos Cement	185	60	1.85 out of 5	\$442	81,739
Distribution Main	3285	P-7445	COV	Adams Dr	8	Asbestos Cement	363	42	1.14 out of 5	\$442	160,491
Distribution Main	6615	P-7445	COV	Adams Dr	8	Asbestos Cement	4	42	1.14 out of 5	\$442	1,919
Distribution Main	6616	P-7445	COV	Adams Dr	8	Asbestos Cement	152	42	1.14 out of 5	\$442	67,361
Distribution Main	7434	P-7176	COV	Adams Dr	8	Asbestos Cement	501	41	1.14 out of 5	\$442	221,243
Transmission Main	7514	P-8387	COV	Adams Dr	12	Ductile Iron	31	30	0.14 out of 5	\$442	13,610
Transmission Main	7519	P-8387	COV	Adams Dr	12	Ductile Iron	294	30	0.14 out of 5	\$442	129,841
Distribution Main	7806	P-7175	COV	Adams Dr	8	Asbestos Cement	316	41	1.14 out of 5	\$442	139,646
Distribution Main	9949		COV	Adams Dr	8	Ductile Iron	18	21	0.14 out of 5	N/A	\$0
Transmission Main	10870	P-8386	COV	Adams Dr	12	Ductile Iron	147	30	0.14 out of 5	\$442	64,760
Transmission Main	10871	P-7445	COV	Adams Dr	12	Ductile Iron	5	30	0.14 out of 5	\$442	2,015
Distribution Main	11345	P-7176	COV	Adams Dr	8	Asbestos Cement	5	41	1.14 out of 5	\$442	2,015
Distribution Main	1757	P-7578	COV	Alaska St	2	Galvanized Iron	20	86	3.43 out of 5	\$442	8,883
Distribution Main	2297	P-8297	COV	Alaska St	8	Ductile Iron	134	19	0 out of 5	N/A	\$0
Distribution Main	2782	P-7578	COV	Alaska St	2	Galvanized Iron	378	86	3.43 out of 5	\$442	167,185
Distribution Main	3029	P-9030	COV	Albro Lane	1	Unknown	195	UNK	1.42 out of 5	\$442	86,339
Distribution Main	1176	P-8117	COV	Alexis St	8	Ductile Iron	286	27	0.14 out of 5	\$442	126,266
Distribution Main	1186	P-8116	COV	Alexis St	8	Ductile Iron	599	27	0.14 out of 5	\$442	264,914
Distribution Main	1333	P-7354	COV	Almond Way	8	Ductile Iron	220	21	0.14 out of 5	N/A	\$0
Distribution Main	5304	P-7248	COV	Alvero Rd	8	Ductile Iron	5	18	0 out of 5	N/A	\$0
Distribution Main	5305	P-7248	COV	Alvero Rd	8	Ductile Iron	712	18	0 out of 5	N/A	\$0
Distribution Main	7923	P-7248	COV	Alvero Rd	8	Ductile Iron	12	18	0 out of 5	N/A	\$0
Distribution Main	7934	P-7230	COV	Alvero Rd	8	Asbestos Cement	20	56	1.14 out of 5	\$442	8,961
Distribution Main	7935	P-7230	COV	Alvero Rd	8	Asbestos Cement	430	56	1.14 out of 5	\$442	190,227
Distribution Main	7938	P-7237	COV	Alvero Rd	8	Asbestos Cement	57	56	1.14 out of 5	\$442	25,136
Distribution Main	7939	P-7237	COV	Alvero Rd	8	Asbestos Cement	314	56	1.14 out of 5	\$442	138,912
Distribution Main	11416	P-7237	COV	Alvero Rd	8	Asbestos Cement	5	56	1.14 out of 5	\$442	2,175
Transmission Main	3709	P-8841	COV	Ames St	16	Asbestos Cement	439	62	1.29 out of 5	\$442	194,133
Transmission Main	3710	P-8841	COV	Ames St	16	Asbestos Cement	77	62	1.29 out of 5	\$442	33,849

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	8522	P-8371	COV	Ames St	16	Ductile Iron	425	13	0 out of 5	N/A	\$0
Transmission Main	8523	P-8371	COV	Ames St	16	Ductile Iron	64	13	0 out of 5	N/A	\$0
Transmission Main	8526	P-8370	COV	Ames St	16	Ductile Iron	560	13	0 out of 5	N/A	\$0
Transmission Main	8550	P-8371	COV	Ames St	16	Ductile Iron	16	13	0 out of 5	N/A	\$0
Transmission Main	11041	P-1929	COV	Ames St	16	Asbestos Cement	27	62	1.29 out of 5	\$442	12,128
Transmission Main	208	P-8838	COV	Ames St.	16	Asbestos Cement	543	62	1.29 out of 5	\$442	239,888
Transmission Main	209	P-8838	COV	Ames St.	16	Asbestos Cement	384	62	1.29 out of 5	\$442	169,843
Distribution Main	1496	P-7816	COV	Amherst Ave	6	Asbestos Cement	527	52	1.85 out of 5	\$442	232,907
Distribution Main	2716	P-7996	COV	Anderson Ave	6	Asbestos Cement	221	58	1.85 out of 5	\$442	97,687
Distribution Main	2717	P-7996	COV	Anderson Ave	6	Asbestos Cement	485	58	1.85 out of 5	\$442	214,246
Distribution Main	2553	P-7623	COV	Angelwood Rd.	6	Asbestos Cement	29	60	1.85 out of 5	\$442	12,676
Distribution Main	2562	P-7622	COV	Angelwood Rd.	6	Asbestos Cement	279	60	1.85 out of 5	\$442	123,320
Distribution Main	2621	P-7623	COV	Angelwood Rd.	6	Asbestos Cement	456	60	1.85 out of 5	\$442	201,457
Transmission Main	8058	P-8142	COV	Angus St.	12	Ductile Iron	565	11	0 out of 5	N/A	\$0
Transmission Main	8059	P-8142	COV	Angus St.	12	Ductile Iron	928	11	0 out of 5	N/A	\$0
Distribution Main	573	P-8024	COV	Ann Ct.	2	Copper	313	79	2.43 out of 5	\$442	138,292
Distribution Main	1951	P-7866	COV	Anthony St.	6	Cast Iron	7	86	2.43 out of 5	\$442	2,992
Distribution Main	2827	P-7866	COV	Anthony St.	6	Cast Iron	181	86	2.43 out of 5	\$442	79,953
Distribution Main	2828	P-7866	COV	Anthony St.	6	Cast Iron	286	86	2.43 out of 5	\$442	126,595
Distribution Main	3075	P-9031	COV	Anthony St.	6	Cast Iron	324	86	2.43 out of 5	\$442	143,237
Distribution Main	3076	P-9031	COV	Anthony St.	6	Cast Iron	107	86	2.43 out of 5	\$442	47,099
Distribution Main	10071	P-9031	COV	Anthony St.	6	Cast Iron	21	86	2.43 out of 5	\$442	9,280
Distribution Main	7211	P-8955	COV	Apple Blossom Ln.	6	Asbestos Cement	147	57	1.85 out of 5	\$442	64,819
Distribution Main	7212	P-8955	COV	Apple Blossom Ln.	6	Asbestos Cement	86	57	1.85 out of 5	\$442	38,117
Distribution Main	7807	P-7034	COV	Apple Blossom Ln.	6	Asbestos Cement	710	57	1.85 out of 5	\$442	313,623
Distribution Main	7831	P-7035	COV	Apple Blossom Ln.	6	Asbestos Cement	606	57	1.85 out of 5	\$442	267,814
Distribution Main	11363	P-8955	COV	Apple Blossom Ln.	6	Asbestos Cement	4	57	1.85 out of 5	\$442	1,764
Distribution Main	8093	P-8391	COV	Arbor Dr	8	Ductile Iron	286	12	0 out of 5	N/A	\$0
Distribution Main	8094	P-8391	COV	Arbor Dr	8	Ductile Iron	230	12	0 out of 5	N/A	\$0
Distribution Main	8099	P-8394	COV	Arbor Dr	8	Ductile Iron	41	12	0 out of 5	N/A	\$0
Distribution Main	8100	P-8393	COV	Arbor Dr	8	Ductile Iron	42	12	0 out of 5	N/A	\$0
Distribution Main	8372	P-8390	COV	Arbor Dr	8	Ductile Iron	505	12	0 out of 5	N/A	\$0
Distribution Main	8373	P-8390	COV	Arbor Dr	8	Ductile Iron	511	12	0 out of 5	N/A	\$0
Distribution Main	8374	P-8404	COV	Arbor Dr	8	Ductile Iron	136	12	0 out of 5	N/A	\$0
Distribution Main	8375	P-8404	COV	Arbor Dr	8	Ductile Iron	206	12	0 out of 5	N/A	\$0
Distribution Main	10846	P-8387	COV	Arbor Dr	8	Ductile Iron	276	12	0 out of 5	N/A	\$0
Distribution Main	11430	P-8391	COV	Arbor Dr	8	Ductile Iron	48	12	0 out of 5	N/A	\$0
Distribution Main	11431	P-8391	COV	Arbor Dr	8	Ductile Iron	151	12	0 out of 5	N/A	\$0
Distribution Main	11871	P-8390	COV	Arbor Dr	8	Ductile Iron	270	12	0 out of 5	N/A	\$0
Distribution Main	7958	P-7124	COV	Arbutus Tr.	8	Ductile Iron	70	27	0.14 out of 5	\$442	31,070
Distribution Main	7959	P-7124	COV	Arbutus Tr.	8	Ductile Iron	301	27	0.14 out of 5	\$442	133,042
Distribution Main	7966	P-7123	COV	Arbutus Tr.	8	Ductile Iron	332	27	0.14 out of 5	\$442	146,783
Distribution Main	7967	P-7120	COV	Arbutus Tr.	8	Ductile Iron	538	27	0.14 out of 5	\$442	237,998
Distribution Main	479	P-7582	COV	Arizona St.	2	Cast Iron	20	86	3.14 out of 5	\$442	8,656

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	529	P-8295	COV	Arizona St.	8	Ductile Iron	69	19	0 out of 5	N/A	\$0
Distribution Main	1057	P-7579	COV	Arizona St.	2	Galvanized Iron	25	86	3.43 out of 5	\$442	10,984
Distribution Main	1058	P-7579	COV	Arizona St.	2	Galvanized Iron	524	86	3.43 out of 5	\$442	231,638
Distribution Main	1124	P-7582	COV	Arizona St.	2	Cast Iron	284	86	3.85 out of 5	\$442	125,350
Distribution Main	1306	P-8295	COV	Arizona St.	2	Galvanized Iron	8	86	3.43 out of 5	\$442	3,530
Distribution Main	2633	P-7579	COV	Arizona St.	2	Galvanized Iron	31	86	3.43 out of 5	\$442	13,686
Transmission Main	186	P-7697	COV	Arnold Rd.	16	Cast Iron	640	129	1.86 out of 5	\$442	283,063
Transmission Main	188	P-8984	COV	Arnold Rd.	16	Cast Iron	26	129	1.86 out of 5	\$442	11,380
Transmission Main	257	P-1779	COV	Arnold Rd.	16	Ductile Iron	10	28	0.14 out of 5	\$442	4,278
Transmission Main	258	P-1779	COV	Arnold Rd.	16	Ductile Iron	193	28	0.14 out of 5	\$442	85,093
Transmission Main	259	P-1766	COV	Arnold Rd.	16	Ductile Iron	104	28	0.14 out of 5	\$442	45,971
Transmission Main	260	P-8185	COV	Arnold Rd.	16	Ductile Iron	108	28	0.14 out of 5	\$442	47,605
Transmission Main	261	P-8185	COV	Arnold Rd.	16	Ductile Iron	830	28	0.14 out of 5	\$442	367,052
Transmission Main	273	P-8183	COV	Arnold Rd.	16	Ductile Iron	167	28	0.14 out of 5	\$442	73,598
Transmission Main	274	P-8183	COV	Arnold Rd.	16	Ductile Iron	37	28	0.14 out of 5	\$442	16,313
Transmission Main	349		COV	Arnold Rd.	12	Ductile Iron	41	28	0.14 out of 5	\$442	18,095
Transmission Main	350		COV	Arnold Rd.	12	Ductile Iron	8	UNK	0 out of 5	N/A	\$0
Distribution Main	352		COV	Arnold Rd.	8	Ductile Iron	12	28	0.14 out of 5	\$442	5,447
Distribution Main	353		COV	Arnold Rd.	8	Ductile Iron	4	28	0.14 out of 5	\$442	1,573
Distribution Main	354	P-8314	COV	Arnold Rd.	8	Ductile Iron	21	28	0.14 out of 5	\$442	9,069
Transmission Main	690	P-8183	COV	Arnold Rd.	16	Ductile Iron	148	28	0.14 out of 5	\$442	65,400
Transmission Main	693	P-8183	COV	Arnold Rd.	16	Ductile Iron	36	28	0.14 out of 5	\$442	15,805
Distribution Main	715		COV	Arnold Rd.	8	Asbestos Cement	23	50	1.14 out of 5	\$442	10,142
Distribution Main	716	P-8187	COV	Arnold Rd.	8	Asbestos Cement	272	50	1.14 out of 5	\$442	120,268
Distribution Main	717	P-8187	COV	Arnold Rd.	8	Asbestos Cement	148	50	1.14 out of 5	\$442	65,559
Transmission Main	764	P-8185	COV	Arnold Rd.	16	Ductile Iron	894	28	0.14 out of 5	\$442	395,098
Transmission Main	765	P-7697	COV	Arnold Rd.	16	Cast Iron	137	129	1.86 out of 5	\$442	60,740
Transmission Main	768	P-8188	COV	Arnold Rd.	16	Ductile Iron	140	28	0.14 out of 5	\$442	61,687
Transmission Main	769	P-8188	COV	Arnold Rd.	16	Ductile Iron	395	28	0.14 out of 5	\$442	174,519
Distribution Main	1035	P-8176	COV	Arnold Rd.	8	Asbestos Cement	4	50	1.14 out of 5	\$442	1,856
Transmission Main	1041	P-7692	COV	Arnold Rd.	16	Cast Iron	57	129	1.86 out of 5	\$442	25,089
Transmission Main	1422	P-8188	COV	Arnold Rd.	16	Ductile Iron	236	28	0.14 out of 5	\$442	104,458
Transmission Main	1423	P-8984	COV	Arnold Rd.	16	Cast Iron	237	129	1.86 out of 5	\$442	104,613
Distribution Main	1424	P-7711	COV	Arnold Rd.	8	Asbestos Cement	157	50	1.14 out of 5	\$442	69,558
Distribution Main	1425	P-7711	COV	Arnold Rd.	8	Asbestos Cement	154	50	1.14 out of 5	\$442	67,962
Distribution Main	1428	P-8176	COV	Arnold Rd.	8	Asbestos Cement	300	50	1.14 out of 5	\$442	132,536
Distribution Main	1453		COV	Arnold Rd.	6	Unknown	4	UNK	0.71 out of 5	\$442	1,595
Transmission Main	1618	P-8188	COV	Arnold Rd.	16	Ductile Iron	1,401	28	0.14 out of 5	\$442	619,426
Transmission Main	1619	P-8188	COV	Arnold Rd.	16	Ductile Iron	85	28	0.14 out of 5	\$442	37,534
Distribution Main	1620	P-8185	COV	Arnold Rd.	8	Asbestos Cement	88	50	1.14 out of 5	\$442	39,033
Distribution Main	1621	P-8185	COV	Arnold Rd.	8	Asbestos Cement	561	50	1.14 out of 5	\$442	247,976
Transmission Main	1622	P-8185	COV	Arnold Rd.	16	Ductile Iron	456	28	0.14 out of 5	\$442	201,669
Transmission Main	1623	P-8188	COV	Arnold Rd.	16	Ductile Iron	133	28	0.14 out of 5	\$442	58,831
Transmission Main	1624	P-8188	COV	Arnold Rd.	16	Ductile Iron	646	28	0.14 out of 5	\$442	285,703

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	1650	P-7711	COV	Arnold Rd.	8	Asbestos Cement	132	50	1.14 out of 5	\$442	58,363
Transmission Main	1653	P-7697	COV	Arnold Rd.	16	Cast Iron	38	129	1.86 out of 5	\$442	16,772
Transmission Main	1654	P-7690	COV	Arnold Rd.	16	Cast Iron	171	129	1.86 out of 5	\$442	75,577
Transmission Main	1655	P-7694	COV	Arnold Rd.	16	Cast Iron	233	129	1.86 out of 5	\$442	103,083
Transmission Main	1656	P-8306	COV	Arnold Rd.	16	Cast Iron	162	129	1.86 out of 5	\$442	71,709
Transmission Main	1657	P-8306	COV	Arnold Rd.	16	Cast Iron	67	129	1.86 out of 5	\$442	29,643
Transmission Main	1753	P-7596	COV	Arnold Rd.	16	Cast Iron	162	129	1.86 out of 5	\$442	71,544
Transmission Main	1760	P-7597	COV	Arnold Rd.	16	Cast Iron	149	129	1.86 out of 5	\$442	65,977
Transmission Main	1761	P-7651	COV	Arnold Rd.	16	Cast Iron	16	129	1.86 out of 5	\$442	6,947
Transmission Main	1762	P-7651	COV	Arnold Rd.	16	Cast Iron	286	129	1.86 out of 5	\$442	126,287
Distribution Main	2186	P-8176	COV	Arnold Rd.	8	Asbestos Cement	17	50	1.14 out of 5	\$442	7,708
Distribution Main	2192	P-8313	COV	Arnold Rd.	8	Asbestos Cement	213	50	1.14 out of 5	\$442	94,362
Transmission Main	2289	P-7650	COV	Arnold Rd.	16	Cast Iron	992	129	1.86 out of 5	\$442	438,283
Distribution Main	2448	P-8313	COV	Arnold Rd.	8	Asbestos Cement	4	50	1.14 out of 5	\$442	1,621
Distribution Main	2564		COV	Arnold Rd.	6	Unknown	4	UNK	0.71 out of 5	\$442	1,737
Distribution Main	2582	P-8187	COV	Arnold Rd.	8	Asbestos Cement	388	50	1.14 out of 5	\$442	171,528
Distribution Main	2583		COV	Arnold Rd.	8	Asbestos Cement	6	50	1.14 out of 5	\$442	2,790
Transmission Main	2590		COV	Arnold Rd.	16	Cast Iron	33	UNK	1.14 out of 5	\$442	14,772
Transmission Main	2591		COV	Arnold Rd.	16	Cast Iron	33	UNK	1.14 out of 5	\$442	14,566
Transmission Main	2592	P-7688	COV	Arnold Rd.	16	Ductile Iron	173	129	0.72 out of 5	\$442	76,279
Transmission Main	2596	P-8310	COV	Arnold Rd.	16	Cast Iron	285	129	1.86 out of 5	\$442	126,142
Transmission Main	2597	P-8308	COV	Arnold Rd.	16	Cast Iron	205	129	1.86 out of 5	\$442	90,760
Transmission Main	2598	P-8308	COV	Arnold Rd.	16	Cast Iron	33	129	1.86 out of 5	\$442	14,744
Transmission Main	2599	P-7663	COV	Arnold Rd.	16	Cast Iron	241	129	1.86 out of 5	\$442	106,621
Transmission Main	2600	P-7659	COV	Arnold Rd.	16	Cast Iron	175	129	1.86 out of 5	\$442	77,412
Transmission Main	2601	P-8984	COV	Arnold Rd.	16	Ductile Iron	15	129	0.72 out of 5	\$442	6,775
Transmission Main	2602	P-8984	COV	Arnold Rd.	16	Ductile Iron	19	28	0.14 out of 5	\$442	8,388
Transmission Main	2630	P-8267	COV	Arnold Rd.	16	Cast Iron	35	129	1.86 out of 5	\$442	15,648
Transmission Main	2631	P-8267	COV	Arnold Rd.	16	Cast Iron	224	129	1.86 out of 5	\$442	99,116
Transmission Main	2792	P-8793	COV	Arnold Rd.	16	Cast Iron	168	129	1.86 out of 5	\$442	74,104
Transmission Main	2793	P-8793	COV	Arnold Rd.	16	Cast Iron	198	129	1.86 out of 5	\$442	87,473
Transmission Main	2794	P-7589	COV	Arnold Rd.	16	Cast Iron	6	129	1.86 out of 5	\$442	2,663
Transmission Main	2795	P-7589	COV	Arnold Rd.	16	Cast Iron	66	129	1.86 out of 5	\$442	29,391
Transmission Main	2796	P-7588	COV	Arnold Rd.	16	Cast Iron	398	129	1.86 out of 5	\$442	175,853
Distribution Main	3139	P-8314	COV	Arnold Rd.	8	Asbestos Cement	138	50	1.14 out of 5	\$442	60,790
Distribution Main	3141	P-8313	COV	Arnold Rd.	8	Asbestos Cement	180	50	1.14 out of 5	\$442	79,481
Distribution Main	3142	P-8314	COV	Arnold Rd.	8	Asbestos Cement	383	50	1.14 out of 5	\$442	169,325
Transmission Main	9583	P-8184	COV	Arnold Rd.	16	Ductile Iron	157	28	0.14 out of 5	\$442	69,294
Distribution Main	9584	P-8313	COV	Arnold Rd.	8	Asbestos Cement	28	50	1.14 out of 5	\$442	12,568
Distribution Main	10351		COV	Arnold Rd.	8	Ductile Iron	62	28	0.14 out of 5	\$442	27,519
Distribution Main	10352		COV	Arnold Rd.	8	Ductile Iron	136	28	0.14 out of 5	\$442	59,984
Transmission Main	11025	P-7697	COV	Arnold Rd.	16	Cast Iron	10	129	1.86 out of 5	\$442	4,299
Transmission Main	11138	P-8306	COV	Arnold Rd.	16	Cast Iron	7	129	1.86 out of 5	\$442	3,106
Transmission Main	11177	P-7694	COV	Arnold Rd.	16	Cast Iron	4	129	1.86 out of 5	\$442	1,820

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11188	P-8793	COV	Arnold Rd.	16	Cast Iron	38	133	1.86 out of 5	\$442	16,743
Distribution Main	11201	P-8314	COV	Arnold Rd.	8	Asbestos Cement	24	50	1.14 out of 5	\$442	10,591
Distribution Main	3146	P-9038	COV	Arnold St.	1	Copper	113	86	2.57 out of 5	\$442	49,916
Distribution Main	7963	P-7134	COV	Ash Ln.	8	Ductile Iron	250	20	0 out of 5	N/A	\$0
Distribution Main	7964	P-7134	COV	Ash Ln.	8	Ductile Iron	9	20	0 out of 5	N/A	\$0
Distribution Main	1855	P-7606	COV	Audrey Ct.	6	Asbestos Cement	182	60	1.85 out of 5	\$442	80,227
Distribution Main	8727	P-7108	COV	Azalea Way	8	Asbestos Cement	16	40	1 out of 5	\$442	6,997
Distribution Main	8728	P-7107	COV	Azalea Way	8	Asbestos Cement	790	40	1 out of 5	\$442	349,362
Distribution Main	2922	P-8848	COV	Bakerville	6	Unknown	156	UNK	0.71 out of 5	\$442	69,097
Distribution Main	9918	P-8848	COV	Bakerville	6	Unknown	52	UNK	0.71 out of 5	\$442	23,062
Distribution Main	420	P-7699	COV	Balsam Rd.	6	Asbestos Cement	288	60	1.85 out of 5	\$442	127,424
Distribution Main	2563	P-7699	COV	Balsam Rd.	6	Asbestos Cement	9	60	1.85 out of 5	\$442	4,124
Distribution Main	2593	P-7700	COV	Balsam Rd.	6	Asbestos Cement	136	60	1.85 out of 5	\$442	59,914
Distribution Main	9619	P-7538	COV	Bank St	8	PVC	290	35	0.43 out of 5	\$442	128,085
Distribution Main	9620	P-7538	COV	Bank St	8	PVC	8	35	0.43 out of 5	\$442	3,576
Distribution Main	5326	P-7518	COV	Barber St.	2	Galvanized Iron	498	121	3.57 out of 5	\$442	220,016
Distribution Main	5327	P-7518	COV	Barber St.	2	Galvanized Iron	67	121	3.57 out of 5	\$442	29,700
Distribution Main	10073	P-7518	COV	Barber St.	4	Cast Iron	16	121	3.29 out of 5	\$442	6,864
Distribution Main	10074	P-7518	COV	Barber St.	4	Ductile Iron	20	27	1.57 out of 5	\$442	8,840
Distribution Main	11298	P-7518	COV	Barber St.	2	Galvanized Iron	6	121	3.57 out of 5	\$442	2,731
Distribution Main	226	P-7897	COV	Barberry Ct.	6	Asbestos Cement	278	39	1.71 out of 5	\$442	122,706
Distribution Main	941	P-8030	COV	Bassett St.	2	Galvanized Iron	276	109	3.57 out of 5	\$442	121,994
Distribution Main	312	P-8278	COV	Bates Ave.	8	Cast Iron	365	132	1.86 out of 5	\$442	161,153
Distribution Main	574		COV	Bates Ave.	6	Cast Iron	14	32	1.99 out of 5	\$442	6,188
Distribution Main	2699	P-8278	COV	Bates Ave.	8	Cast Iron	175	79	1.57 out of 5	\$442	77,421
Distribution Main	6180	P-8280	COV	Bates Ave.	6	Cast Iron	433	79	2.28 out of 5	\$442	191,170
Distribution Main	6181	P-8280	COV	Bates Ave.	6	Cast Iron	115	79	2.28 out of 5	\$442	50,812
Distribution Main	6182	P-8279	COV	Bates Ave.	2	Cast Iron	385	79	3 out of 5	\$442	170,199
Distribution Main	6183	P-9057	COV	Bates Ave.	2	Cast Iron	209	132	3.29 out of 5	\$442	92,460
Distribution Main	6184	P-8034	COV	Bates Ave.	6	Cast Iron	5	132	2.57 out of 5	\$442	2,245
Distribution Main	6185	P-8034	COV	Bates Ave.	6	Cast Iron	494	132	2.57 out of 5	\$442	218,141
Distribution Main	2819	P-7847	COV	Batley Ave.	6	Ductile Iron	164	29	0.85 out of 5	\$442	72,417
Distribution Main	2820	P-7847	COV	Batley Ave.	6	Ductile Iron	376	29	0.85 out of 5	\$442	166,387
Distribution Main	9650	P-7847	COV	Batley Ave.	6	Ductile Iron	316	29	0.85 out of 5	\$442	139,567
Distribution Main	842	P-7787	COV	Baylor Dr.	6	Asbestos Cement	246	53	1.85 out of 5	\$442	108,829
Distribution Main	1483	P-7783	COV	Baylor Dr.	6	Asbestos Cement	26	53	1.85 out of 5	\$442	11,438
Distribution Main	1484	P-7783	COV	Baylor Dr.	6	Asbestos Cement	452	53	1.85 out of 5	\$442	199,900
Distribution Main	9807	P-8989	COV	Beach St	8	Ductile Iron	161	12	0 out of 5	N/A	\$0
Distribution Main	9808	P-8988	COV	Beach St	8	Ductile Iron	6	12	0 out of 5	N/A	\$0
Distribution Main	11610	P-8988	COV	Beach St	8	Ductile Iron	8	12	0 out of 5	N/A	\$0
Distribution Main	767	P-8988	COV	Beach St.	1	Copper	50	1	1.99 out of 5	N/A	\$0
Distribution Main	1457	P-8992	COV	Beach St.	2	Copper	262	65	2.43 out of 5	\$442	115,872
Distribution Main	1645	P-7660	COV	Beach St.	6	Cast Iron	43	65	2.28 out of 5	\$442	19,020
Distribution Main	11137	P-7660	COV	Beach St.	6	Cast Iron	7	65	2.28 out of 5	\$442	3,020

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5049	P-7531	COV	Beaton St.	6	Asbestos Cement	401	71	2 out of 5	\$442	177,063
Distribution Main	5056	P-7531	COV	Beaton St.	6	Asbestos Cement	76	71	2 out of 5	\$442	33,399
Distribution Main	9082	P-9040	COV	Beaulieu Ave	1	Copper	447	UNK	1.99 out of 5	\$442	197,629
Distribution Main	9218	P-8836	COV	Bee St	8	Ductile Iron	291	8	0 out of 5	N/A	\$0
Distribution Main	1064	P-8977	COV	Beechwood St.	6	Asbestos Cement	67	65	2 out of 5	\$442	29,788
Distribution Main	1065	P-8977	COV	Beechwood St.	6	Asbestos Cement	207	65	2 out of 5	\$442	91,694
Distribution Main	1451		COV	Beechwood St.	6	Asbestos Cement	28	65	2 out of 5	\$442	12,173
Distribution Main	2641	P-8303	COV	Beechwood St.	6	Asbestos Cement	246	65	2 out of 5	\$442	108,777
Distribution Main	10869	P-8304	COV	Beechwood St.	6	Asbestos Cement	244	65	2 out of 5	\$442	107,634
Distribution Main	11099	P-8304	COV	Beechwood St.	6	Asbestos Cement	19	65	2 out of 5	\$442	8,543
Distribution Main	9089	P-8886	COV	Bellmare Rd	8	Ductile Iron	72	13	0 out of 5	N/A	\$0
Distribution Main	9090	P-8886	COV	Bellmare Rd	8	Ductile Iron	286	13	0 out of 5	N/A	\$0
Distribution Main	828	P-7401	COV	Benoit St.	6	Ductile Iron	839	27	0.85 out of 5	\$442	371,051
Distribution Main	829	P-7401	COV	Benoit St.	6	Ductile Iron	475	27	0.85 out of 5	\$442	209,979
Distribution Main	2831	P-7401	COV	Benoit St.	6	Ductile Iron	30	27	0.85 out of 5	\$442	13,157
Distribution Main	3078	P-9033	COV	Benoit St.	6	Ductile Iron	245	27	0.85 out of 5	\$442	108,116
Distribution Main	3079	P-9033	COV	Benoit St.	6	Ductile Iron	188	27	0.85 out of 5	\$442	83,143
Distribution Main	10070	P-9033	COV	Benoit St.	6	Ductile Iron	3	27	0.85 out of 5	\$442	1,316
Distribution Main	8371	P-9010	COV	Berkshire Rd.	1	Copper	96	13	1.99 out of 5	N/A	\$0
Distribution Main	844	P-7813	COV	Bernard Dr.	6	Asbestos Cement	68	65	2 out of 5	\$442	29,865
Distribution Main	845	P-7813	COV	Bernard Dr.	6	Asbestos Cement	150	65	2 out of 5	\$442	66,495
Distribution Main	9562	P-7813	COV	Bernard Dr.	6	Asbestos Cement	176	65	2 out of 5	\$442	77,766
Transmission Main	7540		COV	Bestwick Trail	12	Ductile Iron	73	UNK	0 out of 5	N/A	\$0
Transmission Main	7541		COV	Bestwick Trail	12	Ductile Iron	6	UNK	0 out of 5	N/A	\$0
Distribution Main	143	P-7924	COV	Birchwood Ln.	8	PVC	560	39	0.43 out of 5	\$442	247,389
Distribution Main	3014	P-8338	COV	Birdie Ct.	6	Ductile Iron	245	30	0.85 out of 5	\$442	108,117
Distribution Main	1025	P-7923	COV	Black Walnut Dr.	8	PVC	504	36	0.43 out of 5	\$442	222,917
Distribution Main	1026	P-7921	COV	Black Walnut Dr.	8	PVC	137	36	0.43 out of 5	\$442	60,381
Distribution Main	1027	P-7919	COV	Black Walnut Dr.	8	PVC	79	36	0.43 out of 5	\$442	34,770
Distribution Main	1050	P-7927	COV	Black Walnut Dr.	8	PVC	216	36	0.43 out of 5	\$442	95,404
Distribution Main	1051	P-7921	COV	Black Walnut Dr.	8	PVC	210	36	0.43 out of 5	\$442	92,762
Distribution Main	1913	P-7929	COV	Black Walnut Dr.	8	PVC	21	36	0.43 out of 5	\$442	9,426
Distribution Main	1914	P-7929	COV	Black Walnut Dr.	8	PVC	430	36	0.43 out of 5	\$442	190,114
Distribution Main	2463	P-7917	COV	Black Walnut Dr.	8	PVC	296	36	0.43 out of 5	\$442	130,942
Distribution Main	2576	P-7925	COV	Black Walnut Dr.	8	PVC	380	36	0.43 out of 5	\$442	167,836
Distribution Main	2577	P-7925	COV	Black Walnut Dr.	8	PVC	99	36	0.43 out of 5	\$442	43,901
Distribution Main	11865	P-7929	COV	Black Walnut Dr.	8	PVC	238	36	0.43 out of 5	\$442	105,234
Distribution Main	1138	P-8874	COV	Black Walnut St.	8	Ductile Iron	7	15	0 out of 5	N/A	\$0
Distribution Main	1139	P-8874	COV	Black Walnut St.	8	Ductile Iron	28	15	0 out of 5	N/A	\$0
Transmission Main	601	P-7970	COV	Blackrock Rd	24	Ductile Iron	306	15	0 out of 5	N/A	\$0
Distribution Main	602	P-7397	COV	Blackrock Rd	8	Asbestos Cement	489	70	1.29 out of 5	\$442	215,931
Distribution Main	603	P-7397	COV	Blackrock Rd	8	Asbestos Cement	223	70	1.29 out of 5	\$442	98,631
Transmission Main	8179	P-8500	COV	Blackrock Rd	24	Ductile Iron	71	15	0 out of 5	N/A	\$0
Transmission Main	8180	P-8500	COV	Blackrock Rd	24	Ductile Iron	1,081	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	8183	P-7396	COV	Blackrock Rd	12	Ductile Iron	49	15	0 out of 5	N/A	\$0
Transmission Main	8186	P-8499	COV	Blackrock Rd	24	Ductile Iron	263	15	0 out of 5	N/A	\$0
Distribution Main	8188	P-7397	COV	Blackrock Rd	8	Asbestos Cement	93	70	1.29 out of 5	\$442	40,946
Transmission Main	8189	P-8499	COV	Blackrock Rd	24	Ductile Iron	25	15	0 out of 5	N/A	\$0
Transmission Main	8190	P-8499	COV	Blackrock Rd	24	Ductile Iron	581	15	0 out of 5	N/A	\$0
Transmission Main	8192	P-7944	COV	Blackrock Rd	24	Ductile Iron	98	15	0 out of 5	N/A	\$0
Transmission Main	8193	P-7944	COV	Blackrock Rd	24	Ductile Iron	325	15	0 out of 5	N/A	\$0
Transmission Main	8194	P-7936	COV	Blackrock Rd	24	Ductile Iron	594	15	0 out of 5	N/A	\$0
Transmission Main	8222	P-7970	COV	Blackrock Rd	24	Ductile Iron	45	15	0 out of 5	N/A	\$0
Transmission Main	8223	P-7970	COV	Blackrock Rd	24	Ductile Iron	517	15	0 out of 5	N/A	\$0
Distribution Main	8225	P-7397	COV	Blackrock Rd	8	Asbestos Cement	569	70	1.29 out of 5	\$442	251,524
Distribution Main	8226	P-7397	COV	Blackrock Rd	8	Asbestos Cement	35	70	1.29 out of 5	\$442	15,313
Transmission Main	8227	P-8499	COV	Blackrock Rd	24	Ductile Iron	543	15	0 out of 5	N/A	\$0
Transmission Main	8229	P-8501	COV	Blackrock Rd	24	Ductile Iron	144	15	0 out of 5	N/A	\$0
Transmission Main	8230	P-8501	COV	Blackrock Rd	24	Ductile Iron	374	15	0 out of 5	N/A	\$0
Transmission Main	8234	P-8501	COV	Blackrock Rd	24	Ductile Iron	615	15	0 out of 5	N/A	\$0
Transmission Main	8236	P-8501	COV	Blackrock Rd	24	Ductile Iron	722	15	0 out of 5	N/A	\$0
Transmission Main	8237	P-8501	COV	Blackrock Rd	24	Ductile Iron	322	15	0 out of 5	N/A	\$0
Transmission Main	10063	P-8497	COV	Blackrock Rd	24	Ductile Iron	32	15	0 out of 5	N/A	\$0
Distribution Main	10080	P-7397	COV	Blackrock Rd	8	Ductile Iron	9	15	0 out of 5	N/A	\$0
Distribution Main	10389	P-7397	COV	Blackrock Rd	8	Ductile Iron	13	15	0 out of 5	N/A	\$0
Distribution Main	10390	P-7397	COV	Blackrock Rd	8	Ductile Iron	183	15	0 out of 5	N/A	\$0
Distribution Main	11033	P-7397	COV	Blackrock Rd	8	Asbestos Cement	155	70	1.29 out of 5	\$442	68,431
Transmission Main	11036	P-7970	COV	Blackrock Rd	24	Ductile Iron	257	15	0 out of 5	N/A	\$0
Transmission Main	11072	P-7944	COV	Blackrock Rd	24	Ductile Iron	479	15	0 out of 5	N/A	\$0
Transmission Main	11073	P-7944	COV	Blackrock Rd	24	Ductile Iron	9	15	0 out of 5	N/A	\$0
Transmission Main	11442	P-7396	COV	Blackrock Rd	12	Ductile Iron	5	15	0 out of 5	N/A	\$0
Transmission Main	11444	P-7944	COV	Blackrock Rd	24	Ductile Iron	36	15	0 out of 5	N/A	\$0
Transmission Main	11445	P-7944	COV	Blackrock Rd	24	Ductile Iron	258	15	0 out of 5	N/A	\$0
Transmission Main	11447	P-7936	COV	Blackrock Rd	24	Ductile Iron	2	15	0 out of 5	N/A	\$0
Transmission Main	11452	P-8501	COV	Blackrock Rd	24	Ductile Iron	175	15	0 out of 5	N/A	\$0
Transmission Main	11639	P-8497	COV	Blackrock Rd	24	Ductile Iron	6	15	0 out of 5	N/A	\$0
Distribution Main	7746	P-7060	COV	Blue Spruce Dr	8	Asbestos Cement	803	43	1.14 out of 5	\$442	354,783
Distribution Main	7747	P-7060	COV	Blue Spruce Dr	8	Asbestos Cement	206	44	1.14 out of 5	\$442	91,183
Distribution Main	7819	P-7060	COV	Blue Spruce Dr	8	Asbestos Cement	30	43	1.14 out of 5	\$442	13,257
Distribution Main	7735	P-7050	COV	Blueberry Ln	6	Asbestos Cement	369	57	1.85 out of 5	\$442	163,133
Distribution Main	9629	P-9015	COV	Bonney St	6	Ductile Iron	2	12	0.71 out of 5	N/A	\$0
Distribution Main	9632	P-9015	COV	Bonney St	8	Ductile Iron	50	12	0 out of 5	N/A	\$0
Distribution Main	2259	P-7766	COV	Bonney St.	8	Ductile Iron	32	59	0.29 out of 5	\$442	14,100
Distribution Main	3682	P-7766	COV	Bonney St.	6	Asbestos Cement	12	59	1.85 out of 5	\$442	5,269
Distribution Main	3683	P-7766	COV	Bonney St.	6	Asbestos Cement	445	59	1.85 out of 5	\$442	196,807
Distribution Main	10081		COV	Boston St	4	Ductile Iron	30	12	1.42 out of 5	N/A	\$0
Distribution Main	200	P-7867	COV	Boston St.	6	Cast Iron	344	91	2.43 out of 5	\$442	152,209
Distribution Main	253	P-8377	COV	Boston St.	6	Asbestos Cement	776	70	2 out of 5	\$442	343,026

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	597	P-8376	COV	Boston St.	6	Ductile Iron	887	27	0.85 out of 5	\$442	391,858
Distribution Main	598	P-8376	COV	Boston St.	6	Ductile Iron	37	27	0.85 out of 5	\$442	16,299
Distribution Main	2375	P-9037	COV	Boston St.	6	Cast Iron	402	91	2.43 out of 5	\$442	177,677
Distribution Main	2376	P-9037	COV	Boston St.	6	Cast Iron	105	91	2.43 out of 5	\$442	46,207
Distribution Main	2377	P-7403	COV	Boston St.	6	Cast Iron	8	91	2.43 out of 5	\$442	3,518
Distribution Main	2378	P-7403	COV	Boston St.	6	Cast Iron	755	91	2.43 out of 5	\$442	333,842
Distribution Main	3082	P-7402	COV	Boston St.	6	Cast Iron	112	91	2.43 out of 5	\$442	49,458
Distribution Main	8182	P-8377	COV	Boston St.	8	Ductile Iron	18	15	0 out of 5	N/A	\$0
Transmission Main	8187	P-7396	COV	Boston St.	12	Ductile Iron	398	15	0 out of 5	N/A	\$0
Distribution Main	8228	P-8377	COV	Boston St.	6	Asbestos Cement	47	70	2 out of 5	\$442	20,918
Distribution Main	10069	P-7399	COV	Boston St.	6	Cast Iron	38	91	2.43 out of 5	\$442	16,774
Distribution Main	10072	P-9037	COV	Boston St.	6	Cast Iron	13	91	2.43 out of 5	\$442	5,916
Transmission Main	10078	P-7396	COV	Boston St.	12	Ductile Iron	171	15	0 out of 5	N/A	\$0
Distribution Main	11032	P-8377	COV	Boston St.	6	Asbestos Cement	64	70	2 out of 5	\$442	28,502
Distribution Main	11779	P-7403	COV	Boston St.	6	Cast Iron	461	91	2.43 out of 5	\$442	203,674
Distribution Main	7885	P-7214	COV	Boulder Dr.	8	Ductile Iron	28	29	0.14 out of 5	\$442	12,325
Distribution Main	7886	P-7214	COV	Boulder Dr.	8	Ductile Iron	307	29	0.14 out of 5	\$442	135,628
Distribution Main	7888	P-7213	COV	Boulder Dr.	8	Ductile Iron	232	29	0.14 out of 5	\$442	102,737
Distribution Main	7889	P-7213	COV	Boulder Dr.	8	Ductile Iron	486	29	0.14 out of 5	\$442	214,866
Distribution Main	3015	P-8335	COV	Brassie Ct.	6	Ductile Iron	325	30	0.85 out of 5	\$442	143,656
Distribution Main	1617	P-7364	COV	Breezy Lake Dr.	6	Asbestos Cement	201	54	1.85 out of 5	\$442	88,898
Distribution Main	2120	P-8884	COV	Breezy Lake Dr.	1	Unknown	59	UNK	1.42 out of 5	\$442	26,147
Distribution Main	2121	P-8882	COV	Breezy Lake Dr.	6	Asbestos Cement	30	54	1.85 out of 5	\$442	13,320
Distribution Main	2122	P-8882	COV	Breezy Lake Dr.	6	Asbestos Cement	369	54	1.85 out of 5	\$442	163,070
Distribution Main	2123	P-8883	COV	Breezy Lake Dr.	6	Asbestos Cement	213	54	1.85 out of 5	\$442	94,314
Distribution Main	2124	P-7365	COV	Breezy Lake Dr.	6	Asbestos Cement	499	54	1.85 out of 5	\$442	220,767
Distribution Main	2125	P-7367	COV	Breezy Lake Dr.	6	Asbestos Cement	185	54	1.85 out of 5	\$442	81,862
Distribution Main	2126	P-7366	COV	Breezy Lake Dr.	6	Asbestos Cement	167	54	1.85 out of 5	\$442	73,905
Distribution Main	1613	P-7364	COV	Breezy Lake Rd	8	Ductile Iron	56	15	0 out of 5	N/A	\$0
Distribution Main	8786		COV	Brenda Dr	8	Ductile Iron	34	8	0 out of 5	N/A	\$0
Distribution Main	7854	P-7184	COV	Brenda Dr.	6	Asbestos Cement	541	48	1.85 out of 5	\$442	239,195
Distribution Main	8788	P-8895	COV	Brenda Dr.	6	Ductile Iron	2	8	0.71 out of 5	N/A	\$0
Distribution Main	2629	P-7556	COV	Brentwood Dr.	6	Asbestos Cement	379	66	2 out of 5	\$442	167,331
Distribution Main	9940	P-8995	COV	Briar Point Ave	8	Ductile Iron	41	11	0 out of 5	N/A	\$0
Distribution Main	9941	P-8995	COV	Briar Point Ave	8	Ductile Iron	136	11	0 out of 5	N/A	\$0
Distribution Main	1461	P-7695	COV	Briar Point Ave.	6	Asbestos Cement	460	72	2 out of 5	\$442	203,111
Distribution Main	1049	P-7926	COV	Briarwood Ct.	8	PVC	242	39	0.43 out of 5	\$442	106,896
Transmission Main	8389	P-8219	COV	Broad St	12	Ductile Iron	239	10	0 out of 5	N/A	\$0
Transmission Main	8457	P-1910	COV	Broad St	12	Ductile Iron	192	10	0 out of 5	N/A	\$0
Transmission Main	8460	P-1248	COV	Broad St	12	Ductile Iron	177	10	0 out of 5	N/A	\$0
Transmission Main	9676	P-1910	COV	Broad St	12	Ductile Iron	27	10	0 out of 5	N/A	\$0
Transmission Main	9677	P-1910	COV	Broad St	12	Ductile Iron	16	10	0 out of 5	N/A	\$0
Distribution Main	815	P-7387	COV	Brookfield Rd.	8	Ductile Iron	512	28	0.14 out of 5	\$442	226,515
Distribution Main	9470	P-8905	COV	Brookside Lane	2	Copper	5	69	2.43 out of 5	\$442	2,342

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9471	P-8905	COV	Brookside Lane	2	Copper	292	69	2.43 out of 5	\$442	129,222
Distribution Main	9215	P-8074	COV	Brown St	8	Ductile Iron	10	8	0 out of 5	N/A	\$0
Distribution Main	2748	P-8074	COV	Brown St.	8	Cast Iron	457	91	1.72 out of 5	\$442	201,935
Distribution Main	2749	P-8074	COV	Brown St.	8	Cast Iron	604	91	1.72 out of 5	\$442	266,907
Distribution Main	11860	P-8074	COV	Brown St.	8	Cast Iron	15	91	1.72 out of 5	\$442	6,422
Distribution Main	4811	P-7076	COV	Butternut Dr.	8	Ductile Iron	184	28	0.14 out of 5	\$442	81,320
Distribution Main	4812	P-7076	COV	Butternut Dr.	8	Ductile Iron	19	28	0.14 out of 5	\$442	8,398
Distribution Main	7592	P-7076	COV	Butternut Dr.	8	Asbestos Cement	42	41	1.14 out of 5	\$442	18,482
Distribution Main	7779	P-7157	COV	Butternut Dr.	8	Asbestos Cement	339	41	1.14 out of 5	\$442	149,867
Distribution Main	7780	P-7157	COV	Butternut Dr.	8	Asbestos Cement	371	41	1.14 out of 5	\$442	163,842
Distribution Main	3002	P-8934	COV	Cady Street	8	Ductile Iron	227	30	0.14 out of 5	\$442	100,263
Distribution Main	679	P-8113	COV	Canyon Dr.	6	Asbestos Cement	25	59	1.85 out of 5	\$442	11,219
Distribution Main	2109	P-8113	COV	Canyon Dr.	6	Asbestos Cement	341	59	1.85 out of 5	\$442	150,614
Distribution Main	2617	P-7667	COV	Cape Way	6	Asbestos Cement	151	44	1.85 out of 5	\$442	66,782
Distribution Main	399	P-8289	COV	Capwell Ave.	8	Cast Iron	472	132	1.86 out of 5	\$442	208,701
Distribution Main	400	P-8289	COV	Capwell Ave.	8	Cast Iron	44	132	1.86 out of 5	\$442	19,354
Distribution Main	9518	P-8292	COV	Capwell Ave.	6	Cast Iron	532	132	2.57 out of 5	\$442	235,184
Distribution Main	1504	P-7573	COV	Card St.	6	Cast Iron	411	132	2.57 out of 5	\$442	181,448
Distribution Main	1505	P-7573	COV	Card St.	6	Cast Iron	23	132	2.57 out of 5	\$442	10,170
Distribution Main	1765	P-7814	COV	Card St.	2	PVC	4	30	1.85 out of 5	\$442	1,876
Distribution Main	9587	P-7814	COV	Card St.	2	PVC	89	30	1.85 out of 5	\$442	39,186
Distribution Main	3039		COV	Cardinal Ave.	6	Asbestos Cement	4	71	2 out of 5	\$442	1,659
Distribution Main	3042	P-7987	COV	Cardinal Ave.	6	Asbestos Cement	234	71	2 out of 5	\$442	103,305
Transmission Main	8673	P-8347	COV	Carol Ct	12	PVC	483	32	0.43 out of 5	\$442	213,346
Distribution Main	741	P-7634	COV	Carolyn St.	6	Asbestos Cement	37	58	1.85 out of 5	\$442	16,236
Distribution Main	742	P-7634	COV	Carolyn St.	6	Asbestos Cement	3	58	1.85 out of 5	\$442	1,512
Distribution Main	743	P-7634	COV	Carolyn St.	6	Asbestos Cement	157	58	1.85 out of 5	\$442	69,287
Distribution Main	4786	P-7519	COV	Carr Street	2	Galvanized Iron	194	92	3.43 out of 5	\$442	85,963
Distribution Main	6317	P-7130	COV	Catalpa Way	8	Ductile Iron	66	25	0.14 out of 5	N/A	\$0
Distribution Main	6318	P-7130	COV	Catalpa Way	8	Ductile Iron	305	25	0.14 out of 5	N/A	\$0
Distribution Main	7961	P-7135	COV	Catalpa Way	8	Ductile Iron	224	25	0.14 out of 5	N/A	\$0
Distribution Main	7962	P-7135	COV	Catalpa Way	8	Ductile Iron	243	25	0.14 out of 5	N/A	\$0
Distribution Main	7965	P-7122	COV	Catalpa Way	8	Ductile Iron	787	25	0.14 out of 5	N/A	\$0
Distribution Main	7973	P-7136	COV	Catalpa Way	8	Ductile Iron	489	25	0.14 out of 5	N/A	\$0
Distribution Main	8731	P-7130	COV	Catalpa Way	8	Ductile Iron	4	25	0.14 out of 5	N/A	\$0
Distribution Main	8732	P-7122	COV	Catalpa Way	8	Ductile Iron	4	25	0.14 out of 5	N/A	\$0
Distribution Main	570	P-7994	COV	Cecile Ave.	6	Asbestos Cement	374	67	2 out of 5	\$442	165,136
Distribution Main	571	P-7994	COV	Cecile Ave.	6	Asbestos Cement	305	67	2 out of 5	\$442	134,854
Distribution Main	2711	P-7990	COV	Cecile Ave.	6	Asbestos Cement	214	67	2 out of 5	\$442	94,503
Distribution Main	2712	P-7990	COV	Cecile Ave.	6	Asbestos Cement	24	67	2 out of 5	\$442	10,825
Distribution Main	2730	P-7992	COV	Cecile Ave.	6	Asbestos Cement	236	67	2 out of 5	\$442	104,177
Distribution Main	673	P-8109	COV	Cedar St.	6	Asbestos Cement	467	60	1.85 out of 5	\$442	206,238
Distribution Main	674	P-8109	COV	Cedar St.	6	Asbestos Cement	48	60	1.85 out of 5	\$442	21,060
Distribution Main	2110	P-8121	COV	Cedar St.	6	Ductile Iron	608	25	0.85 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2638	P-8985	COV	Cedar Tree Lane	2	Copper	145	84	2.57 out of 5	\$442	64,169
Distribution Main	2639	P-8986	COV	Cedar Tree Lane	2	Copper	100	84	2.57 out of 5	\$442	44,420
Distribution Main	2586	P-8985	COV	Cedar Tree Ln	6	Asbestos Cement	97	72	2 out of 5	\$442	42,669
Distribution Main	9727	P-8849	COV	Centennial St	8	Ductile Iron	2	26	0.14 out of 5	\$442	884
Distribution Main	9728	P-8849	COV	Centennial St	6	Ductile Iron	110	26	0.85 out of 5	\$442	48,695
Distribution Main	680	P-7384	COV	Centennial St.	8	Asbestos Cement	113	48	1.14 out of 5	\$442	49,732
Distribution Main	681	P-7384	COV	Centennial St.	8	Asbestos Cement	679	48	1.14 out of 5	\$442	300,121
Distribution Main	1468	P-7375	COV	Centennial St.	8	Asbestos Cement	275	48	1.14 out of 5	\$442	121,542
Distribution Main	1469	P-7376	COV	Centennial St.	8	Asbestos Cement	159	48	1.14 out of 5	\$442	70,291
Distribution Main	9726	P-7385	COV	Centennial St.	8	Asbestos Cement	145	48	1.14 out of 5	\$442	64,077
Transmission Main	25	P-8465	COV	Center Of N.E. Blvd	16	Unknown	7	UNK	0 out of 5	N/A	\$0
Transmission Main	9317	P-8411	COV	Centre New England Blvd	12	Ductile Iron	6	9	0 out of 5	N/A	\$0
Distribution Main	1587	P-7835	COV	Centre St.	6	Ductile Iron	529	25	0.85 out of 5	N/A	\$0
Distribution Main	3147	P-7822	COV	Centre St.	8	Asbestos Cement	779	56	1.14 out of 5	\$442	344,112
Distribution Main	10113	P-7822	COV	Centre St.	8	Asbestos Cement	14	56	1.14 out of 5	\$442	6,036
Distribution Main	10114	P-7822	COV	Centre St.	8	Asbestos Cement	24	56	1.14 out of 5	\$442	10,756
Distribution Main	11640	P-7822	COV	Centre St.	8	Asbestos Cement	9	56	1.14 out of 5	\$442	3,861
Distribution Main	7947	P-7211	COV	Chandler Dr.	8	Asbestos Cement	40	45	1.14 out of 5	\$442	17,827
Distribution Main	7948	P-7211	COV	Chandler Dr.	8	Asbestos Cement	349	45	1.14 out of 5	\$442	154,185
Distribution Main	7955	P-7208	COV	Chandler Dr.	8	Asbestos Cement	573	45	1.14 out of 5	\$442	253,128
Distribution Main	7956	P-7208	COV	Chandler Dr.	8	Asbestos Cement	1,067	45	1.14 out of 5	\$442	471,576
Distribution Main	7957	P-7198	COV	Chandler Dr.	8	Asbestos Cement	485	45	1.14 out of 5	\$442	214,312
Distribution Main	1668	P-7612	COV	Charlotte St.	6	Asbestos Cement	606	60	1.85 out of 5	\$442	267,644
Distribution Main	1252	P-7329	COV	Charwood Dr.	8	Asbestos Cement	481	41	1.14 out of 5	\$442	212,788
Distribution Main	1254	P-7334	COV	Charwood Dr.	8	Asbestos Cement	232	41	1.14 out of 5	\$442	102,588
Distribution Main	1339	P-7334	COV	Charwood Dr.	8	Asbestos Cement	133	41	1.14 out of 5	\$442	58,636
Distribution Main	7741	P-7038	COV	Cherry Blossom Ln.	6	Asbestos Cement	608	57	1.85 out of 5	\$442	268,847
Distribution Main	7742	P-7038	COV	Cherry Blossom Ln.	6	Asbestos Cement	531	57	1.85 out of 5	\$442	234,858
Distribution Main	249	P-8119	COV	Chestnut Street	1	Copper	20	63	2.43 out of 5	\$442	8,911
Distribution Main	1418	P-8119	COV	Chestnut Street	1	Copper	141	63	2.43 out of 5	\$442	62,198
Distribution Main	9468	P-8858	COV	Chestnut Street	0.75	Copper	323	UNK	1.99 out of 5	\$442	142,987
Distribution Main	5331	P-8522	COV	Chloe Court	8	Ductile Iron	434	14	0 out of 5	N/A	\$0
Distribution Main	1688	P-9042	COV	Chopin Street	2	Galvanized Iron	147	124	3.57 out of 5	\$442	65,114
Distribution Main	9641	P-9042	COV	Chopin Street	6	Asbestos Cement	106	71	2 out of 5	\$442	46,695
Distribution Main	1956	P-7290	COV	Cindy Ln.	6	Asbestos Cement	466	53	1.85 out of 5	\$442	205,860
Distribution Main	3054	P-7340	COV	Cinnamon Dr.	8	Ductile Iron	465	21	0.14 out of 5	N/A	\$0
Distribution Main	4455	P-7022	COV	Circlewood Dr.	8	Asbestos Cement	465	41	1.14 out of 5	\$442	205,713
Distribution Main	4456	P-7022	COV	Circlewood Dr.	8	Asbestos Cement	786	41	1.14 out of 5	\$442	347,341
Distribution Main	7748	P-7024	COV	Circlewood Dr.	8	Asbestos Cement	424	41	1.14 out of 5	\$442	187,350
Distribution Main	7749	P-7024	COV	Circlewood Dr.	8	Asbestos Cement	144	41	1.14 out of 5	\$442	63,566
Distribution Main	11799	P-7022	COV	Circlewood Dr.	8	Asbestos Cement	628	41	1.14 out of 5	\$442	277,400
Transmission Main	2552	P-8968	COV	Clark Mill St.	12	Ductile Iron	39	22	0.14 out of 5	N/A	\$0
Transmission Main	2622	P-8968	COV	Clark Mill St.	12	Ductile Iron	54	22	0.14 out of 5	N/A	\$0
Distribution Main	6173	P-8200	COV	Clark Mill St.	8	Ductile Iron	21	22	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6174	P-8200	COV	Clark Mill St.	8	Ductile Iron	58	22	0.14 out of 5	N/A	\$0
Distribution Main	6175	P-8200	COV	Clark Mill St.	8	Ductile Iron	359	22	0.14 out of 5	N/A	\$0
Distribution Main	6176	P-8525	COV	Clark Mill St.	8	Ductile Iron	335	22	0.14 out of 5	N/A	\$0
Distribution Main	6177	P-8525	COV	Clark Mill St.	8	Ductile Iron	487	22	0.14 out of 5	N/A	\$0
Distribution Main	8095	P-8966	COV	Clark Mill St.	8	Ductile Iron	394	22	0.14 out of 5	N/A	\$0
Distribution Main	8376	P-8399	COV	Clark Mill St.	8	Ductile Iron	274	22	0.14 out of 5	N/A	\$0
Distribution Main	8377	P-8399	COV	Clark Mill St.	8	Ductile Iron	215	22	0.14 out of 5	N/A	\$0
Distribution Main	8378	P-8525	COV	Clark Mill St.	8	Ductile Iron	227	22	0.14 out of 5	N/A	\$0
Distribution Main	8379	P-8525	COV	Clark Mill St.	8	Ductile Iron	163	22	0.14 out of 5	N/A	\$0
Distribution Main	10842	P-8966	COV	Clark Mill St.	8	Ductile Iron	9	22	0.14 out of 5	N/A	\$0
Distribution Main	10843	P-8966	COV	Clark Mill St.	8	Ductile Iron	273	22	0.14 out of 5	N/A	\$0
Distribution Main	11872	P-8525	COV	Clark Mill St.	8	Ductile Iron	224	22	0.14 out of 5	N/A	\$0
Transmission Main	225	P-7908	COV	Clarke Rd.	20	Asbestos Cement	375	51	1.14 out of 5	\$442	165,647
Transmission Main	1014	P-7892	COV	Clarke Rd.	20	Asbestos Cement	790	51	1.14 out of 5	\$442	349,337
Transmission Main	1015	P-7892	COV	Clarke Rd.	20	Asbestos Cement	96	51	1.14 out of 5	\$442	42,230
Transmission Main	1179	P-7911	COV	Clarke Rd.	20	Asbestos Cement	385	51	1.85 out of 5	\$442	170,012
Transmission Main	1927	P-7907	COV	Clarke Rd.	20	Asbestos Cement	291	51	1 out of 5	\$442	128,406
Transmission Main	1928	P-7907	COV	Clarke Rd.	20	Asbestos Cement	53	51	1.14 out of 5	\$442	23,564
Transmission Main	2460	P-7916	COV	Clarke Rd.	20	Asbestos Cement	1,010	51	1.14 out of 5	\$442	446,316
Transmission Main	2461	P-7916	COV	Clarke Rd.	20	Asbestos Cement	776	51	1 out of 5	\$442	343,178
Transmission Main	8104	P-8488	COV	Clarke Rd.	12	Ductile Iron	26	UNK	0 out of 5	N/A	\$0
Distribution Main	8106	P-8488	COV	Clarke Rd.	8	Ductile Iron	10	UNK	0 out of 5	N/A	\$0
Transmission Main	9966	P-7909	COV	Clarke Rd.	20	Asbestos Cement	4	51	1.14 out of 5	\$442	1,642
Transmission Main	9967	P-7909	COV	Clarke Rd.	20	Asbestos Cement	254	51	1.14 out of 5	\$442	112,275
Distribution Main	700	P-7566	COV	Clearview Dr.	6	Asbestos Cement	236	67	2 out of 5	\$442	104,135
Distribution Main	1061	P-7571	COV	Clearview Dr.	6	Asbestos Cement	26	67	2 out of 5	\$442	11,655
Distribution Main	1062	P-7571	COV	Clearview Dr.	6	Asbestos Cement	268	67	2 out of 5	\$442	118,576
Distribution Main	1639	P-8514	COV	Clifton Ave.	6	Asbestos Cement	12	63	2 out of 5	\$442	5,119
Distribution Main	1660	P-7491	COV	Clifton Ave.	6	Asbestos Cement	194	63	2 out of 5	\$442	85,849
Distribution Main	1665	P-8969	COV	Clifton Ave.	6	Asbestos Cement	214	63	2 out of 5	\$442	94,795
Distribution Main	2763	P-7493	COV	Clifton Ave.	6	Asbestos Cement	211	63	2 out of 5	\$442	93,066
Distribution Main	2764	P-7493	COV	Clifton Ave.	6	Asbestos Cement	96	63	2 out of 5	\$442	42,278
Distribution Main	4809	P-7150	COV	Clubhouse Rd.	8	PVC	235	31	0.43 out of 5	\$442	103,879
Distribution Main	4810	P-7150	COV	Clubhouse Rd.	8	PVC	384	31	0.43 out of 5	\$442	169,549
Distribution Main	7452	P-7091	COV	Clubhouse Rd.	8	Asbestos Cement	7	45	1.14 out of 5	\$442	2,980
Distribution Main	7453	P-7091	COV	Clubhouse Rd.	8	Asbestos Cement	169	45	1.14 out of 5	\$442	74,520
Distribution Main	7462	P-7147	COV	Clubhouse Rd.	8	Asbestos Cement	1,007	45	1.14 out of 5	\$442	445,279
Distribution Main	7463	P-7092	COV	Clubhouse Rd.	8	Asbestos Cement	718	45	1.14 out of 5	\$442	317,310
Distribution Main	7596	P-8364	COV	Clubhouse Rd.	8	PVC	392	31	0.43 out of 5	\$442	173,475
Distribution Main	7600	P-7148	COV	Clubhouse Rd.	8	Asbestos Cement	509	45	1.14 out of 5	\$442	225,171
Distribution Main	7774	P-8361	COV	Clubhouse Rd.	8	Asbestos Cement	79	45	1.14 out of 5	\$442	34,754
Distribution Main	7775	P-8362	COV	Clubhouse Rd.	8	Asbestos Cement	58	45	1.14 out of 5	\$442	25,774
Distribution Main	7788	P-8362	COV	Clubhouse Rd.	8	Asbestos Cement	327	45	1.14 out of 5	\$442	144,388
Distribution Main	7789	P-8362	COV	Clubhouse Rd.	8	Asbestos Cement	204	45	1.14 out of 5	\$442	89,981

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11397	P-7148	COV	Clubhouse Rd.	8	Asbestos Cement	37	45	1.14 out of 5	\$442	16,254
Distribution Main	7777	P-8360	COV	Clubhouse Rd. (Coventry H	8	Ductile Iron	1,019	29	0.14 out of 5	\$442	450,243
Distribution Main	7778	P-8360	COV	Clubhouse Rd. (Coventry H	8	Ductile Iron	1	29	0.14 out of 5	\$442	575
Distribution Main	10504	P-7152	COV	Clubhouse Rd. (Coventry H	8	Ductile Iron	26	29	0.14 out of 5	\$442	11,460
Distribution Main	10505	P-7152	COV	Clubhouse Rd. (Coventry H	8	Ductile Iron	594	29	0.14 out of 5	\$442	262,654
Transmission Main	847	P-7190	COV	Cobblestone Ter.	12	Ductile Iron	31	25	0.14 out of 5	N/A	\$0
Transmission Main	848	P-7190	COV	Cobblestone Ter.	12	Ductile Iron	725	25	0.14 out of 5	N/A	\$0
Distribution Main	849	P-7189	COV	Cobblestone Ter.	8	Ductile Iron	229	25	0.14 out of 5	N/A	\$0
Transmission Main	850	P-7191	COV	Cobblestone Ter.	12	Ductile Iron	963	26	0.14 out of 5	\$442	425,471
Transmission Main	851	P-7191	COV	Cobblestone Ter.	12	Ductile Iron	59	25	0.14 out of 5	N/A	\$0
Distribution Main	5849	P-8808	COV	Cobblestone Ter.	8	Ductile Iron	81	25	0.14 out of 5	N/A	\$0
Distribution Main	5853	P-7188	COV	Cobblestone Ter.	8	Ductile Iron	468	25	0.14 out of 5	N/A	\$0
Distribution Main	5855	P-8808	COV	Cobblestone Ter.	8	Ductile Iron	394	25	0.14 out of 5	N/A	\$0
Distribution Main	5856	P-8808	COV	Cobblestone Ter.	8	Ductile Iron	346	25	0.14 out of 5	N/A	\$0
Distribution Main	5857	P-7189	COV	Cobblestone Ter.	8	Ductile Iron	438	25	0.14 out of 5	N/A	\$0
Distribution Main	7960	P-7191	COV	Cobblestone Ter.	8	Ductile Iron	19	26	0.14 out of 5	\$442	8,463
Distribution Main	10976	P-7188	COV	Cobblestone Ter.	8	Ductile Iron	18	25	0.14 out of 5	N/A	\$0
Transmission Main	11031	P-7190	COV	Cobblestone Ter.	12	Ductile Iron	2	25	0.14 out of 5	N/A	\$0
Transmission Main	11979	P-7191	COV	Cobblestone Ter.	12	Ductile Iron	806	26	0.14 out of 5	\$442	356,275
Distribution Main	5854	P-8892	COV	Cobblestone Terr	8	Ductile Iron	39	25	0.14 out of 5	N/A	\$0
Distribution Main	3176	P-7784	COV	Colby Dr.	6	Asbestos Cement	501	56	1.85 out of 5	\$442	221,401
Distribution Main	7914	P-8908	COV	Collier Way	6	Asbestos Cement	5	65	2 out of 5	\$442	2,316
Distribution Main	7915	P-8908	COV	Collier Way	6	Asbestos Cement	202	65	2 out of 5	\$442	89,091
Distribution Main	7916		COV	Collier Way	6	Unknown	12	65	1.14 out of 5	\$442	5,438
Distribution Main	11275	P-8908	COV	Collier Way	6	Asbestos Cement	5	65	2 out of 5	\$442	2,115
Distribution Main	1593	P-7644	COV	Colonial Rd.	6	Asbestos Cement	382	53	1.85 out of 5	\$442	169,005
Distribution Main	2609		COV	Colonial Rd.	6	Asbestos Cement	26	53	1.85 out of 5	\$442	11,336
Distribution Main	2612	P-7645	COV	Colonial Rd.	6	Asbestos Cement	379	53	1.85 out of 5	\$442	167,455
Distribution Main	2613	P-7645	COV	Colonial Rd.	6	Asbestos Cement	254	53	1.85 out of 5	\$442	112,140
Distribution Main	2614	P-7644	COV	Colonial Rd.	6	Asbestos Cement	6	53	1.85 out of 5	\$442	2,633
Distribution Main	1123	P-7581	COV	Colorado St.	2	Galvanized Iron	539	86	4.14 out of 5	\$442	238,279
Distribution Main	1172	P-7581	COV	Colorado St.	2	Galvanized Iron	31	86	3.43 out of 5	\$442	13,624
Distribution Main	1173	P-7581	COV	Colorado St.	2	Galvanized Iron	2	86	3.43 out of 5	\$442	780
Distribution Main	1711	P-7796	COV	Columbia Ave.	6	Asbestos Cement	1,016	60	1.85 out of 5	\$442	449,030
Distribution Main	1712	P-7796	COV	Columbia Ave.	6	Asbestos Cement	781	60	1.85 out of 5	\$442	345,117
Distribution Main	1713	P-7773	COV	Columbia Ave.	6	Asbestos Cement	24	60	1.85 out of 5	\$442	10,746
Distribution Main	1714	P-7773	COV	Columbia Ave.	6	Asbestos Cement	618	60	1.85 out of 5	\$442	273,254
Distribution Main	2202	P-7796	COV	Columbia Ave.	6	Asbestos Cement	20	60	1.85 out of 5	\$442	8,911
Distribution Main	10972	P-7773	COV	Columbia Ave.	6	Asbestos Cement	7	60	1.85 out of 5	\$442	2,895
Distribution Main	11115	P-7796	COV	Columbia Ave.	6	Asbestos Cement	10	60	1.85 out of 5	\$442	4,247
Transmission Main	10391	P-8872	COV	Colvin St.	24	Ductile Iron	121	15	0 out of 5	N/A	\$0
Transmission Main	10392	P-8872	COV	Colvin St.	24	Ductile Iron	403	15	0 out of 5	N/A	\$0
Transmission Main	12235		COV	Colvin St.	24	Ductile Iron	95	15	0 out of 5	N/A	\$0
Distribution Main	1911	P-8474	COV	Colvintown Rd.	8	Ductile Iron	650	16	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	1912	P-8474	COV	Colvintown Rd.	8	Ductile Iron	448	16	0 out of 5	N/A	\$0
Distribution Main	2411	P-8890	COV	Colvintown Rd.	8	Ductile Iron	155	16	0 out of 5	N/A	\$0
Distribution Main	2412	P-8890	COV	Colvintown Rd.	8	Ductile Iron	639	16	0 out of 5	N/A	\$0
Distribution Main	2413	P-8269	COV	Colvintown Rd.	8	Ductile Iron	229	16	0 out of 5	N/A	\$0
Distribution Main	2414	P-8269	COV	Colvintown Rd.	8	Ductile Iron	715	16	0 out of 5	N/A	\$0
Distribution Main	2415	P-8269	COV	Colvintown Rd.	8	Ductile Iron	292	16	0 out of 5	N/A	\$0
Distribution Main	2416	P-8269	COV	Colvintown Rd.	8	Ductile Iron	893	16	0 out of 5	N/A	\$0
Distribution Main	2417	P-8269	COV	Colvintown Rd.	8	Ductile Iron	152	16	0 out of 5	N/A	\$0
Distribution Main	2418	P-8269	COV	Colvintown Rd.	8	Ductile Iron	964	16	0 out of 5	N/A	\$0
Distribution Main	2971	P-8474	COV	Colvintown Rd.	8	Ductile Iron	261	16	0 out of 5	N/A	\$0
Distribution Main	2972	P-8474	COV	Colvintown Rd.	8	Ductile Iron	41	16	0 out of 5	N/A	\$0
Distribution Main	4101	P-8474	COV	Colvintown Rd.	8	Ductile Iron	472	16	0 out of 5	N/A	\$0
Distribution Main	4102	P-8474	COV	Colvintown Rd.	8	Ductile Iron	439	16	0 out of 5	N/A	\$0
Distribution Main	5301	P-8273	COV	Colvintown Rd.	8	Asbestos Cement	513	48	1.14 out of 5	\$442	226,649
Distribution Main	5302	P-8273	COV	Colvintown Rd.	8	Asbestos Cement	611	48	1.14 out of 5	\$442	270,199
Distribution Main	5303	P-7421	COV	Colvintown Rd.	8	Asbestos Cement	4	48	1.14 out of 5	\$442	1,630
Distribution Main	7162	P-7220	COV	Colvintown Rd.	8	Asbestos Cement	4	48	1.14 out of 5	\$442	1,606
Distribution Main	7166	P-7316	COV	Colvintown Rd.	8	Asbestos Cement	36	48	1.14 out of 5	\$442	15,993
Distribution Main	7167	P-7316	COV	Colvintown Rd.	8	Asbestos Cement	482	48	1.14 out of 5	\$442	213,160
Distribution Main	7168	P-7314	COV	Colvintown Rd.	8	Asbestos Cement	656	48	1.14 out of 5	\$442	290,030
Distribution Main	7169	P-7343	COV	Colvintown Rd.	8	Asbestos Cement	7	48	1.14 out of 5	\$442	3,025
Distribution Main	7521	P-8774	COV	Colvintown Rd.	8	Asbestos Cement	11	48	1.14 out of 5	\$442	5,015
Distribution Main	7522	P-8774	COV	Colvintown Rd.	8	Asbestos Cement	218	48	1.14 out of 5	\$442	96,357
Distribution Main	7852	P-8270	COV	Colvintown Rd.	8	Asbestos Cement	300	48	1.14 out of 5	\$442	132,533
Distribution Main	7853	P-8270	COV	Colvintown Rd.	8	Asbestos Cement	604	48	1.14 out of 5	\$442	266,831
Distribution Main	7907	P-7315	COV	Colvintown Rd.	8	Asbestos Cement	299	48	1.14 out of 5	\$442	132,225
Distribution Main	7908	P-7315	COV	Colvintown Rd.	8	Asbestos Cement	54	48	1.14 out of 5	\$442	23,724
Distribution Main	7910	P-7294	COV	Colvintown Rd.	8	Asbestos Cement	251	48	1.14 out of 5	\$442	111,083
Distribution Main	7911	P-7294	COV	Colvintown Rd.	8	Asbestos Cement	182	48	1.14 out of 5	\$442	80,390
Distribution Main	7912	P-7314	COV	Colvintown Rd.	8	Asbestos Cement	4	48	1.14 out of 5	\$442	1,557
Distribution Main	7917	P-7218	COV	Colvintown Rd.	8	Asbestos Cement	440	48	1.14 out of 5	\$442	194,345
Distribution Main	7918	P-7218	COV	Colvintown Rd.	8	Asbestos Cement	303	48	1.14 out of 5	\$442	133,885
Distribution Main	7919	P-7240	COV	Colvintown Rd.	8	Asbestos Cement	428	48	1.14 out of 5	\$442	189,117
Distribution Main	7931	P-7220	COV	Colvintown Rd.	8	Asbestos Cement	60	48	1.14 out of 5	\$442	26,528
Distribution Main	9301	P-8891	COV	Colvintown Rd.	8	Ductile Iron	8	16	0 out of 5	N/A	\$0
Distribution Main	9302	P-8891	COV	Colvintown Rd.	8	Ductile Iron	23	16	0 out of 5	N/A	\$0
Distribution Main	9434	P-7314	COV	Colvintown Rd.	8	Asbestos Cement	43	48	1.14 out of 5	\$442	18,807
Distribution Main	10082	P-8890	COV	Colvintown Rd.	8	Ductile Iron	274	16	0 out of 5	N/A	\$0
Distribution Main	10974	P-7315	COV	Colvintown Rd.	8	Asbestos Cement	33	48	1.14 out of 5	\$442	14,401
Distribution Main	11173	P-8269	COV	Colvintown Rd.	8	Ductile Iron	109	16	0 out of 5	N/A	\$0
Distribution Main	11243	P-8474	COV	Colvintown Rd.	8	Ductile Iron	83	16	0 out of 5	N/A	\$0
Distribution Main	11414	P-7218	COV	Colvintown Rd.	8	Asbestos Cement	40	48	1.14 out of 5	\$442	17,810
Distribution Main	11415	P-7218	COV	Colvintown Rd.	8	Asbestos Cement	15	48	1.14 out of 5	\$442	6,502
Transmission Main	268	P-8174	COV	Compton Rd.	12	Ductile Iron	886	47	0.29 out of 5	\$442	391,762

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	355	P-8176	COV	Compton Rd.	12	Asbestos Cement	2	47	1.14 out of 5	\$442	917
Transmission Main	691	P-8176	COV	Compton Rd.	12	Asbestos Cement	12	47	1.14 out of 5	\$442	5,193
Distribution Main	8224	P-9036	COV	Congdon St.	4	Cast Iron	495	70	3 out of 5	\$442	218,883
Distribution Main	9519	P-7398	COV	Congdon St.	6	Cast Iron	471	70	2.28 out of 5	\$442	208,337
Distribution Main	9335	P-8395	COV	Conifer Ct	8	Ductile Iron	177	9	0 out of 5	N/A	\$0
Distribution Main	9336	P-8396	COV	Conifer Ct	8	Ductile Iron	6	9	0 out of 5	N/A	\$0
Distribution Main	9337	P-8396	COV	Conifer Ct	8	Ductile Iron	344	9	0 out of 5	N/A	\$0
Distribution Main	1447	P-7858	COV	Contentment Dr.	8	Asbestos Cement	258	50	1.14 out of 5	\$442	114,118
Distribution Main	1448	P-7858	COV	Contentment Dr.	8	Asbestos Cement	231	50	1.14 out of 5	\$442	102,319
Distribution Main	2379	P-7858	COV	Contentment Dr.	8	Asbestos Cement	11	50	1.14 out of 5	\$442	4,770
Distribution Main	10461		COV	Contentment Dr.	8	Asbestos Cement	3	50	1.14 out of 5	\$442	1,516
Distribution Main	11130	P-7858	COV	Contentment Dr.	8	Asbestos Cement	182	50	1.14 out of 5	\$442	80,600
Distribution Main	710	P-8312	COV	Cook St.	6	Ductile Iron	538	18	0.71 out of 5	N/A	\$0
Distribution Main	3229	P-7800	COV	Cornell Ct.	6	Asbestos Cement	401	52	1.85 out of 5	\$442	177,096
Distribution Main	698	P-7842	COV	Cote Ct.	6	Ductile Iron	201	19	0.71 out of 5	N/A	\$0
Distribution Main	699	P-7841	COV	Cote Ct.	6	Ductile Iron	448	19	0.71 out of 5	N/A	\$0
Distribution Main	3172	P-7838	COV	Cote Ct.	6	Ductile Iron	608	19	0.71 out of 5	N/A	\$0
Distribution Main	3173	P-7838	COV	Cote Ct.	6	Ductile Iron	19	19	0.71 out of 5	N/A	\$0
Distribution Main	816	P-7388	COV	Country View Dr.	8	Ductile Iron	49	30	0.14 out of 5	\$442	21,448
Distribution Main	817	P-7388	COV	Country View Dr.	8	Ductile Iron	500	30	0.14 out of 5	\$442	221,136
Distribution Main	11090	P-7388	COV	Country View Dr.	8	Ductile Iron	289	30	0.14 out of 5	\$442	127,643
Distribution Main	11861	P-7388	COV	Country View Dr.	8	Ductile Iron	342	30	0.14 out of 5	\$442	151,185
Distribution Main	1174	P-7670	COV	Cove Rd.	6	Asbestos Cement	618	56	1.85 out of 5	\$442	273,029
Distribution Main	1175	P-7670	COV	Cove Rd.	6	Asbestos Cement	43	56	1.85 out of 5	\$442	18,983
Distribution Main	1178	P-7619	COV	Coventry Dr.	6	Asbestos Cement	555	60	1.85 out of 5	\$442	245,500
Distribution Main	1637	P-7607	COV	Coventry Dr.	6	Asbestos Cement	518	60	1.85 out of 5	\$442	229,079
Distribution Main	1638	P-7614	COV	Coventry Dr.	6	Asbestos Cement	101	60	1.85 out of 5	\$442	44,854
Distribution Main	1662	P-7603	COV	Coventry Dr.	6	Asbestos Cement	203	60	1.85 out of 5	\$442	89,514
Distribution Main	1664	P-7614	COV	Coventry Dr.	6	Asbestos Cement	35	60	1.85 out of 5	\$442	15,407
Distribution Main	1842	P-7605	COV	Coventry Dr.	6	Asbestos Cement	39	60	1.85 out of 5	\$442	17,454
Distribution Main	1843	P-7605	COV	Coventry Dr.	6	Asbestos Cement	248	60	1.85 out of 5	\$442	109,408
Distribution Main	9507	P-8944	COV	Coventry Dr.	8	Ductile Iron	34	19	0 out of 5	N/A	\$0
Distribution Main	9508	P-8944	COV	Coventry Dr.	8	Ductile Iron	26	19	0 out of 5	N/A	\$0
Distribution Main	9571	P-8945	COV	Coventry Dr.	6	Ductile Iron	4	19	0.71 out of 5	N/A	\$0
Transmission Main	5330		COV	Coventry/Spring Lake Well	12	Ductile Iron	378	30	0.14 out of 5	\$442	166,955
Distribution Main	5341		COV	Coventry/Spring Lake Well	8	Ductile Iron	94	30	0.14 out of 5	\$442	41,692
Distribution Main	5342		COV	Coventry/Spring Lake Well	8	Ductile Iron	334	30	0.14 out of 5	\$442	147,475
Transmission Main	11299		COV	Coventry/Spring Lake Well	12	Ductile Iron	17	30	0.14 out of 5	\$442	7,712
Distribution Main	2466	P-7905	COV	Crabapple Ct.	6	Asbestos Cement	252	39	1.71 out of 5	\$442	111,515
Distribution Main	9760	P-619	COV	Creighton Pl	8	Ductile Iron	211	8	0 out of 5	N/A	\$0
Distribution Main	9767	P-619	COV	Creighton Pl	8	Ductile Iron	364	8	0 out of 5	N/A	\$0
Distribution Main	9768	P-619	COV	Creighton Pl	8	Ductile Iron	38	8	0 out of 5	N/A	\$0
Distribution Main	2584	P-7708	COV	Crestwood Rd.	8	Asbestos Cement	502	60	1.14 out of 5	\$442	222,034
Transmission Main	266	P-8538	COV	Crompton Rd.	16	Ductile Iron	276	28	0.14 out of 5	\$442	122,188

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	267	P-8711	COV	Crompton Rd.	16	Ductile Iron	32	28	0.14 out of 5	\$442	14,058
Transmission Main	692	P-8172	COV	Crompton Rd.	16	Ductile Iron	4	28	0.14 out of 5	\$442	1,595
Transmission Main	12060	P-8711	COV	Crompton Rd.	16	Ductile Iron	154	28	0.14 out of 5	\$442	68,167
Distribution Main	7157	P-7236	COV	Cynthia Dr.	8	Asbestos Cement	442	54	1.14 out of 5	\$442	195,370
Distribution Main	7158	P-7233	COV	Cynthia Dr.	8	Asbestos Cement	706	54	1.14 out of 5	\$442	312,061
Distribution Main	7159	P-7233	COV	Cynthia Dr.	8	Asbestos Cement	297	54	1.14 out of 5	\$442	131,457
Distribution Main	7863	P-7235	COV	Cynthia Dr.	8	Asbestos Cement	493	54	1.14 out of 5	\$442	217,972
Distribution Main	7926	P-7232	COV	Cynthia Dr.	8	Asbestos Cement	211	54	1.14 out of 5	\$442	93,320
Distribution Main	2268	P-7764	COV	Cypruss Rd.	6	Asbestos Cement	555	57	1.85 out of 5	\$442	245,523
Distribution Main	2272	P-7764	COV	Cypruss Rd.	6	Asbestos Cement	32	57	1.85 out of 5	\$442	14,252
Distribution Main	7155	P-7203	COV	Daniel Dr.	6	Asbestos Cement	48	44	1.85 out of 5	\$442	21,006
Distribution Main	7864	P-7210	COV	Daniel Dr.	6	Asbestos Cement	544	44	1.85 out of 5	\$442	240,501
Distribution Main	7865	P-7210	COV	Daniel Dr.	6	Asbestos Cement	38	44	1.85 out of 5	\$442	16,689
Distribution Main	7913	P-7202	COV	Daniel Dr.	6	Asbestos Cement	998	44	1.85 out of 5	\$442	441,043
Distribution Main	7952	P-7199	COV	Daniel Dr.	6	Asbestos Cement	379	44	1.85 out of 5	\$442	167,317
Distribution Main	8356	P-7721	COV	Darton St.	8	Ductile Iron	162	13	0 out of 5	N/A	\$0
Distribution Main	10273		COV	David Drive	6	Ductile Iron	662	5	0.71 out of 5	N/A	\$0
Distribution Main	9631	P-9017	COV	Dawley St	6	Ductile Iron	2	12	0.71 out of 5	N/A	\$0
Distribution Main	9633	P-9017	COV	Dawley St	8	Ductile Iron	29	12	0 out of 5	N/A	\$0
Distribution Main	1594	P-7767	COV	Dawley St.	8	Ductile Iron	23	66	0.43 out of 5	\$442	10,292
Distribution Main	2258	P-7767	COV	Dawley St.	6	Asbestos Cement	521	66	2 out of 5	\$442	230,132
Distribution Main	199	P-7283	COV	Dawn Ln.	6	Asbestos Cement	403	57	1.85 out of 5	\$442	177,945
Distribution Main	11028	P-7283	COV	Dawn Ln.	6	Asbestos Cement	31	57	1.85 out of 5	\$442	13,713
Distribution Main	40	P-7472	COV	Deborah Ave	6	Asbestos Cement	47	57	1.85 out of 5	\$442	20,769
Distribution Main	2765	P-7469	COV	Deborah Ave.	6	Asbestos Cement	310	57	1.85 out of 5	\$442	137,149
Distribution Main	2766	P-7469	COV	Deborah Ave.	6	Asbestos Cement	268	57	1.85 out of 5	\$442	118,576
Distribution Main	7873	P-7310	COV	Deer Run Rd.	6	Asbestos Cement	1,038	35	1.71 out of 5	\$442	458,637
Distribution Main	7874	P-7310	COV	Deer Run Rd.	6	Asbestos Cement	22	35	1.71 out of 5	\$442	9,840
Distribution Main	7880	P-7310	COV	Deer Run Rd.	6	Asbestos Cement	35	35	1.71 out of 5	\$442	15,509
Distribution Main	11977	P-7310	COV	Deer Run Rd.	6	Asbestos Cement	36	35	1.71 out of 5	\$442	16,045
Distribution Main	2269	P-7761	COV	Deerfield Rd.	6	Asbestos Cement	6	55	1.85 out of 5	\$442	2,570
Distribution Main	2273	P-7761	COV	Deerfield Rd.	6	Asbestos Cement	12	55	1.85 out of 5	\$442	5,226
Distribution Main	3677	P-7761	COV	Deerfield Rd.	6	Asbestos Cement	83	55	1.85 out of 5	\$442	36,802
Distribution Main	3678	P-7761	COV	Deerfield Rd.	6	Asbestos Cement	568	55	1.85 out of 5	\$442	250,849
Distribution Main	3816	P-7760	COV	Deerfield Rd.	8	Asbestos Cement	158	UNK	0.85 out of 5	\$442	69,627
Distribution Main	10364	P-7760	COV	Deerfield Rd.	8	Ductile Iron	62	19	0 out of 5	N/A	\$0
Distribution Main	10365	P-7760	COV	Deerfield Rd.	8	Ductile Iron	7	19	0 out of 5	N/A	\$0
Distribution Main	1859	P-7546	COV	Dell St.	6	Asbestos Cement	325	69	2 out of 5	\$442	143,617
Distribution Main	1860	P-7546	COV	Dell St.	6	Asbestos Cement	6	69	2 out of 5	\$442	2,814
Distribution Main	9219	P-8835	COV	Dennis St	8	Ductile Iron	213	8	0 out of 5	N/A	\$0
Distribution Main	2844	P-7811	COV	Dexter St.	6	Asbestos Cement	499	69	2 out of 5	\$442	220,726
Distribution Main	7871	P-7205	COV	Diane Dr.	8	Asbestos Cement	40	40	1 out of 5	\$442	17,862
Distribution Main	7950	P-7206	COV	Diane Dr.	8	Asbestos Cement	595	40	1 out of 5	\$442	262,887
Distribution Main	7951	P-7206	COV	Diane Dr.	8	Asbestos Cement	363	40	1 out of 5	\$442	160,629

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	314	P-9052	COV	Dion Ave	1	Copper	130	70	2.43 out of 5	\$442	57,421
Distribution Main	953	P-8007	COV	Dion Ave.	6	Asbestos Cement	241	70	2 out of 5	\$442	106,312
Distribution Main	9635	P-9050	COV	Dion Ave.	6	Asbestos Cement	88	70	2 out of 5	\$442	39,023
Distribution Main	9636	P-9049	COV	Dion Ave.	1	Copper	113	70	2.43 out of 5	\$442	50,034
Distribution Main	9805	P-8990	COV	Dixie Rd	8	Ductile Iron	103	12	0 out of 5	N/A	\$0
Distribution Main	9806	P-8991	COV	Dixie Rd	6	Ductile Iron	13	12	0.71 out of 5	N/A	\$0
Distribution Main	1651	P-7658	COV	Dixie Rd.	6	Ductile Iron	10	25	0.85 out of 5	N/A	\$0
Distribution Main	1652	P-7658	COV	Dixie Rd.	6	Ductile Iron	561	25	0.85 out of 5	N/A	\$0
Distribution Main	9630	P-9016	COV	Dodd St	8	Ductile Iron	327	12	0 out of 5	N/A	\$0
Distribution Main	7723	P-7019	COV	Dogwood Dr.	6	PVC	56	33	1.14 out of 5	\$442	24,781
Distribution Main	7724	P-7019	COV	Dogwood Dr.	6	PVC	570	33	1.14 out of 5	\$442	251,809
Distribution Main	7170	P-8271	COV	Donna'S Way	8	Ductile Iron	323	30	0.14 out of 5	\$442	142,808
Distribution Main	7171	P-8271	COV	Donna'S Way	8	Ductile Iron	111	30	0.14 out of 5	\$442	49,271
Distribution Main	2729	P-7989	COV	Doolittle St.	6	Asbestos Cement	532	61	2 out of 5	\$442	235,059
Distribution Main	2731	P-7981	COV	Doolittle St.	6	Asbestos Cement	466	61	2 out of 5	\$442	205,918
Distribution Main	2732	P-8001	COV	Doolittle St.	6	Asbestos Cement	435	61	2.71 out of 5	\$442	192,279
Distribution Main	6313	P-7143	COV	Doric Ct.	6	Asbestos Cement	20	39	1.71 out of 5	\$442	8,680
Distribution Main	7277	P-7143	COV	Doric Ct.	6	Asbestos Cement	259	39	1.71 out of 5	\$442	114,610
Distribution Main	1567	P-8052	COV	Doris St.	6	Asbestos Cement	311	56	1.85 out of 5	\$442	137,542
Distribution Main	8581	P-9048	COV	Douglas Ct	8	Ductile Iron	36	10	0 out of 5	N/A	\$0
Distribution Main	8582	P-9048	COV	Douglas Ct	8	Ductile Iron	233	10	0 out of 5	N/A	\$0
Distribution Main	9338	P-8393	COV	Douglas Fir Way	8	Ductile Iron	147	9	0 out of 5	N/A	\$0
Distribution Main	9339	P-8393	COV	Douglas Fir Way	8	Ductile Iron	144	9	0 out of 5	N/A	\$0
Distribution Main	1337	P-7330	COV	Driftwood Dr.	8	Asbestos Cement	1,042	48	1.14 out of 5	\$442	460,711
Distribution Main	1338	P-7330	COV	Driftwood Dr.	8	Asbestos Cement	34	48	1.14 out of 5	\$442	15,027
Distribution Main	11789	P-7330	COV	Driftwood Dr.	8	Asbestos Cement	227	48	1.14 out of 5	\$442	100,521
Distribution Main	4808	P-8276	COV	Dumont Farm Rd.	6	Ductile Iron	250	17	0.71 out of 5	N/A	\$0
Distribution Main	514	P-8380	COV	Easement	6	Asbestos Cement	171	53	1.85 out of 5	\$442	75,794
Distribution Main	1187	P-8375	COV	Easement	6	Cast Iron	310	119	2.57 out of 5	\$442	137,224
Distribution Main	1999	P-8346	COV	Easement	8	Ductile Iron	133	30	0.14 out of 5	\$442	58,705
Transmission Main	2000	P-8330	COV	Easement	12	Ductile Iron	276	30	0.14 out of 5	\$442	122,165
Transmission Main	4806	P-8329	COV	Easement	12	Ductile Iron	1,730	30	0.14 out of 5	\$442	764,571
Distribution Main	10170	P-8789	COV	Easement	8	Ductile Iron	187	24	0.14 out of 5	N/A	\$0
Distribution Main	10235	P-8812	COV	Easement	8	Ductile Iron	528	25	0.14 out of 5	N/A	\$0
Distribution Main	696	P-7741	COV	East Shore Dr	8	Ductile Iron	419	27	0.14 out of 5	\$442	185,213
Distribution Main	697	P-7741	COV	East Shore Dr	8	Ductile Iron	199	27	0.14 out of 5	\$442	87,970
Distribution Main	2293	P-7739	COV	East Shore Dr	8	Ductile Iron	382	27	0.14 out of 5	\$442	168,859
Distribution Main	9943	P-7739	COV	East Shore Dr	6	Ductile Iron	8	27	0.85 out of 5	\$442	3,721
Distribution Main	11912	P-7741	COV	East Shore Dr	8	Ductile Iron	24	27	0.14 out of 5	\$442	10,645
Distribution Main	694	P-7738	COV	East Shore Dr.	8	Asbestos Cement	272	49	1.14 out of 5	\$442	120,030
Distribution Main	695	P-7738	COV	East Shore Dr.	8	Asbestos Cement	5	49	1.14 out of 5	\$442	2,014
Distribution Main	1293	P-7719	COV	East Shore Dr.	8	Ductile Iron	435	13	0 out of 5	N/A	\$0
Distribution Main	2292	P-7737	COV	East Shore Dr.	8	Asbestos Cement	373	49	1.14 out of 5	\$442	164,675
Distribution Main	8362	P-9013	COV	East Shore Dr.	8	Ductile Iron	92	13	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	8363	P-9011	COV	East Shore Dr.	8	Ductile Iron	18	13	0 out of 5	N/A	\$0
Distribution Main	8364	P-7721	COV	East Shore Dr.	8	Ductile Iron	88	13	0 out of 5	N/A	\$0
Distribution Main	8365	P-7721	COV	East Shore Dr.	8	Ductile Iron	110	13	0 out of 5	N/A	\$0
Distribution Main	8370	P-7722	COV	East Shore Dr.	8	Ductile Iron	278	13	0 out of 5	N/A	\$0
Distribution Main	10854	P-7720	COV	East Shore Dr.	8	Ductile Iron	203	13	0 out of 5	N/A	\$0
Distribution Main	10855	P-7720	COV	East Shore Dr.	8	Ductile Iron	14	13	0 out of 5	N/A	\$0
Distribution Main	10856	P-7733	COV	East Shore Dr.	8	Ductile Iron	298	13	0 out of 5	N/A	\$0
Distribution Main	10857	P-8763	COV	East Shore Dr.	8	Ductile Iron	115	13	0 out of 5	N/A	\$0
Distribution Main	10858	P-8763	COV	East Shore Dr.	8	Ductile Iron	139	13	0 out of 5	N/A	\$0
Distribution Main	11466	P-7720	COV	East Shore Dr.	8	Ductile Iron	6	13	0 out of 5	N/A	\$0
Distribution Main	11467	P-7719	COV	East Shore Dr.	8	Ductile Iron	246	13	0 out of 5	N/A	\$0
Distribution Main	7273	P-7144	COV	Eastgate Dr.	8	Asbestos Cement	389	40	1 out of 5	\$442	172,127
Distribution Main	7274	P-7144	COV	Eastgate Dr.	8	Asbestos Cement	60	40	1 out of 5	\$442	26,720
Distribution Main	7275	P-7142	COV	Eastgate Dr.	8	Asbestos Cement	7	40	1 out of 5	\$442	3,235
Distribution Main	7276	P-7142	COV	Eastgate Dr.	8	Asbestos Cement	375	40	1 out of 5	\$442	165,900
Distribution Main	7279	P-7146	COV	Eastgate Dr.	8	Asbestos Cement	429	40	1 out of 5	\$442	189,516
Distribution Main	7974	P-7144	COV	Eastgate Dr.	8	Asbestos Cement	47	40	1 out of 5	\$442	20,934
Distribution Main	9670	P-8794	COV	Edith St	8	Ductile Iron	68	8	0 out of 5	N/A	\$0
Distribution Main	2768	P-7635	COV	Edna St.	6	Asbestos Cement	324	58	1.85 out of 5	\$442	143,125
Distribution Main	8580	P-9046	COV	Edward St	8	Ductile Iron	402	10	0 out of 5	N/A	\$0
Distribution Main	10874	P-9047	COV	Edward St	8	Ductile Iron	50	10	0 out of 5	N/A	\$0
Distribution Main	1170	P-7972	COV	Edward St.	6	Asbestos Cement	115	72	2 out of 5	\$442	50,689
Distribution Main	1214	P-9043	COV	Edward St.	2	Galvanized Iron	299	UNK	2.85 out of 5	\$442	131,967
Distribution Main	1215	P-9043	COV	Edward St.	2	Galvanized Iron	171	21	2.99 out of 5	N/A	\$0
Distribution Main	2363	P-7971	COV	Edward St.	2	Galvanized Iron	219	89	3.43 out of 5	\$442	96,800
Distribution Main	2734	P-7991	COV	Edward St.	6	Asbestos Cement	11	67	2 out of 5	\$442	4,761
Distribution Main	2735	P-7991	COV	Edward St.	6	Asbestos Cement	302	67	2 out of 5	\$442	133,602
Distribution Main	2737	P-7968	COV	Edward St.	6	Ductile Iron	166	21	0.85 out of 5	N/A	\$0
Distribution Main	9638	P-9044	COV	Edward St.	6	Asbestos Cement	77	UNK	1.56 out of 5	\$442	34,203
Distribution Main	9639	P-9044	COV	Edward St.	6	Asbestos Cement	94	UNK	1.56 out of 5	\$442	41,486
Distribution Main	9735	P-607	COV	Eileen Dr	8	Ductile Iron	228	8	0 out of 5	N/A	\$0
Distribution Main	11594	P-606	COV	Eileen Dr	8	Ductile Iron	107	8	0 out of 5	N/A	\$0
Distribution Main	576	P-7984	COV	Eisenhower St.	6	Asbestos Cement	387	48	1.85 out of 5	\$442	171,229
Distribution Main	577	P-7984	COV	Eisenhower St.	6	Asbestos Cement	39	48	1.85 out of 5	\$442	17,331
Distribution Main	2709	P-7983	COV	Eisenhower St.	6	Asbestos Cement	513	48	1.85 out of 5	\$442	226,787
Distribution Main	668	P-8110	COV	Eleanor Dr.	6	Asbestos Cement	201	59	1.85 out of 5	\$442	88,757
Distribution Main	669	P-8110	COV	Eleanor Dr.	6	Asbestos Cement	535	59	1.85 out of 5	\$442	236,637
Distribution Main	11857	P-8110	COV	Eleanor Dr.	6	Asbestos Cement	48	59	1.85 out of 5	\$442	21,401
Distribution Main	236	P-8125	COV	Elm St.	6	Cast Iron	70	119	2.57 out of 5	\$442	30,970
Distribution Main	237	P-8125	COV	Elm St.	6	Cast Iron	309	119	2.57 out of 5	\$442	136,758
Distribution Main	675	P-8112	COV	Elmonte Dr.	6	Asbestos Cement	322	59	1.85 out of 5	\$442	142,536
Distribution Main	676	P-8112	COV	Elmonte Dr.	6	Asbestos Cement	28	59	1.85 out of 5	\$442	12,368
Distribution Main	677	P-8856	COV	Elmonte Dr.	6	Asbestos Cement	113	59	1.85 out of 5	\$442	49,776
Distribution Main	2108	P-8111	COV	Elmonte Dr.	6	Asbestos Cement	247	59	1.85 out of 5	\$442	109,150

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	142	P-7928	COV	Elmwood Ct.	8	PVC	147	39	0.43 out of 5	\$442	64,964
Distribution Main	2465	P-7928	COV	Elmwood Ct.	8	PVC	16	39	0.43 out of 5	\$442	7,173
Transmission Main	8343	P-7731	COV	Elton St	12	Asbestos Cement	165	66	1.29 out of 5	\$442	72,780
Distribution Main	8333	P-7728	COV	Elton St.	8	Ductile Iron	46	17	0 out of 5	N/A	\$0
Distribution Main	8334	P-7728	COV	Elton St.	8	Ductile Iron	170	17	0 out of 5	N/A	\$0
Distribution Main	8355	P-7723	COV	Elton St.	8	Ductile Iron	240	13	0 out of 5	N/A	\$0
Distribution Main	8366	P-7723	COV	Elton St.	8	Ductile Iron	260	13	0 out of 5	N/A	\$0
Distribution Main	8367	P-7728	COV	Elton St.	8	Ductile Iron	19	17	0 out of 5	N/A	\$0
Distribution Main	9558	P-9009	COV	Elton St.	8	Ductile Iron	24	19	0 out of 5	N/A	\$0
Distribution Main	11465	P-7728	COV	Elton St.	8	Ductile Iron	8	13	0 out of 5	N/A	\$0
Distribution Main	2270	P-7762	COV	Englewood Rd.	6	Asbestos Cement	325	55	1.85 out of 5	\$442	143,869
Distribution Main	3817		COV	Englewood Rd.	6	Asbestos Cement	83	55	1.85 out of 5	\$442	36,630
Distribution Main	9701	P-9019	COV	Englewood Rd.	8	Ductile Iron	135	11	0 out of 5	N/A	\$0
Distribution Main	9702	P-9020	COV	Englewood Rd.	6	Ductile Iron	5	11	0.71 out of 5	N/A	\$0
Distribution Main	12108	P-9019	COV	Englewood Rd.	8	Ductile Iron	21	11	0 out of 5	N/A	\$0
Distribution Main	814	P-7933	COV	Evergreen Ct.	8	Ductile Iron	609	21	0.14 out of 5	N/A	\$0
Distribution Main	175	P-7974	COV	Fairview Ave.	6	Cast Iron	23	132	2.57 out of 5	\$442	10,318
Distribution Main	176	P-7974	COV	Fairview Ave.	6	Cast Iron	122	132	2.57 out of 5	\$442	53,813
Transmission Main	210	P-8701	COV	Fairview Ave.	16	Asbestos Cement	970	75	1.29 out of 5	\$442	428,816
Transmission Main	211	P-8701	COV	Fairview Ave.	16	Asbestos Cement	286	75	1.29 out of 5	\$442	126,632
Transmission Main	212	P-1258	COV	Fairview Ave.	12	Cast Iron	136	124	1.86 out of 5	\$442	60,116
Transmission Main	409	P-7977	COV	Fairview Ave.	16	Asbestos Cement	119	75	1.29 out of 5	\$442	52,630
Transmission Main	410	P-7977	COV	Fairview Ave.	16	Asbestos Cement	588	75	1.29 out of 5	\$442	259,955
Distribution Main	411	P-7975	COV	Fairview Ave.	6	Cast Iron	350	132	2.57 out of 5	\$442	154,873
Distribution Main	452	P-7959	COV	Fairview Ave.	6	Cast Iron	579	132	2.57 out of 5	\$442	255,737
Distribution Main	453	P-7959	COV	Fairview Ave.	6	Cast Iron	212	132	2.57 out of 5	\$442	93,625
Transmission Main	1285	P-7977	COV	Fairview Ave.	16	Asbestos Cement	150	75	1.29 out of 5	\$442	66,448
Distribution Main	1289	P-7959	COV	Fairview Ave.	6	Cast Iron	32	132	2.57 out of 5	\$442	13,958
Distribution Main	1507		COV	Fairview Ave.	6	Cast Iron	663	132	2.57 out of 5	\$442	292,836
Distribution Main	1509	P-7442	COV	Fairview Ave.	6	Cast Iron	306	132	2.57 out of 5	\$442	135,388
Distribution Main	1510	P-7442	COV	Fairview Ave.	6	Cast Iron	581	132	2.57 out of 5	\$442	256,723
Distribution Main	1797		COV	Fairview Ave.	6	Cast Iron	605	134	2.57 out of 5	\$442	267,526
Transmission Main	2132	P-7977	COV	Fairview Ave.	16	Asbestos Cement	126	75	1.29 out of 5	\$442	55,776
Distribution Main	2401	P-8845	COV	Fairview Ave.	6	Cast Iron	275	132	2.57 out of 5	\$442	121,593
Transmission Main	2403	P-8057	COV	Fairview Ave.	16	Asbestos Cement	378	75	1.29 out of 5	\$442	167,233
Transmission Main	2677	P-8070	COV	Fairview Ave.	16	Asbestos Cement	99	75	1.29 out of 5	\$442	43,663
Transmission Main	2916	P-8061	COV	Fairview Ave.	16	Asbestos Cement	31	75	1.29 out of 5	\$442	13,801
Transmission Main	2917	P-8061	COV	Fairview Ave.	16	Asbestos Cement	223	75	1.29 out of 5	\$442	98,484
Transmission Main	2925	P-8059	COV	Fairview Ave.	16	Asbestos Cement	357	75	1.29 out of 5	\$442	157,892
Transmission Main	2928	P-7072	COV	Fairview Ave.	16	Asbestos Cement	582	75	1.29 out of 5	\$442	257,442
Transmission Main	2932	P-8057	COV	Fairview Ave.	16	Asbestos Cement	31	75	1.29 out of 5	\$442	13,679
Transmission Main	3020	P-8065	COV	Fairview Ave.	16	Asbestos Cement	622	75	1.29 out of 5	\$442	274,889
Transmission Main	3034	P-9039	COV	Fairview Ave.	16	Asbestos Cement	34	75	1.29 out of 5	\$442	14,880
Transmission Main	3035	P-9039	COV	Fairview Ave.	16	Asbestos Cement	702	75	1.29 out of 5	\$442	310,296

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	3036	P-7978	COV	Fairview Ave.	16	Asbestos Cement	28	75	1.29 out of 5	\$442	12,365
Transmission Main	3037		COV	Fairview Ave.	16	Unknown	5	UNK	0 out of 5	N/A	\$0
Transmission Main	3038	P-8066	COV	Fairview Ave.	16	Asbestos Cement	342	75	1.29 out of 5	\$442	151,117
Transmission Main	3478	P-7914	COV	Fairview Ave.	16	Asbestos Cement	509	75	1.29 out of 5	\$442	224,939
Distribution Main	3705		COV	Fairview Ave.	6	Cast Iron	261	132	2.57 out of 5	\$442	115,533
Distribution Main	3711	P-1210	COV	Fairview Ave.	6	Cast Iron	299	132	2.57 out of 5	\$442	132,338
Distribution Main	3712	P-1210	COV	Fairview Ave.	6	Cast Iron	684	132	2.57 out of 5	\$442	302,412
Distribution Main	3713	P-1209	COV	Fairview Ave.	6	Cast Iron	514	124	2.57 out of 5	\$442	227,276
Transmission Main	3714	P-1213	COV	Fairview Ave.	16	Asbestos Cement	26	75	1.29 out of 5	\$442	11,446
Transmission Main	3715	P-1213	COV	Fairview Ave.	16	Asbestos Cement	246	75	1.29 out of 5	\$442	108,714
Transmission Main	8272	P-7963	COV	Fairview Ave.	24	Ductile Iron	16	15	0 out of 5	N/A	\$0
Transmission Main	8273	P-7963	COV	Fairview Ave.	16	Asbestos Cement	16	75	1.29 out of 5	\$442	6,980
Distribution Main	8601	P-7975	COV	Fairview Ave.	6	Ductile Iron	343	20	0.71 out of 5	N/A	\$0
Distribution Main	8602	P-7975	COV	Fairview Ave.	6	Ductile Iron	178	20	0.71 out of 5	N/A	\$0
Transmission Main	9083	P-7977	COV	Fairview Ave.	16	Asbestos Cement	14	75	1.29 out of 5	\$442	6,107
Distribution Main	9085		COV	Fairview Ave.	6	Cast Iron	4	124	2.57 out of 5	\$442	1,948
Transmission Main	10965	P-7977	COV	Fairview Ave.	24	Ductile Iron	8	15	0 out of 5	N/A	\$0
Distribution Main	11023	P-7974	COV	Fairview Ave.	6	Cast Iron	9	132	2.57 out of 5	\$442	3,810
Distribution Main	11024	P-7974	COV	Fairview Ave.	6	Cast Iron	2	132	2.57 out of 5	\$442	766
Transmission Main	11035	P-8070	COV	Fairview Ave.	16	Asbestos Cement	14	75	1.29 out of 5	\$442	6,199
Transmission Main	11200	P-9039	COV	Fairview Ave.	16	Asbestos Cement	135	75	1.29 out of 5	\$442	59,457
Distribution Main	11225	P-1209	COV	Fairview Ave.	6	Cast Iron	6	124	2.57 out of 5	\$442	2,719
Distribution Main	11226		COV	Fairview Ave.	6	Cast Iron	14	134	2.57 out of 5	\$442	6,305
Distribution Main	11781	P-7959	COV	Fairview Ave.	6	Cast Iron	468	132	2.57 out of 5	\$442	206,739
Distribution Main	589	P-8333	COV	Fairway Dr.	8	Ductile Iron	257	30	0.14 out of 5	\$442	113,565
Distribution Main	590	P-8333	COV	Fairway Dr.	8	Ductile Iron	374	30	0.14 out of 5	\$442	165,337
Transmission Main	591	P-8324	COV	Fairway Dr.	12	Ductile Iron	264	30	0.14 out of 5	\$442	116,825
Distribution Main	592	P-8343	COV	Fairway Dr.	8	Ductile Iron	42	30	0.14 out of 5	\$442	18,745
Distribution Main	593	P-8343	COV	Fairway Dr.	8	Ductile Iron	423	30	0.14 out of 5	\$442	186,757
Transmission Main	599		COV	Fairway Dr.	12	Ductile Iron	133	30	0.14 out of 5	\$442	58,862
Distribution Main	1329	P-8332	COV	Fairway Dr.	8	Ductile Iron	738	30	0.14 out of 5	\$442	326,328
Distribution Main	1330	P-8332	COV	Fairway Dr.	8	Ductile Iron	67	30	0.14 out of 5	\$442	29,816
Distribution Main	1331	P-8332	COV	Fairway Dr.	8	Ductile Iron	250	30	0.14 out of 5	\$442	110,485
Distribution Main	1332	P-8332	COV	Fairway Dr.	8	Ductile Iron	15	30	0.14 out of 5	\$442	6,524
Transmission Main	3016	P-8328	COV	Fairway Dr.	12	Ductile Iron	466	30	0.14 out of 5	\$442	206,130
Distribution Main	3017	P-8331	COV	Fairway Dr.	8	Ductile Iron	351	30	0.14 out of 5	\$442	155,202
Distribution Main	4807	P-8333	COV	Fairway Dr.	8	Ductile Iron	54	30	0.14 out of 5	\$442	23,663
Distribution Main	5058	P-8334	COV	Fairway Dr.	8	Ductile Iron	95	30	0.14 out of 5	\$442	42,145
Distribution Main	5059	P-8334	COV	Fairway Dr.	8	Ductile Iron	26	30	0.14 out of 5	\$442	11,491
Distribution Main	5060	P-8340	COV	Fairway Dr.	8	Ductile Iron	3	30	0.14 out of 5	\$442	1,131
Distribution Main	5061	P-8340	COV	Fairway Dr.	8	Ductile Iron	81	30	0.14 out of 5	\$442	35,611
Distribution Main	5932	P-8340	COV	Fairway Dr.	8	Ductile Iron	121	30	0.14 out of 5	\$442	53,575
Distribution Main	5933	P-8337	COV	Fairway Dr.	8	Ductile Iron	241	30	0.14 out of 5	\$442	106,653
Distribution Main	5934	P-8339	COV	Fairway Dr.	8	Ductile Iron	200	30	0.14 out of 5	\$442	88,413

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	10293		COV	Fairway Dr.	12	Ductile Iron	3	30	0.14 out of 5	\$442	1,218
Distribution Main	11890	P-8343	COV	Fairway Dr.	8	Ductile Iron	349	30	0.14 out of 5	\$442	154,474
Transmission Main	182	P-7963	COV	Fariview Ave.	16	Asbestos Cement	1,276	75	1.29 out of 5	\$442	563,861
Transmission Main	2131	P-7963	COV	Fariview Ave.	16	Asbestos Cement	10	75	1.29 out of 5	\$442	4,508
Distribution Main	3011	P-8342	COV	Fariway Dr.	8	Ductile Iron	206	30	0.14 out of 5	\$442	91,205
Distribution Main	8091	P-8967	COV	Fawns Ct	8	Ductile Iron	28	22	0.14 out of 5	N/A	\$0
Distribution Main	8092	P-8967	COV	Fawns Ct	8	Ductile Iron	6	22	0.14 out of 5	N/A	\$0
Distribution Main	9769	P-616	COV	Fenland Dr	8	Ductile Iron	141	8	0 out of 5	N/A	\$0
Distribution Main	9770	P-616	COV	Fenland Dr	8	Ductile Iron	163	8	0 out of 5	N/A	\$0
Distribution Main	791	P-7540	COV	Ferncrest Avenue	6	Asbestos Cement	425	50	1.85 out of 5	\$442	187,889
Distribution Main	792	P-7540	COV	Ferncrest Avenue	6	Asbestos Cement	51	50	1.85 out of 5	\$442	22,605
Distribution Main	1478	P-8322	COV	Ferncrest St.	8	Ductile Iron	332	18	0 out of 5	N/A	\$0
Distribution Main	2817	P-8322	COV	Ferncrest St.	8	Ductile Iron	127	18	0 out of 5	N/A	\$0
Distribution Main	9510	P-7540	COV	Ferncrest St.	6	Ductile Iron	5	18	0.71 out of 5	N/A	\$0
Distribution Main	11189	P-8322	COV	Ferncrest St.	8	Ductile Iron	22	18	0 out of 5	N/A	\$0
Distribution Main	2294	P-7740	COV	Ferris Dr.	8	Ductile Iron	313	27	0.14 out of 5	\$442	138,521
Distribution Main	1597	P-1173	COV	Field Ave.	8	Ductile Iron	54	19	0 out of 5	N/A	\$0
Distribution Main	4970	P-1173	COV	Field Ave.	6	Asbestos Cement	451	72	2 out of 5	\$442	199,517
Distribution Main	4971	P-1173	COV	Field Ave.	6	Asbestos Cement	200	72	2 out of 5	\$442	88,260
Distribution Main	7759	P-7227	COV	First St.	6	Asbestos Cement	13	65	2 out of 5	\$442	5,812
Distribution Main	7760	P-7227	COV	First St.	6	Asbestos Cement	26	65	2 out of 5	\$442	11,581
Distribution Main	7763	P-7226	COV	First St.	6	Asbestos Cement	242	65	2 out of 5	\$442	107,096
Transmission Main	8753	P-7222	COV	Flat River Rd	16	Ductile Iron	51	8	0 out of 5	N/A	\$0
Transmission Main	8754	P-7222	COV	Flat River Rd	16	Ductile Iron	483	8	0 out of 5	N/A	\$0
Transmission Main	8755	P-7193	COV	Flat River Rd	16	Ductile Iron	103	8	0 out of 5	N/A	\$0
Transmission Main	8756	P-7193	COV	Flat River Rd	16	Ductile Iron	806	8	0 out of 5	N/A	\$0
Transmission Main	8765	P-7185	COV	Flat River Rd	20	Ductile Iron	680	8	0 out of 5	N/A	\$0
Transmission Main	8777	P-7193	COV	Flat River Rd	20	Ductile Iron	290	8	0 out of 5	N/A	\$0
Transmission Main	8778	P-7193	COV	Flat River Rd	20	Ductile Iron	142	8	0 out of 5	N/A	\$0
Distribution Main	8802		COV	Flat River Rd	6	Ductile Iron	3	8	0.71 out of 5	N/A	\$0
Transmission Main	10431	P-7193	COV	Flat River Rd	20	Ductile Iron	115	8	0 out of 5	N/A	\$0
Transmission Main	10860	P-7193	COV	Flat River Rd	16	Ductile Iron	622	8	0 out of 5	N/A	\$0
Transmission Main	10861	P-7183	COV	Flat River Rd	20	Ductile Iron	38	8	0 out of 5	N/A	\$0
Transmission Main	10862	P-7183	COV	Flat River Rd	20	Ductile Iron	317	8	0 out of 5	N/A	\$0
Transmission Main	11499	P-7222	COV	Flat River Rd	16	Ductile Iron	287	8	0 out of 5	N/A	\$0
Transmission Main	11500	P-7222	COV	Flat River Rd	16	Ductile Iron	109	8	0 out of 5	N/A	\$0
Transmission Main	11501	P-7193	COV	Flat River Rd	16	Ductile Iron	47	8	0 out of 5	N/A	\$0
Transmission Main	11506	P-7183	COV	Flat River Rd	20	Ductile Iron	44	8	0 out of 5	N/A	\$0
Transmission Main	11507	P-7193	COV	Flat River Rd	20	Ductile Iron	42	8	0 out of 5	N/A	\$0
Transmission Main	11510	P-7193	COV	Flat River Rd	20	Ductile Iron	15	8	0 out of 5	N/A	\$0
Transmission Main	11511	P-7193	COV	Flat River Rd	20	Ductile Iron	12	8	0 out of 5	N/A	\$0
Transmission Main	11974	P-7193	COV	Flat River Rd	16	Ductile Iron	77	8	0 out of 5	N/A	\$0
Transmission Main	12097	P-7222	COV	Flat River Rd	16	Ductile Iron	25	8	0 out of 5	N/A	\$0
Transmission Main	12098	P-7222	COV	Flat River Rd	16	Ductile Iron	24	8	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4916	P-8344	COV	Flat River Rd.	8	Ductile Iron	109	0	0 out of 5	N/A	\$0
Distribution Main	4917	P-8344	COV	Flat River Rd.	8	Ductile Iron	544	0	0 out of 5	N/A	\$0
Distribution Main	5055	P-7255	COV	Flat River Rd.	8	Ductile Iron	20	0	0 out of 5	N/A	\$0
Distribution Main	5944	P-8345	COV	Flat River Rd.	8	Ductile Iron	16	0	0 out of 5	N/A	\$0
Distribution Main	7160	P-7229	COV	Flat River Rd.	8	Asbestos Cement	9	69	1.29 out of 5	\$442	3,864
Distribution Main	7161	P-7229	COV	Flat River Rd.	8	Ductile Iron	759	0	0 out of 5	N/A	\$0
Distribution Main	7756		COV	Flat River Rd.	8	Asbestos Cement	518	UNK	0.85 out of 5	\$442	229,155
Distribution Main	7757		COV	Flat River Rd.	8	Asbestos Cement	52	UNK	0.85 out of 5	\$442	22,773
Distribution Main	7920	P-8345	COV	Flat River Rd.	8	Ductile Iron	16	0	0 out of 5	N/A	\$0
Distribution Main	7921	P-7249	COV	Flat River Rd.	8	Ductile Iron	9	0	0 out of 5	N/A	\$0
Distribution Main	7922	P-7249	COV	Flat River Rd.	8	Ductile Iron	482	0	0 out of 5	N/A	\$0
Distribution Main	11274	P-8344	COV	Flat River Rd.	8	Ductile Iron	62	0	0 out of 5	N/A	\$0
Distribution Main	1087	P-7693	COV	Florida Ave.	6	Asbestos Cement	30	65	2 out of 5	\$442	13,132
Distribution Main	1088	P-7693	COV	Florida Ave.	6	Asbestos Cement	507	65	2 out of 5	\$442	224,124
Distribution Main	2585	P-8998	COV	Florida Ave.	1	Copper	254	65	2.43 out of 5	\$442	112,328
Distribution Main	9220	P-8078	COV	Fones St	8	Ductile Iron	84	8	0 out of 5	N/A	\$0
Distribution Main	9221	P-8078	COV	Fones St	8	Ductile Iron	208	8	0 out of 5	N/A	\$0
Distribution Main	11555	P-8834	COV	Fones St	8	Ductile Iron	85	8	0 out of 5	N/A	\$0
Distribution Main	1459	P-8308	COV	Forest St.	6	Asbestos Cement	460	65	2 out of 5	\$442	203,121
Distribution Main	1758	P-9007	COV	Forestdale Dr	6	Asbestos Cement	251	51	1.85 out of 5	\$442	111,025
Distribution Main	2623	P-7569	COV	Forestdale St.	6	Asbestos Cement	473	51	1.85 out of 5	\$442	209,214
Distribution Main	2624	P-7569	COV	Forestdale St.	6	Asbestos Cement	19	51	1.85 out of 5	\$442	8,200
Distribution Main	9076	P-8974	COV	Forge Rd	8	Ductile Iron	321	13	0 out of 5	N/A	\$0
Distribution Main	2462	P-7900	COV	Forsythia Ct.	6	Asbestos Cement	279	39	1.71 out of 5	\$442	123,450
Distribution Main	2997		COV	Foster Dr.	6	Asbestos Cement	220	72	2 out of 5	\$442	97,403
Distribution Main	2998		COV	Foster Dr.	6	Asbestos Cement	7	72	2 out of 5	\$442	3,248
Distribution Main	3003	P-7278	COV	Foster Dr.	6	Asbestos Cement	389	72	2 out of 5	\$442	171,761
Distribution Main	7944	P-7244	COV	Frances Ct.	6	Asbestos Cement	196	56	1.85 out of 5	\$442	86,782
Distribution Main	10799	P-7267	COV	Francis St.	8	Ductile Iron	201	0	0 out of 5	N/A	\$0
Distribution Main	10803	P-7266	COV	Francis St.	8	Ductile Iron	396	0	0 out of 5	N/A	\$0
Distribution Main	2704		COV	Gadoury St.	6	Asbestos Cement	9	70	2 out of 5	\$442	3,923
Distribution Main	2710	P-7980	COV	Gadoury St.	6	Asbestos Cement	403	70	2 out of 5	\$442	178,097
Distribution Main	11034	P-7980	COV	Gadoury St.	6	Asbestos Cement	19	70	2 out of 5	\$442	8,362
Distribution Main	7924	P-7250	COV	Gail Ct.	8	Asbestos Cement	242	50	1.14 out of 5	\$442	107,114
Distribution Main	7925	P-7250	COV	Gail Ct.	8	Asbestos Cement	402	50	1.14 out of 5	\$442	177,821
Distribution Main	8458		COV	Garden St.	8	Ductile Iron	20	10	0 out of 5	N/A	\$0
Distribution Main	6449	P-7174	COV	Garfield Dr.	8	Asbestos Cement	19	40	1 out of 5	\$442	8,231
Distribution Main	6454	P-7174	COV	Garfield Dr.	8	Asbestos Cement	358	40	1 out of 5	\$442	158,309
Distribution Main	6455	P-7174	COV	Garfield Dr.	8	Asbestos Cement	545	40	1 out of 5	\$442	240,938
Distribution Main	1036	P-8177	COV	Gay St.	8	PVC	20	33	0.43 out of 5	\$442	8,965
Distribution Main	1037	P-8177	COV	Gay St.	8	PVC	299	33	0.43 out of 5	\$442	132,098
Distribution Main	1429	P-8177	COV	Gay St.	8	PVC	3	33	0.43 out of 5	\$442	1,514
Distribution Main	2718	P-8005	COV	Gerald Ave.	6	Asbestos Cement	498	70	2 out of 5	\$442	220,253
Distribution Main	10201		COV	Gervais St	6	Ductile Iron	8	15	0.71 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	8184	P-7363	COV	Gervais St.	12	Ductile Iron	384	15	0 out of 5	N/A	\$0
Transmission Main	8185	P-7363	COV	Gervais St.	12	Ductile Iron	320	15	0 out of 5	N/A	\$0
Distribution Main	8191	P-8378	COV	Gervais St.	8	Asbestos Cement	721	57	1.14 out of 5	\$442	318,875
Transmission Main	8214	P-8497	COV	Gervais St.	20	Ductile Iron	619	15	0 out of 5	N/A	\$0
Transmission Main	8215	P-8497	COV	Gervais St.	20	Ductile Iron	366	15	0 out of 5	N/A	\$0
Distribution Main	8231	P-8379	COV	Gervais St.	8	Asbestos Cement	23	57	1.14 out of 5	\$442	10,250
Distribution Main	8232	P-8379	COV	Gervais St.	8	Asbestos Cement	417	57	1.14 out of 5	\$442	184,531
Distribution Main	8233	P-8379	COV	Gervais St.	8	Asbestos Cement	143	57	1.14 out of 5	\$442	63,169
Distribution Main	8235	P-8379	COV	Gervais St.	8	Asbestos Cement	619	57	1.14 out of 5	\$442	273,714
Transmission Main	8257	P-8497	COV	Gervais St.	20	Ductile Iron	397	15	0 out of 5	N/A	\$0
Transmission Main	8258	P-8497	COV	Gervais St.	20	Ductile Iron	724	15	0 out of 5	N/A	\$0
Transmission Main	8259	P-7363	COV	Gervais St.	12	Ductile Iron	397	15	0 out of 5	N/A	\$0
Transmission Main	8260	P-7363	COV	Gervais St.	12	Ductile Iron	768	15	0 out of 5	N/A	\$0
Transmission Main	8261	P-8497	COV	Gervais St.	20	Ductile Iron	275	15	0 out of 5	N/A	\$0
Transmission Main	8262	P-7395	COV	Gervais St.	12	Ductile Iron	102	15	0 out of 5	N/A	\$0
Transmission Main	8263	P-7395	COV	Gervais St.	12	Ductile Iron	155	15	0 out of 5	N/A	\$0
Transmission Main	10061	P-8379	COV	Gervais St.	24	Ductile Iron	82	15	0 out of 5	N/A	\$0
Transmission Main	10062	P-8497	COV	Gervais St.	20	Ductile Iron	407	15	0 out of 5	N/A	\$0
Transmission Main	10077	P-7390	COV	Gervais St.	12	Ductile Iron	152	15	0 out of 5	N/A	\$0
Transmission Main	10079	P-7391	COV	Gervais St.	12	Ductile Iron	328	15	0 out of 5	N/A	\$0
Transmission Main	10111	P-8497	COV	Gervais St.	20	Ductile Iron	36	15	0 out of 5	N/A	\$0
Distribution Main	10894	P-8378	COV	Gervais St.	8	Asbestos Cement	95	57	1.14 out of 5	\$442	41,901
Transmission Main	11443	P-7363	COV	Gervais St.	12	Ductile Iron	16	15	0 out of 5	N/A	\$0
Transmission Main	11455	P-7395	COV	Gervais St.	12	Ductile Iron	19	15	0 out of 5	N/A	\$0
Transmission Main	12092	P-7363	COV	Gervais St.	12	Ductile Iron	218	15	0 out of 5	N/A	\$0
Transmission Main	12093	P-7363	COV	Gervais St.	12	Ductile Iron	47	15	0 out of 5	N/A	\$0
Distribution Main	5912	P-7110	COV	Giblin Ln.	8	Ductile Iron	328	29	0.14 out of 5	\$442	145,078
Distribution Main	5914	P-7111	COV	Giblin Ln.	8	Ductile Iron	514	29	0.14 out of 5	\$442	227,223
Distribution Main	5915	P-7111	COV	Giblin Ln.	8	Ductile Iron	407	29	0.14 out of 5	\$442	179,997
Distribution Main	2267	P-7752	COV	Gilles St.	8	Ductile Iron	452	19	0 out of 5	N/A	\$0
Distribution Main	10168	P-8787	COV	Ginger Tr	8	Ductile Iron	279	5	0 out of 5	N/A	\$0
Distribution Main	10169	P-8787	COV	Ginger Tr	8	Ductile Iron	456	5	0 out of 5	N/A	\$0
Distribution Main	10171	P-8788	COV	Ginger Tr	8	Ductile Iron	300	5	0 out of 5	N/A	\$0
Distribution Main	10172	P-8790	COV	Ginger Tr	8	Ductile Iron	212	5	0 out of 5	N/A	\$0
Distribution Main	11030	P-8790	COV	Ginger Tr	8	Ductile Iron	40	5	0 out of 5	N/A	\$0
Distribution Main	11792	P-8788	COV	Ginger Tr	8	Ductile Iron	36	5	0 out of 5	N/A	\$0
Distribution Main	1251	P-7353	COV	Ginger Tr.	8	Ductile Iron	178	21	0.14 out of 5	N/A	\$0
Distribution Main	1253	P-7335	COV	Ginger Tr.	8	Ductile Iron	5	21	0.14 out of 5	N/A	\$0
Distribution Main	1255	P-7355	COV	Ginger Tr.	8	Ductile Iron	360	21	0.14 out of 5	N/A	\$0
Distribution Main	1257	P-7335	COV	Ginger Tr.	8	Ductile Iron	3	21	0.14 out of 5	N/A	\$0
Distribution Main	1258	P-7353	COV	Ginger Tr.	8	Ductile Iron	5	21	0.14 out of 5	N/A	\$0
Distribution Main	1334	P-7335	COV	Ginger Tr.	8	Ductile Iron	439	21	0.14 out of 5	N/A	\$0
Distribution Main	1335	P-7335	COV	Ginger Tr.	8	Ductile Iron	75	21	0.14 out of 5	N/A	\$0
Distribution Main	1336	P-7335	COV	Ginger Tr.	8	Ductile Iron	250	21	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3049	P-7337	COV	Ginger Tr.	8	Ductile Iron	407	21	0.14 out of 5	N/A	\$0
Distribution Main	3050	P-7337	COV	Ginger Tr.	8	Ductile Iron	43	21	0.14 out of 5	N/A	\$0
Distribution Main	3051	P-7337	COV	Ginger Tr.	8	Ductile Iron	245	21	0.14 out of 5	N/A	\$0
Distribution Main	3052	P-7337	COV	Ginger Tr.	8	Ductile Iron	106	21	0.14 out of 5	N/A	\$0
Distribution Main	3053	P-7337	COV	Ginger Tr.	8	Ductile Iron	484	21	0.14 out of 5	N/A	\$0
Distribution Main	4415	P-7339	COV	Ginger Tr.	8	Ductile Iron	411	21	0.14 out of 5	N/A	\$0
Distribution Main	4417	P-7339	COV	Ginger Tr.	8	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Distribution Main	4418	P-7337	COV	Ginger Tr.	8	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Distribution Main	4420	P-8888	COV	Ginger Tr.	8	Ductile Iron	510	21	0.14 out of 5	N/A	\$0
Distribution Main	4421	P-8888	COV	Ginger Tr.	8	Ductile Iron	3	21	0.14 out of 5	N/A	\$0
Distribution Main	4422	P-7339	COV	Ginger Tr.	8	Ductile Iron	103	21	0.14 out of 5	N/A	\$0
Distribution Main	7859	P-7341	COV	Ginger Tr.	8	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Distribution Main	7860	P-7341	COV	Ginger Tr.	8	Ductile Iron	373	21	0.14 out of 5	N/A	\$0
Distribution Main	10110	P-7337	COV	Ginger Tr.	8	Ductile Iron	17	21	0.14 out of 5	N/A	\$0
Distribution Main	12179		COV	Glacier Way	8	Ductile Iron	414	17	0 out of 5	N/A	\$0
Distribution Main	12180		COV	Glacier Way	8	Ductile Iron	178	29	0.14 out of 5	\$442	78,619
Distribution Main	2781	P-7657	COV	Glen Ave.	8	Ductile Iron	196	18	0 out of 5	N/A	\$0
Distribution Main	1925	P-7912	COV	Glenview Ct.	8	Asbestos Cement	526	43	1.14 out of 5	\$442	232,506
Distribution Main	1926	P-7912	COV	Glenview Ct.	8	Asbestos Cement	46	43	1.14 out of 5	\$442	20,326
Distribution Main	587	P-7326	COV	Glenwood Dr.	8	Asbestos Cement	455	43	1.14 out of 5	\$442	201,037
Distribution Main	1250	P-7328	COV	Glenwood Dr.	8	Asbestos Cement	134	43	1.14 out of 5	\$442	59,027
Distribution Main	1259	P-8787	COV	Glenwood Dr.	8	Asbestos Cement	138	43	1.14 out of 5	\$442	60,998
Distribution Main	1340	P-7328	COV	Glenwood Dr.	8	Asbestos Cement	93	43	1.14 out of 5	\$442	41,286
Distribution Main	1341	P-7328	COV	Glenwood Dr.	8	Asbestos Cement	450	43	1.14 out of 5	\$442	199,083
Distribution Main	2118	P-7326	COV	Glenwood Dr.	8	Asbestos Cement	11	43	1.14 out of 5	\$442	4,915
Distribution Main	3143	P-8179	COV	Grafton St.	8	PVC	390	28	0.43 out of 5	\$442	172,592
Distribution Main	1033	P-8181	COV	Grand View St.	8	Ductile Iron	329	28	0.14 out of 5	\$442	145,569
Distribution Main	1426	P-8999	COV	Grand View St.	8	Ductile Iron	15	28	0.14 out of 5	\$442	6,733
Distribution Main	1427	P-8999	COV	Grand View St.	8	Ductile Iron	94	28	0.14 out of 5	\$442	41,694
Distribution Main	3138	P-8315	COV	Grand View St.	8	Ductile Iron	237	28	0.14 out of 5	\$442	104,598
Distribution Main	3140	P-8181	COV	Grand View St.	8	Ductile Iron	3	28	0.14 out of 5	\$442	1,379
Distribution Main	1089		COV	Grant Dr.	6	Asbestos Cement	16	57	1.85 out of 5	\$442	7,086
Distribution Main	1460	P-7691	COV	Grant Dr.	6	Asbestos Cement	716	57	1.85 out of 5	\$442	316,409
Distribution Main	2610	P-7674	COV	Grant Dr.	6	Asbestos Cement	294	57	1.85 out of 5	\$442	130,106
Distribution Main	2611	P-7675	COV	Grant Dr.	6	Asbestos Cement	459	57	1.85 out of 5	\$442	202,901
Distribution Main	834	P-7833	COV	Greene St.	2	Galvanized Iron	25	73	3.28 out of 5	\$442	10,888
Distribution Main	3151	P-7833	COV	Greene St.	2	Galvanized Iron	455	73	3.28 out of 5	\$442	201,272
Distribution Main	6452	P-7178	COV	Hancock Dr.	8	Asbestos Cement	116	42	1.14 out of 5	\$442	51,278
Distribution Main	6453	P-7178	COV	Hancock Dr.	8	Asbestos Cement	735	42	1.14 out of 5	\$442	324,956
Distribution Main	11338	P-7178	COV	Hancock Dr.	8	Asbestos Cement	7	42	1.14 out of 5	\$442	3,148
Distribution Main	11866	P-7178	COV	Hancock Dr.	8	Asbestos Cement	401	42	1.14 out of 5	\$442	177,252
Distribution Main	790	P-8935	COV	Harding Street	1	Copper	367	UNK	1.99 out of 5	\$442	162,022
Transmission Main	5292	P-7001	COV	Harkney Hill Rd.	12	Ductile Iron	10	30	0.14 out of 5	\$442	4,293
Transmission Main	7261	P-7001	COV	Harkney Hill Rd.	12	Ductile Iron	504	30	0.14 out of 5	\$442	222,744

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	7262	P-7001	COV	Harkney Hill Rd.	12	Ductile Iron	400	30	0.14 out of 5	\$442	176,935
Transmission Main	7263	P-7002	COV	Harkney Hill Rd.	12	Ductile Iron	29	30	0.14 out of 5	\$442	12,768
Transmission Main	7787	P-7002	COV	Harkney Hill Rd.	12	Ductile Iron	7	30	0.14 out of 5	\$442	2,930
Transmission Main	7801	P-7001	COV	Harkney Hill Rd.	12	Ductile Iron	7	30	0.14 out of 5	\$442	3,101
Transmission Main	11802	P-7001	COV	Harkney Hill Rd.	12	Ductile Iron	436	30	0.14 out of 5	\$442	192,566
Distribution Main	9787	P-629	COV	Harley St	8	Ductile Iron	123	8	0 out of 5	N/A	\$0
Distribution Main	714	P-7706	COV	Harrington Rd.	6	Asbestos Cement	13	54	1.85 out of 5	\$442	5,722
Distribution Main	2587	P-7701	COV	Harrington Rd.	6	Asbestos Cement	304	54	1.85 out of 5	\$442	134,200
Distribution Main	2588	P-7701	COV	Harrington Rd.	6	Asbestos Cement	14	54	1.85 out of 5	\$442	6,364
Distribution Main	2589	P-7706	COV	Harrington Rd.	6	Asbestos Cement	352	54	1.85 out of 5	\$442	155,648
Distribution Main	9658	P-7706	COV	Harrington Rd.	6	Asbestos Cement	346	54	1.85 out of 5	\$442	152,986
Transmission Main	8383	P-8752	COV	Harris St	12	Ductile Iron	156	10	0 out of 5	N/A	\$0
Transmission Main	8444		COV	Harris St	12	Ductile Iron	16	10	0 out of 5	N/A	\$0
Distribution Main	232		COV	Harris St.	6	Unknown	2	UNK	0.71 out of 5	\$442	802
Distribution Main	9738	P-608	COV	Harvest Dr	8	Ductile Iron	565	8	0 out of 5	N/A	\$0
Distribution Main	2690	P-7947	COV	Hawthorne Rd.	8	Asbestos Cement	522	55	1.14 out of 5	\$442	230,726
Distribution Main	2691	P-7946	COV	Hawthorne Rd.	8	Asbestos Cement	420	55	1.14 out of 5	\$442	185,497
Distribution Main	1861	P-7602	COV	Haywood Rd.	8	Asbestos Cement	255	60	1.14 out of 5	\$442	112,490
Distribution Main	2468	P-8227	COV	Haywood Rd.	8	Ductile Iron	195	20	0 out of 5	N/A	\$0
Distribution Main	2469	P-8227	COV	Haywood Rd.	8	Ductile Iron	366	20	0 out of 5	N/A	\$0
Distribution Main	9951	P-8227	COV	Haywood Rd.	8	Asbestos Cement	11	60	1.14 out of 5	\$442	4,938
Distribution Main	566	P-7966	COV	Hazard St.	6	Cast Iron	434	79	2.28 out of 5	\$442	191,754
Distribution Main	567	P-7966	COV	Hazard St.	6	Cast Iron	14	79	2.28 out of 5	\$442	6,227
Distribution Main	1689	P-9041	COV	Hazard St.	6	Cast Iron	168	79	2.28 out of 5	\$442	74,307
Distribution Main	1690	P-9041	COV	Hazard St.	6	Cast Iron	5	79	2.28 out of 5	\$442	2,135
Distribution Main	2694	P-9041	COV	Hazard St.	6	Cast Iron	145	79	2.28 out of 5	\$442	64,085
Distribution Main	2740	P-8282	COV	Hazard St.	6	Cast Iron	168	79	2.28 out of 5	\$442	74,118
Distribution Main	2741	P-8283	COV	Hazard St.	6	Cast Iron	449	79	2.28 out of 5	\$442	198,662
Distribution Main	2742	P-7976	COV	Hazard St.	6	Cast Iron	14	79	2.28 out of 5	\$442	6,009
Distribution Main	2743	P-7976	COV	Hazard St.	6	Cast Iron	226	79	2.28 out of 5	\$442	99,805
Distribution Main	9084	P-7976	COV	Hazard St.	6	Cast Iron	15	79	2.28 out of 5	\$442	6,728
Distribution Main	1763	P-8300	COV	Hazel St.	2	Copper	275	78	2.43 out of 5	\$442	121,609
Distribution Main	1764	P-8300	COV	Hazel St.	6	Asbestos Cement	4	78	2 out of 5	\$442	1,944
Distribution Main	2778	P-8300	COV	Hazel St.	6	Asbestos Cement	22	78	2 out of 5	\$442	9,937
Distribution Main	7877	P-7305	COV	Heather Ct.	8	Asbestos Cement	242	34	1 out of 5	\$442	107,000
Transmission Main	1626	P-8266	COV	Helen Ave.	12	Ductile Iron	45	30	0.14 out of 5	\$442	19,764
Distribution Main	2360	P-8518	COV	Helen Ave.	6	Asbestos Cement	999	65	2 out of 5	\$442	441,556
Distribution Main	2361	P-7484	COV	Helen Ave.	6	Asbestos Cement	16	65	2 out of 5	\$442	7,292
Transmission Main	4414	P-7165	COV	Helen Ave.	12	Ductile Iron	933	30	0.14 out of 5	\$442	412,301
Distribution Main	6613	P-7483	COV	Helen Ave.	6	Asbestos Cement	138	65	2 out of 5	\$442	61,215
Distribution Main	6614	P-7483	COV	Helen Ave.	6	Asbestos Cement	137	65	2 out of 5	\$442	60,762
Distribution Main	6619	P-7468	COV	Helen Ave.	6	Asbestos Cement	94	65	2 out of 5	\$442	41,656
Distribution Main	6620	P-7482	COV	Helen Ave.	6	Asbestos Cement	274	65	2 out of 5	\$442	121,004
Distribution Main	6623	P-7461	COV	Helen Ave.	6	Asbestos Cement	108	65	2 out of 5	\$442	47,603

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	7188	P-7164	COV	Helen Ave.	12	Ductile Iron	645	30	0.14 out of 5	\$442	285,109
Transmission Main	7189	P-7164	COV	Helen Ave.	12	Ductile Iron	3	30	0.14 out of 5	\$442	1,326
Transmission Main	7192	P-7164	COV	Helen Ave.	12	Ductile Iron	125	30	0.14 out of 5	\$442	55,128
Distribution Main	7438	P-7457	COV	Helen Ave.	6	Asbestos Cement	383	65	2 out of 5	\$442	169,217
Distribution Main	7439	P-7457	COV	Helen Ave.	6	Asbestos Cement	469	65	2 out of 5	\$442	207,179
Transmission Main	7513	P-7164	COV	Helen Ave.	12	Ductile Iron	135	30	0.14 out of 5	\$442	59,664
Transmission Main	8134	P-8266	COV	Helen Ave.	12	Ductile Iron	21	30	0.14 out of 5	\$442	9,112
Transmission Main	8135		COV	Helen Ave.	12	Ductile Iron	15	30	0.14 out of 5	\$442	6,718
Transmission Main	8136	P-7165	COV	Helen Ave.	12	Ductile Iron	14	30	0.14 out of 5	\$442	6,281
Transmission Main	9503		COV	Helen Ave.	12	Ductile Iron	12	30	0.14 out of 5	\$442	5,218
Transmission Main	11440	P-8266	COV	Helen Ave.	12	Ductile Iron	7	30	0.14 out of 5	\$442	3,040
Transmission Main	11441	P-7165	COV	Helen Ave.	12	Ductile Iron	8	30	0.14 out of 5	\$442	3,393
Distribution Main	12173		COV	Helen Ave.	6	Asbestos Cement	157	65	2 out of 5	\$442	69,412
Distribution Main	2784	P-7655	COV	Henry Ave.	8	Ductile Iron	226	18	0 out of 5	N/A	\$0
Distribution Main	1011	P-8871	COV	Henry Court	4	Cast Iron	207	32	2.71 out of 5	\$442	91,554
Distribution Main	8081	P-9019	COV	Hibiscus Ln	8	Ductile Iron	154	11	0 out of 5	N/A	\$0
Distribution Main	8082	P-9019	COV	Hibiscus Ln	8	Ductile Iron	652	11	0 out of 5	N/A	\$0
Distribution Main	516	P-7943	COV	Hickory Rd.	6	Asbestos Cement	521	34	1.71 out of 5	\$442	230,378
Distribution Main	517	P-7943	COV	Hickory Rd.	6	Asbestos Cement	428	34	1.71 out of 5	\$442	189,057
Transmission Main	8382	P-8752	COV	Highland Ave	12	Ductile Iron	375	10	0 out of 5	N/A	\$0
Transmission Main	8384	P-8752	COV	Highland Ave	12	Ductile Iron	10	10	0 out of 5	N/A	\$0
Transmission Main	8441	P-8127	COV	Highland Ave	12	Ductile Iron	123	10	0 out of 5	N/A	\$0
Transmission Main	8442	P-8127	COV	Highland Ave	12	Ductile Iron	88	10	0 out of 5	N/A	\$0
Distribution Main	8443	P-8830	COV	Highland Ave	8	Ductile Iron	23	10	0 out of 5	N/A	\$0
Distribution Main	228	P-8125	COV	Highland Ave.	6	Cast Iron	7	25	1.99 out of 5	N/A	\$0
Distribution Main	242	P-8126	COV	Highland Ave.	6	Cast Iron	319	25	1.99 out of 5	N/A	\$0
Distribution Main	243	P-8126	COV	Highland Ave.	6	Cast Iron	212	25	1.99 out of 5	N/A	\$0
Distribution Main	11864	P-8126	COV	Highland Ave.	6	Cast Iron	265	25	1.99 out of 5	N/A	\$0
Distribution Main	594	P-7324	COV	Highwood Dr.	8	Asbestos Cement	24	55	1.14 out of 5	\$442	10,573
Distribution Main	1342	P-7332	COV	Highwood Dr.	8	Asbestos Cement	853	41	1.14 out of 5	\$442	377,012
Distribution Main	1343	P-7332	COV	Highwood Dr.	8	Asbestos Cement	625	41	1.14 out of 5	\$442	276,434
Distribution Main	2116	P-7327	COV	Highwood Dr.	8	Asbestos Cement	159	55	1.14 out of 5	\$442	70,276
Distribution Main	2117	P-7327	COV	Highwood Dr.	8	Asbestos Cement	529	55	1.14 out of 5	\$442	233,673
Distribution Main	2119	P-7324	COV	Highwood Dr.	8	Asbestos Cement	186	55	1.14 out of 5	\$442	82,369
Distribution Main	10134	P-7331	COV	Highwood Dr.	8	Asbestos Cement	495	48	1.14 out of 5	\$442	218,838
Distribution Main	11790	P-7332	COV	Highwood Dr.	8	Asbestos Cement	566	41	1.14 out of 5	\$442	250,107
Transmission Main	8857	P-8770	COV	Hill Farm Rd	12	Ductile Iron	190	13	0 out of 5	N/A	\$0
Transmission Main	8858	P-8770	COV	Hill Farm Rd	12	Ductile Iron	4	13	0 out of 5	N/A	\$0
Transmission Main	4790	P-7008	COV	Hill Farm Rd.	12	Asbestos Cement	109	37	1 out of 5	\$442	48,209
Transmission Main	4791	P-7008	COV	Hill Farm Rd.	12	Asbestos Cement	843	37	1 out of 5	\$442	372,801
Transmission Main	7586	P-7010	COV	Hill Farm Rd.	12	PVC	1,279	31	0.43 out of 5	\$442	565,429
Transmission Main	7587	P-7010	COV	Hill Farm Rd.	12	PVC	648	31	0.43 out of 5	\$442	286,430
Transmission Main	7588	P-8769	COV	Hill Farm Rd.	12	Asbestos Cement	724	37	1 out of 5	\$442	320,007
Transmission Main	7589	P-8769	COV	Hill Farm Rd.	12	Asbestos Cement	520	37	1 out of 5	\$442	229,865

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	7766	P-7003	COV	Hill Farm Rd.	12	Ductile Iron	5	30	0.14 out of 5	\$442	2,142
Transmission Main	7770	P-7003	COV	Hill Farm Rd.	12	Ductile Iron	390	30	0.14 out of 5	\$442	172,350
Transmission Main	7771	P-7003	COV	Hill Farm Rd.	12	Ductile Iron	157	30	0.14 out of 5	\$442	69,507
Transmission Main	8329	P-8523	COV	Hill Farm Rd.	12	Asbestos Cement	61	37	1 out of 5	\$442	27,123
Transmission Main	8330	P-8523	COV	Hill Farm Rd.	12	Asbestos Cement	25	37	1 out of 5	\$442	11,122
Transmission Main	8856	P-7004	COV	Hill Farm Rd.	12	Asbestos Cement	305	37	1 out of 5	\$442	134,798
Transmission Main	9432	P-8962	COV	Hill Farm Rd.	12	Asbestos Cement	15	37	1 out of 5	\$442	6,582
Transmission Main	11264	P-7008	COV	Hill Farm Rd.	12	Asbestos Cement	9	37	1 out of 5	\$442	4,104
Transmission Main	11392	P-8769	COV	Hill Farm Rd.	12	Asbestos Cement	31	37	1 out of 5	\$442	13,632
Transmission Main	11519	P-7004	COV	Hill Farm Rd.	12	Asbestos Cement	23	37	1 out of 5	\$442	9,996
Transmission Main	11800	P-7008	COV	Hill Farm Rd.	12	Asbestos Cement	664	37	1 out of 5	\$442	293,631
Transmission Main	11801	P-7010	COV	Hill Farm Rd.	12	PVC	381	31	0.43 out of 5	\$442	168,538
Transmission Main	8204	P-8099	COV	Hill St	16	Asbestos Cement	483	63	1.29 out of 5	\$442	213,638
Transmission Main	8205	P-8099	COV	Hill St	16	Asbestos Cement	475	63	1.29 out of 5	\$442	209,917
Transmission Main	8206	P-8099	COV	Hill St	16	Asbestos Cement	20	63	1.29 out of 5	\$442	9,005
Transmission Main	8207	P-6045	COV	Hill St	16	Asbestos Cement	466	63	1.29 out of 5	\$442	206,157
Transmission Main	8208	P-6045	COV	Hill St	16	Asbestos Cement	670	63	1.29 out of 5	\$442	296,017
Transmission Main	8246	P-8101	COV	Hill St	16	Asbestos Cement	31	63	1.29 out of 5	\$442	13,646
Transmission Main	8249	P-8101	COV	Hill St	16	Asbestos Cement	927	63	1.29 out of 5	\$442	409,725
Transmission Main	8250	P-8101	COV	Hill St	16	Asbestos Cement	130	63	1.29 out of 5	\$442	57,323
Transmission Main	8253	P-6045	COV	Hill St	16	Asbestos Cement	324	63	1.29 out of 5	\$442	143,297
Transmission Main	8525	P-8839	COV	Hill St	16	Ductile Iron	39	13	0 out of 5	N/A	\$0
Transmission Main	11450	P-8099	COV	Hill St	16	Asbestos Cement	4	63	1.29 out of 5	\$442	1,952
Distribution Main	152	P-8097	COV	Hill St.	8	Asbestos Cement	12	72	1.29 out of 5	\$442	5,217
Distribution Main	224		COV	Hill St.	1	Unknown	5	UNK	1.42 out of 5	\$442	2,074
Distribution Main	425	P-8081	COV	Hill St	6	Cast Iron	192	91	2.43 out of 5	\$442	84,866
Distribution Main	625	P-8105	COV	Hill St.	4	Cast Iron	61	132	3.29 out of 5	\$442	27,126
Distribution Main	626	P-8105	COV	Hill St.	4	Cast Iron	19	132	3.29 out of 5	\$442	8,611
Distribution Main	822	P-8103	COV	Hill St.	6	Cast Iron	85	132	2.57 out of 5	\$442	37,734
Distribution Main	1010	P-8103	COV	Hill St.	6	Cast Iron	105	132	2.57 out of 5	\$442	46,250
Distribution Main	1099	P-8097	COV	Hill St.	8	Asbestos Cement	139	72	1.29 out of 5	\$442	61,630
Distribution Main	1100	P-8868	COV	Hill St.	6	Cast Iron	45	132	2.57 out of 5	\$442	19,735
Distribution Main	1101	P-8868	COV	Hill St.	6	Cast Iron	101	132	2.57 out of 5	\$442	44,702
Distribution Main	1110	P-8105	COV	Hill St.	4	Cast Iron	351	132	3.29 out of 5	\$442	155,345
Transmission Main	1137	P-8091	COV	Hill St.	24	Ductile Iron	99	15	0 out of 5	N/A	\$0
Distribution Main	1171	P-8096	COV	Hill St.	8	Asbestos Cement	18	72	1.29 out of 5	\$442	7,947
Distribution Main	1180		COV	Hill St.	1	Unknown	4	UNK	1.42 out of 5	\$442	1,756
Distribution Main	1318	P-8868	COV	Hill St.	6	Cast Iron	21	132	2.57 out of 5	\$442	9,062
Distribution Main	1319	P-8861	COV	Hill St.	4	Cast Iron	220	132	3.29 out of 5	\$442	97,070
Distribution Main	1440	P-8372	COV	Hill St.	8	Ductile Iron	477	18	0 out of 5	N/A	\$0
Distribution Main	1791	P-8083	COV	Hill St.	6	Cast Iron	180	91	2.43 out of 5	\$442	79,672
Distribution Main	2106	P-7939	COV	Hill St.	8	Asbestos Cement	571	72	1.29 out of 5	\$442	252,222
Distribution Main	2107	P-7939	COV	Hill St.	8	Asbestos Cement	13	72	1.29 out of 5	\$442	5,939
Distribution Main	2113	P-8098	COV	Hill St.	6	Cast Iron	285	132	2.57 out of 5	\$442	125,974

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2114	P-8096	COV	Hill St.	8	Asbestos Cement	623	72	1.29 out of 5	\$442	275,562
Distribution Main	2745	P-8073	COV	Hill St.	8	Asbestos Cement	302	72	1.29 out of 5	\$442	133,542
Distribution Main	2746	P-8073	COV	Hill St.	8	Asbestos Cement	368	72	1.29 out of 5	\$442	162,745
Distribution Main	2747	P-7953	COV	Hill St.	8	Asbestos Cement	307	72	1.29 out of 5	\$442	135,508
Distribution Main	3722	P-8083	COV	Hill St.	8	Ductile Iron	30	18	0 out of 5	N/A	\$0
Distribution Main	8195	P-7939	COV	Hill St.	8	Ductile Iron	45	15	0 out of 5	N/A	\$0
Distribution Main	8196	P-7939	COV	Hill St.	8	Ductile Iron	20	15	0 out of 5	N/A	\$0
Transmission Main	8197	P-7935	COV	Hill St.	24	Ductile Iron	157	15	0 out of 5	N/A	\$0
Transmission Main	8198	P-7935	COV	Hill St.	24	Ductile Iron	464	15	0 out of 5	N/A	\$0
Transmission Main	8199	P-8852	COV	Hill St.	24	Ductile Iron	40	15	0 out of 5	N/A	\$0
Transmission Main	8200	P-7930	COV	Hill St.	24	Ductile Iron	114	15	0 out of 5	N/A	\$0
Transmission Main	8201	P-7930	COV	Hill St.	24	Ductile Iron	358	15	0 out of 5	N/A	\$0
Transmission Main	8238	P-7935	COV	Hill St.	24	Ductile Iron	294	15	0 out of 5	N/A	\$0
Transmission Main	8239	P-7935	COV	Hill St.	24	Ductile Iron	282	15	0 out of 5	N/A	\$0
Transmission Main	8240	P-7930	COV	Hill St.	24	Ductile Iron	226	15	0 out of 5	N/A	\$0
Transmission Main	8241	P-8090	COV	Hill St.	24	Ductile Iron	54	15	0 out of 5	N/A	\$0
Transmission Main	8242	P-8090	COV	Hill St.	24	Ductile Iron	410	15	0 out of 5	N/A	\$0
Transmission Main	8243	P-8092	COV	Hill St.	24	Ductile Iron	476	15	0 out of 5	N/A	\$0
Transmission Main	8244	P-8506	COV	Hill St.	24	Ductile Iron	484	15	0 out of 5	N/A	\$0
Transmission Main	8245	P-8506	COV	Hill St.	24	Ductile Iron	507	15	0 out of 5	N/A	\$0
Transmission Main	9688	P-8505	COV	Hill St.	24	Ductile Iron	69	15	0 out of 5	N/A	\$0
Transmission Main	11016	P-8506	COV	Hill St.	24	Ductile Iron	16	15	0 out of 5	N/A	\$0
Distribution Main	11125	P-8868	COV	Hill St.	6	Cast Iron	10	132	2.57 out of 5	\$442	4,333
Transmission Main	11446	P-7935	COV	Hill St.	24	Ductile Iron	17	15	0 out of 5	N/A	\$0
Transmission Main	11448	P-7930	COV	Hill St.	24	Ductile Iron	132	15	0 out of 5	N/A	\$0
Transmission Main	11453	P-8092	COV	Hill St.	24	Ductile Iron	18	15	0 out of 5	N/A	\$0
Distribution Main	83		COV	Hilldan Street	8	Asbestos Cement	141	UNK	0.85 out of 5	\$442	62,121
Distribution Main	9214	P-1212	COV	Hillside Ave	8	Ductile Iron	744	8	0 out of 5	N/A	\$0
Distribution Main	9216	P-8077	COV	Hillside Ave	8	Ductile Iron	225	8	0 out of 5	N/A	\$0
Distribution Main	9217	P-8077	COV	Hillside Ave	8	Ductile Iron	224	8	0 out of 5	N/A	\$0
Distribution Main	9662	P-8075	COV	Hillside Ave	8	Ductile Iron	191	8	0 out of 5	N/A	\$0
Distribution Main	10403	P-8079	COV	Hillside Ave	8	Ductile Iron	12	8	0 out of 5	N/A	\$0
Distribution Main	2578	P-9001	COV	Hilltop Avenue	6	Asbestos Cement	236	60	1.85 out of 5	\$442	104,512
Distribution Main	10801	P-7265	COV	Holden St	8	Ductile Iron	74	0	0 out of 5	N/A	\$0
Distribution Main	10802	P-7264	COV	Holden St	8	Ductile Iron	216	0	0 out of 5	N/A	\$0
Distribution Main	11735	P-7265	COV	Holden St	8	Ductile Iron	20	0	0 out of 5	N/A	\$0
Distribution Main	528		COV	Holloway Ave.	6	Asbestos Cement	12	19	1.56 out of 5	N/A	\$0
Distribution Main	1710	P-7777	COV	Holloway Ave.	6	Asbestos Cement	232	61	2 out of 5	\$442	102,347
Distribution Main	2203		COV	Holloway Ave.	2	Unknown	56	UNK	1.42 out of 5	\$442	24,878
Distribution Main	3180	P-7781	COV	Holloway Ave.	6	Asbestos Cement	243	61	2 out of 5	\$442	107,536
Distribution Main	3185	P-7774	COV	Holloway Ave.	6	Asbestos Cement	239	61	2 out of 5	\$442	105,591
Distribution Main	9556	P-7774	COV	Holloway Ave.	8	Ductile Iron	19	19	0 out of 5	N/A	\$0
Distribution Main	9557	P-7774	COV	Holloway Ave.	6	Ductile Iron	13	19	0.71 out of 5	N/A	\$0
Distribution Main	1918	P-8876	COV	Holly Court	8	Unknown	139	UNK	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9690	P-8876	COV	Holly Court	8	Unknown	4	UNK	0 out of 5	N/A	\$0
Distribution Main	554	P-7687	COV	Holmes Rd.	6	Asbestos Cement	13	65	2 out of 5	\$442	5,924
Distribution Main	722	P-7685	COV	Holmes Rd.	6	Asbestos Cement	440	65	2 out of 5	\$442	194,523
Distribution Main	723	P-7685	COV	Holmes Rd.	6	Asbestos Cement	442	65	2 out of 5	\$442	195,239
Distribution Main	1092	P-8187	COV	Holmes Rd.	6	Asbestos Cement	372	65	2 out of 5	\$442	164,536
Distribution Main	5333	P-7528	COV	Homestead Dr.	6	Asbestos Cement	78	58	1.85 out of 5	\$442	34,327
Distribution Main	5334	P-7528	COV	Homestead Dr.	6	Asbestos Cement	96	58	1.85 out of 5	\$442	42,609
Distribution Main	1921	P-7899	COV	Honey Locust Ct.	6	Asbestos Cement	332	40	1.85 out of 5	\$442	146,952
Distribution Main	6450	P-7173	COV	Hoover Dr.	8	Asbestos Cement	316	41	1.14 out of 5	\$442	139,787
Distribution Main	7435	P-7172	COV	Hoover Dr.	8	Asbestos Cement	382	41	1.14 out of 5	\$442	168,698
Distribution Main	575	P-8026	COV	Hope Ct	2	Galvanized Iron	243	73	3.28 out of 5	\$442	107,443
Distribution Main	2715	P-8026	COV	Hope Ct	2	Galvanized Iron	21	73	3.28 out of 5	\$442	9,384
Distribution Main	2405	P-8060	COV	Hopeview Avenue	2	Copper	287	71	2.43 out of 5	\$442	126,965
Distribution Main	7936	P-7231	COV	Hopkins Ct.	6	Asbestos Cement	121	56	1.85 out of 5	\$442	53,484
Distribution Main	7937	P-7231	COV	Hopkins Ct.	6	Asbestos Cement	192	56	1.85 out of 5	\$442	84,804
Transmission Main	61	P-7485	COV	Hopkins Hill Rd	12	Ductile Iron	14	30	0.14 out of 5	\$442	6,106
Distribution Main	9425	P-8388	COV	Hopkins Hill Rd		Ductile Iron	8	30	0.14 out of 5	\$442	3,536
Transmission Main	422	P-7489	COV	Hopkins Hill Rd.	12	Ductile Iron	185	30	0.14 out of 5	\$442	81,656
Transmission Main	535	P-7495	COV	Hopkins Hill Rd.	20	Ductile Iron	24	19	0 out of 5	N/A	\$0
Transmission Main	707		COV	Hopkins Hill Rd.	12	Ductile Iron	25	19	0 out of 5	N/A	\$0
Transmission Main	727	P-8199	COV	Hopkins Hill Rd.	12	Ductile Iron	18	30	0.14 out of 5	\$442	7,767
Transmission Main	731	P-7485	COV	Hopkins Hill Rd.	12	Ductile Iron	250	30	0.14 out of 5	\$442	110,286
Transmission Main	736	P-7477	COV	Hopkins Hill Rd.	12	Ductile Iron	458	30	0.14 out of 5	\$442	202,599
Transmission Main	737	P-7477	COV	Hopkins Hill Rd.	12	Ductile Iron	192	30	0.14 out of 5	\$442	84,755
Transmission Main	738	P-7479	COV	Hopkins Hill Rd.	12	Ductile Iron	205	30	0.14 out of 5	\$442	90,420
Transmission Main	739	P-7480	COV	Hopkins Hill Rd.	12	Ductile Iron	49	30	0.14 out of 5	\$442	21,497
Transmission Main	1271	P-8464	COV	Hopkins Hill Rd.	12	Ductile Iron	124	30	0.14 out of 5	\$442	54,682
Transmission Main	1272	P-8464	COV	Hopkins Hill Rd.	12	Ductile Iron	592	30	0.14 out of 5	\$442	261,577
Transmission Main	1640	P-7495	COV	Hopkins Hill Rd.	12	Ductile Iron	565	30	0.14 out of 5	\$442	249,675
Transmission Main	1641	P-7495	COV	Hopkins Hill Rd.	12	Ductile Iron	234	30	0.14 out of 5	\$442	103,552
Transmission Main	1684	P-7495	COV	Hopkins Hill Rd.	12	Ductile Iron	443	19	0 out of 5	N/A	\$0
Transmission Main	1836	P-7495	COV	Hopkins Hill Rd.	12	Ductile Iron	9	30	0.14 out of 5	\$442	3,787
Transmission Main	1837	P-7490	COV	Hopkins Hill Rd.	12	Ductile Iron	138	30	0.14 out of 5	\$442	61,031
Transmission Main	1838	P-7490	COV	Hopkins Hill Rd.	12	Ductile Iron	129	30	0.14 out of 5	\$442	56,807
Transmission Main	1867	P-8512	COV	Hopkins Hill Rd.	12	Ductile Iron	7	30	0.14 out of 5	\$442	3,161
Transmission Main	2359	P-8512	COV	Hopkins Hill Rd.	12	Ductile Iron	124	30	0.14 out of 5	\$442	54,740
Distribution Main	2607	P-7489	COV	Hopkins Hill Rd.	6	Ductile Iron	20	30	0.85 out of 5	\$442	8,822
Transmission Main	2754	P-7488	COV	Hopkins Hill Rd.	12	Ductile Iron	200	30	0.14 out of 5	\$442	88,600
Transmission Main	2767	P-7488	COV	Hopkins Hill Rd.	12	Ductile Iron	28	30	0.14 out of 5	\$442	12,230
Transmission Main	2769	P-8199	COV	Hopkins Hill Rd.	12	Ductile Iron	157	30	0.14 out of 5	\$442	69,265
Transmission Main	2770	P-8199	COV	Hopkins Hill Rd.	12	Ductile Iron	57	30	0.14 out of 5	\$442	25,016
Transmission Main	4922	P-7495	COV	Hopkins Hill Rd.	12	Ductile Iron	77	30	0.14 out of 5	\$442	34,230
Transmission Main	5325	P-7542	COV	Hopkins Hill Rd.	12	PVC	12	33	0.43 out of 5	\$442	5,146
Transmission Main	5345	P-7542	COV	Hopkins Hill Rd.	12	PVC	40	33	0.43 out of 5	\$442	17,631

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	5346	P-7542	COV	Hopkins Hill Rd.	12	PVC	452	33	0.43 out of 5	\$442	200,001
Transmission Main	7542	P-8388	COV	Hopkins Hill Rd.	12	Ductile Iron	612	30	0.14 out of 5	\$442	270,659
Transmission Main	7574	P-8408	COV	Hopkins Hill Rd.	12	Ductile Iron	359	30	0.14 out of 5	\$442	158,853
Transmission Main	7575	P-8408	COV	Hopkins Hill Rd.	12	Ductile Iron	1,100	30	0.14 out of 5	\$442	486,390
Transmission Main	8096	P-8388	COV	Hopkins Hill Rd.	12	Ductile Iron	152	30	0.14 out of 5	\$442	67,342
Transmission Main	8097	P-8388	COV	Hopkins Hill Rd.	12	Ductile Iron	146	30	0.14 out of 5	\$442	64,362
Transmission Main	8098	P-8388	COV	Hopkins Hill Rd.	12	Ductile Iron	96	30	0.14 out of 5	\$442	42,349
Transmission Main	9426	P-8512	COV	Hopkins Hill Rd.	12	Ductile Iron	2	30	0.14 out of 5	\$442	710
Transmission Main	11276	P-7495	COV	Hopkins Hill Rd.	12	Ductile Iron	24	30	0.14 out of 5	\$442	10,451
Transmission Main	11389	P-8408	COV	Hopkins Hill Rd.	12	Ductile Iron	59	30	0.14 out of 5	\$442	25,945
Transmission Main	11432	P-8388	COV	Hopkins Hill Rd.	12	Ductile Iron	13	30	0.14 out of 5	\$442	5,731
Transmission Main	11868	P-8408	COV	Hopkins Hill Rd.	12	Ductile Iron	844	30	0.14 out of 5	\$442	373,001
Transmission Main	12082	P-7542	COV	Hopkins Hill Rd.	12	PVC	36	33	0.43 out of 5	\$442	15,873
Distribution Main	1143	P-7945	COV	Hornbeam Rd	8	Ductile Iron	47	15	0 out of 5	N/A	\$0
Distribution Main	9340	P-8417	COV	Hornbeam Rd	8	Ductile Iron	393	10	0 out of 5	N/A	\$0
Distribution Main	9341	P-8417	COV	Hornbeam Rd	8	Ductile Iron	508	10	0 out of 5	N/A	\$0
Distribution Main	521	P-7948	COV	Hornbeam Rd.	8	Asbestos Cement	415	55	1.14 out of 5	\$442	183,318
Distribution Main	522	P-7948	COV	Hornbeam Rd.	8	Asbestos Cement	518	55	1.85 out of 5	\$442	229,021
Distribution Main	523	P-7945	COV	Hornbeam Rd.	8	Asbestos Cement	251	55	1.14 out of 5	\$442	110,744
Distribution Main	8302	P-8412	COV	Hornbeam Rd.	8	Ductile Iron	791	14	0 out of 5	N/A	\$0
Distribution Main	8305	P-8416	COV	Hornbeam Rd.	8	Ductile Iron	26	14	0 out of 5	N/A	\$0
Distribution Main	8306	P-8416	COV	Hornbeam Rd.	8	Ductile Iron	505	14	0 out of 5	N/A	\$0
Distribution Main	10895	P-8412	COV	Hornbeam Rd.	8	Ductile Iron	76	14	0 out of 5	N/A	\$0
Distribution Main	69	P-8114	COV	Howard Ave	8	Ductile Iron	27	15	0 out of 5	N/A	\$0
Distribution Main	70	P-8114	COV	Howard Ave	8	Ductile Iron	10	15	0 out of 5	N/A	\$0
Transmission Main	95	P-8859	COV	Howard Ave.	16	Ductile Iron	25	15	0 out of 5	N/A	\$0
Distribution Main	233	P-8857	COV	Howard Ave.	6	Cast Iron	22	132	2.57 out of 5	\$442	9,857
Distribution Main	245	P-8857	COV	Howard Ave.	6	Cast Iron	92	132	2.57 out of 5	\$442	40,729
Distribution Main	246	P-8115	COV	Howard Ave.	6	Cast Iron	995	132	2.57 out of 5	\$442	439,729
Distribution Main	247	P-8115	COV	Howard Ave.	6	Cast Iron	291	132	2.57 out of 5	\$442	128,689
Distribution Main	248	P-8857	COV	Howard Ave.	6	Cast Iron	33	132	2.57 out of 5	\$442	14,734
Transmission Main	306	P-8369	COV	Howard Ave.	16	Asbestos Cement	214	62	1.29 out of 5	\$442	94,443
Transmission Main	307	P-8369	COV	Howard Ave.	16	Asbestos Cement	156	62	1.29 out of 5	\$442	68,933
Distribution Main	1177	P-8366	COV	Howard Ave.	6	Cast Iron	19	132	2.57 out of 5	\$442	8,475
Transmission Main	1213	P-8509	COV	Howard Ave.	16	Asbestos Cement	225	63	1.29 out of 5	\$442	99,442
Distribution Main	1416	P-8857	COV	Howard Ave.	6	Cast Iron	31	132	2.57 out of 5	\$442	13,910
Distribution Main	1417	P-8857	COV	Howard Ave.	6	Cast Iron	55	132	2.57 out of 5	\$442	24,225
Transmission Main	1632	P-8118	COV	Howard Ave.	16	Asbestos Cement	2,102	63	1.29 out of 5	\$442	928,877
Distribution Main	1633	P-8114	COV	Howard Ave.	8	Asbestos Cement	419	63	1.29 out of 5	\$442	185,247
Distribution Main	1634	P-8114	COV	Howard Ave.	8	Asbestos Cement	573	63	1.29 out of 5	\$442	253,075
Distribution Main	2575	P-8089	COV	Howard Ave.	6	Ductile Iron	95	18	0.71 out of 5	N/A	\$0
Distribution Main	9691		COV	Howard Ave.		Unknown	9	UNK	0 out of 5	N/A	\$0
Distribution Main	9692		COV	Howard Ave.		Unknown	12	UNK	0 out of 5	N/A	\$0
Distribution Main	10376	P-8089	COV	Howard Ave.	6	Ductile Iron	14	18	0.71 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10377		COV	Howard Ave.	6	Cast Iron	3	132	2.57 out of 5	\$442	1,542
Transmission Main	11015	P-8859	COV	Howard Ave.	16	Ductile Iron	12	15	0 out of 5	N/A	\$0
Distribution Main	11046	P-8857	COV	Howard Ave.	6	Cast Iron	4	132	2.57 out of 5	\$442	1,919
Distribution Main	11047	P-8115	COV	Howard Ave.	6	Cast Iron	218	132	2.57 out of 5	\$442	96,324
Transmission Main	11109	P-8509	COV	Howard Ave.	16	Asbestos Cement	5	62	1.29 out of 5	\$442	2,314
Transmission Main	11134	P-8118	COV	Howard Ave.	16	Asbestos Cement	743	63	1.29 out of 5	\$442	328,396
Transmission Main	11135	P-8118	COV	Howard Ave.	16	Asbestos Cement	12	63	1.29 out of 5	\$442	5,484
Distribution Main	11858	P-8114	COV	Howard Ave.	8	Asbestos Cement	349	63	1.29 out of 5	\$442	154,085
Distribution Main	9040	P-1208	COV	Hoxie Ct.	8	Ductile Iron	101	17	0 out of 5	N/A	\$0
Distribution Main	9041	P-1208	COV	Hoxie Ct.	8	Ductile Iron	188	17	0 out of 5	N/A	\$0
Distribution Main	7738	P-8957	COV	Huckleberry Road	6	Asbestos Cement	10	57	1.85 out of 5	\$442	4,322
Distribution Main	7830	P-8957	COV	Huckleberry Road	6	Asbestos Cement	351	57	1.85 out of 5	\$442	155,316
Transmission Main	3046	P-7360	COV	Hunters Crossing Dr.	16	Ductile Iron	388	24	0.14 out of 5	N/A	\$0
Transmission Main	3047	P-8885	COV	Hunters Crossing Dr.	16	Ductile Iron	383	24	0.14 out of 5	N/A	\$0
Transmission Main	3055	P-7350	COV	Hunters Crossing Dr.	16	Ductile Iron	297	24	0.14 out of 5	N/A	\$0
Transmission Main	3056	P-7350	COV	Hunters Crossing Dr.	16	Ductile Iron	450	24	0.14 out of 5	N/A	\$0
Transmission Main	3057	P-7350	COV	Hunters Crossing Dr.	16	Ductile Iron	19	24	0.14 out of 5	N/A	\$0
Transmission Main	3059	P-7358	COV	Hunters Crossing Dr.	16	Ductile Iron	171	24	0.14 out of 5	N/A	\$0
Transmission Main	3063	P-7357	COV	Hunters Crossing Dr.	16	Ductile Iron	654	24	0.14 out of 5	N/A	\$0
Transmission Main	3064	P-7349	COV	Hunters Crossing Dr.	16	Ductile Iron	1,325	24	0.14 out of 5	N/A	\$0
Transmission Main	5850	P-7344	COV	Hunters Crossing Dr.	16	Ductile Iron	454	24	0.14 out of 5	N/A	\$0
Transmission Main	5851	P-7344	COV	Hunters Crossing Dr.	16	Ductile Iron	344	24	0.14 out of 5	N/A	\$0
Transmission Main	5852	P-8887	COV	Hunters Crossing Dr.	16	Ductile Iron	9	24	0.14 out of 5	N/A	\$0
Distribution Main	9965	P-8887	COV	Hunters Crossing Dr.	8	Ductile Iron	6	24	0.14 out of 5	N/A	\$0
Distribution Main	1120	P-7580	COV	Idaho St.	2	Galvanized Iron	24	86	3.43 out of 5	\$442	10,518
Distribution Main	1121	P-7583	COV	Idaho St.	2	Galvanized Iron	252	86	3.43 out of 5	\$442	111,436
Distribution Main	1122	P-7580	COV	Idaho St.	2	Galvanized Iron	509	86	4.14 out of 5	\$442	225,012
Distribution Main	2634	P-7580	COV	Idaho St.	2	Galvanized Iron	13	86	3.43 out of 5	\$442	5,585
Distribution Main	5939	P-8898	COV	Industrial Drive	8	Asbestos Cement	193	54	1.14 out of 5	\$442	85,294
Distribution Main	5940	P-8898	COV	Industrial Drive	8	Asbestos Cement	380	54	1.14 out of 5	\$442	168,140
Distribution Main	5945	P-8898	COV	Industrial Drive	8	Asbestos Cement	224	54	1.14 out of 5	\$442	99,168
Distribution Main	7505	P-8898	COV	Industrial Drive	8	Asbestos Cement	306	54	1.14 out of 5	\$442	135,264
Distribution Main	8779	P-8898	COV	Industrial Drive	8	Ductile Iron	33	8	0 out of 5	N/A	\$0
Distribution Main	10497		COV	Industrial Drive	6	Asbestos Cement	1	54	1.85 out of 5	\$442	646
Distribution Main	11320	P-8898	COV	Industrial Drive	8	Asbestos Cement	50	54	1.14 out of 5	\$442	22,220
Distribution Main	823	P-9034	COV	Irene Ln	6	Asbestos Cement	121	50	1.85 out of 5	\$442	53,535
Distribution Main	824	P-9034	COV	Irene Ln	6	Asbestos Cement	21	50	1.85 out of 5	\$442	9,393
Distribution Main	827	P-7404	COV	Irene Ln	6	Asbestos Cement	460	50	1.85 out of 5	\$442	203,174
Distribution Main	2830	P-9034	COV	Irene Ln	6	Asbestos Cement	147	50	1.85 out of 5	\$442	64,841
Distribution Main	7882	P-7306	COV	Ironwood Dr.	8	Asbestos Cement	371	34	1 out of 5	\$442	164,155
Distribution Main	7894	P-7304	COV	Ironwood Dr.	8	Asbestos Cement	190	34	1 out of 5	\$442	83,959
Distribution Main	7895	P-7304	COV	Ironwood Dr.	8	Asbestos Cement	193	34	1 out of 5	\$442	85,320
Distribution Main	7897	P-7302	COV	Ironwood Dr.	8	Asbestos Cement	373	34	1 out of 5	\$442	164,658
Distribution Main	7634	P-7100	COV	Island Dr.	6	Ductile Iron	147	26	0.85 out of 5	\$442	64,923

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7635	P-7099	COV	Island Dr.	6	Ductile Iron	150	26	0.85 out of 5	\$442	66,360
Distribution Main	7636	P-7099	COV	Island Dr.	6	Ductile Iron	53	26	0.85 out of 5	\$442	23,303
Distribution Main	7637	P-7098	COV	Island Dr.	6	Ductile Iron	74	26	0.85 out of 5	\$442	32,844
Distribution Main	7638	P-7098	COV	Island Dr.	6	Ductile Iron	723	26	0.85 out of 5	\$442	319,481
Distribution Main	7781	P-7096	COV	Island Dr.	8	Asbestos Cement	44	43	1.14 out of 5	\$442	19,581
Distribution Main	7794	P-7096	COV	Island Dr.	8	Asbestos Cement	106	43	1.14 out of 5	\$442	46,680
Distribution Main	7795	P-7096	COV	Island Dr.	8	Asbestos Cement	606	43	1.14 out of 5	\$442	267,780
Distribution Main	7796	P-7093	COV	Island Dr.	8	Asbestos Cement	40	43	1.14 out of 5	\$442	17,564
Distribution Main	7797	P-7093	COV	Island Dr.	8	Asbestos Cement	366	43	1.14 out of 5	\$442	161,917
Distribution Main	10065	P-7096	COV	Island Dr.	8	PVC	85	26	0.43 out of 5	\$442	37,758
Distribution Main	7768	P-7007	COV	Isle Of Capri Rd.	6	Ductile Iron	523	28	0.85 out of 5	\$442	231,325
Distribution Main	7769	P-7007	COV	Isle Of Capri Rd.	6	Ductile Iron	71	28	0.85 out of 5	\$442	31,274
Distribution Main	9998	P-7007	COV	Isle Of Capri Rd.	6	Ductile Iron	6	28	0.85 out of 5	\$442	2,788
Distribution Main	7896	P-7299	COV	Ivy Dr.	8	Asbestos Cement	511	40	1 out of 5	\$442	225,874
Distribution Main	7820	P-7042	COV	Jack Pine Rd.	6	Asbestos Cement	194	57	1.85 out of 5	\$442	85,735
Distribution Main	7821	P-7042	COV	Jack Pine Rd.	6	Asbestos Cement	219	57	1.85 out of 5	\$442	96,988
Distribution Main	7822	P-7048	COV	Jack Pine Rd.	6	Asbestos Cement	346	57	1.85 out of 5	\$442	153,140
Distribution Main	7832	P-7031	COV	Jack Pine Rd.	6	Asbestos Cement	254	57	2.57 out of 5	\$442	112,164
Distribution Main	8296	P-7031	COV	Jack Pine Rd.	6	Asbestos Cement	15	57	1.85 out of 5	\$442	6,713
Distribution Main	11411	P-7042	COV	Jack Pine Rd.	6	Asbestos Cement	47	57	1.85 out of 5	\$442	20,769
Distribution Main	11412	P-7048	COV	Jack Pine Rd.	6	Asbestos Cement	6	57	1.85 out of 5	\$442	2,493
Distribution Main	545	P-7681	COV	Jade Rd.	8	Asbestos Cement	44	50	1.14 out of 5	\$442	19,252
Distribution Main	546	P-7681	COV	Jade Rd.	8	Asbestos Cement	208	50	1.14 out of 5	\$442	92,061
Distribution Main	720	P-7682	COV	Jade Rd.	8	Asbestos Cement	487	50	1.14 out of 5	\$442	215,132
Distribution Main	721	P-7682	COV	Jade Rd.	8	Asbestos Cement	388	50	1.14 out of 5	\$442	171,471
Distribution Main	1256	P-7336	COV	Jasmine Ct.	8	Ductile Iron	191	21	0.14 out of 5	N/A	\$0
Distribution Main	10181	P-7161	COV	Jefferson Dr		Unknown	15	UNK	0 out of 5	N/A	\$0
Transmission Main	2984	P-7161	COV	Jefferson Dr.	12	Ductile Iron	45	30	0.14 out of 5	\$442	19,981
Transmission Main	2985	P-7161	COV	Jefferson Dr.	12	Ductile Iron	551	30	0.14 out of 5	\$442	243,389
Transmission Main	4839	P-7162	COV	Jefferson Dr.	12	Ductile Iron	53	30	0.14 out of 5	\$442	23,250
Transmission Main	4840	P-7162	COV	Jefferson Dr.	12	Ductile Iron	805	30	0.14 out of 5	\$442	355,880
Transmission Main	4923	P-8244	COV	Jefferson Dr.	12	Ductile Iron	12	30	0.14 out of 5	\$442	5,493
Distribution Main	5323	P-7443	COV	Jefferson Dr.	8	Asbestos Cement	717	42	1.14 out of 5	\$442	316,907
Distribution Main	5324	P-7443	COV	Jefferson Dr.	8	Asbestos Cement	49	42	1.14 out of 5	\$442	21,739
Distribution Main	6617	P-7444	COV	Jefferson Dr.	8	Asbestos Cement	801	42	1.14 out of 5	\$442	354,221
Distribution Main	6618	P-7444	COV	Jefferson Dr.	8	Asbestos Cement	57	42	1.14 out of 5	\$442	25,110
Distribution Main	6621	P-7444	COV	Jefferson Dr.	8	Asbestos Cement	7	42	1.14 out of 5	\$442	3,049
Distribution Main	6622	P-7444	COV	Jefferson Dr.	8	Asbestos Cement	18	42	1.14 out of 5	\$442	7,747
Distribution Main	9260	P-7443	COV	Jefferson Dr.	8	Asbestos Cement	4	42	1.14 out of 5	\$442	1,563
Distribution Main	9948		COV	Jefferson Dr.	8	Ductile Iron	18	30	0.14 out of 5	\$442	8,062
Distribution Main	11297	P-7443	COV	Jefferson Dr.	8	Asbestos Cement	336	42	1.14 out of 5	\$442	148,400
Distribution Main	11336	P-7444	COV	Jefferson Dr.	8	Asbestos Cement	3	42	1.14 out of 5	\$442	1,481
Transmission Main	11337	P-7161	COV	Jefferson Dr.	12	Ductile Iron	4	30	0.14 out of 5	\$442	1,793
Distribution Main	11344	P-7444	COV	Jefferson Dr.	8	Asbestos Cement	2	42	1.14 out of 5	\$442	1,021

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11975	P-7161	COV	Jefferson Dr.	12	Ductile Iron	304	30	0.14 out of 5	\$442	134,365
Transmission Main	11978	P-7161	COV	Jefferson Dr.	12	Ductile Iron	194	30	0.14 out of 5	\$442	85,789
Distribution Main	2198	P-7746	COV	Jennifer Ln.	8	Ductile Iron	7	27	0.14 out of 5	\$442	3,242
Distribution Main	2199	P-7748	COV	Jennifer Ln.	8	Ductile Iron	90	27	0.14 out of 5	\$442	39,787
Distribution Main	2200	P-7748	COV	Jennifer Ln.	8	Ductile Iron	141	27	0.14 out of 5	\$442	62,510
Distribution Main	2201	P-7750	COV	Jennifer Ln.	8	Ductile Iron	80	24	0.14 out of 5	N/A	\$0
Distribution Main	2901	P-7750	COV	Jennifer Ln.	8	Ductile Iron	323	24	0.14 out of 5	N/A	\$0
Distribution Main	2902	P-7750	COV	Jennifer Ln.	8	Ductile Iron	147	24	0.14 out of 5	N/A	\$0
Distribution Main	9572		COV	Jennifer Ln.	8	Ductile Iron	3	27	0.14 out of 5	\$442	1,497
Distribution Main	9927	P-7746	COV	Jennifer Ln.	8	Ductile Iron	171	27	0.14 out of 5	\$442	75,399
Transmission Main	337	P-7627	COV	Johnson Blvd.	12	Asbestos Cement	22	58	1.14 out of 5	\$442	9,769
Transmission Main	338	P-7627	COV	Johnson Blvd.	12	Asbestos Cement	187	58	1.14 out of 5	\$442	82,506
Transmission Main	339	P-7627	COV	Johnson Blvd.	12	Asbestos Cement	71	58	1.14 out of 5	\$442	31,273
Transmission Main	342	P-7627	COV	Johnson Blvd.	12	Asbestos Cement	36	58	1.14 out of 5	\$442	15,918
Transmission Main	343	P-8191	COV	Johnson Blvd.	16	Ductile Iron	658	28	0.14 out of 5	\$442	291,042
Transmission Main	351	P-7648	COV	Johnson Blvd.	16	Ductile Iron	3	28	0.14 out of 5	\$442	1,256
Transmission Main	682	P-7642	COV	Johnson Blvd.	12	Asbestos Cement	241	58	1.14 out of 5	\$442	106,719
Transmission Main	683	P-8194	COV	Johnson Blvd.	16	Ductile Iron	306	28	0.14 out of 5	\$442	135,270
Transmission Main	684	P-7637	COV	Johnson Blvd.	16	Ductile Iron	10	28	0.14 out of 5	\$442	4,483
Transmission Main	689	P-8193	COV	Johnson Blvd.	16	Ductile Iron	923	28	0.14 out of 5	\$442	408,075
Distribution Main	728	P-7637	COV	Johnson Blvd.	10	Asbestos Cement	602	63	1.29 out of 5	\$442	265,993
Distribution Main	729	P-7637	COV	Johnson Blvd.	10	Asbestos Cement	116	63	1.29 out of 5	\$442	51,331
Distribution Main	730	P-7629	COV	Johnson Blvd.	10	Asbestos Cement	84	58	1.14 out of 5	\$442	37,082
Distribution Main	744	P-7631	COV	Johnson Blvd.	10	Asbestos Cement	246	63	1.29 out of 5	\$442	108,825
Distribution Main	748	P-7629	COV	Johnson Blvd.	10	Asbestos Cement	255	58	1.14 out of 5	\$442	112,801
Transmission Main	766	P-8194	COV	Johnson Blvd.	16	Ductile Iron	27	28	0.14 out of 5	\$442	12,095
Transmission Main	770		COV	Johnson Blvd.	12	PVC	206	28	0.43 out of 5	\$442	91,208
Transmission Main	772	P-7639	COV	Johnson Blvd.	12	Asbestos Cement	219	58	1.14 out of 5	\$442	96,740
Transmission Main	774	P-8191	COV	Johnson Blvd.	16	Ductile Iron	389	28	0.14 out of 5	\$442	171,727
Transmission Main	775	P-8191	COV	Johnson Blvd.	16	Ductile Iron	744	28	0.14 out of 5	\$442	328,715
Transmission Main	1421	P-8193	COV	Johnson Blvd.	16	Ductile Iron	4	28	0.14 out of 5	\$442	1,645
Transmission Main	1625	P-7637	COV	Johnson Blvd.	16	Ductile Iron	23	28	0.14 out of 5	\$442	10,205
Transmission Main	1658	P-7643	COV	Johnson Blvd.	12	Asbestos Cement	36	58	1.14 out of 5	\$442	16,028
Transmission Main	1659	P-7639	COV	Johnson Blvd.	12	Asbestos Cement	70	58	1.14 out of 5	\$442	31,012
Transmission Main	1866	P-7627	COV	Johnson Blvd.	12	Asbestos Cement	6	58	1.14 out of 5	\$442	2,569
Transmission Main	1872	P-7640	COV	Johnson Blvd.	12	PVC	395	28	0.43 out of 5	\$442	174,676
Distribution Main	2606	P-7627	COV	Johnson Blvd.	10	Asbestos Cement	259	58	1.14 out of 5	\$442	114,600
Distribution Main	2762	P-7486	COV	Johnson Blvd.	10	Asbestos Cement	208	63	1.29 out of 5	\$442	92,054
Distribution Main	2773	P-7486	COV	Johnson Blvd.	10	Asbestos Cement	38	58	1.14 out of 5	\$442	16,889
Transmission Main	9925	P-7627	COV	Johnson Blvd.	12	Asbestos Cement	14	58	1.14 out of 5	\$442	6,365
Transmission Main	9926	P-7627	COV	Johnson Blvd.	12	Asbestos Cement	45	58	1.14 out of 5	\$442	19,704
Transmission Main	11087		COV	Johnson Blvd.	12	PVC	8	28	0.43 out of 5	\$442	3,702
Transmission Main	72		COV	Johnson Blvd. Ps	16	Ductile Iron	6	UNK	0 out of 5	N/A	\$0
Transmission Main	73		COV	Johnson Blvd. Ps	16	Ductile Iron	5	UNK	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	74		COV	Johnson Blvd. Ps	16	Ductile Iron	41	UNK	0 out of 5	N/A	\$0
Transmission Main	75		COV	Johnson Blvd. Ps	16	Ductile Iron	31	UNK	0 out of 5	N/A	\$0
Distribution Main	76	P-7627	COV	Johnson Blvd. Ps	10	Ductile Iron	3	UNK	0 out of 5	N/A	\$0
Distribution Main	77		COV	Johnson Blvd. Ps	10	Ductile Iron	14	UNK	0 out of 5	N/A	\$0
Transmission Main	78		COV	Johnson Blvd. Ps	16	Ductile Iron	20	UNK	0 out of 5	N/A	\$0
Transmission Main	79		COV	Johnson Blvd. Ps	16	Ductile Iron	7	UNK	0 out of 5	N/A	\$0
Transmission Main	80		COV	Johnson Blvd. Ps	16	Ductile Iron	205	UNK	0 out of 5	N/A	\$0
Transmission Main	81		COV	Johnson Blvd. Ps	16	Ductile Iron	8	UNK	0 out of 5	N/A	\$0
Transmission Main	340		COV	Johnson Blvd. Ps	16	Ductile Iron	193	28	0.14 out of 5	\$442	85,281
Transmission Main	341		COV	Johnson Blvd. Ps	16	Ductile Iron	467	28	0.14 out of 5	\$442	206,272
Transmission Main	771	P-7648	COV	Johnson Blvd. Ps	16	Ductile Iron	21	28	0.14 out of 5	\$442	9,125
Transmission Main	773	P-7643	COV	Johnson Blvd. Ps	16	Ductile Iron	1,147	28	0.14 out of 5	\$442	506,846
Transmission Main	1616		COV	Johnson Blvd. Ps	16	Ductile Iron	183	28	0.14 out of 5	\$442	80,665
Distribution Main	1922	P-7894	COV	Juniper Ct.	6	Asbestos Cement	167	40	1.71 out of 5	\$442	73,709
Distribution Main	6113	P-7114	COV	Juniper Hill Dr.	8	Ductile Iron	306	21	0.14 out of 5	N/A	\$0
Distribution Main	6114	P-7114	COV	Juniper Hill Dr.	8	Ductile Iron	69	21	0.14 out of 5	N/A	\$0
Distribution Main	7272	P-7109	COV	Juniper Hill Dr.	8	Asbestos Cement	393	40	1 out of 5	\$442	173,920
Distribution Main	7465	P-7106	COV	Juniper Hill Dr.	8	Asbestos Cement	659	40	1 out of 5	\$442	291,435
Distribution Main	7978	P-7114	COV	Juniper Hill Dr.	8	Ductile Iron	157	21	0.14 out of 5	N/A	\$0
Distribution Main	7979	P-7114	COV	Juniper Hill Dr.	8	Ductile Iron	435	21	0.14 out of 5	N/A	\$0
Distribution Main	578	P-7999	COV	Justa Ave.	6	Asbestos Cement	239	72	2 out of 5	\$442	105,657
Distribution Main	2733	P-8000	COV	Justa Ave.	6	Asbestos Cement	235	72	2 out of 5	\$442	103,899
Distribution Main	9751	P-8211	COV	Kathy Ave	8	Ductile Iron	349	8	0 out of 5	N/A	\$0
Distribution Main	9752	P-8211	COV	Kathy Ave	8	Ductile Iron	22	8	0 out of 5	N/A	\$0
Distribution Main	812	P-7765	COV	Kennedy Dr.	8	Asbestos Cement	310	58	1.14 out of 5	\$442	136,951
Distribution Main	2271	P-7765	COV	Kennedy Dr.	8	Ductile Iron	6	19	0 out of 5	N/A	\$0
Distribution Main	3684	P-7763	COV	Kennedy Dr.	8	Asbestos Cement	562	58	1.14 out of 5	\$442	248,262
Distribution Main	9703	P-7763	COV	Kennedy Dr.	8	Ductile Iron	26	11	0 out of 5	N/A	\$0
Distribution Main	10362	P-7767	COV	Kennedy Dr.	8	Ductile Iron	8	19	0 out of 5	N/A	\$0
Distribution Main	10363	P-7767	COV	Kennedy Dr.	8	Ductile Iron	36	19	0 out of 5	N/A	\$0
Distribution Main	9741	P-8205	COV	Kennington Ave	8	Ductile Iron	538	8	0 out of 5	N/A	\$0
Distribution Main	6116	P-8948	COV	Kiley Way	8	Ductile Iron	550	20	0 out of 5	N/A	\$0
Distribution Main	6117	P-8948	COV	Kiley Way	8	Ductile Iron	459	20	0 out of 5	N/A	\$0
Distribution Main	6311	P-7141	COV	Kiley Way	8	Ductile Iron	91	20	0 out of 5	N/A	\$0
Distribution Main	6312	P-7139	COV	Kiley Way	8	Ductile Iron	428	20	0 out of 5	N/A	\$0
Distribution Main	8173	P-8949	COV	Kiley Way	8	Ductile Iron	1,039	15	0 out of 5	N/A	\$0
Distribution Main	8174	P-7140	COV	Kiley Way	8	Ductile Iron	28	15	0 out of 5	N/A	\$0
Distribution Main	8175	P-7140	COV	Kiley Way	8	Ductile Iron	797	15	0 out of 5	N/A	\$0
Distribution Main	11331	P-7141	COV	Kiley Way	8	Ductile Iron	378	20	0 out of 5	N/A	\$0
Distribution Main	2369	P-7541	COV	Kilton St.	8	Ductile Iron	459	18	0 out of 5	N/A	\$0
Distribution Main	9749	P-8208	COV	Kimberly Ave	8	Ductile Iron	483	8	0 out of 5	N/A	\$0
Transmission Main	734	P-8216	COV	King St.	12	Ductile Iron	15	25	0.14 out of 5	N/A	\$0
Distribution Main	735	P-8216	COV	King St.	6	Ductile Iron	11	25	0.85 out of 5	N/A	\$0
Distribution Main	2755	P-8216	COV	King St.	6	Ductile Iron	253	25	0.85 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2756	P-8216	COV	King St.	6	Ductile Iron	27	25	0.85 out of 5	N/A	\$0
Distribution Main	2757	P-8216	COV	King St.	6	Ductile Iron	336	25	0.85 out of 5	N/A	\$0
Distribution Main	2758	P-8216	COV	King St.	6	Ductile Iron	377	25	0.85 out of 5	N/A	\$0
Distribution Main	2759	P-8216	COV	King St.	6	Ductile Iron	12	25	0.85 out of 5	N/A	\$0
Transmission Main	2772	P-8196	COV	King St.	12	Ductile Iron	350	30	0.14 out of 5	\$442	154,909
Transmission Main	11086	P-8216	COV	King St.	12	Ductile Iron	6	30	0.14 out of 5	\$442	2,490
Distribution Main	7798	P-7094	COV	Kingfisher Dr.	8	PVC	322	38	0.43 out of 5	\$442	142,542
Distribution Main	7799	P-7094	COV	Kingfisher Dr.	8	PVC	888	38	0.43 out of 5	\$442	392,311
Distribution Main	9257	P-7095	COV	Kingfisher Dr.	6	PVC	245	34	1.14 out of 5	\$442	108,156
Distribution Main	9258	P-8950	COV	Kingfisher Dr.	8	PVC	5	34	0.43 out of 5	\$442	2,295
Distribution Main	9259	P-8951	COV	Kingfisher Dr.	8	PVC	23	34	0.43 out of 5	\$442	10,253
Distribution Main	10008	P-7095	COV	Kingfisher Dr.	8	PVC	3	34	0.43 out of 5	\$442	1,295
Distribution Main	10009	P-7095	COV	Kingfisher Dr.	8	PVC	8	34	0.43 out of 5	\$442	3,608
Distribution Main	10010	P-8950	COV	Kingfisher Dr.	8	PVC	216	38	0.43 out of 5	\$442	95,338
Distribution Main	7707	P-7028	COV	Kingswood Dr.	6	Asbestos Cement	300	51	1.85 out of 5	\$442	132,535
Distribution Main	7714	P-7029	COV	Kingswood Dr.	6	Asbestos Cement	11	51	1.85 out of 5	\$442	4,744
Distribution Main	7732	P-7027	COV	Kingswood Dr.	6	Asbestos Cement	4	51	1.85 out of 5	\$442	1,584
Distribution Main	7733	P-7027	COV	Kingswood Dr.	6	Asbestos Cement	530	51	1.85 out of 5	\$442	234,348
Distribution Main	11403	P-7028	COV	Kingswood Dr.	6	Asbestos Cement	4	51	1.85 out of 5	\$442	1,674
Distribution Main	9637		COV	Knight St	2	Unknown	6	UNK	1.42 out of 5	\$442	2,595
Distribution Main	568	P-7967	COV	Knight St.	6	Cast Iron	19	79	2.28 out of 5	\$442	8,245
Distribution Main	2738	P-7967	COV	Knight St.	6	Cast Iron	514	79	2.28 out of 5	\$442	227,191
Distribution Main	2739	P-7967	COV	Knight St.	6	Cast Iron	24	79	2.28 out of 5	\$442	10,416
Distribution Main	9968		COV	Knight St.	6	Cast Iron	11	79	2.28 out of 5	\$442	4,922
Distribution Main	8107	P-8880	COV	Knotty Oak Ln	8	Ductile Iron	53	15	0 out of 5	N/A	\$0
Transmission Main	113	P-8253	COV	Knotty Oak Rd	16	Asbestos Cement	20	51	1.14 out of 5	\$442	8,871
Distribution Main	115	P-7275	COV	Knotty Oak Rd	8	Asbestos Cement	461	72	1.29 out of 5	\$442	203,563
Transmission Main	216	P-7888	COV	Knotty Oak Rd.	20	Ductile Iron	414	15	0 out of 5	N/A	\$0
Transmission Main	217	P-7888	COV	Knotty Oak Rd.	20	Ductile Iron	348	15	0 out of 5	N/A	\$0
Transmission Main	218		COV	Knotty Oak Rd.	16	Ductile Iron	24	UNK	0 out of 5	N/A	\$0
Transmission Main	219	P-7361	COV	Knotty Oak Rd.	16	Ductile Iron	3	24	0.14 out of 5	N/A	\$0
Transmission Main	220	P-7363	COV	Knotty Oak Rd.	12	Ductile Iron	36	UNK	0 out of 5	N/A	\$0
Transmission Main	221	P-7881	COV	Knotty Oak Rd.	20	Ductile Iron	329	15	0 out of 5	N/A	\$0
Transmission Main	222	P-8497	COV	Knotty Oak Rd.	20	Ductile Iron	59	15	0 out of 5	N/A	\$0
Transmission Main	223	P-8496	COV	Knotty Oak Rd.	20	Ductile Iron	33	15	0 out of 5	N/A	\$0
Distribution Main	251	P-8242	COV	Knotty Oak Rd.	8	Asbestos Cement	18	72	1.29 out of 5	\$442	7,840
Distribution Main	252	P-8242	COV	Knotty Oak Rd.	8	Asbestos Cement	28	72	1.29 out of 5	\$442	12,180
Transmission Main	1030	P-8877	COV	Knotty Oak Rd.	20	Ductile Iron	36	15	0 out of 5	N/A	\$0
Transmission Main	1031	P-8877	COV	Knotty Oak Rd.	20	Ductile Iron	837	15	0 out of 5	N/A	\$0
Transmission Main	1042	P-8489	COV	Knotty Oak Rd.	20	Ductile Iron	113	15	0 out of 5	N/A	\$0
Transmission Main	1047	P-8490	COV	Knotty Oak Rd.	20	Ductile Iron	103	15	0 out of 5	N/A	\$0
Transmission Main	1048	P-8490	COV	Knotty Oak Rd.	20	Ductile Iron	951	15	0 out of 5	N/A	\$0
Transmission Main	1109	P-8491	COV	Knotty Oak Rd.	20	Ductile Iron	135	15	0 out of 5	N/A	\$0
Transmission Main	1112	P-7887	COV	Knotty Oak Rd.	20	Ductile Iron	54	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	1115	P-8879	COV	Knotty Oak Rd.	20	Ductile Iron	16	15	0 out of 5	N/A	\$0
Transmission Main	1116	P-8879	COV	Knotty Oak Rd.	20	Ductile Iron	62	15	0 out of 5	N/A	\$0
Transmission Main	1117	P-8879	COV	Knotty Oak Rd.	20	Ductile Iron	514	15	0 out of 5	N/A	\$0
Transmission Main	1118	P-7890	COV	Knotty Oak Rd.	20	Ductile Iron	607	15	0 out of 5	N/A	\$0
Transmission Main	1184	P-7362	COV	Knotty Oak Rd.	12	Asbestos Cement	19	57	1.14 out of 5	\$442	8,235
Transmission Main	1185	P-7362	COV	Knotty Oak Rd.	12	Asbestos Cement	792	57	1.14 out of 5	\$442	349,850
Transmission Main	1216	P-7361	COV	Knotty Oak Rd.	20	Asbestos Cement	336	24	1 out of 5	N/A	\$0
Transmission Main	1217	P-8496	COV	Knotty Oak Rd.	20	Ductile Iron	11	15	0 out of 5	N/A	\$0
Transmission Main	1218	P-8496	COV	Knotty Oak Rd.	20	Ductile Iron	9	15	0 out of 5	N/A	\$0
Transmission Main	1219	P-8496	COV	Knotty Oak Rd.	20	Ductile Iron	68	15	0 out of 5	N/A	\$0
Transmission Main	1220	P-8495	COV	Knotty Oak Rd.	20	Asbestos Cement	410	51	1.14 out of 5	\$442	181,336
Transmission Main	1221	P-7887	COV	Knotty Oak Rd.	20	Ductile Iron	24	15	0 out of 5	N/A	\$0
Transmission Main	1222	P-8879	COV	Knotty Oak Rd.	20	Ductile Iron	631	15	0 out of 5	N/A	\$0
Transmission Main	1223	P-8879	COV	Knotty Oak Rd.	20	Ductile Iron	728	15	0 out of 5	N/A	\$0
Distribution Main	1260	P-7317	COV	Knotty Oak Rd.	8	Asbestos Cement	305	72	1.29 out of 5	\$442	135,009
Transmission Main	1269	P-8495	COV	Knotty Oak Rd.	20	Asbestos Cement	652	51	1.14 out of 5	\$442	288,196
Transmission Main	1446	P-7873	COV	Knotty Oak Rd.	20	Asbestos Cement	1,234	72	1.29 out of 5	\$442	545,580
Transmission Main	1450	P-8253	COV	Knotty Oak Rd.	16	Asbestos Cement	10	51	1.14 out of 5	\$442	4,338
Transmission Main	1635	P-7362	COV	Knotty Oak Rd.	12	Ductile Iron	37	24	0.14 out of 5	N/A	\$0
Transmission Main	2291	P-8253	COV	Knotty Oak Rd.	20	Asbestos Cement	587	51	1.14 out of 5	\$442	259,429
Transmission Main	2456	P-8491	COV	Knotty Oak Rd.	20	Ductile Iron	13	15	0 out of 5	N/A	\$0
Transmission Main	2457	P-7880	COV	Knotty Oak Rd.	20	Asbestos Cement	32	51	1.14 out of 5	\$442	14,115
Transmission Main	2574	P-8879	COV	Knotty Oak Rd.	20	Ductile Iron	216	15	0 out of 5	N/A	\$0
Transmission Main	2666		COV	Knotty Oak Rd.	12	Ductile Iron	18	UNK	0 out of 5	N/A	\$0
Transmission Main	2674	P-8495	COV	Knotty Oak Rd.	20	Asbestos Cement	535	51	1.14 out of 5	\$442	236,337
Transmission Main	2675	P-7279	COV	Knotty Oak Rd.	12	Asbestos Cement	19	72	1.29 out of 5	\$442	8,250
Transmission Main	2678	P-8916	COV	Knotty Oak Rd.	12	Asbestos Cement	790	57	1.14 out of 5	\$442	348,988
Transmission Main	2679	P-8916	COV	Knotty Oak Rd.	12	Asbestos Cement	674	57	1.14 out of 5	\$442	298,028
Transmission Main	2680	P-7875	COV	Knotty Oak Rd.	20	Asbestos Cement	2,331	51	1.14 out of 5	\$442	1,030,462
Distribution Main	2813	P-8245	COV	Knotty Oak Rd.	8	Asbestos Cement	575	72	1.29 out of 5	\$442	254,274
Distribution Main	2822	P-8245	COV	Knotty Oak Rd.	8	Asbestos Cement	11	72	1.29 out of 5	\$442	5,049
Distribution Main	2991	P-7274	COV	Knotty Oak Rd.	8	Asbestos Cement	5	72	1.29 out of 5	\$442	2,097
Distribution Main	2992	P-7274	COV	Knotty Oak Rd.	8	Asbestos Cement	11	72	1.29 out of 5	\$442	4,669
Distribution Main	2993	P-7317	COV	Knotty Oak Rd.	8	Asbestos Cement	4	72	1.29 out of 5	\$442	1,857
Distribution Main	2995	P-7279	COV	Knotty Oak Rd.	8	Asbestos Cement	565	72	1.29 out of 5	\$442	249,728
Distribution Main	2996	P-7279	COV	Knotty Oak Rd.	8	Asbestos Cement	272	72	1.29 out of 5	\$442	120,043
Transmission Main	3008	P-7878	COV	Knotty Oak Rd.	12	Asbestos Cement	763	57	1.14 out of 5	\$442	337,160
Transmission Main	3009	P-7323	COV	Knotty Oak Rd.	12	Asbestos Cement	118	57	1.14 out of 5	\$442	51,958
Transmission Main	3010	P-7323	COV	Knotty Oak Rd.	12	Asbestos Cement	59	57	1.14 out of 5	\$442	25,893
Transmission Main	8101	P-8488	COV	Knotty Oak Rd.	20	Ductile Iron	6	UNK	0 out of 5	N/A	\$0
Transmission Main	8102	P-8489	COV	Knotty Oak Rd.	20	Ductile Iron	25	UNK	0 out of 5	N/A	\$0
Transmission Main	8103	P-8489	COV	Knotty Oak Rd.	20	Ductile Iron	24	UNK	0 out of 5	N/A	\$0
Distribution Main	8105	P-7891	COV	Knotty Oak Rd.	8	Ductile Iron	32	30	0.14 out of 5	\$442	14,088
Transmission Main	8108	P-7890	COV	Knotty Oak Rd.	20	Ductile Iron	242	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	8109	P-7891	COV	Knotty Oak Rd.	8	Asbestos Cement	549	30	1 out of 5	\$442	242,798
Distribution Main	8110	P-7891	COV	Knotty Oak Rd.	8	Ductile Iron	27	30	0.14 out of 5	\$442	12,028
Transmission Main	8113	P-7890	COV	Knotty Oak Rd.	20	Ductile Iron	342	15	0 out of 5	N/A	\$0
Transmission Main	8114	P-7890	COV	Knotty Oak Rd.	20	Ductile Iron	49	15	0 out of 5	N/A	\$0
Transmission Main	8115	P-8879	COV	Knotty Oak Rd.	20	Ductile Iron	397	15	0 out of 5	N/A	\$0
Transmission Main	8116	P-8495	COV	Knotty Oak Rd.	20	Asbestos Cement	243	51	1.14 out of 5	\$442	107,574
Transmission Main	8117	P-8495	COV	Knotty Oak Rd.	20	Asbestos Cement	47	51	1.14 out of 5	\$442	20,813
Transmission Main	8118	P-7362	COV	Knotty Oak Rd.	12	Asbestos Cement	115	57	1.14 out of 5	\$442	50,719
Transmission Main	8119	P-7362	COV	Knotty Oak Rd.	12	Asbestos Cement	244	57	1.14 out of 5	\$442	107,720
Transmission Main	8120	P-8495	COV	Knotty Oak Rd.	20	Asbestos Cement	140	51	1.14 out of 5	\$442	61,922
Transmission Main	8121	P-8495	COV	Knotty Oak Rd.	20	Asbestos Cement	20	51	1.14 out of 5	\$442	8,688
Transmission Main	8122	P-7362	COV	Knotty Oak Rd.	12	Asbestos Cement	411	57	1.14 out of 5	\$442	181,674
Transmission Main	8216	P-6015	COV	Knotty Oak Rd.	12	Ductile Iron	241	30	0.14 out of 5	\$442	106,499
Transmission Main	10085	P-8489	COV	Knotty Oak Rd.	20	Ductile Iron	50	15	0 out of 5	N/A	\$0
Transmission Main	11045	P-7361	COV	Knotty Oak Rd.	16	Ductile Iron	2	24	0.14 out of 5	N/A	\$0
Transmission Main	11136	P-7362	COV	Knotty Oak Rd.	12	Ductile Iron	4	24	0.14 out of 5	N/A	\$0
Transmission Main	11433	P-7892	COV	Knotty Oak Rd.	20	Ductile Iron	5	UNK	0 out of 5	N/A	\$0
Transmission Main	11434	P-8488	COV	Knotty Oak Rd.	20	Ductile Iron	4	UNK	0 out of 5	N/A	\$0
Transmission Main	11435	P-8489	COV	Knotty Oak Rd.	20	Ductile Iron	16	UNK	0 out of 5	N/A	\$0
Transmission Main	11436	P-8489	COV	Knotty Oak Rd.	20	Ductile Iron	3	UNK	0 out of 5	N/A	\$0
Distribution Main	11437	P-7891	COV	Knotty Oak Rd.	8	Ductile Iron	5	30	0.14 out of 5	\$442	2,232
Distribution Main	11438	P-7891	COV	Knotty Oak Rd.	8	Asbestos Cement	257	30	1 out of 5	\$442	113,520
Distribution Main	11777	P-7279	COV	Knotty Oak Rd.	8	Asbestos Cement	5	72	1.29 out of 5	\$442	2,329
Transmission Main	11778	P-8916	COV	Knotty Oak Rd.	12	Asbestos Cement	58	57	1.14 out of 5	\$442	25,747
Transmission Main	12059	P-7782	COV	Knotty Oak Rd.	20	Ductile Iron	63	15	0 out of 5	N/A	\$0
Distribution Main	250	P-8920	COV	Knotty Oak Rd. Ps	10	Ductile Iron	28	24	0.14 out of 5	N/A	\$0
Distribution Main	497	P-8920	COV	Knotty Oak Rd. Ps	10	Ductile Iron	34	24	0.14 out of 5	N/A	\$0
Transmission Main	498	P-8924	COV	Knotty Oak Rd. Ps	12	Ductile Iron	7	24	0.14 out of 5	N/A	\$0
Distribution Main	499	P-8922	COV	Knotty Oak Rd. Ps	10	Ductile Iron	23	24	0.14 out of 5	N/A	\$0
Transmission Main	1265	P-8927	COV	Knotty Oak Rd. Ps	12	Ductile Iron	24	24	0.14 out of 5	N/A	\$0
Transmission Main	1266	P-8923	COV	Knotty Oak Rd. Ps	12	Ductile Iron	24	24	0.14 out of 5	N/A	\$0
Transmission Main	1615	P-8924	COV	Knotty Oak Rd. Ps	12	Ductile Iron	32	24	0.14 out of 5	N/A	\$0
Transmission Main	8264	P-6135	COV	Knotty Oak Road	24	Ductile Iron	233	15	0 out of 5	N/A	\$0
Transmission Main	8265	P-6135	COV	Knotty Oak Road	24	Ductile Iron	290	15	0 out of 5	N/A	\$0
Transmission Main	10399	P-6089	COV	Knotty Oak Road	24	Ductile Iron	535	15	0 out of 5	N/A	\$0
Transmission Main	11456	P-6135	COV	Knotty Oak Road	24	Ductile Iron	51	15	0 out of 5	N/A	\$0
Distribution Main	1224	P-8878	COV	Knotty Oak Shores	8	Ductile Iron	334	15	0 out of 5	N/A	\$0
Distribution Main	1225	P-8878	COV	Knotty Oak Shores	8	Ductile Iron	43	15	0 out of 5	N/A	\$0
Distribution Main	10426	P-8878	COV	Knotty Oak Shores	8	Ductile Iron	33	15	0 out of 5	N/A	\$0
Distribution Main	1444	P-7378	COV	La Casa Dr.	6	Asbestos Cement	362	49	1.85 out of 5	\$442	160,160
Distribution Main	1445	P-7378	COV	La Casa Dr.	6	Asbestos Cement	46	49	1.85 out of 5	\$442	20,403
Distribution Main	2290	P-7380	COV	La Casa Dr.	6	Asbestos Cement	358	49	1.85 out of 5	\$442	158,086
Distribution Main	11129	P-7378	COV	La Casa Dr.	6	Asbestos Cement	25	49	1.85 out of 5	\$442	10,875
Distribution Main	185	P-7369	COV	La Forge Dr.	8	Ductile Iron	11	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	447	P-7377	COV	La Forge Dr.	8	Asbestos Cement	56	51	1.14 out of 5	\$442	24,763
Distribution Main	1465	P-8850	COV	La Forge Dr.	8	Asbestos Cement	132	51	1.14 out of 5	\$442	58,147
Distribution Main	10270	P-8850	COV	La Forge Dr.	8	Asbestos Cement	15	51	1.14 out of 5	\$442	6,783
Distribution Main	1923	P-7913	COV	Labrea Way	8	Ductile Iron	470	29	0.14 out of 5	\$442	207,585
Distribution Main	1924	P-7913	COV	Labrea Way	8	Ductile Iron	222	29	0.14 out of 5	\$442	97,979
Distribution Main	1464	P-7379	COV	Laforge Drive	8	Asbestos Cement	298	51	1.14 out of 5	\$442	131,681
Distribution Main	1466	P-7369	COV	Laforge Drive	8	Asbestos Cement	72	51	1.14 out of 5	\$442	31,758
Distribution Main	1467	P-7369	COV	Laforge Drive	8	Asbestos Cement	272	51	1.14 out of 5	\$442	120,077
Distribution Main	1470	P-7377	COV	Laforge Drive	8	Asbestos Cement	313	51	1.14 out of 5	\$442	138,310
Distribution Main	1746	P-7005	COV	Lakehurst Dr.	6	Ductile Iron	601	28	0.85 out of 5	\$442	265,576
Distribution Main	7767	P-7005	COV	Lakehurst Dr.	6	Ductile Iron	55	28	0.85 out of 5	\$442	24,115
Distribution Main	11409	P-7005	COV	Lakehurst Dr.	6	Ductile Iron	29	28	0.85 out of 5	\$442	12,760
Distribution Main	36	P-7584	COV	Lakeside Dr	3	Galvanized Iron	575	86	3.43 out of 5	\$442	254,217
Distribution Main	37	P-7585	COV	Lakeside Dr	2	Galvanized Iron	283	86	3.43 out of 5	\$442	125,055
Distribution Main	9680		COV	Lakeside Dr	0.75	Copper	7	8	1.99 out of 5	N/A	\$0
Distribution Main	9681		COV	Lakeside Dr	0.75	Copper	8	8	1.99 out of 5	N/A	\$0
Distribution Main	9682		COV	Lakeside Dr	0.75	Copper	8	8	1.99 out of 5	N/A	\$0
Distribution Main	1685	P-9002	COV	Lakeside Dr.	1.5	Copper	1,284	86	2.57 out of 5	\$442	567,698
Distribution Main	1759	P-9002	COV	Lakeside Dr.	1.5	Copper	17	86	2.57 out of 5	\$442	7,594
Distribution Main	11139	P-9002	COV	Lakeside Dr.	1.5	Copper	72	86	2.57 out of 5	\$442	31,869
Distribution Main	11140	P-9002	COV	Lakeside Dr.	1.5	Copper	2	86	2.57 out of 5	\$442	951
Distribution Main	11141	P-9002	COV	Lakeside Dr.	1.5	Copper	2	86	2.57 out of 5	\$442	878
Distribution Main	1851	P-8320	COV	Lambert St.	1	Unknown	218	22	1.57 out of 5	N/A	\$0
Distribution Main	8390	P-1224	COV	Lamphear St	8	Ductile Iron	23	10	0 out of 5	N/A	\$0
Distribution Main	8461	P-1224	COV	Lamphear St	6	Ductile Iron	5	10	0.71 out of 5	N/A	\$0
Distribution Main	10177		COV	Lamphear St	1.5	PVC	10	10	1.71 out of 5	N/A	\$0
Distribution Main	1595	P-7771	COV	Lantern Ln.	8	Ductile Iron	42	59	0.29 out of 5	\$442	18,778
Distribution Main	2256	P-7771	COV	Lantern Ln.	6	Asbestos Cement	23	59	1.85 out of 5	\$442	10,374
Distribution Main	2257	P-7771	COV	Lantern Ln.	6	Asbestos Cement	399	59	1.85 out of 5	\$442	176,171
Distribution Main	418	P-7703	COV	Larch Dr.	6	Asbestos Cement	16	60	1.85 out of 5	\$442	6,921
Distribution Main	419	P-7703	COV	Larch Dr.	6	Asbestos Cement	564	60	1.85 out of 5	\$442	249,340
Distribution Main	1452	P-7704	COV	Larch Dr.	6	Asbestos Cement	162	60	1.85 out of 5	\$442	71,656
Distribution Main	1454		COV	Larch Dr.	6	Asbestos Cement	7	60	1.85 out of 5	\$442	3,278
Distribution Main	1646	P-7698	COV	Larch Dr.	8	Asbestos Cement	13	60	1.14 out of 5	\$442	5,749
Distribution Main	1647	P-7698	COV	Larch Dr.	8	Asbestos Cement	207	60	1.14 out of 5	\$442	91,554
Distribution Main	2594	P-7702	COV	Larch Dr.	6	Asbestos Cement	638	60	1.85 out of 5	\$442	282,024
Distribution Main	2595	P-7698	COV	Larch Dr.	8	Asbestos Cement	50	60	1.14 out of 5	\$442	21,959
Distribution Main	11026	P-7698	COV	Larch Dr.	8	Asbestos Cement	28	60	1.14 out of 5	\$442	12,172
Distribution Main	1856	P-7600	COV	Larchmont Dr.	8	Asbestos Cement	959	53	1.14 out of 5	\$442	424,039
Distribution Main	1857	P-7600	COV	Larchmont Dr.	8	Asbestos Cement	163	53	1.14 out of 5	\$442	71,967
Distribution Main	2637	P-7599	COV	Larchmont Dr.	8	Asbestos Cement	203	53	1.14 out of 5	\$442	89,796
Distribution Main	7878	P-7303	COV	Laura Ct.	8	Asbestos Cement	27	34	1 out of 5	\$442	12,021
Distribution Main	7879	P-7303	COV	Laura Ct.	8	Asbestos Cement	345	34	1 out of 5	\$442	152,393
Distribution Main	832	P-7828	COV	Laurel Ave.	6	Cast Iron	181	132	2.57 out of 5	\$442	79,927

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	833	P-7829	COV	Laurel Ave.	6	Cast Iron	234	132	2.57 out of 5	\$442	103,235
Distribution Main	839	P-7830	COV	Laurel Ave.	6	Cast Iron	109	132	2.57 out of 5	\$442	48,368
Distribution Main	840	P-7830	COV	Laurel Ave.	6	Cast Iron	27	132	2.57 out of 5	\$442	12,014
Distribution Main	841	P-7826	COV	Laurel Ave.	6	Asbestos Cement	304	52	1.85 out of 5	\$442	134,264
Distribution Main	1482	P-7820	COV	Laurel Ave.	6	Asbestos Cement	268	52	1.85 out of 5	\$442	118,550
Distribution Main	1494	P-7839	COV	Laurel Ave.	6	Asbestos Cement	69	50	1.85 out of 5	\$442	30,471
Distribution Main	3150	P-7826	COV	Laurel Ave.	6	Asbestos Cement	25	52	1.85 out of 5	\$442	11,133
Distribution Main	3152	P-7862	COV	Laurel Ave.	6	Cast Iron	48	132	2.57 out of 5	\$442	21,103
Distribution Main	3158	P-7821	COV	Laurel Ave.	6	Asbestos Cement	257	52	1.85 out of 5	\$442	113,674
Distribution Main	3159	P-7821	COV	Laurel Ave.	6	Asbestos Cement	3	52	1.85 out of 5	\$442	1,395
Distribution Main	3161	P-7839	COV	Laurel Ave.	6	Asbestos Cement	144	50	1.85 out of 5	\$442	63,550
Distribution Main	3162	P-7840	COV	Laurel Ave.	6	Asbestos Cement	217	50	1.85 out of 5	\$442	95,774
Distribution Main	3163	P-7840	COV	Laurel Ave.	6	Asbestos Cement	317	52	1.85 out of 5	\$442	139,954
Distribution Main	10112	P-7839	COV	Laurel Ave.	6	Asbestos Cement	4	50	1.85 out of 5	\$442	1,709
Distribution Main	11091	P-7826	COV	Laurel Ave.	6	Asbestos Cement	13	52	1.85 out of 5	\$442	5,720
Distribution Main	6460	P-7463	COV	Laurie Ave.	6	Asbestos Cement	596	49	1.85 out of 5	\$442	263,572
Distribution Main	423	P-7624	COV	Lawnwood Rd.	6	Asbestos Cement	173	50	1.85 out of 5	\$442	76,249
Distribution Main	424	P-7624	COV	Lawnwood Rd.	6	Asbestos Cement	17	50	1.85 out of 5	\$442	7,551
Distribution Main	2557	P-7624	COV	Lawnwood Rd.	6	Asbestos Cement	319	50	1.85 out of 5	\$442	141,066
Distribution Main	2558	P-7625	COV	Lawnwood Rd.	6	Asbestos Cement	64	50	1.85 out of 5	\$442	28,405
Distribution Main	2620	P-7625	COV	Lawnwood Rd.	6	Asbestos Cement	292	50	1.85 out of 5	\$442	128,892
Distribution Main	7758	P-7224	COV	Leader St.	6	Asbestos Cement	234	69	2 out of 5	\$442	103,312
Distribution Main	7761	P-7225	COV	Leader St.	6	Asbestos Cement	209	69	2 out of 5	\$442	92,261
Distribution Main	9803	P-7224	COV	Leader St.	6	Asbestos Cement	37	69	2 out of 5	\$442	16,407
Distribution Main	1868	P-7630	COV	Ledo St.	6	Asbestos Cement	496	57	1.85 out of 5	\$442	219,129
Distribution Main	10446	P-7952	COV	Leisure Way	8	Ductile Iron	64	UNK	0 out of 5	N/A	\$0
Distribution Main	4073	P-8135	COV	Lemis St.	6	Asbestos Cement	672	59	1.85 out of 5	\$442	297,063
Distribution Main	4074	P-8135	COV	Lemis St.	6	Asbestos Cement	359	59	1.85 out of 5	\$442	158,654
Distribution Main	8776	P-8899	COV	Leuba Rd	8	Ductile Iron	43	26	0.14 out of 5	\$442	19,027
Distribution Main	10423	P-8899	COV	Leuba Rd	8	Ductile Iron	39	8	0 out of 5	N/A	\$0
Distribution Main	852	P-7194	COV	Leuba Rd.	8	Asbestos Cement	110	45	1.14 out of 5	\$442	48,802
Distribution Main	7503	P-7192	COV	Leuba Rd.	8	Ductile Iron	149	26	0.14 out of 5	\$442	66,032
Distribution Main	7504	P-7192	COV	Leuba Rd.	8	Ductile Iron	642	26	0.14 out of 5	\$442	283,845
Distribution Main	7870	P-7197	COV	Leuba Rd.	8	Asbestos Cement	616	45	1.14 out of 5	\$442	272,097
Distribution Main	7945	P-7196	COV	Leuba Rd.	8	Asbestos Cement	309	45	1.14 out of 5	\$442	136,541
Distribution Main	7946	P-7196	COV	Leuba Rd.	8	Asbestos Cement	218	45	1.14 out of 5	\$442	96,432
Distribution Main	8775	P-7192	COV	Leuba Rd.	8	Ductile Iron	68	26	0.14 out of 5	\$442	30,132
Distribution Main	10109	P-7192	COV	Leuba Rd.	8	Ductile Iron	25	26	0.14 out of 5	\$442	11,157
Distribution Main	10424	P-7192	COV	Leuba Rd.	8	Ductile Iron	265	26	0.14 out of 5	\$442	117,009
Distribution Main	10425	P-7192	COV	Leuba Rd.	8	Ductile Iron	576	26	0.14 out of 5	\$442	254,479
Distribution Main	11980	P-7192	COV	Leuba Rd.	8	Ductile Iron	474	26	0.14 out of 5	\$442	209,428
Distribution Main	94	P-8873	COV	Leveilee St	8	Ductile Iron	19	15	0 out of 5	N/A	\$0
Distribution Main	2454	P-8102	COV	Levielle Street	6	Cast Iron	622	132	2.57 out of 5	\$442	275,110
Distribution Main	2455	P-8102	COV	Levielle Street	6	Cast Iron	13	132	2.57 out of 5	\$442	5,541

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	8524	P-8842	COV	Lincoln Ave	16	Ductile Iron	88	13	0 out of 5	N/A	\$0
Transmission Main	8859	P-8219	COV	Lincoln Ave	12	Ductile Iron	42	13	0 out of 5	N/A	\$0
Distribution Main	8860		COV	Lincoln Ave	6	Ductile Iron	24	12	0.71 out of 5	N/A	\$0
Transmission Main	8861	P-8754	COV	Lincoln Ave	12	Ductile Iron	72	12	0 out of 5	N/A	\$0
Transmission Main	8862	P-8842	COV	Lincoln Ave	16	Ductile Iron	84	12	0 out of 5	N/A	\$0
Transmission Main	8863	P-8754	COV	Lincoln Ave	16	Ductile Iron	258	12	0 out of 5	N/A	\$0
Distribution Main	8864	P-8843	COV	Lincoln Ave	8	Ductile Iron	9	12	0 out of 5	N/A	\$0
Distribution Main	8865	P-8843	COV	Lincoln Ave	8	Ductile Iron	29	12	0 out of 5	N/A	\$0
Distribution Main	9685		COV	Lincoln Ave	8	Ductile Iron	7	12	0 out of 5	N/A	\$0
Distribution Main	229	P-8367	COV	Lincoln Ave.	8	Ductile Iron	259	18	0 out of 5	N/A	\$0
Transmission Main	238	P-8368	COV	Lincoln Ave.	16	Asbestos Cement	107	62	1.29 out of 5	\$442	47,267
Distribution Main	1419	P-8367	COV	Lincoln Ave.	8	Ductile Iron	47	18	0 out of 5	N/A	\$0
Distribution Main	1420	P-8367	COV	Lincoln Ave.	8	Ductile Iron	2	18	0 out of 5	N/A	\$0
Transmission Main	10439	P-8840	COV	Lincoln Ave.	16	Ductile Iron	13	10	0 out of 5	N/A	\$0
Transmission Main	10963	P-8368	COV	Lincoln Ave.	16	Asbestos Cement	17	62	1.29 out of 5	\$442	7,547
Transmission Main	11037	P-8368	COV	Lincoln Ave.	16	Asbestos Cement	24	62	1.29 out of 5	\$442	10,418
Transmission Main	11038	P-8840	COV	Lincoln Ave.	16	Ductile Iron	13	10	0 out of 5	N/A	\$0
Transmission Main	11657	P-8840	COV	Lincoln Ave.	16	Ductile Iron	5	10	0 out of 5	N/A	\$0
Distribution Main	7940	P-7234	COV	Linda Ct.	6	Asbestos Cement	39	51	1.85 out of 5	\$442	17,079
Distribution Main	7941	P-7234	COV	Linda Ct.	6	Asbestos Cement	206	51	1.85 out of 5	\$442	91,059
Distribution Main	7827	P-7059	COV	Linden Ln.	6	Asbestos Cement	377	46	1.85 out of 5	\$442	166,576
Distribution Main	4060	P-8148	COV	Linray St.	6	Asbestos Cement	23	54	1.85 out of 5	\$442	10,092
Distribution Main	4061	P-8148	COV	Linray St.	6	Asbestos Cement	196	54	1.85 out of 5	\$442	86,639
Distribution Main	4955		COV	Linray St.	6	Asbestos Cement	16	54	1.85 out of 5	\$442	7,157
Distribution Main	2751	P-7470	COV	Linwood Dr.	6	Asbestos Cement	285	56	1.85 out of 5	\$442	126,113
Distribution Main	2753	P-8515	COV	Linwood Dr.	6	Asbestos Cement	11	56	1.85 out of 5	\$442	4,739
Distribution Main	2771	P-7478	COV	Linwood Dr.	6	Asbestos Cement	199	56	1.85 out of 5	\$442	88,141
Distribution Main	6458	P-7459	COV	Linwood Dr.	6	Asbestos Cement	189	57	1.85 out of 5	\$442	83,339
Distribution Main	6459	P-7459	COV	Linwood Dr.	6	Asbestos Cement	340	57	1.85 out of 5	\$442	150,296
Distribution Main	7440	P-7470	COV	Linwood Dr.	6	Asbestos Cement	40	57	1.85 out of 5	\$442	17,701
Distribution Main	7442	P-7464	COV	Linwood Dr.	6	Asbestos Cement	317	57	1.85 out of 5	\$442	140,059
Distribution Main	11187	P-7470	COV	Linwood Dr.	6	Asbestos Cement	99	56	1.85 out of 5	\$442	43,616
Distribution Main	1663	P-7618	COV	Lionel Ave.	8	Asbestos Cement	273	60	1.14 out of 5	\$442	120,687
Distribution Main	1839	P-7610	COV	Lionel Ave.	8	Asbestos Cement	516	60	1.14 out of 5	\$442	227,917
Distribution Main	1840	P-7615	COV	Lionel Ave.	8	Asbestos Cement	434	60	1.14 out of 5	\$442	191,761
Distribution Main	1841	P-7615	COV	Lionel Ave.	8	Asbestos Cement	41	60	1.14 out of 5	\$442	18,129
Distribution Main	9506	P-8942	COV	Lionel Ave.	8	Ductile Iron	62	19	0 out of 5	N/A	\$0
Distribution Main	2536	P-8154	COV	Lions Dr.	8	Asbestos Cement	23	46	1.14 out of 5	\$442	10,227
Distribution Main	4567	P-8154	COV	Lions Dr.	8	Asbestos Cement	398	46	1.14 out of 5	\$442	175,785
Distribution Main	7868	P-7245	COV	Lloyd Dr.	8	Asbestos Cement	327	56	1.14 out of 5	\$442	144,683
Distribution Main	7869	P-7245	COV	Lloyd Dr.	8	Asbestos Cement	49	56	1.14 out of 5	\$442	21,780
Distribution Main	7927	P-7238	COV	Lloyd Dr.	8	Asbestos Cement	332	56	1.14 out of 5	\$442	146,598
Distribution Main	7928	P-7238	COV	Lloyd Dr.	8	Asbestos Cement	5	56	1.14 out of 5	\$442	2,077
Distribution Main	7942	P-7243	COV	Lloyd Dr.	8	Asbestos Cement	580	56	1.14 out of 5	\$442	256,453

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7943	P-7247	COV	Lloyd Dr.	8	Asbestos Cement	254	56	1.14 out of 5	\$442	112,346
Distribution Main	2372	P-8323	COV	Locust St.	8	Ductile Iron	270	18	0 out of 5	N/A	\$0
Distribution Main	197	P-7281	COV	Long Pond Rd.	8	Asbestos Cement	337	60	1.14 out of 5	\$442	148,823
Distribution Main	198	P-7280	COV	Long Pond Rd.	8	Asbestos Cement	225	60	1.14 out of 5	\$442	99,280
Distribution Main	1953	P-7285	COV	Long Pond Rd.	8	Asbestos Cement	507	60	1.14 out of 5	\$442	224,140
Distribution Main	11029	P-7285	COV	Long Pond Rd.	8	Asbestos Cement	28	60	1.14 out of 5	\$442	12,467
Distribution Main	2531	P-8155	COV	Longfellow Dr.	8	Asbestos Cement	351	46	1.14 out of 5	\$442	155,303
Distribution Main	2532	P-8155	COV	Longfellow Dr.	8	Asbestos Cement	40	46	1.14 out of 5	\$442	17,733
Distribution Main	2533	P-8153	COV	Longfellow Dr.	8	Asbestos Cement	242	46	1.14 out of 5	\$442	107,047
Distribution Main	2539	P-8156	COV	Longfellow Dr.	8	Asbestos Cement	11	46	1.14 out of 5	\$442	4,992
Distribution Main	4564	P-8159	COV	Longfellow Dr.	8	Asbestos Cement	23	46	1.14 out of 5	\$442	10,125
Distribution Main	4565	P-8156	COV	Longfellow Dr.	8	Asbestos Cement	105	46	1.14 out of 5	\$442	46,598
Distribution Main	4566	P-8156	COV	Longfellow Dr.	8	Asbestos Cement	185	46	1.14 out of 5	\$442	81,769
Distribution Main	4568	P-8159	COV	Longfellow Dr.	8	Asbestos Cement	265	46	1.14 out of 5	\$442	117,111
Distribution Main	4569	P-8159	COV	Longfellow Dr.	8	Asbestos Cement	482	46	1.14 out of 5	\$442	213,233
Distribution Main	11176	P-8156	COV	Longfellow Dr.	8	Asbestos Cement	2	46	1.14 out of 5	\$442	1,027
Distribution Main	2788	P-7653	COV	Loretta Ave.	8	Ductile Iron	228	18	0 out of 5	N/A	\$0
Distribution Main	38	P-7467	COV	Lorraine Ave	6	Asbestos Cement	797	60	1.85 out of 5	\$442	352,334
Distribution Main	39	P-7467	COV	Lorraine Ave	6	Asbestos Cement	421	60	1.85 out of 5	\$442	186,023
Distribution Main	2752	P-7476	COV	Lorraine Ave.	6	Asbestos Cement	20	60	1.85 out of 5	\$442	8,876
Distribution Main	2980	P-7512	COV	Lowell St.	6	Asbestos Cement	456	70	2 out of 5	\$442	201,460
Distribution Main	4787	P-7512	COV	Lowell St.	6	Asbestos Cement	7	70	2 out of 5	\$442	3,170
Distribution Main	5343	P-7516	COV	Lowell St.	6	Asbestos Cement	192	70	2 out of 5	\$442	85,056
Distribution Main	5344	P-7516	COV	Lowell St.	6	Asbestos Cement	38	70	2 out of 5	\$442	16,776
Distribution Main	549	P-7680	COV	Lydia Rd.	8	Asbestos Cement	40	56	1.14 out of 5	\$442	17,619
Distribution Main	550	P-7680	COV	Lydia Rd.	8	Asbestos Cement	708	56	1.14 out of 5	\$442	312,820
Distribution Main	553	P-7681	COV	Lydia Rd.	8	Asbestos Cement	27	56	1.14 out of 5	\$442	12,072
Distribution Main	2554	P-7677	COV	Lydia Rd.	8	Asbestos Cement	241	56	1.14 out of 5	\$442	106,564
Distribution Main	2559	P-7669	COV	Lydia Rd.	8	Asbestos Cement	255	56	1.14 out of 5	\$442	112,791
Distribution Main	2561	P-7676	COV	Lydia Rd.	8	Asbestos Cement	261	56	1.14 out of 5	\$442	115,277
Distribution Main	2603	P-8973	COV	Lydia Rd.	8	Asbestos Cement	605	56	1.14 out of 5	\$442	267,596
Distribution Main	2608	P-7669	COV	Lydia Rd.	8	Asbestos Cement	7	56	1.14 out of 5	\$442	2,891
Distribution Main	11178	P-8973	COV	Lydia Rd.	8	Asbestos Cement	136	56	1.14 out of 5	\$442	60,092
Transmission Main	5253	P-7065	COV	Lynn Dr.	12	PVC	553	32	0.43 out of 5	\$442	244,408
Transmission Main	5254	P-7065	COV	Lynn Dr.	12	PVC	260	32	0.43 out of 5	\$442	115,139
Transmission Main	5255	P-7061	COV	Lynn Dr.	12	PVC	8	32	0.43 out of 5	\$442	3,659
Transmission Main	5256	P-7061	COV	Lynn Dr.	12	PVC	268	32	0.43 out of 5	\$442	118,626
Transmission Main	7813	P-7077	COV	Lynn Dr.	12	PVC	297	32	0.43 out of 5	\$442	131,401
Transmission Main	8674	P-7062	COV	Lynn Dr.	12	PVC	198	32	0.43 out of 5	\$442	87,657
Transmission Main	11293	P-7065	COV	Lynn Dr.	12	PVC	14	32	0.43 out of 5	\$442	6,311
Transmission Main	11491	P-7062	COV	Lynn Dr.	12	PVC	12	32	0.43 out of 5	\$442	5,328
Distribution Main	402	P-8008	COV	Macarthur Blvd.	8	Asbestos Cement	371	71	1.29 out of 5	\$442	163,893
Distribution Main	403	P-8008	COV	Macarthur Blvd.	8	Asbestos Cement	822	71	1.29 out of 5	\$442	363,318
Distribution Main	406	P-7985	COV	Macarthur Blvd.	8	Asbestos Cement	857	71	1.29 out of 5	\$442	378,954

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	414	P-7997	COV	Macarthur Blvd.	8	Asbestos Cement	265	71	1.29 out of 5	\$442	117,249
Distribution Main	415	P-8004	COV	Macarthur Blvd.	8	Asbestos Cement	137	71	1.29 out of 5	\$442	60,709
Distribution Main	416	P-7998	COV	Macarthur Blvd.	8	Asbestos Cement	30	71	1.29 out of 5	\$442	13,477
Distribution Main	417	P-7998	COV	Macarthur Blvd.	8	Asbestos Cement	123	71	1.29 out of 5	\$442	54,489
Distribution Main	2130		COV	Macarthur Blvd.	8	Asbestos Cement	15	71	1.29 out of 5	\$442	6,738
Distribution Main	2133	P-7993	COV	Macarthur Blvd.	8	Asbestos Cement	261	71	1.29 out of 5	\$442	115,421
Distribution Main	2134	P-9053	COV	Macarthur Blvd.	8	Asbestos Cement	273	71	1.29 out of 5	\$442	120,610
Distribution Main	3018	P-7986	COV	Macarthur Blvd.	8	Asbestos Cement	24	71	1.29 out of 5	\$442	10,697
Distribution Main	3019	P-7986	COV	Macarthur Blvd.	8	Asbestos Cement	480	71	1.29 out of 5	\$442	212,006
Distribution Main	3043	P-8008	COV	Macarthur Blvd.	8	Asbestos Cement	4	71	1.29 out of 5	\$442	1,725
Distribution Main	10064	P-7997	COV	Macarthur Blvd.	8	Asbestos Cement	4	71	1.29 out of 5	\$442	1,600
Distribution Main	1910	P-8958	COV	Magnolia Ln.	8	Asbestos Cement	5	51	1.14 out of 5	\$442	2,314
Distribution Main	2970	P-8958	COV	Magnolia Ln.	8	Asbestos Cement	52	51	1.14 out of 5	\$442	23,026
Distribution Main	7706	P-7018	COV	Magnolia Ln.	8	Asbestos Cement	612	51	1.14 out of 5	\$442	270,437
Distribution Main	7708	P-7014	COV	Magnolia Ln.	8	Asbestos Cement	6	51	1.14 out of 5	\$442	2,796
Distribution Main	7711	P-7016	COV	Magnolia Ln.	8	Asbestos Cement	1,011	51	1.14 out of 5	\$442	446,821
Distribution Main	7712	P-7016	COV	Magnolia Ln.	8	Asbestos Cement	63	51	1.14 out of 5	\$442	27,683
Distribution Main	7713	P-7021	COV	Magnolia Ln.	8	Asbestos Cement	408	51	1.14 out of 5	\$442	180,245
Distribution Main	7720	P-7016	COV	Magnolia Ln.	8	Asbestos Cement	14	51	1.14 out of 5	\$442	6,338
Distribution Main	7721	P-7014	COV	Magnolia Ln.	8	Asbestos Cement	193	51	1.14 out of 5	\$442	85,310
Distribution Main	7722	P-7014	COV	Magnolia Ln.	8	Asbestos Cement	8	51	1.14 out of 5	\$442	3,501
Distribution Main	7728	P-7020	COV	Magnolia Ln.	8	Asbestos Cement	165	51	1.14 out of 5	\$442	73,076
Distribution Main	7729	P-7020	COV	Magnolia Ln.	8	Asbestos Cement	54	51	1.14 out of 5	\$442	23,725
Distribution Main	11402	P-7018	COV	Magnolia Ln.	8	Asbestos Cement	3	51	1.14 out of 5	\$442	1,253
Distribution Main	11406	P-7014	COV	Magnolia Ln.	8	Asbestos Cement	7	51	1.14 out of 5	\$442	3,135
Distribution Main	11408	P-7020	COV	Magnolia Ln.	8	Asbestos Cement	28	51	1 out of 5	\$442	12,466
Distribution Main	8761	P-8904	COV	Main St	8	Ductile Iron	43	8	0 out of 5	N/A	\$0
Transmission Main	8762	P-8904	COV	Main St	16	Ductile Iron	584	8	0 out of 5	N/A	\$0
Transmission Main	8763	P-8904	COV	Main St	16	Ductile Iron	109	8	0 out of 5	N/A	\$0
Transmission Main	8764	P-8904	COV	Main St	16	Ductile Iron	100	8	0 out of 5	N/A	\$0
Distribution Main	9347		COV	Main St	8	Ductile Iron	6	8	0 out of 5	N/A	\$0
Distribution Main	10200		COV	Main St	6	Ductile Iron	2	5	0.71 out of 5	N/A	\$0
Distribution Main	11504	P-8904	COV	Main St	8	Ductile Iron	14	8	0 out of 5	N/A	\$0
Distribution Main	11505	P-8904	COV	Main St	8	Ductile Iron	18	8	0 out of 5	N/A	\$0
Transmission Main	227	P-8374	COV	Main St.	12	Cast Iron	11	133	1.86 out of 5	\$442	5,033
Transmission Main	234	P-8373	COV	Main St.	12	Cast Iron	381	133	1.86 out of 5	\$442	168,402
Transmission Main	235	P-8373	COV	Main St.	12	Cast Iron	411	133	1.86 out of 5	\$442	181,870
Transmission Main	239	P-8375	COV	Main St.	12	Cast Iron	305	133	1.86 out of 5	\$442	134,964
Transmission Main	244	P-8828	COV	Main St.	12	Cast Iron	132	133	1.86 out of 5	\$442	58,469
Distribution Main	579	P-8912	COV	Main St.	8	Cast Iron	375	129	1.86 out of 5	\$442	165,713
Distribution Main	580		COV	Main St.	8	Cast Iron	14	129	1.86 out of 5	\$442	5,976
Transmission Main	667	P-8544	COV	Main St.	12	Cast Iron	91	133	1.86 out of 5	\$442	40,201
Transmission Main	789	P-7848	COV	Main St.	16	Cast Iron	222	129	1.86 out of 5	\$442	98,315
Transmission Main	796	P-7587	COV	Main St.	16	Ductile Iron	617	0	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	797	P-7846	COV	Main St.	12	Ductile Iron	290	0	0 out of 5	N/A	\$0
Transmission Main	798	P-7846	COV	Main St.	12	Ductile Iron	585	0	0 out of 5	N/A	\$0
Distribution Main	1013		COV	Main St.	6	Unknown	23	UNK	0.71 out of 5	\$442	10,132
Transmission Main	1053	P-8544	COV	Main St.	12	Cast Iron	106	133	1.86 out of 5	\$442	46,934
Transmission Main	1054	P-8544	COV	Main St.	12	Cast Iron	831	133	1.86 out of 5	\$442	367,232
Distribution Main	1055		COV	Main St.	6	Unknown	38	UNK	0.71 out of 5	\$442	16,833
Distribution Main	1056		COV	Main St.	6	Unknown	28	UNK	0.71 out of 5	\$442	12,580
Transmission Main	1188	P-8132	COV	Main St.	12	Cast Iron	205	119	1.86 out of 5	\$442	90,703
Transmission Main	1189	P-8132	COV	Main St.	12	Cast Iron	166	133	1.86 out of 5	\$442	73,446
Transmission Main	1312	P-8544	COV	Main St.	12	Cast Iron	48	133	1.86 out of 5	\$442	21,085
Transmission Main	1313	P-8544	COV	Main St.	12	Cast Iron	430	133	1.86 out of 5	\$442	190,123
Transmission Main	1314	P-8544	COV	Main St.	12	Cast Iron	334	133	1.86 out of 5	\$442	147,602
Transmission Main	2288	P-7258	COV	Main St.	12	Ductile Iron	651	0	0 out of 5	N/A	\$0
Transmission Main	2810	P-7260	COV	Main St.	12	Ductile Iron	144	0	0 out of 5	N/A	\$0
Transmission Main	2811	P-7260	COV	Main St.	12	Ductile Iron	536	0	0 out of 5	N/A	\$0
Distribution Main	2821	P-7256	COV	Main St.	8	Cast Iron	228	129	1.86 out of 5	\$442	100,908
Transmission Main	2823	P-7260	COV	Main St.	16	Ductile Iron	16	0	0 out of 5	N/A	\$0
Distribution Main	2990	P-8912	COV	Main St.	8	Cast Iron	85	129	2.57 out of 5	\$442	37,724
Transmission Main	2999	P-7844	COV	Main St.	12	Ductile Iron	72	0	0 out of 5	N/A	\$0
Transmission Main	3000	P-7844	COV	Main St.	12	Ductile Iron	281	0	0 out of 5	N/A	\$0
Transmission Main	5054	P-7258	COV	Main St.	16	Cast Iron	3	129	1.86 out of 5	\$442	1,246
Transmission Main	9686	P-1251	COV	Main St.	12	Ductile Iron	15	12	0 out of 5	N/A	\$0
Transmission Main	9687	P-1251	COV	Main St.	12	Ductile Iron	6	12	0 out of 5	N/A	\$0
Distribution Main	10127	P-7255	COV	Main St.	8	Cast Iron	10	129	1.86 out of 5	\$442	4,321
Transmission Main	10596	P-7848	COV	Main St.	16	Ductile Iron	13	2	0 out of 5	N/A	\$0
Distribution Main	10684		COV	Main St.	10	Ductile Iron	58	1	0 out of 5	N/A	\$0
Distribution Main	10685		COV	Main St.	3	Cast Iron	59	UNK	2.56 out of 5	\$442	26,245
Distribution Main	10689		COV	Main St.	2	Copper	10	UNK	1.99 out of 5	\$442	4,531
Distribution Main	10690		COV	Main St.	10	Cast Iron	27	UNK	1.14 out of 5	\$442	12,045
Transmission Main	10985	P-8373	COV	Main St.	12	Cast Iron	7	133	1.86 out of 5	\$442	3,188
Transmission Main	11009	P-7844	COV	Main St.	16	Ductile Iron	4	2	0 out of 5	N/A	\$0
Transmission Main	11082	P-8544	COV	Main St.	12	Cast Iron	80	133	1.86 out of 5	\$442	35,330
Transmission Main	11083	P-8544	COV	Main St.	12	Cast Iron	15	133	1.86 out of 5	\$442	6,541
Transmission Main	11084	P-8544	COV	Main St.	12	Cast Iron	30	133	1.86 out of 5	\$442	13,048
Transmission Main	11089	P-7587	COV	Main St.	16	Cast Iron	20	129	1.86 out of 5	\$442	8,966
Transmission Main	11124	P-8544	COV	Main St.	12	Cast Iron	7	133	1.86 out of 5	\$442	3,099
Transmission Main	11862	P-8373	COV	Main St.	12	Cast Iron	186	133	1.86 out of 5	\$442	82,111
Transmission Main	11863	P-8373	COV	Main St.	12	Cast Iron	32	133	1.86 out of 5	\$442	14,131
Transmission Main	12163	P-8375	COV	Main St.	12	Cast Iron	100	133	1.86 out of 5	\$442	44,010
Transmission Main	12164	P-8375	COV	Main St.	12	Cast Iron	16	133	1.86 out of 5	\$442	6,957
Transmission Main	8111	P-6087	COV	Main St. (Sci)	24	Ductile Iron	1,191	15	0 out of 5	N/A	\$0
Transmission Main	8112	P-6087	COV	Main St. (Sci)	24	Ductile Iron	1,001	15	0 out of 5	N/A	\$0
Transmission Main	8268	P-6135	COV	Main St. (Sci)	24	Ductile Iron	88	15	0 out of 5	N/A	\$0
Distribution Main	7844	P-8910	COV	Main Street	8	Ductile Iron	154	0	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7845	P-8910	COV	Main Street	8	Ductile Iron	17	0	0 out of 5	N/A	\$0
Distribution Main	7846	P-8910	COV	Main Street	6	Asbestos Cement	5	UNK	1.56 out of 5	\$442	2,384
Distribution Main	7847	P-8910	COV	Main Street	6	Asbestos Cement	537	UNK	1.56 out of 5	\$442	237,224
Distribution Main	7850	P-8911	COV	Main Street	8	Ductile Iron	199	0	0 out of 5	N/A	\$0
Distribution Main	7851	P-8911	COV	Main Street	8	Ductile Iron	761	0	0 out of 5	N/A	\$0
Transmission Main	9435	P-8910	COV	Main Street	12	Ductile Iron	590	0	0 out of 5	N/A	\$0
Distribution Main	9436	P-7255	COV	Main Street	8	Ductile Iron	312	0	0 out of 5	N/A	\$0
Distribution Main	732	P-7632	COV	Majorie St.	6	Asbestos Cement	242	57	1.85 out of 5	\$442	106,947
Distribution Main	745	P-7633	COV	Majorie St.	6	Asbestos Cement	391	57	1.85 out of 5	\$442	172,946
Distribution Main	520	P-7937	COV	Manning Ct.	6	Asbestos Cement	323	60	1.85 out of 5	\$442	142,845
Distribution Main	1140	P-7937	COV	Manning Ct.	8	Ductile Iron	56	15	0 out of 5	N/A	\$0
Distribution Main	1141	P-7937	COV	Manning Ct.	8	Ductile Iron	5	15	0 out of 5	N/A	\$0
Distribution Main	10449		COV	Manning Ct.	0.75	Copper	62	UNK	1.99 out of 5	\$442	27,258
Distribution Main	10450		COV	Manning Ct.	0.75	Copper	102	UNK	1.99 out of 5	\$442	44,938
Distribution Main	11071	P-7937	COV	Manning Ct.	6	Asbestos Cement	6	60	1.85 out of 5	\$442	2,702
Distribution Main	1661	P-7527	COV	Manor Dr.	6	Asbestos Cement	500	58	1.85 out of 5	\$442	220,823
Distribution Main	5332	P-7527	COV	Manor Dr.	6	Asbestos Cement	80	58	1.85 out of 5	\$442	35,186
Distribution Main	5335	P-8940	COV	Manor Dr.	6	Asbestos Cement	16	58	1.85 out of 5	\$442	6,882
Distribution Main	5336	P-8940	COV	Manor Dr.	6	Asbestos Cement	274	58	1.85 out of 5	\$442	121,100
Distribution Main	7783	P-7422	COV	Maple Root Rd.	6	Asbestos Cement	930	54	1.85 out of 5	\$442	411,005
Distribution Main	788	P-7270	COV	Maple St.	8	Asbestos Cement	354	63	1.29 out of 5	\$442	156,284
Distribution Main	800	P-7270	COV	Maple St.	8	Asbestos Cement	640	63	1.29 out of 5	\$442	282,897
Distribution Main	801	P-7268	COV	Maple St.	8	Asbestos Cement	135	63	1.29 out of 5	\$442	59,659
Distribution Main	1261		COV	Maple St.	8	Asbestos Cement	3	63	1.29 out of 5	\$442	1,325
Distribution Main	2816	P-7268	COV	Maple St.	8	Asbestos Cement	935	63	1.29 out of 5	\$442	413,474
Distribution Main	2994		COV	Maple St.	6	Asbestos Cement	346	63	2 out of 5	\$442	152,738
Distribution Main	3001		COV	Maple St.	6	Unknown	8	UNK	0.71 out of 5	\$442	3,551
Distribution Main	396	P-7854	COV	Mapledale St.	4	Cast Iron	310	129	3.29 out of 5	\$442	136,848
Distribution Main	397	P-7855	COV	Mapledale St.	4	Cast Iron	13	129	3.29 out of 5	\$442	5,925
Distribution Main	398	P-7855	COV	Mapledale St.	4	Cast Iron	406	129	3.29 out of 5	\$442	179,352
Distribution Main	1286	P-7853	COV	Mapledale St.	6	Cast Iron	416	81	2.43 out of 5	\$442	183,840
Distribution Main	1287	P-7853	COV	Mapledale St.	6	Cast Iron	20	81	2.43 out of 5	\$442	8,647
Distribution Main	9626	P-7856	COV	Mapledale St.	4	Cast Iron	74	129	3.29 out of 5	\$442	32,525
Distribution Main	585	P-7325	COV	Maplewood Dr.	8	Asbestos Cement	699	55	1.14 out of 5	\$442	309,048
Distribution Main	586	P-7325	COV	Maplewood Dr.	8	Asbestos Cement	437	55	1.14 out of 5	\$442	193,182
Distribution Main	3067	P-7885	COV	Marie Dr.	8	Asbestos Cement	64	50	1.14 out of 5	\$442	28,130
Distribution Main	3068	P-7885	COV	Marie Dr.	8	Asbestos Cement	936	50	1.14 out of 5	\$442	413,535
Distribution Main	3069	P-7884	COV	Marie Dr.	8	Asbestos Cement	532	50	1.14 out of 5	\$442	235,068
Distribution Main	10428	P-7886	COV	Marie Dr.	8	Ductile Iron	45	50	0.29 out of 5	\$442	19,761
Distribution Main	1686	P-7492	COV	Marion Ave.	6	Asbestos Cement	334	57	1.85 out of 5	\$442	147,783
Distribution Main	2619	P-7492	COV	Marion Ave.	6	Asbestos Cement	11	57	1.85 out of 5	\$442	4,806
Distribution Main	7450	P-7101	COV	Marion Dr.	8	Asbestos Cement	695	44	1.14 out of 5	\$442	307,199
Distribution Main	7451	P-7101	COV	Marion Dr.	8	Asbestos Cement	53	44	1.14 out of 5	\$442	23,538
Distribution Main	7458	P-7103	COV	Marion Dr.	8	Asbestos Cement	405	44	1.14 out of 5	\$442	178,951

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2402	P-8058	COV	Marshall Cir.	6	Asbestos Cement	24	71	2 out of 5	\$442	10,640
Distribution Main	2404	P-8058	COV	Marshall Cir.	6	Asbestos Cement	9	71	2 out of 5	\$442	4,072
Distribution Main	2406	P-8064	COV	Marshall Cir.	6	Ductile Iron	473	27	0.85 out of 5	\$442	209,214
Distribution Main	2918	P-8063	COV	Marshall Cir.	6	Ductile Iron	154	27	0.85 out of 5	\$442	67,893
Distribution Main	2926	P-8058	COV	Marshall Cir.	6	Asbestos Cement	203	71	2 out of 5	\$442	89,522
Distribution Main	2927	P-8058	COV	Marshall Cir.	6	Asbestos Cement	226	71	2 out of 5	\$442	99,872
Distribution Main	10066	P-8063	COV	Marshall Cir.	6	Ductile Iron	79	27	0.85 out of 5	\$442	34,968
Distribution Main	10067	P-8064	COV	Marshall Cir.	6	Ductile Iron	23	27	0.85 out of 5	\$442	10,161
Distribution Main	10068	P-8064	COV	Marshall Cir.	6	Ductile Iron	58	27	0.85 out of 5	\$442	25,787
Distribution Main	4062	P-8150	COV	Martin St.	6	Asbestos Cement	130	59	1.85 out of 5	\$442	57,569
Distribution Main	4954	P-8182	COV	Martin St.	6	Asbestos Cement	602	59	1.85 out of 5	\$442	266,141
Distribution Main	5935	P-8336	COV	Mashie Cir.	6	Ductile Iron	11	30	0.85 out of 5	\$442	4,663
Distribution Main	5936	P-8336	COV	Mashie Cir.	6	Ductile Iron	221	30	0.85 out of 5	\$442	97,519
Distribution Main	3148	P-7825	COV	Matteson St.	6	Asbestos Cement	407	52	1.85 out of 5	\$442	179,984
Distribution Main	3149	P-7825	COV	Matteson St.	6	Asbestos Cement	29	52	1.85 out of 5	\$442	12,799
Distribution Main	11786	P-7825	COV	Matteson St.	6	Asbestos Cement	271	52	1.85 out of 5	\$442	119,641
Distribution Main	2760	P-7481	COV	Maude Ave.	6	Asbestos Cement	630	61	2 out of 5	\$442	278,300
Distribution Main	2761	P-7481	COV	Maude Ave.	6	Asbestos Cement	490	61	2 out of 5	\$442	216,421
Distribution Main	2774	P-8517	COV	Maude Ave.	6	Asbestos Cement	8	61	2 out of 5	\$442	3,512
Distribution Main	6456	P-7481	COV	Maude Ave.	6	Asbestos Cement	16	61	2 out of 5	\$442	7,175
Distribution Main	6457	P-7481	COV	Maude Ave.	6	Asbestos Cement	10	61	2 out of 5	\$442	4,413
Distribution Main	8339		COV	Mead St	6	Ductile Iron	3	14	0.71 out of 5	N/A	\$0
Distribution Main	8340		COV	Mead St	8	Ductile Iron	61	14	0 out of 5	N/A	\$0
Distribution Main	8341	P-8717	COV	Mead St	8	Ductile Iron	16	14	0 out of 5	N/A	\$0
Distribution Main	8342	P-8717	COV	Mead St	8	Ductile Iron	21	14	0 out of 5	N/A	\$0
Distribution Main	10454		COV	Mead St	6	Steel	3	14	1.28 out of 5	N/A	\$0
Distribution Main	10387	P-7724	COV	Mead St.	8	Ductile Iron	259	13	0 out of 5	N/A	\$0
Distribution Main	10388	P-7724	COV	Mead St.	8	Ductile Iron	46	13	0 out of 5	N/A	\$0
Distribution Main	11655	P-7726	COV	Mead St.	8	Ductile Iron	209	13	0 out of 5	N/A	\$0
Distribution Main	3070	P-7287	COV	Meadow Ln.	6	Asbestos Cement	380	43	1.85 out of 5	\$442	167,994
Distribution Main	565		COV	Meadowbrook Farm Road	8	Ductile Iron	20	UNK	0 out of 5	N/A	\$0
Distribution Main	1500	P-7869	COV	Meeting St.	6	Cast Iron	8	81	2.43 out of 5	\$442	3,700
Distribution Main	1501	P-7869	COV	Meeting St.	6	Cast Iron	396	81	2.43 out of 5	\$442	175,232
Distribution Main	1502	P-7872	COV	Meeting St.	2	Galvanized Iron	142	81	3.43 out of 5	\$442	62,728
Distribution Main	1949	P-7868	COV	Meeting St.	6	Cast Iron	235	81	2.43 out of 5	\$442	103,694
Distribution Main	11132	P-7869	COV	Meeting St.	6	Cast Iron	19	81	2.43 out of 5	\$442	8,435
Distribution Main	11780	P-7869	COV	Meeting St.	6	Cast Iron	117	81	2.43 out of 5	\$442	51,724
Distribution Main	194	P-7291	COV	Meredith Dr.	6	Asbestos Cement	395	60	1.85 out of 5	\$442	174,616
Distribution Main	195	P-7292	COV	Meredith Dr.	6	Asbestos Cement	14	60	1.85 out of 5	\$442	6,226
Distribution Main	196	P-7292	COV	Meredith Dr.	6	Asbestos Cement	204	60	1.85 out of 5	\$442	90,097
Distribution Main	1954	P-7286	COV	Meredith Dr.	6	Asbestos Cement	282	60	1.85 out of 5	\$442	124,707
Distribution Main	1955	P-7286	COV	Meredith Dr.	6	Asbestos Cement	13	60	1.85 out of 5	\$442	5,939
Distribution Main	3085	P-7282	COV	Meredith Dr.	6	Asbestos Cement	359	60	1.85 out of 5	\$442	158,797
Distribution Main	3086		COV	Meredith Dr.	6	Asbestos Cement	85	60	1.85 out of 5	\$442	37,436

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11027	P-7292	COV	Meredith Dr.	6	Asbestos Cement	4	60	1.85 out of 5	\$442	1,621
Distribution Main	7866	P-7200	COV	Metro Dr.	8	Asbestos Cement	79	44	1.14 out of 5	\$442	34,783
Distribution Main	7867	P-7200	COV	Metro Dr.	8	Asbestos Cement	569	44	1.14 out of 5	\$442	251,629
Distribution Main	7949	P-7204	COV	Metro Dr.	8	Asbestos Cement	386	44	1.14 out of 5	\$442	170,695
Distribution Main	7953	P-7207	COV	Metro Dr.	8	Asbestos Cement	268	44	1.14 out of 5	\$442	118,387
Distribution Main	7954	P-7207	COV	Metro Dr.	8	Asbestos Cement	316	44	1.14 out of 5	\$442	139,826
Distribution Main	9969	O-7201	COV	Metro Dr.	8	Asbestos Cement	381	44	1.14 out of 5	\$442	168,260
Distribution Main	936	P-9061	COV	Michael Court	1	Copper	241	UNK	1.99 out of 5	\$442	106,318
Distribution Main	8391	P-8832	COV	Mill St	8	Ductile Iron	25	10	0 out of 5	N/A	\$0
Distribution Main	8459	P-8833	COV	Mill St	6	Ductile Iron	13	10	0.71 out of 5	N/A	\$0
Transmission Main	1	P-8263	COV	Mishnock Rd	12	Ductile Iron	11	30	0.14 out of 5	\$442	5,072
Distribution Main	2		COV	Mishnock Rd	8	Ductile Iron	22	30	0.14 out of 5	\$442	9,549
Distribution Main	3		COV	Mishnock Rd	8	Ductile Iron	43	30	0.14 out of 5	\$442	18,857
Transmission Main	4	P-8263	COV	Mishnock Rd	12	Ductile Iron	11	30	0.14 out of 5	\$442	4,875
Transmission Main	1743	P-7456	COV	Mishnock Rd.	12	Ductile Iron	131	30	0.14 out of 5	\$442	57,713
Transmission Main	1744	P-7456	COV	Mishnock Rd.	12	Ductile Iron	581	30	0.14 out of 5	\$442	256,825
Transmission Main	1745	P-8263	COV	Mishnock Rd.	12	Ductile Iron	310	30	0.14 out of 5	\$442	137,155
Transmission Main	4813	P-3005	COV	Mishnock Rd.	12	Ductile Iron	343	30	0.14 out of 5	\$442	151,450
Transmission Main	4814	P-3005	COV	Mishnock Rd.	12	Ductile Iron	585	30	0.14 out of 5	\$442	258,521
Transmission Main	4918	P-3005	COV	Mishnock Rd.	12	Ductile Iron	300	30	0.14 out of 5	\$442	132,806
Transmission Main	5351		COV	Mishnock Rd.	12	Ductile Iron	51	30	0.14 out of 5	\$442	22,517
Transmission Main	5352		COV	Mishnock Rd.	12	Ductile Iron	86	30	0.14 out of 5	\$442	37,837
Transmission Main	10105		COV	Mishnock Rd.	12	Ductile Iron	78	30	0.14 out of 5	\$442	34,635
Transmission Main	11869	P-7456	COV	Mishnock Rd.	12	Ductile Iron	57	30	0.14 out of 5	\$442	25,179
Transmission Main	496		COV	Mishnock Wells	12	Ductile Iron	699	30	0.14 out of 5	\$442	308,739
Transmission Main	11065		COV	Mishnock Wells	12	Ductile Iron	51	30	0.14 out of 5	\$442	22,553
Distribution Main	8357	P-7735	COV	Mohawk St	8	Ductile Iron	453	13	0 out of 5	N/A	\$0
Distribution Main	8358	P-7735	COV	Mohawk St	8	Ductile Iron	443	13	0 out of 5	N/A	\$0
Distribution Main	8360	P-8765	COV	Mohawk St	8	Ductile Iron	52	13	0 out of 5	N/A	\$0
Distribution Main	8361	P-8765	COV	Mohawk St	8	Ductile Iron	145	13	0 out of 5	N/A	\$0
Distribution Main	8368	P-8767	COV	Mohawk St	8	Ductile Iron	188	13	0 out of 5	N/A	\$0
Distribution Main	8369	P-8767	COV	Mohawk St	8	Ductile Iron	276	13	0 out of 5	N/A	\$0
Distribution Main	9511	P-9014	COV	Mohawk St	8	Ductile Iron	92	13	0 out of 5	N/A	\$0
Distribution Main	9942	P-7737	COV	Mohawk St	8	Ductile Iron	35	13	0 out of 5	N/A	\$0
Distribution Main	9944	P-8766	COV	Mohawk St	8	Ductile Iron	25	13	0 out of 5	N/A	\$0
Distribution Main	9945	P-8766	COV	Mohawk St	8	Ductile Iron	191	13	0 out of 5	N/A	\$0
Distribution Main	8352	P-7727	COV	Mohawk St.	8	Ductile Iron	705	13	0 out of 5	N/A	\$0
Distribution Main	9950		COV	Monroe Dr	8	Ductile Iron	15	21	0.14 out of 5	N/A	\$0
Distribution Main	6451	P-7166	COV	Monroe Dr.	8	Asbestos Cement	500	42	1.14 out of 5	\$442	220,891
Distribution Main	6461	P-7170	COV	Monroe Dr.	8	Ductile Iron	20	20	0 out of 5	N/A	\$0
Distribution Main	6462	P-7170	COV	Monroe Dr.	8	Ductile Iron	569	20	0 out of 5	N/A	\$0
Distribution Main	7436	P-7167	COV	Monroe Dr.	8	Asbestos Cement	416	42	1.14 out of 5	\$442	184,010
Distribution Main	7437	P-7167	COV	Monroe Dr.	8	Asbestos Cement	77	42	1.14 out of 5	\$442	33,861
Distribution Main	7802	P-7168	COV	Monroe Dr.	8	Asbestos Cement	41	34	1 out of 5	\$442	18,142

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7803	P-7168	COV	Monroe Dr.	8	Asbestos Cement	785	34	1 out of 5	\$442	346,940
Distribution Main	7804	P-7169	COV	Monroe Dr.	8	Ductile Iron	338	20	0 out of 5	N/A	\$0
Distribution Main	9504	P-7171	COV	Monroe Dr.	8	Ductile Iron	78	20	0 out of 5	N/A	\$0
Distribution Main	9505	P-7171	COV	Monroe Dr.	8	Ductile Iron	344	20	0 out of 5	N/A	\$0
Distribution Main	11335	P-7166	COV	Monroe Dr.	8	Asbestos Cement	11	42	1.14 out of 5	\$442	4,855
Distribution Main	11867	P-7168	COV	Monroe Dr.	8	Asbestos Cement	46	42	1.14 out of 5	\$442	20,202
Distribution Main	478	P-7575	COV	Montana Ave.	3	Galvanized Iron	233	86	3.43 out of 5	\$442	102,986
Distribution Main	1119	P-7574	COV	Montana Ave.	3	Galvanized Iron	377	86	3.43 out of 5	\$442	166,852
Distribution Main	1755		COV	Montana Ave.	3	Galvanized Iron	13	86	3.43 out of 5	\$442	5,586
Distribution Main	1756	P-7577	COV	Montana Ave.	3	Galvanized Iron	226	86	3.43 out of 5	\$442	100,046
Distribution Main	2635	P-7576	COV	Montana Ave.	3	Galvanized Iron	236	86	3.43 out of 5	\$442	104,348
Distribution Main	2786		COV	Montana Ave.	3	Galvanized Iron	6	86	3.43 out of 5	\$442	2,555
Distribution Main	2681	P-7979	COV	Morin Ave.	1	Copper	417	54	2.28 out of 5	\$442	184,230
Distribution Main	6170	P-8384	COV	Morningside Dr.	8	Asbestos Cement	19	47	1.14 out of 5	\$442	8,396
Distribution Main	1853	P-7616	COV	Morris St.	6	Asbestos Cement	195	60	1.85 out of 5	\$442	86,370
Distribution Main	2625	P-7613	COV	Morris St.	6	Asbestos Cement	90	60	1.85 out of 5	\$442	39,739
Distribution Main	2626	P-7613	COV	Morris St.	6	Asbestos Cement	283	60	1.85 out of 5	\$442	125,211
Distribution Main	819	P-7346	COV	Moss Ln.	8	Ductile Iron	932	24	0.14 out of 5	N/A	\$0
Distribution Main	8303	P-8260	COV	Mountain Laurel Dr	8	Ductile Iron	633	14	0 out of 5	N/A	\$0
Distribution Main	8307	P-8413	COV	Mountain Laurel Dr	8	Ductile Iron	237	14	0 out of 5	N/A	\$0
Distribution Main	8308	P-8413	COV	Mountain Laurel Dr	8	Ductile Iron	216	14	0 out of 5	N/A	\$0
Distribution Main	8309	P-8413	COV	Mountain Laurel Dr	8	Ductile Iron	129	14	0 out of 5	N/A	\$0
Distribution Main	9615	P-8415	COV	Mountain Laurel Dr	8	Ductile Iron	75	14	0 out of 5	N/A	\$0
Distribution Main	1111	P-7920	COV	Mulberry Ct.	8	PVC	253	39	0.43 out of 5	\$442	111,949
Distribution Main	230	P-8089	COV	Mumford St.	8	Ductile Iron	245	18	0 out of 5	N/A	\$0
Distribution Main	231	P-8089	COV	Mumford St.	8	Ductile Iron	16	18	0 out of 5	N/A	\$0
Distribution Main	543	P-8086	COV	Mumford St.	8	Ductile Iron	195	18	0 out of 5	N/A	\$0
Distribution Main	544	P-8086	COV	Mumford St.	8	Ductile Iron	258	18	0 out of 5	N/A	\$0
Distribution Main	1766	P-8086	COV	Mumford St.	8	Ductile Iron	185	18	0 out of 5	N/A	\$0
Distribution Main	3490	P-8084	COV	Mumford St.	8	Ductile Iron	359	18	0 out of 5	N/A	\$0
Distribution Main	3491	P-8084	COV	Mumford St.	8	Ductile Iron	33	18	0 out of 5	N/A	\$0
Distribution Main	3725	P-8837	COV	Mumford St.	8	Ductile Iron	37	18	0 out of 5	N/A	\$0
Distribution Main	10962	P-8085	COV	Mumford St.	8	Ductile Iron	362	18	0 out of 5	N/A	\$0
Distribution Main	11859	P-8089	COV	Mumford St.	8	Ductile Iron	228	18	0 out of 5	N/A	\$0
Distribution Main	3077	P-9035	COV	Murray St	6	Asbestos Cement	484	50	1.85 out of 5	\$442	213,982
Distribution Main	547	P-7684	COV	Myra Rd.	6	Asbestos Cement	158	56	1.85 out of 5	\$442	69,712
Distribution Main	548	P-7679	COV	Myra Rd.	6	Asbestos Cement	241	56	1.85 out of 5	\$442	106,668
Distribution Main	555	P-7683	COV	Myra Rd.	6	Asbestos Cement	608	56	1.85 out of 5	\$442	268,810
Distribution Main	183	P-7954	COV	Nancy Ct.	6	Asbestos Cement	393	56	1.85 out of 5	\$442	173,560
Distribution Main	746	P-7636	COV	Nancy St.	6	Asbestos Cement	309	59	1.85 out of 5	\$442	136,576
Distribution Main	8274	P-7954	COV	Nancy St.	8	Ductile Iron	23	15	0 out of 5	N/A	\$0
Distribution Main	8275	P-7954	COV	Nancy St.	8	Ductile Iron	29	15	0 out of 5	N/A	\$0
Transmission Main	31	P-8317	COV	New London Tpk	12	Ductile Iron	407	22	0.14 out of 5	N/A	\$0
Transmission Main	32	P-8316	COV	New London Tpk	12	PVC	143	31	0.43 out of 5	\$442	62,996

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	62		COV	New London Tpk	12	Unknown	14	UNK	0 out of 5	N/A	\$0
Transmission Main	63		COV	New London Tpk	12	Unknown	2	UNK	0 out of 5	N/A	\$0
Transmission Main	269	P-8170	COV	New London Tpk.	16	Ductile Iron	24	24	0.14 out of 5	N/A	\$0
Transmission Main	270	P-8170	COV	New London Tpk.	16	Ductile Iron	4	24	0.14 out of 5	N/A	\$0
Transmission Main	271	P-8170	COV	New London Tpk.	16	Ductile Iron	3	24	0.14 out of 5	N/A	\$0
Transmission Main	272	P-8170	COV	New London Tpk.	16	Ductile Iron	7	24	0.14 out of 5	N/A	\$0
Distribution Main	1162	P-8317	COV	New London Tpk.	8	Ductile Iron	31	22	0.14 out of 5	N/A	\$0
Transmission Main	1163	P-8317	COV	New London Tpk.	12	Ductile Iron	13	22	0.14 out of 5	N/A	\$0
Distribution Main	1627	P-8170	COV	New London Tpk.	8	Asbestos Cement	8	50	1.14 out of 5	\$442	3,546
Transmission Main	1630	P-8175	COV	New London Tpk.	16	Ductile Iron	482	24	0.14 out of 5	N/A	\$0
Distribution Main	2184	P-8170	COV	New London Tpk.	8	Asbestos Cement	4	50	1.14 out of 5	\$442	1,662
Distribution Main	2185	P-8169	COV	New London Tpk.	8	Asbestos Cement	414	50	1.14 out of 5	\$442	182,989
Transmission Main	2187	P-8316	COV	New London Tpk.	12	Asbestos Cement	188	59	1.14 out of 5	\$442	82,884
Transmission Main	2188	P-8316	COV	New London Tpk.	12	Asbestos Cement	48	59	1.14 out of 5	\$442	21,267
Transmission Main	2878	P-8136	COV	New London Tpk.	12	Asbestos Cement	43	59	1.14 out of 5	\$442	18,881
Transmission Main	2879	P-8136	COV	New London Tpk.	12	Asbestos Cement	266	59	1.14 out of 5	\$442	117,394
Transmission Main	2882	P-8162	COV	New London Tpk.	12	Asbestos Cement	375	59	1.14 out of 5	\$442	165,846
Distribution Main	3145	P-8169	COV	New London Tpk.	8	Asbestos Cement	4	50	1.14 out of 5	\$442	1,662
Transmission Main	4063	P-8137	COV	New London Tpk.	12	Asbestos Cement	257	59	1.14 out of 5	\$442	113,726
Transmission Main	4064	P-8145	COV	New London Tpk.	12	Asbestos Cement	274	59	1.14 out of 5	\$442	121,324
Transmission Main	4065	P-8151	COV	New London Tpk.	12	Asbestos Cement	126	59	1.85 out of 5	\$442	55,619
Transmission Main	4066	P-8168	COV	New London Tpk.	12	Asbestos Cement	137	59	1.14 out of 5	\$442	60,607
Transmission Main	4067	P-8168	COV	New London Tpk.	12	Asbestos Cement	15	59	1.14 out of 5	\$442	6,665
Transmission Main	4068	P-8166	COV	New London Tpk.	12	Asbestos Cement	423	59	1.14 out of 5	\$442	186,919
Transmission Main	4069	P-8166	COV	New London Tpk.	12	Asbestos Cement	353	59	1.14 out of 5	\$442	156,194
Transmission Main	9580	P-8316	COV	New London Tpk.	12	PVC	6	31	0.43 out of 5	\$442	2,638
Distribution Main	9581	P-8317	COV	New London Tpk.	8	Asbestos Cement	117	50	1.14 out of 5	\$442	51,530
Transmission Main	9582	P-8318	COV	New London Tpk.	12	Ductile Iron	401	22	0.14 out of 5	N/A	\$0
Distribution Main	9613		COV	New London Tpk	8	Ductile Iron	3	11	0 out of 5	N/A	\$0
Transmission Main	1669	P-3134	COV	New London Turnpike	16	Ductile Iron	5	18	0 out of 5	N/A	\$0
Transmission Main	1670	P-3134	COV	New London Turnpike	16	Ductile Iron	123	18	0 out of 5	N/A	\$0
Distribution Main	2824	P-8913	COV	Newell Court	2	Copper	392	85	2.57 out of 5	\$442	173,264
Distribution Main	3012	P-8341	COV	Niblick Cir.	6	Ductile Iron	206	30	0.85 out of 5	\$442	91,012
Distribution Main	3013	P-8341	COV	Niblick Cir.	6	Ductile Iron	525	30	0.85 out of 5	\$442	232,119
Distribution Main	5922	P-3001	COV	Nichole Ln.	8	Asbestos Cement	397	38	1 out of 5	\$442	175,534
Distribution Main	7269	P-3002	COV	Nichole Ln.	8	Asbestos Cement	363	38	1 out of 5	\$442	160,653
Distribution Main	7653	P-3001	COV	Nichole Ln.	8	Asbestos Cement	50	38	1 out of 5	\$442	22,131
Distribution Main	7654	P-3001	COV	Nichole Ln.	8	Asbestos Cement	348	38	1 out of 5	\$442	153,610
Distribution Main	11369	P-3002	COV	Nichole Ln.	8	Asbestos Cement	164	38	1 out of 5	\$442	72,541
Distribution Main	41	P-7472	COV	Noella Ave	6	Asbestos Cement	746	57	1.85 out of 5	\$442	329,544
Distribution Main	6448	P-7460	COV	Noella Ave.	6	Asbestos Cement	225	59	1.85 out of 5	\$442	99,568
Distribution Main	7441	P-7465	COV	Noella Ave.	6	Asbestos Cement	331	57	1.85 out of 5	\$442	146,500
Distribution Main	7805	P-7462	COV	Noella Ave.	6	Asbestos Cement	143	59	1.85 out of 5	\$442	63,132
Distribution Main	9313		COV	Nooseneck Hill Rd	2	Unknown	71	11	1.42 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	10458		COV	Nooseneck Hill Rd	12	Ductile Iron	18	UNK	0 out of 5	N/A	\$0
Transmission Main	10528		COV	Nooseneck Hill Rd	12	HDPE	59	UNK	0.28 out of 5	\$442	26,165
Transmission Main	10529		COV	Nooseneck Hill Rd	12	HDPE	86	UNK	0.28 out of 5	\$442	37,820
Transmission Main	10705		COV	Nooseneck Hill Rd	12	Ductile Iron	24	UNK	0 out of 5	N/A	\$0
Transmission Main	558	P-8760	COV	Nooseneck Hill Rd.	12	Asbestos Cement	624	54	1.14 out of 5	\$442	275,596
Transmission Main	559	P-8215	COV	Nooseneck Hill Rd.	12	Asbestos Cement	523	54	1.14 out of 5	\$442	231,199
Transmission Main	560	P-8215	COV	Nooseneck Hill Rd.	12	Asbestos Cement	223	54	1.14 out of 5	\$442	98,707
Transmission Main	1248	P-8759	COV	Nooseneck Hill Rd.	12	Ductile Iron	632	30	0.14 out of 5	\$442	279,404
Transmission Main	1249	P-8759	COV	Nooseneck Hill Rd.	12	Ductile Iron	30	30	0.14 out of 5	\$442	13,249
Transmission Main	1909	P-7952	COV	Nooseneck Hill Rd.	12	Asbestos Cement	14	54	1.14 out of 5	\$442	6,173
Transmission Main	2986	P-7952	COV	Nooseneck Hill Rd.	12	Asbestos Cement	10	54	1.14 out of 5	\$442	4,209
Transmission Main	4397	P-7419	COV	Nooseneck Hill Rd.	12	Asbestos Cement	17	54	1.14 out of 5	\$442	7,556
Transmission Main	4398	P-7419	COV	Nooseneck Hill Rd.	12	Asbestos Cement	620	54	1.14 out of 5	\$442	274,203
Transmission Main	4792	P-7159	COV	Nooseneck Hill Rd.	12	Asbestos Cement	7	54	1.14 out of 5	\$442	2,903
Transmission Main	4793	P-8215	COV	Nooseneck Hill Rd.	12	Asbestos Cement	139	54	1.14 out of 5	\$442	61,395
Transmission Main	4794	P-7952	COV	Nooseneck Hill Rd.	12	Asbestos Cement	194	54	1.14 out of 5	\$442	85,883
Transmission Main	4795	P-7952	COV	Nooseneck Hill Rd.	12	Asbestos Cement	287	54	1.14 out of 5	\$442	126,646
Transmission Main	5306	P-7952	COV	Nooseneck Hill Rd.	12	Asbestos Cement	245	54	1.14 out of 5	\$442	108,206
Distribution Main	5920		COV	Nooseneck Hill Rd.	8	Unknown	20	UNK	0 out of 5	N/A	\$0
Transmission Main	5921	P-7417	COV	Nooseneck Hill Rd.	12	Asbestos Cement	49	54	1.14 out of 5	\$442	21,690
Transmission Main	6626		COV	Nooseneck Hill Rd.	12	Ductile Iron	10	30	0.14 out of 5	\$442	4,346
Transmission Main	6627	P-8755	COV	Nooseneck Hill Rd.	12	Ductile Iron	1,144	30	0.14 out of 5	\$442	505,813
Transmission Main	6629	P-8755	COV	Nooseneck Hill Rd.	12	Ductile Iron	1,524	30	0.14 out of 5	\$442	673,710
Transmission Main	7147	P-8215	COV	Nooseneck Hill Rd.	12	Asbestos Cement	873	54	1.14 out of 5	\$442	385,683
Transmission Main	7148	P-8215	COV	Nooseneck Hill Rd.	12	Asbestos Cement	46	54	1.14 out of 5	\$442	20,450
Transmission Main	7149	P-8526	COV	Nooseneck Hill Rd.	12	Asbestos Cement	225	54	1.14 out of 5	\$442	99,577
Transmission Main	7150	P-8226	COV	Nooseneck Hill Rd.	12	Asbestos Cement	527	54	1.14 out of 5	\$442	232,955
Transmission Main	7151	P-8226	COV	Nooseneck Hill Rd.	12	Asbestos Cement	78	54	1.14 out of 5	\$442	34,274
Transmission Main	7152	P-8751	COV	Nooseneck Hill Rd.	12	Asbestos Cement	1,477	54	1.14 out of 5	\$442	652,922
Transmission Main	7153	P-8358	COV	Nooseneck Hill Rd.	12	Asbestos Cement	381	54	1.14 out of 5	\$442	168,599
Distribution Main	7154	P-8520	COV	Nooseneck Hill Rd.	8	Unknown	61	UNK	0 out of 5	N/A	\$0
Distribution Main	7194	P-7426	COV	Nooseneck Hill Rd.	10	Asbestos Cement	373	54	1.14 out of 5	\$442	164,788
Transmission Main	7206	P-8750	COV	Nooseneck Hill Rd.	12	Asbestos Cement	187	54	1.14 out of 5	\$442	82,575
Transmission Main	7258	P-8755	COV	Nooseneck Hill Rd.	12	Ductile Iron	408	30	0.14 out of 5	\$442	180,267
Transmission Main	7259		COV	Nooseneck Hill Rd.	12	Ductile Iron	9	30	0.14 out of 5	\$442	4,123
Transmission Main	7260		COV	Nooseneck Hill Rd.	12	Ductile Iron	40	30	0.14 out of 5	\$442	17,524
Transmission Main	7510	P-8750	COV	Nooseneck Hill Rd.	12	Asbestos Cement	1,020	54	1.14 out of 5	\$442	451,044
Transmission Main	7511	P-8750	COV	Nooseneck Hill Rd.	12	Asbestos Cement	534	54	1.14 out of 5	\$442	236,193
Distribution Main	7544	P-8954	COV	Nooseneck Hill Rd.	8	Unknown	19	UNK	0 out of 5	N/A	\$0
Transmission Main	7545	P-8953	COV	Nooseneck Hill Rd.	12	Asbestos Cement	3	54	1.14 out of 5	\$442	1,529
Transmission Main	7546	P-8953	COV	Nooseneck Hill Rd.	12	Asbestos Cement	27	54	1.14 out of 5	\$442	11,976
Distribution Main	7548		COV	Nooseneck Hill Rd.	8	Unknown	18	UNK	0 out of 5	N/A	\$0
Transmission Main	7549	P-8226	COV	Nooseneck Hill Rd.	12	Asbestos Cement	140	54	1.14 out of 5	\$442	62,030
Transmission Main	7550	P-3062	COV	Nooseneck Hill Rd.	12	Asbestos Cement	27	54	1.14 out of 5	\$442	11,809

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	7551	P-3062	COV	Nooseneck Hill Rd.	12	Asbestos Cement	744	54	1.14 out of 5	\$442	328,705
Distribution Main	7685		COV	Nooseneck Hill Rd.	8	Unknown	4	UNK	0 out of 5	N/A	\$0
Distribution Main	7686		COV	Nooseneck Hill Rd.	8	Unknown	4	UNK	0 out of 5	N/A	\$0
Distribution Main	7687	P-8954	COV	Nooseneck Hill Rd.	8	Unknown	7	UNK	0 out of 5	N/A	\$0
Transmission Main	7688	P-8226	COV	Nooseneck Hill Rd.	12	Asbestos Cement	86	54	1.14 out of 5	\$442	38,044
Transmission Main	7800	P-7419	COV	Nooseneck Hill Rd.	12	Asbestos Cement	33	54	1.14 out of 5	\$442	14,473
Distribution Main	9123		COV	Nooseneck Hill Rd.	8	Ductile Iron	12	UNK	0 out of 5	N/A	\$0
Distribution Main	9124		COV	Nooseneck Hill Rd.	8	Ductile Iron	3	UNK	0 out of 5	N/A	\$0
Transmission Main	10230	P-3038	COV	Nooseneck Hill Rd.	12	Asbestos Cement	21	54	1.14 out of 5	\$442	9,483
Transmission Main	11066	P-7417	COV	Nooseneck Hill Rd.	12	Asbestos Cement	7	54	1.14 out of 5	\$442	3,265
Transmission Main	11069	P-8755	COV	Nooseneck Hill Rd.	12	Ductile Iron	48	30	0.14 out of 5	\$442	21,307
Transmission Main	11346	P-8755	COV	Nooseneck Hill Rd.	12	Ductile Iron	71	30	0.14 out of 5	\$442	31,527
Transmission Main	11387	P-3062	COV	Nooseneck Hill Rd.	12	Asbestos Cement	143	54	1.14 out of 5	\$442	63,300
Transmission Main	11793	P-8215	COV	Nooseneck Hill Rd.	12	Asbestos Cement	33	54	1.14 out of 5	\$442	14,385
Transmission Main	11794	P-8226	COV	Nooseneck Hill Rd.	12	Asbestos Cement	125	54	1.14 out of 5	\$442	55,104
Transmission Main	11971	P-8750	COV	Nooseneck Hill Rd.	12	Asbestos Cement	154	54	1.14 out of 5	\$442	68,088
Transmission Main	12193	P-3062	COV	Nooseneck Hill Rd.	12	Asbestos Cement	637	54	1.14 out of 5	\$442	281,383
Transmission Main	562		COV	Nooseneck Hill Road	12	Unknown	78	UNK	0 out of 5	N/A	\$0
Transmission Main	563		COV	Nooseneck Hill Road	12	Unknown	3	UNK	0 out of 5	N/A	\$0
Transmission Main	3440		COV	Nooseneck Hill Road	16	Ductile Iron	5	UNK	0 out of 5	N/A	\$0
Transmission Main	3441		COV	Nooseneck Hill Road	16	Ductile Iron	8	UNK	0 out of 5	N/A	\$0
Transmission Main	3442		COV	Nooseneck Hill Road	16	Ductile Iron	5	UNK	0 out of 5	N/A	\$0
Transmission Main	3443	P-8959	COV	Nooseneck Hill Road	16	Ductile Iron	4	UNK	0 out of 5	N/A	\$0
Transmission Main	3444	P-8959	COV	Nooseneck Hill Road	16	Ductile Iron	9	UNK	0 out of 5	N/A	\$0
Transmission Main	3445	P-8959	COV	Nooseneck Hill Road	16	Ductile Iron	5	UNK	0 out of 5	N/A	\$0
Transmission Main	3446	P-8959	COV	Nooseneck Hill Road	16	Ductile Iron	13	UNK	0 out of 5	N/A	\$0
Transmission Main	3447	P-8959	COV	Nooseneck Hill Road	16	Ductile Iron	455	UNK	0 out of 5	N/A	\$0
Transmission Main	5313	P-8959	COV	Nooseneck Hill Road	16	Ductile Iron	18	UNK	0 out of 5	N/A	\$0
Distribution Main	718	P-7709	COV	North Glen Dr.	6	Asbestos Cement	633	60	1.85 out of 5	\$442	279,958
Distribution Main	719	P-7709	COV	North Glen Dr.	6	Asbestos Cement	12	60	1.85 out of 5	\$442	5,318
Distribution Main	1585	P-8013	COV	North St.	6	Cast Iron	433	91	2.43 out of 5	\$442	191,578
Distribution Main	1586	P-8013	COV	North St.	2	Copper	17	14	1.99 out of 5	N/A	\$0
Distribution Main	8331	P-8524	COV	Northup Plat Rd	8	Ductile Iron	491	14	0 out of 5	N/A	\$0
Distribution Main	2750	P-8082	COV	Notre Dame St.	2	Copper	551	82	2.57 out of 5	\$442	243,433
Transmission Main	466	P-1442	COV	Nottingham Dr.	16	Ductile Iron	986	19	0 out of 5	N/A	\$0
Transmission Main	467	P-1277	COV	Nottingham Dr.	16	Ductile Iron	6	19	0 out of 5	N/A	\$0
Transmission Main	468		COV	Nottingham Dr.	16	Ductile Iron	5	19	0 out of 5	N/A	\$0
Transmission Main	984	P-1277	COV	Nottingham Dr.	16	Ductile Iron	726	19	0 out of 5	N/A	\$0
Transmission Main	986		COV	Nottingham Dr.	16	Ductile Iron	5	19	0 out of 5	N/A	\$0
Transmission Main	987		COV	Nottingham Dr.	16	Ductile Iron	31	19	0 out of 5	N/A	\$0
Transmission Main	988	P-1449	COV	Nottingham Dr.	16	Ductile Iron	25	22	0.14 out of 5	N/A	\$0
Transmission Main	2351		COV	Nottingham Dr.	16	Ductile Iron	21	19	0 out of 5	N/A	\$0
Distribution Main	4419	P-8889	COV	Nutmeg Circle	8	Ductile Iron	195	21	0.14 out of 5	N/A	\$0
Distribution Main	2644	P-7598	COV	Oak Rd.	6	Asbestos Cement	56	UNK	1.56 out of 5	\$442	24,557

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2645	P-7598	COV	Oak Rd.	6	Asbestos Cement	40	UNK	1.56 out of 5	\$442	17,824
Distribution Main	2777	P-7593	COV	Oak Rd.	6	Ductile Iron	15	19	0.71 out of 5	N/A	\$0
Distribution Main	2780	P-7598	COV	Oak Rd.	8	Ductile Iron	229	19	0 out of 5	N/A	\$0
Distribution Main	2801	P-7593	COV	Oak Rd.	8	Ductile Iron	238	19	0 out of 5	N/A	\$0
Distribution Main	9469	P-8860	COV	Oak St.	0.75	Copper	282	UNK	1.99 out of 5	\$442	124,728
Distribution Main	3048	P-8494	COV	Oak Wy	8	Ductile Iron	46	15	0 out of 5	N/A	\$0
Distribution Main	1028	P-7889	COV	Old Hope Rd.	8	Ductile Iron	9	29	0.14 out of 5	\$442	3,950
Distribution Main	1113	P-7889	COV	Old Hope Rd.	8	Ductile Iron	216	29	0.14 out of 5	\$442	95,575
Distribution Main	1114	P-7889	COV	Old Hope Rd.	8	Ductile Iron	347	29	0.14 out of 5	\$442	153,156
Distribution Main	10427	P-7889	COV	Old Hope Rd.	8	Ductile Iron	59	29	0.14 out of 5	\$442	25,938
Distribution Main	8770	P-8903	COV	Old Main St	8	Ductile Iron	21	8	0 out of 5	N/A	\$0
Distribution Main	8771	P-8903	COV	Old Main St	8	Ductile Iron	18	8	0 out of 5	N/A	\$0
Distribution Main	8772	P-8902	COV	Old Main St	8	Ductile Iron	39	8	0 out of 5	N/A	\$0
Distribution Main	3283	P-8274	COV	Old Main St.	8	Asbestos Cement	7	48	1.14 out of 5	\$442	3,283
Distribution Main	4910	P-8275	COV	Old Main St.	8	Asbestos Cement	191	48	1.14 out of 5	\$442	84,409
Distribution Main	4911	P-7221	COV	Old Main St.	8	Asbestos Cement	233	69	1.29 out of 5	\$442	102,852
Distribution Main	4912	P-7221	COV	Old Main St.	8	Asbestos Cement	309	69	1.29 out of 5	\$442	136,718
Distribution Main	7932	P-8274	COV	Old Main St.	8	Asbestos Cement	397	48	1.14 out of 5	\$442	175,496
Distribution Main	7933	P-7223	COV	Old Main St.	8	Asbestos Cement	472	69	1.29 out of 5	\$442	208,703
Distribution Main	8784	P-7221	COV	Old Main St.	8	Asbestos Cement	36	69	1.29 out of 5	\$442	15,991
Distribution Main	8785	P-8275	COV	Old Main St.	8	Asbestos Cement	50	48	1.14 out of 5	\$442	21,914
Distribution Main	9804	P-7229	COV	Old Main St.	8	Asbestos Cement	66	69	1.29 out of 5	\$442	29,366
Distribution Main	11609	P-7223	COV	Old Main St.	8	Asbestos Cement	32	69	1.29 out of 5	\$442	14,279
Distribution Main	5918	P-7447	COV	Old Mishnock Highway	8	Ductile Iron	36	26	0.14 out of 5	\$442	15,846
Distribution Main	5919	P-7447	COV	Old Mishnock Highway	8	Ductile Iron	258	26	0.14 out of 5	\$442	113,883
Distribution Main	7571	P-7446	COV	Old Mishnock Highway	8	Ductile Iron	36	26	0.14 out of 5	\$442	15,751
Distribution Main	7572	P-7446	COV	Old Mishnock Highway	8	Ductile Iron	590	26	0.14 out of 5	\$442	260,596
Distribution Main	7645	P-7447	COV	Old Mishnock Highway	8	Ductile Iron	198	26	0.14 out of 5	\$442	87,527
Distribution Main	7651	P-8964	COV	Old Mishnock Highway	8	Ductile Iron	23	26	0.14 out of 5	\$442	10,081
Distribution Main	11370	P-7446	COV	Old Mishnock Highway	8	Ductile Iron	28	26	0.14 out of 5	\$442	12,453
Distribution Main	11870	P-7446	COV	Old Mishnock Highway	8	Ductile Iron	393	26	0.14 out of 5	\$442	173,836
Transmission Main	8060	P-8143	COV	Old North Rd	12	Ductile Iron	693	11	0 out of 5	N/A	\$0
Transmission Main	8061	P-8143	COV	Old North Rd	12	Ductile Iron	623	11	0 out of 5	N/A	\$0
Transmission Main	8062	P-8173	COV	Old North Rd	12	Ductile Iron	1,165	11	0 out of 5	N/A	\$0
Transmission Main	8063	P-8173	COV	Old North Rd	12	Ductile Iron	180	11	0 out of 5	N/A	\$0
Transmission Main	8070	P-9024	COV	Old North Rd	12	Ductile Iron	573	11	0 out of 5	N/A	\$0
Transmission Main	8071	P-9024	COV	Old North Rd	12	Ductile Iron	83	11	0 out of 5	N/A	\$0
Transmission Main	8072	P-7753	COV	Old North Rd	12	Ductile Iron	104	11	0 out of 5	N/A	\$0
Transmission Main	11418	P-9024	COV	Old North Rd	12	Ductile Iron	42	11	0 out of 5	N/A	\$0
Transmission Main	11424	P-9024	COV	Old North Rd	12	Ductile Iron	393	11	0 out of 5	N/A	\$0
Transmission Main	11909	P-9024	COV	Old North Rd	12	Ductile Iron	75	11	0 out of 5	N/A	\$0
Transmission Main	11910	P-9024	COV	Old North Rd	12	Ductile Iron	35	11	0 out of 5	N/A	\$0
Transmission Main	2274	P-7756	COV	Old North Rd.	12	PVC	505	43	0.57 out of 5	\$442	223,399
Transmission Main	2275	P-7756	COV	Old North Rd.	12	PVC	164	43	0.57 out of 5	\$442	72,286

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	3810	P-9021	COV	Old North Rd.	12	Ductile Iron	243	17	0 out of 5	N/A	\$0
Transmission Main	8078	P-9022	COV	Old North Rd.	12	Ductile Iron	282	17	0 out of 5	N/A	\$0
Transmission Main	9892		COV	Old North Rd.	12	Ductile Iron	141	17	0 out of 5	N/A	\$0
Transmission Main	9893	P-7756	COV	Old North Rd.	12	Ductile Iron	12	17	0 out of 5	N/A	\$0
Transmission Main	11234	P-9021	COV	Old North Rd.	12	Ductile Iron	12	17	0 out of 5	N/A	\$0
Transmission Main	11421	P-7756	COV	Old North Rd.	12	PVC	140	43	0.57 out of 5	\$442	61,921
Transmission Main	11425		COV	Old North Rd.	12	Ductile Iron	9	17	0 out of 5	N/A	\$0
Distribution Main	5916	P-7115	COV	Orchid Tr.	8	Ductile Iron	381	27	0.14 out of 5	\$442	168,599
Distribution Main	6115	P-7116	COV	Orchid Tr.	8	Ductile Iron	421	27	0.14 out of 5	\$442	186,209
Distribution Main	7855	P-8947	COV	Orchid Tr.	8	Ductile Iron	8	27	0.14 out of 5	\$442	3,354
Distribution Main	7976	P-7116	COV	Orchid Tr.	8	Ductile Iron	63	27	0.14 out of 5	\$442	27,815
Distribution Main	7977	P-7116	COV	Orchid Tr.	8	Ductile Iron	20	27	0.14 out of 5	\$442	8,697
Distribution Main	629	P-1175	COV	Oriole Ave.	6	Asbestos Cement	331	69	2 out of 5	\$442	146,434
Distribution Main	630	P-1175	COV	Oriole Ave.	6	Asbestos Cement	256	69	2 out of 5	\$442	113,137
Distribution Main	1596	P-1175	COV	Oriole Ave.	8	Ductile Iron	55	19	0 out of 5	N/A	\$0
Distribution Main	9073	P-8981	COV	Osceola Ave	2	PVC	324	30	1.85 out of 5	\$442	143,154
Distribution Main	9086	P-8983	COV	Osceola Ave	6	Asbestos Cement	205	UNK	1.56 out of 5	\$442	90,587
Distribution Main	9087	P-8978	COV	Osceola Ave	6	Unknown	232	UNK	0.71 out of 5	\$442	102,520
Distribution Main	7792	P-7097	COV	Osprey Dr.	8	PVC	211	34	0.43 out of 5	\$442	93,079
Distribution Main	7793	P-7097	COV	Osprey Dr.	8	PVC	26	34	0.43 out of 5	\$442	11,679
Distribution Main	1270	P-9000	COV	Overview Dr.	2	Copper	94	79	2.43 out of 5	\$442	41,430
Distribution Main	2285	P-7592	COV	Overview Dr.	6	Asbestos Cement	94	70	2 out of 5	\$442	41,453
Distribution Main	2775	P-9000	COV	Overview Dr.	6	Asbestos Cement	30	30	1.71 out of 5	\$442	13,106
Distribution Main	2776	P-9000	COV	Overview Dr.	6	Asbestos Cement	24	30	1.71 out of 5	\$442	10,722
Distribution Main	2789	P-9000	COV	Overview Dr.	1.5	Copper	323	79	2.43 out of 5	\$442	142,810
Distribution Main	2791	P-7591	COV	Overview Dr.	6	Asbestos Cement	228	70	2 out of 5	\$442	100,706
Distribution Main	2800	P-9000	COV	Overview Dr.	6	Asbestos Cement	6	30	1.71 out of 5	\$442	2,499
Distribution Main	7594	P-7086	COV	Pamela Ct.	8	Ductile Iron	106	28	0.14 out of 5	\$442	46,821
Distribution Main	1564	P-8051	COV	Park Ave.	6	Asbestos Cement	15	57	1.85 out of 5	\$442	6,442
Distribution Main	1566	P-8054	COV	Park Ave.	6	Asbestos Cement	261	57	1.85 out of 5	\$442	115,280
Distribution Main	2939	P-8051	COV	Park Ave.	6	Asbestos Cement	233	57	1.85 out of 5	\$442	102,879
Distribution Main	3755	P-8054	COV	Park Ave.	8	Asbestos Cement	10	57	1.14 out of 5	\$442	4,220
Distribution Main	8752	P-8053	COV	Park Ave.	6	Asbestos Cement	31	57	1.85 out of 5	\$442	13,736
Distribution Main	10800	P-7263	COV	Park St	8	Ductile Iron	267	0	0 out of 5	N/A	\$0
Distribution Main	2826	P-7539	COV	Parker St.	8	Ductile Iron	591	18	0 out of 5	N/A	\$0
Distribution Main	1442	P-7956	COV	Partridge Dr.	8	Ductile Iron	453	24	0.14 out of 5	N/A	\$0
Distribution Main	1443	P-7956	COV	Partridge Dr.	8	Ductile Iron	47	24	0.14 out of 5	N/A	\$0
Distribution Main	2689	P-7958	COV	Partridge Dr.	8	Ductile Iron	382	24	0.14 out of 5	N/A	\$0
Distribution Main	2197	P-7747	COV	Patience Ln.	8	Ductile Iron	335	27	0.14 out of 5	\$442	148,202
Distribution Main	2129		COV	Patton St.	6	Asbestos Cement	10	70	2 out of 5	\$442	4,239
Distribution Main	3040	P-7988	COV	Patton St.	6	Asbestos Cement	424	70	2 out of 5	\$442	187,435
Distribution Main	3041	P-7988	COV	Patton St.	6	Asbestos Cement	338	70	2 out of 5	\$442	149,290
Distribution Main	7929	P-7246	COV	Patty St.	8	Asbestos Cement	90	56	1.14 out of 5	\$442	39,613
Distribution Main	7930	P-7246	COV	Patty St.	8	Asbestos Cement	342	56	1.85 out of 5	\$442	151,269

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	678	P-8106	COV	Paulette Dr.	6	Asbestos Cement	518	59	1.85 out of 5	\$442	228,970
Distribution Main	7737	P-8956	COV	Peach Tree Lane	6	Asbestos Cement	25	44	1.85 out of 5	\$442	11,028
Distribution Main	7815	P-7032	COV	Peach Tree Lane	6	Asbestos Cement	21	44	1.85 out of 5	\$442	9,124
Distribution Main	7816	P-7032	COV	Peach Tree Lane	6	Asbestos Cement	930	44	1.85 out of 5	\$442	410,966
Distribution Main	7829	P-8956	COV	Peach Tree Lane	6	Asbestos Cement	447	44	1.85 out of 5	\$442	197,449
Distribution Main	1441	P-8002	COV	Peacock Dr.	8	Ductile Iron	615	24	0.14 out of 5	N/A	\$0
Distribution Main	2814	P-8915	COV	Pearl St	2	Galvanized Iron	298	87	3.43 out of 5	\$442	131,674
Distribution Main	846	P-7788	COV	Pembroke Ln.	6	Asbestos Cement	591	53	1.85 out of 5	\$442	261,373
Distribution Main	1480	P-7790	COV	Pembroke Ln.	6	Asbestos Cement	436	53	1.85 out of 5	\$442	192,537
Distribution Main	1485	P-7786	COV	Pembroke Ln.	6	Asbestos Cement	341	53	1.85 out of 5	\$442	150,897
Distribution Main	1486	P-7786	COV	Pembroke Ln.	6	Asbestos Cement	525	53	1.85 out of 5	\$442	231,925
Distribution Main	1707	P-7782	COV	Pembroke Ln.	6	Asbestos Cement	300	53	1.85 out of 5	\$442	132,608
Distribution Main	1708	P-7778	COV	Pembroke Ln.	6	Asbestos Cement	23	53	1.85 out of 5	\$442	10,139
Distribution Main	1709	P-7778	COV	Pembroke Ln.	6	Asbestos Cement	651	53	1.85 out of 5	\$442	287,817
Distribution Main	1718	P-7775	COV	Pembroke Ln.	6	Asbestos Cement	234	53	1.85 out of 5	\$442	103,522
Distribution Main	3183	P-7772	COV	Pembroke Ln.	6	Asbestos Cement	227	53	1.85 out of 5	\$442	100,212
Distribution Main	9550	P-7772	COV	Pembroke Ln.	6	Ductile Iron	28	19	0.71 out of 5	N/A	\$0
Distribution Main	9551	P-7772	COV	Pembroke Ln.	8	Ductile Iron	14	19	0 out of 5	N/A	\$0
Distribution Main	8852	P-7053	COV	Peninsula Ct	8	Ductile Iron	533	13	0 out of 5	N/A	\$0
Distribution Main	4416	P-7338	COV	Peppermint Lane	8	Ductile Iron	177	21	0.14 out of 5	N/A	\$0
Distribution Main	1487	P-7789	COV	Pettine St.	6	Asbestos Cement	370	60	1.85 out of 5	\$442	163,481
Distribution Main	1488	P-7789	COV	Pettine St.	6	Asbestos Cement	13	60	1.85 out of 5	\$442	5,626
Distribution Main	1706	P-7785	COV	Pettine St.	6	Asbestos Cement	671	60	1.85 out of 5	\$442	296,452
Distribution Main	3184	P-7779	COV	Pettine St.	6	Asbestos Cement	223	60	1.85 out of 5	\$442	98,617
Distribution Main	8830	P-9065	COV	Phillip St.	8	Ductile Iron	42	11	0 out of 5	N/A	\$0
Distribution Main	8831	P-8041	COV	Phillip St.	8	Ductile Iron	572	11	0 out of 5	N/A	\$0
Distribution Main	8832	P-8041	COV	Phillip St.	8	Ductile Iron	508	11	0 out of 5	N/A	\$0
Distribution Main	11516	P-8042	COV	Phillip St.	8	Ductile Iron	207	11	0 out of 5	N/A	\$0
Distribution Main	624	P-8062	COV	Pierce St.	4	Cast Iron	81	132	3.29 out of 5	\$442	35,864
Distribution Main	1320	P-8862	COV	Pierce St.	4	Cast Iron	195	132	3.29 out of 5	\$442	86,291
Distribution Main	1321	P-8104	COV	Pierce St.	4	Cast Iron	134	132	3.29 out of 5	\$442	59,144
Distribution Main	2458	P-8867	COV	Pierce St.	4	Cast Iron	181	132	3.29 out of 5	\$442	80,009
Distribution Main	2459	P-8866	COV	Pierce St.	4	Cast Iron	189	132	3.29 out of 5	\$442	83,666
Distribution Main	2669	P-8867	COV	Pierce St.	4	Cast Iron	4	132	3.29 out of 5	\$442	1,987
Distribution Main	11126	P-8862	COV	Pierce St.	4	Cast Iron	12	132	3.29 out of 5	\$442	5,293
Distribution Main	706		COV	Pilgrim Ave.	6	Asbestos Cement	6	70	2 out of 5	\$442	2,633
Distribution Main	835	P-7823	COV	Pilgrim Ave.	8	Asbestos Cement	79	61	1.29 out of 5	\$442	35,092
Distribution Main	836	P-7824	COV	Pilgrim Ave.	8	Asbestos Cement	372	61	1.29 out of 5	\$442	164,283
Distribution Main	837	P-7861	COV	Pilgrim Ave.	6	Asbestos Cement	891	61	2 out of 5	\$442	393,639
Distribution Main	838	P-7861	COV	Pilgrim Ave.	6	Asbestos Cement	3	70	2 out of 5	\$442	1,487
Distribution Main	1479	P-7823	COV	Pilgrim Ave.	8	Asbestos Cement	194	61	1.29 out of 5	\$442	85,812
Distribution Main	1959		COV	Pilgrim Ave.		Unknown	40	UNK	0 out of 5	N/A	\$0
Distribution Main	3153	P-7862	COV	Pilgrim Ave.	6	Asbestos Cement	20	70	2 out of 5	\$442	8,820
Distribution Main	3164	P-7808	COV	Pilgrim Ave.	8	Asbestos Cement	294	61	1.29 out of 5	\$442	130,071

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3165	P-7808	COV	Pilgrim Ave.	8	Asbestos Cement	301	61	1.29 out of 5	\$442	133,150
Distribution Main	3166	P-7808	COV	Pilgrim Ave.	8	Asbestos Cement	87	61	1.29 out of 5	\$442	38,472
Distribution Main	3167	P-7810	COV	Pilgrim Ave.	8	Asbestos Cement	329	61	1.29 out of 5	\$442	145,325
Distribution Main	3177	P-7812	COV	Pilgrim Ave.	6	Asbestos Cement	890	70	2 out of 5	\$442	393,190
Distribution Main	3178	P-7812	COV	Pilgrim Ave.	6	Asbestos Cement	42	70	2 out of 5	\$442	18,365
Distribution Main	3179	P-7808	COV	Pilgrim Ave.	8	Asbestos Cement	205	61	1.14 out of 5	\$442	90,453
Distribution Main	3224	P-7818	COV	Pilgrim Ave.	8	Asbestos Cement	121	61	1.14 out of 5	\$442	53,650
Distribution Main	3225	P-7818	COV	Pilgrim Ave.	8	Asbestos Cement	156	61	1.29 out of 5	\$442	68,967
Distribution Main	9563	P-7812	COV	Pilgrim Ave.	8	Ductile Iron	24	19	0 out of 5	N/A	\$0
Distribution Main	9564	P-7812	COV	Pilgrim Ave.	8	Ductile Iron	2	19	0 out of 5	N/A	\$0
Distribution Main	9565	P-7812	COV	Pilgrim Ave.	6	Ductile Iron	7	19	0.71 out of 5	N/A	\$0
Distribution Main	2464	P-7922	COV	Pin Oak Ct.	8	PVC	252	39	0.43 out of 5	\$442	111,440
Distribution Main	1052		COV	Pine Acres Boulevard	8	Ductile Iron	35	15	0 out of 5	N/A	\$0
Distribution Main	1085	P-7595	COV	Pine Ave.	8	Ductile Iron	730	19	0 out of 5	N/A	\$0
Distribution Main	2779	P-7595	COV	Pine Ave.	8	Ductile Iron	4	19	0 out of 5	N/A	\$0
Distribution Main	2790	P-7594	COV	Pine Ave.	8	Ductile Iron	171	19	0 out of 5	N/A	\$0
Distribution Main	477	P-7570	COV	Pinehurst Rd.	6	Asbestos Cement	364	65	2 out of 5	\$442	160,788
Distribution Main	10451		COV	Pioneer Rd.	1	Copper	18	UNK	1.99 out of 5	\$442	7,996
Distribution Main	7808	P-7046	COV	Plum Tree Ln.	8	Asbestos Cement	21	46	1.14 out of 5	\$442	9,482
Distribution Main	7835	P-7046	COV	Plum Tree Ln.	8	Asbestos Cement	235	46	1.14 out of 5	\$442	103,669
Distribution Main	7836	P-7046	COV	Plum Tree Ln.	8	Asbestos Cement	634	46	1.14 out of 5	\$442	280,249
Distribution Main	184	P-7392	COV	Pond View Dr.	6	Asbestos Cement	150	53	1.85 out of 5	\$442	66,395
Distribution Main	604	P-7392	COV	Pond View Dr.	8	Ductile Iron	117	15	0 out of 5	N/A	\$0
Distribution Main	2127	P-7393	COV	Pond View Dr.	6	Asbestos Cement	592	53	1.85 out of 5	\$442	261,602
Distribution Main	2128	P-7393	COV	Pond View Dr.	6	Asbestos Cement	547	53	1.85 out of 5	\$442	241,630
Distribution Main	144	P-7918	COV	Poplar Ct.	8	PVC	267	39	0.43 out of 5	\$442	117,958
Transmission Main	8381	P-8128	COV	Potter Ct	12	Ductile Iron	1,011	10	0 out of 5	N/A	\$0
Transmission Main	8381	P-8128	COV	Potter Ct	12	Ductile Iron	26	25	0.14 out of 5	N/A	\$0
Distribution Main	1844	P-8941	COV	Potters St.	6	Asbestos Cement	138	69	2 out of 5	\$442	61,108
Distribution Main	1845	P-7543	COV	Potters St.	6	Asbestos Cement	233	69	2 out of 5	\$442	103,072
Distribution Main	1852	P-7544	COV	Potters St.	6	Asbestos Cement	193	69	2 out of 5	\$442	85,472
Distribution Main	2627	P-8305	COV	Powhatan Ave.	6	Asbestos Cement	395	53	1.85 out of 5	\$442	174,588
Distribution Main	9617	P-8939	COV	Prince Street	6	Asbestos Cement	80	62	2 out of 5	\$442	35,328
Distribution Main	9618		COV	Prince Street	1	Copper	5	62	2.43 out of 5	\$442	2,198
Distribution Main	11284	P-8939	COV	Prince Street	6	Asbestos Cement	1	62	2 out of 5	\$442	530
Distribution Main	4788	P-8937	COV	Princess Street	2	Galvanized Iron	318	61	3.28 out of 5	\$442	140,585
Distribution Main	5048	P-8938	COV	Princess Street	2	Galvanized Iron	252	129	3.57 out of 5	\$442	111,245
Distribution Main	11283	P-8938	COV	Princess Street	2	Galvanized Iron	4	129	3.57 out of 5	\$442	1,940
Distribution Main	1449	P-7807	COV	Princeton Ave.	8	Asbestos Cement	239	59	1.14 out of 5	\$442	105,516
Distribution Main	1489	P-7794	COV	Princeton Ave.	8	Asbestos Cement	472	59	1.14 out of 5	\$442	208,814
Distribution Main	1490	P-7794	COV	Princeton Ave.	8	Asbestos Cement	29	59	1.14 out of 5	\$442	13,035
Distribution Main	1493	P-9028	COV	Princeton Ave.	8	Asbestos Cement	255	59	1.14 out of 5	\$442	112,863
Distribution Main	1495	P-7803	COV	Princeton Ave.	8	Asbestos Cement	244	59	1.14 out of 5	\$442	107,837
Distribution Main	1717	P-7793	COV	Princeton Ave.	8	Asbestos Cement	844	59	1.14 out of 5	\$442	372,947

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3160	P-7797	COV	Princeton Ave.	8	Asbestos Cement	259	59	1.14 out of 5	\$442	114,608
Distribution Main	3186	P-7776	COV	Princeton Ave.	8	Asbestos Cement	28	59	1.14 out of 5	\$442	12,384
Distribution Main	3187	P-7776	COV	Princeton Ave.	8	Asbestos Cement	569	59	1.14 out of 5	\$442	251,307
Distribution Main	3226	P-7805	COV	Princeton Ave.	8	Asbestos Cement	25	59	1.14 out of 5	\$442	10,971
Distribution Main	3227	P-7802	COV	Princeton Ave.	8	Asbestos Cement	238	59	1.14 out of 5	\$442	105,120
Distribution Main	3230	P-7801	COV	Princeton Ave.	8	Asbestos Cement	444	59	1.14 out of 5	\$442	196,277
Distribution Main	3231	P-7801	COV	Princeton Ave.	8	Asbestos Cement	48	59	1.14 out of 5	\$442	21,251
Distribution Main	3234	P-7805	COV	Princeton Ave.	8	Asbestos Cement	51	59	1.14 out of 5	\$442	22,512
Distribution Main	3235	P-7805	COV	Princeton Ave.	8	Asbestos Cement	317	59	1.14 out of 5	\$442	140,021
Distribution Main	1636	P-8319	COV	Prospect Ave.	6	Asbestos Cement	104	67	2 out of 5	\$442	45,767
Distribution Main	1849	P-8319	COV	Prospect Ave.	6	Asbestos Cement	9	67	2 out of 5	\$442	4,104
Distribution Main	2648	P-7545	COV	Prospect Ave.	6	Asbestos Cement	23	67	2 out of 5	\$442	10,173
Distribution Main	2649	P-7545	COV	Prospect Ave.	6	Asbestos Cement	294	67	2 out of 5	\$442	129,885
Transmission Main	631	P-591	COV	Pulaski St.	12	Ductile Iron	655	14	0 out of 5	N/A	\$0
Transmission Main	632	P-591	COV	Pulaski St.	12	Ductile Iron	102	14	0 out of 5	N/A	\$0
Transmission Main	7427	P-8017	COV	Pulaski St.	12	Ductile Iron	252	14	0 out of 5	N/A	\$0
Transmission Main	7428	P-8017	COV	Pulaski St.	12	Ductile Iron	302	14	0 out of 5	N/A	\$0
Transmission Main	7429	P-8014	COV	Pulaski St.	12	Ductile Iron	133	14	0 out of 5	N/A	\$0
Transmission Main	7430	P-8014	COV	Pulaski St.	12	Ductile Iron	44	14	0 out of 5	N/A	\$0
Transmission Main	7431	P-8012	COV	Pulaski St.	12	Ductile Iron	347	14	0 out of 5	N/A	\$0
Transmission Main	8149	P-8019	COV	Pulaski St.	12	Ductile Iron	32	14	0 out of 5	N/A	\$0
Transmission Main	8168	P-591	COV	Pulaski St.	12	Ductile Iron	84	14	0 out of 5	N/A	\$0
Transmission Main	11787	P-591	COV	Pulaski St.	12	Ductile Iron	246	14	0 out of 5	N/A	\$0
Distribution Main	3083	P-7400	COV	Puritan Ave.	6	Asbestos Cement	634	57	1.85 out of 5	\$442	280,307
Distribution Main	3084	P-7400	COV	Puritan Ave.	6	Asbestos Cement	32	57	1.85 out of 5	\$442	14,183
Distribution Main	11788	P-7400	COV	Puritan Ave.	6	Asbestos Cement	370	57	1.85 out of 5	\$442	163,440
Distribution Main	2671		COV	Quidnick Street	8	Unknown	22	UNK	0 out of 5	N/A	\$0
Distribution Main	2672		COV	Quidnick Street	6	Unknown	12	UNK	0.71 out of 5	\$442	5,276
Distribution Main	10347		COV	Quidnick Street	8	Unknown	58	UNK	0 out of 5	N/A	\$0
Distribution Main	10348		COV	Quidnick Street	6	Unknown	40	UNK	0.71 out of 5	\$442	17,896
Distribution Main	10349		COV	Quidnick Street	6	Unknown	42	UNK	0.71 out of 5	\$442	18,450
Distribution Main	9077	P-7666	COV	Quiet / Forge	8	Ductile Iron	242	13	0 out of 5	N/A	\$0
Distribution Main	11179	P-7666	COV	Quiet / Forge	8	Ductile Iron	31	13	0 out of 5	N/A	\$0
Distribution Main	421	P-8303	COV	Quiet Ave.	6	Asbestos Cement	104	53	1.85 out of 5	\$442	46,101
Distribution Main	2618		COV	Quiet Ave.	6	Asbestos Cement	53	53	1.85 out of 5	\$442	23,464
Distribution Main	9074	P-8976	COV	Quiet Ave.	6	Ductile Iron	3	31	0.85 out of 5	\$442	1,434
Distribution Main	9075	P-8976	COV	Quiet Ave.	6	Ductile Iron	119	31	0.85 out of 5	\$442	52,538
Distribution Main	11057	P-8303	COV	Quiet Ave.	6	Asbestos Cement	7	53	1.85 out of 5	\$442	2,964
Distribution Main	947	P-9069	COV	Rainville Avenue	1	Unknown	299	UNK	1.42 out of 5	\$442	132,330
Distribution Main	1644	P-7552	COV	Rathbun St.	2	Copper	751	78	2.43 out of 5	\$442	332,048
Distribution Main	1683	P-7552	COV	Rathbun St.	2	Copper	12	78	2.43 out of 5	\$442	5,420
Distribution Main	1850	P-7552	COV	Rathbun St.	2	Copper	80	78	2.43 out of 5	\$442	35,566
Distribution Main	8359	P-7736	COV	Rawlinson Dr	8	Ductile Iron	314	13	0 out of 5	N/A	\$0
Distribution Main	531		COV	Rawlinson Dr.	6	Asbestos Cement	47	UNK	1.56 out of 5	\$442	20,987

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2301	P-7742	COV	Rawlinson Dr.	8	Ductile Iron	43	19	0 out of 5	N/A	\$0
Distribution Main	3181	P-7742	COV	Rawlinson Dr.	6	Asbestos Cement	335	60	1.85 out of 5	\$442	147,892
Distribution Main	3182	P-7742	COV	Rawlinson Dr.	6	Asbestos Cement	817	60	1.85 out of 5	\$442	361,206
Distribution Main	9548	P-7742	COV	Rawlinson Dr.	6	Ductile Iron	7	19	0.71 out of 5	N/A	\$0
Distribution Main	9552	P-7742	COV	Rawlinson Dr.	6	Ductile Iron	7	19	0.71 out of 5	N/A	\$0
Distribution Main	11203	P-7742	COV	Rawlinson Dr.	6	Asbestos Cement	4	60	1.85 out of 5	\$442	1,672
Distribution Main	11785	P-7742	COV	Rawlinson Dr.	6	Asbestos Cement	152	60	1.85 out of 5	\$442	67,030
Distribution Main	1097	P-8846	COV	Ray St.	6	PVC	20	38	1.14 out of 5	\$442	8,989
Distribution Main	1559	P-8055	COV	Ray St.	6	PVC	165	38	1.14 out of 5	\$442	72,876
Distribution Main	1560	P-8055	COV	Ray St.	6	PVC	196	38	1.14 out of 5	\$442	86,680
Distribution Main	2923	P-7071	COV	Ray St.	6	PVC	106	38	1.14 out of 5	\$442	46,958
Distribution Main	2924	P-7071	COV	Ray St.	6	PVC	523	38	1.14 out of 5	\$442	231,359
Distribution Main	11783	P-7071	COV	Ray St.	6	PVC	26	38	1.14 out of 5	\$442	11,274
Distribution Main	954	P-8006	COV	Raymond St	6	Asbestos Cement	256	70	2 out of 5	\$442	113,168
Distribution Main	313	P-9051	COV	Raymond St.	6	Asbestos Cement	78	70	2 out of 5	\$442	34,428
Distribution Main	569	P-7995	COV	Raymond St.	6	Asbestos Cement	274	70	2 out of 5	\$442	121,020
Distribution Main	2727	P-8003	COV	Raymond St.	6	Asbestos Cement	31	70	2 out of 5	\$442	13,642
Distribution Main	2728	P-8003	COV	Raymond St.	6	Asbestos Cement	222	70	2 out of 5	\$442	98,046
Distribution Main	8993	P-8038	COV	Read Ave	8	Ductile Iron	7	9	0 out of 5	N/A	\$0
Distribution Main	11517	P-8039	COV	Read Ave	8	Ductile Iron	6	9	0 out of 5	N/A	\$0
Distribution Main	315	P-9060	COV	Read Ave.	6	Cast Iron	68	132	2.57 out of 5	\$442	30,086
Distribution Main	937	P-9062	COV	Read Ave.	6	Cast Iron	68	132	2.57 out of 5	\$442	30,126
Distribution Main	938	P-8031	COV	Read Ave.	6	Cast Iron	157	132	2.57 out of 5	\$442	69,562
Distribution Main	939	P-8031	COV	Read Ave.	6	Cast Iron	3	132	2.57 out of 5	\$442	1,506
Distribution Main	940	P-8029	COV	Read Ave.	8	Cast Iron	7	132	1.86 out of 5	\$442	3,113
Distribution Main	943	P-9066	COV	Read Ave.	6	Cast Iron	209	132	2.57 out of 5	\$442	92,502
Distribution Main	944	P-9066	COV	Read Ave.	6	Cast Iron	14	132	2.57 out of 5	\$442	6,157
Distribution Main	946	P-9068	COV	Read Ave.	6	Cast Iron	108	132	2.57 out of 5	\$442	47,540
Distribution Main	948	P-8032	COV	Read Ave.	6	Cast Iron	72	132	2.57 out of 5	\$442	31,639
Distribution Main	949	P-8039	COV	Read Ave.	6	Cast Iron	214	132	2.57 out of 5	\$442	94,754
Distribution Main	950	P-8039	COV	Read Ave.	6	Cast Iron	751	132	2.57 out of 5	\$442	331,977
Distribution Main	951	P-8043	COV	Read Ave.	6	Cast Iron	264	132	2.57 out of 5	\$442	116,664
Distribution Main	952	P-8043	COV	Read Ave.	6	Cast Iron	329	132	2.57 out of 5	\$442	145,577
Distribution Main	2697	P-8028	COV	Read Ave.	8	Cast Iron	13	132	1.86 out of 5	\$442	5,672
Distribution Main	2698	P-8023	COV	Read Ave.	6	Cast Iron	31	132	2.57 out of 5	\$442	13,708
Distribution Main	2703	P-8029	COV	Read Ave.	6	Cast Iron	215	132	2.57 out of 5	\$442	95,058
Distribution Main	2705	P-8038	COV	Read Ave.	6	Cast Iron	365	132	2.57 out of 5	\$442	161,235
Distribution Main	2708	P-9055	COV	Read Ave.	6	Cast Iron	357	132	2.57 out of 5	\$442	157,819
Distribution Main	2713	P-9054	COV	Read Ave.	6	Cast Iron	230	132	2.57 out of 5	\$442	101,636
Distribution Main	2714	P-9054	COV	Read Ave.	6	Cast Iron	14	132	2.57 out of 5	\$442	6,381
Distribution Main	2719	P-8027	COV	Read Ave.	6	Cast Iron	177	132	2.57 out of 5	\$442	78,373
Distribution Main	2720	P-8027	COV	Read Ave.	6	Cast Iron	24	132	2.57 out of 5	\$442	10,680
Distribution Main	2722	P-9036	COV	Read Ave.	6	Cast Iron	10	132	2.57 out of 5	\$442	4,498
Distribution Main	2723	P-9036	COV	Read Ave.	6	Cast Iron	144	132	2.57 out of 5	\$442	63,514

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2725	P-8023	COV	Read Ave.	6	Cast Iron	343	132	2.57 out of 5	\$442	151,603
Distribution Main	2920	P-8043	COV	Read Ave.	6	Cast Iron	24	132	2.57 out of 5	\$442	10,783
Distribution Main	2921	P-8043	COV	Read Ave.	6	Cast Iron	534	132	2.57 out of 5	\$442	235,831
Distribution Main	2930	P-8043	COV	Read Ave.	6	Cast Iron	581	132	2.57 out of 5	\$442	256,669
Transmission Main	2931	P-8045	COV	Read Ave.	16	Asbestos Cement	1,089	75	1.29 out of 5	\$442	481,285
Transmission Main	2933	P-8056	COV	Read Ave.	16	Asbestos Cement	74	75	1.29 out of 5	\$442	32,870
Transmission Main	8991	P-8056	COV	Read Ave.	16	Asbestos Cement	4	75	1.29 out of 5	\$442	1,794
Distribution Main	11186	P-9054	COV	Read Ave.	6	Cast Iron	229	132	2.57 out of 5	\$442	101,235
Distribution Main	11782	P-9054	COV	Read Ave.	6	Cast Iron	83	132	2.57 out of 5	\$442	36,717
Transmission Main	8798	P-8785	COV	Read School House Rd	20	Ductile Iron	114	10	0 out of 5	N/A	\$0
Transmission Main	8799		COV	Read School House Rd	20	Ductile Iron	46	10	0 out of 5	N/A	\$0
Transmission Main	8804	P-8786	COV	Read School House Rd	20	Ductile Iron	47	10	0 out of 5	N/A	\$0
Transmission Main	8805	P-8786	COV	Read School House Rd	20	Ductile Iron	32	10	0 out of 5	N/A	\$0
Transmission Main	11512	P-8786	COV	Read School House Rd	20	Ductile Iron	21	10	0 out of 5	N/A	\$0
Distribution Main	7172		COV	Read School House Rd.	6	Unknown	5	UNK	0.71 out of 5	\$442	2,410
Transmission Main	7173		COV	Read School House Rd.	12	Unknown	72	UNK	0 out of 5	N/A	\$0
Transmission Main	7902		COV	Read School House Rd.	12	Unknown	6	UNK	0 out of 5	N/A	\$0
Transmission Main	8757	P-8785	COV	Read Schoolhouse Rd	20	Ductile Iron	1,731	8	0 out of 5	N/A	\$0
Transmission Main	8758	P-8785	COV	Read Schoolhouse Rd	20	Ductile Iron	49	8	0 out of 5	N/A	\$0
Transmission Main	8766	P-7181	COV	Read Schoolhouse Rd	20	Ductile Iron	582	8	0 out of 5	N/A	\$0
Transmission Main	8767	P-7181	COV	Read Schoolhouse Rd	20	Ductile Iron	978	8	0 out of 5	N/A	\$0
Transmission Main	8768	P-8785	COV	Read Schoolhouse Rd	20	Ductile Iron	646	8	0 out of 5	N/A	\$0
Transmission Main	8769	P-8785	COV	Read Schoolhouse Rd	20	Ductile Iron	710	8	0 out of 5	N/A	\$0
Transmission Main	8783		COV	Read Schoolhouse Rd	12	Ductile Iron	17	8	0 out of 5	N/A	\$0
Transmission Main	8789	P-7181	COV	Read Schoolhouse Rd	20	Ductile Iron	40	8	0 out of 5	N/A	\$0
Transmission Main	8790	P-7181	COV	Read Schoolhouse Rd	20	Ductile Iron	41	8	0 out of 5	N/A	\$0
Transmission Main	8795		COV	Read Schoolhouse Rd	20	Ductile Iron	13	8	0 out of 5	N/A	\$0
Transmission Main	8796		COV	Read Schoolhouse Rd	12	Ductile Iron	3	8	0 out of 5	N/A	\$0
Transmission Main	11502	P-8785	COV	Read Schoolhouse Rd	20	Ductile Iron	142	8	0 out of 5	N/A	\$0
Transmission Main	11503	P-8785	COV	Read Schoolhouse Rd	20	Ductile Iron	10	8	0 out of 5	N/A	\$0
Transmission Main	11508	P-7181	COV	Read Schoolhouse Rd	20	Ductile Iron	26	8	0 out of 5	N/A	\$0
Transmission Main	11509	P-7181	COV	Read Schoolhouse Rd	20	Ductile Iron	17	8	0 out of 5	N/A	\$0
Transmission Main	11796	P-7181	COV	Read Schoolhouse Rd	20	Ductile Iron	534	8	0 out of 5	N/A	\$0
Transmission Main	8781		COV	Read Schoolhouse Rd.	12	Ductile Iron	12	8	0 out of 5	N/A	\$0
Transmission Main	8782		COV	Read Schoolhouse Rd.	12	Ductile Iron	14	8	0 out of 5	N/A	\$0
Distribution Main	491	P-8854	COV	Rebecca St	8	Ductile Iron	34	15	0 out of 5	N/A	\$0
Distribution Main	9689	P-8855	COV	Rebecca St	6	Ductile Iron	4	15	0.71 out of 5	N/A	\$0
Distribution Main	670	P-8107	COV	Rebecca St.	6	Asbestos Cement	368	58	1.85 out of 5	\$442	162,457
Distribution Main	671	P-8107	COV	Rebecca St.	6	Asbestos Cement	486	58	1.85 out of 5	\$442	215,003
Distribution Main	672		COV	Rebecca St.	6	Asbestos Cement	11	58	1.85 out of 5	\$442	4,781
Distribution Main	2111		COV	Rebecca St.	6	Asbestos Cement	10	58	1.85 out of 5	\$442	4,542
Distribution Main	11085	P-8107	COV	Rebecca St.	6	Asbestos Cement	235	58	1.85 out of 5	\$442	103,839
Distribution Main	7776	P-8363	COV	Red Cedar Dr.	8	Ductile Iron	8	29	0.14 out of 5	\$442	3,721
Distribution Main	7786	P-8952	COV	Red Cedar Dr.	8	Ductile Iron	80	29	0.14 out of 5	\$442	35,424

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7790	P-8363	COV	Red Cedar Dr.	8	Ductile Iron	43	29	0.14 out of 5	\$442	18,906
Distribution Main	7791	P-8363	COV	Red Cedar Dr.	8	Ductile Iron	334	29	0.14 out of 5	\$442	147,812
Distribution Main	8332	P-7089	COV	Red Cedar Dr.	6	Asbestos Cement	277	43	1.85 out of 5	\$442	122,486
Distribution Main	7736	P-7045	COV	Red Maple Rd.	8	Asbestos Cement	20	57	1.14 out of 5	\$442	8,868
Distribution Main	7740	P-7044	COV	Red Maple Rd.	8	Asbestos Cement	541	57	1.14 out of 5	\$442	239,151
Distribution Main	7828	P-4045	COV	Red Maple Rd.	8	Asbestos Cement	276	57	1.14 out of 5	\$442	122,035
Distribution Main	1017	P-7895	COV	Red Oak Dr.	8	Asbestos Cement	355	39	1 out of 5	\$442	156,847
Distribution Main	1018	P-7898	COV	Red Oak Dr.	8	Asbestos Cement	308	39	1 out of 5	\$442	135,919
Distribution Main	1019	P-7898	COV	Red Oak Dr.	8	Asbestos Cement	49	39	1 out of 5	\$442	21,495
Distribution Main	1020	P-7901	COV	Red Oak Dr.	8	Asbestos Cement	207	39	1 out of 5	\$442	91,579
Distribution Main	1021	P-7902	COV	Red Oak Dr.	8	Asbestos Cement	107	39	1 out of 5	\$442	47,509
Distribution Main	1022	P-7902	COV	Red Oak Dr.	8	Asbestos Cement	104	39	1 out of 5	\$442	46,130
Distribution Main	1023	P-7903	COV	Red Oak Dr.	8	Asbestos Cement	371	39	1 out of 5	\$442	164,182
Distribution Main	1024	P-7903	COV	Red Oak Dr.	8	Asbestos Cement	401	39	1 out of 5	\$442	177,228
Distribution Main	1093	P-7893	COV	Red Oak Dr.	8	Asbestos Cement	148	39	1 out of 5	\$442	65,505
Distribution Main	1094	P-7893	COV	Red Oak Dr.	8	Asbestos Cement	253	39	1 out of 5	\$442	111,606
Distribution Main	1919	P-8875	COV	Red Oak Dr.	8	Asbestos Cement	279	39	1 out of 5	\$442	123,216
Distribution Main	1920	P-8875	COV	Red Oak Dr.	8	Asbestos Cement	382	39	1 out of 5	\$442	168,899
Distribution Main	3169	P-7819	COV	Reddington St.	6	Asbestos Cement	935	44	1.85 out of 5	\$442	413,084
Distribution Main	5913	P-8365	COV	Regal Wood Dr.	8	Ductile Iron	188	20	0 out of 5	N/A	\$0
Distribution Main	7856	P-7126	COV	Regal Wood Dr.	8	Ductile Iron	10	20	0 out of 5	N/A	\$0
Distribution Main	7857	P-7126	COV	Regal Wood Dr.	8	Ductile Iron	139	20	0 out of 5	N/A	\$0
Distribution Main	7858	P-7117	COV	Regal Wood Dr.	8	Ductile Iron	392	20	0 out of 5	N/A	\$0
Distribution Main	7861	P-7126	COV	Regal Wood Dr.	8	Ductile Iron	466	20	0 out of 5	N/A	\$0
Distribution Main	7862	P-7126	COV	Regal Wood Dr.	8	Ductile Iron	188	20	0 out of 5	N/A	\$0
Distribution Main	588	P-8917	COV	Regent Street	6	Ductile Iron	663	29	0.85 out of 5	\$442	293,216
Distribution Main	1666	P-8970	COV	Regis Street	6	Asbestos Cement	139	68	2 out of 5	\$442	61,628
Transmission Main	8075	P-9025	COV	Rejane St	12	Ductile Iron	45	11	0 out of 5	N/A	\$0
Distribution Main	4769	P-8146	COV	Rejane St.	6	Asbestos Cement	58	68	2 out of 5	\$442	25,472
Distribution Main	4770	P-8146	COV	Rejane St.	6	Asbestos Cement	445	68	2 out of 5	\$442	196,631
Distribution Main	4953	P-8147	COV	Rejane St.	6	Asbestos Cement	249	68	2 out of 5	\$442	110,154
Distribution Main	818	P-7347	COV	Remington Farm Dr.	8	Ductile Iron	872	24	0.14 out of 5	N/A	\$0
Distribution Main	820	P-7348	COV	Remington Farm Dr.	8	Ductile Iron	53	24	0.14 out of 5	N/A	\$0
Distribution Main	821	P-7348	COV	Remington Farm Dr.	8	Ductile Iron	84	24	0.14 out of 5	N/A	\$0
Distribution Main	2104	P-7345	COV	Remington Farm Dr.	8	Ductile Iron	826	24	0.14 out of 5	N/A	\$0
Distribution Main	2105	P-7345	COV	Remington Farm Dr.	8	Ductile Iron	42	24	0.14 out of 5	N/A	\$0
Distribution Main	9961	P-7347	COV	Remington Farm Dr.	8	Ductile Iron	374	24	0.14 out of 5	N/A	\$0
Distribution Main	9962	P-7345	COV	Remington Farm Dr.	8	Ductile Iron	696	24	0.14 out of 5	N/A	\$0
Distribution Main	9963	P-7345	COV	Remington Farm Dr.	8	Ductile Iron	50	24	0.14 out of 5	N/A	\$0
Distribution Main	11981	P-7345	COV	Remington Farm Dr.	8	Ductile Iron	34	24	0.14 out of 5	N/A	\$0
Distribution Main	724	P-7686	COV	Reno Ct.	6	Asbestos Cement	138	50	1.85 out of 5	\$442	61,065
Distribution Main	725	P-7686	COV	Reno Ct.	6	Asbestos Cement	97	50	1.85 out of 5	\$442	42,706
Distribution Main	10103		COV	Reservoir Rd		Ductile Iron	2	12	0 out of 5	N/A	\$0
Distribution Main	5937	P-7128	COV	Reservoir Rd.	8	Ductile Iron	74	23	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5938	P-7128	COV	Reservoir Rd.	8	Ductile Iron	964	23	0.14 out of 5	N/A	\$0
Transmission Main	6322	P-7137	COV	Reservoir Rd.	12	Ductile Iron	896	26	0.14 out of 5	\$442	396,147
Transmission Main	6323	P-7137	COV	Reservoir Rd.	12	Ductile Iron	100	26	0.14 out of 5	\$442	44,151
Distribution Main	6624	P-7158	COV	Reservoir Rd.	8	Asbestos Cement	308	54	1.14 out of 5	\$442	136,132
Distribution Main	6625	P-7158	COV	Reservoir Rd.	8	Asbestos Cement	298	54	1.14 out of 5	\$442	131,611
Transmission Main	7193	P-8359	COV	Reservoir Rd.	12	Asbestos Cement	60	54	1.14 out of 5	\$442	26,631
Transmission Main	7199		COV	Reservoir Rd.	12	Ductile Iron	14	30	0.14 out of 5	\$442	6,088
Transmission Main	7200	P-8355	COV	Reservoir Rd.	12	PVC	25	32	0.43 out of 5	\$442	11,080
Transmission Main	7204	P-8355	COV	Reservoir Rd.	12	Asbestos Cement	12	54	1.14 out of 5	\$442	5,165
Transmission Main	7506	P-8354	COV	Reservoir Rd.	12	Asbestos Cement	202	54	1.14 out of 5	\$442	89,194
Transmission Main	7507	P-8354	COV	Reservoir Rd.	12	Asbestos Cement	404	54	1.14 out of 5	\$442	178,488
Distribution Main	7508	P-8353	COV	Reservoir Rd.	8	PVC	512	32	0.43 out of 5	\$442	226,320
Distribution Main	7509	P-8353	COV	Reservoir Rd.	8	PVC	171	32	0.43 out of 5	\$442	75,632
Transmission Main	7512	P-8755	COV	Reservoir Rd.	12	Ductile Iron	99	30	0.14 out of 5	\$442	43,670
Transmission Main	7517	P-8354	COV	Reservoir Rd.	12	Ductile Iron	15	30	0.14 out of 5	\$442	6,435
Transmission Main	7518	P-8755	COV	Reservoir Rd.	12	Ductile Iron	3	30	0.14 out of 5	\$442	1,486
Transmission Main	7525	P-7138	COV	Reservoir Rd.	12	PVC	316	31	0.43 out of 5	\$442	139,582
Transmission Main	7526	P-7155	COV	Reservoir Rd.	12	PVC	137	31	0.43 out of 5	\$442	60,428
Transmission Main	7527	P-7155	COV	Reservoir Rd.	12	PVC	290	31	0.43 out of 5	\$442	128,310
Distribution Main	7597	P-7156	COV	Reservoir Rd.	8	Asbestos Cement	250	54	1.14 out of 5	\$442	110,586
Transmission Main	7598	P-7153	COV	Reservoir Rd.	12	PVC	9	32	0.43 out of 5	\$442	3,800
Transmission Main	7599	P-7153	COV	Reservoir Rd.	12	PVC	590	32	0.43 out of 5	\$442	260,978
Transmission Main	7968	P-7129	COV	Reservoir Rd.	12	Ductile Iron	885	26	0.14 out of 5	\$442	391,106
Transmission Main	7969	P-7129	COV	Reservoir Rd.	12	Ductile Iron	945	23	0.14 out of 5	N/A	\$0
Transmission Main	7980	P-7137	COV	Reservoir Rd.	12	Ductile Iron	59	26	0.14 out of 5	\$442	25,919
Transmission Main	8171	P-7137	COV	Reservoir Rd.	12	Ductile Iron	50	26	0.14 out of 5	\$442	22,262
Transmission Main	8172	P-7137	COV	Reservoir Rd.	12	Ductile Iron	4	26	0.14 out of 5	\$442	1,866
Distribution Main	10175	P-7153	COV	Reservoir Rd.	4	Ductile Iron	11	20	1.42 out of 5	N/A	\$0
Transmission Main	10422		COV	Reservoir Rd.	12	Ductile Iron	7	30	0.14 out of 5	\$442	2,991
Transmission Main	11381	P-8354	COV	Reservoir Rd.	12	Asbestos Cement	110	54	1.14 out of 5	\$442	48,755
Transmission Main	11382	P-8755	COV	Reservoir Rd.	12	Ductile Iron	10	30	0.14 out of 5	\$442	4,362
Transmission Main	11383	P-7155	COV	Reservoir Rd.	12	PVC	26	31	0.43 out of 5	\$442	11,560
Transmission Main	11384	P-7155	COV	Reservoir Rd.	12	PVC	5	31	0.43 out of 5	\$442	2,359
Distribution Main	11395	P-7156	COV	Reservoir Rd.	8	Asbestos Cement	4	54	1.14 out of 5	\$442	1,865
Transmission Main	11396	P-7153	COV	Reservoir Rd.	12	PVC	299	32	0.43 out of 5	\$442	132,025
Distribution Main	1144		COV	Reynolds Ct.	6	Ductile Iron	89	15	0.71 out of 5	N/A	\$0
Distribution Main	1012	P-8864	COV	Richard Ct	1.5	Galvanized Iron	88	UNK	2.85 out of 5	\$442	38,841
Distribution Main	2667	P-8865	COV	Richard Ct	1.5	Galvanized Iron	82	UNK	2.85 out of 5	\$442	36,367
Distribution Main	2668	P-8863	COV	Richard Ct	1.5	Galvanized Iron	152	UNK	2.85 out of 5	\$442	67,392
Distribution Main	2783	P-8301	COV	Ridge Ave.	8	Ductile Iron	197	19	0 out of 5	N/A	\$0
Distribution Main	5329	P-7514	COV	Robbins Dr.	6	Asbestos Cement	818	70	2 out of 5	\$442	361,716
Distribution Main	4951	P-8140	COV	Rosebud St.	6	Asbestos Cement	191	58	1.85 out of 5	\$442	84,437
Distribution Main	4952	P-8140	COV	Rosebud St.	6	Asbestos Cement	16	58	1.85 out of 5	\$442	6,984
Distribution Main	10404	P-8140	COV	Rosebud St.	6	Ductile Iron	33	11	0.71 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2408	P-8062	COV	Rosella St.	6	Ductile Iron	525	27	0.85 out of 5	\$442	231,866
Distribution Main	2919	P-8062	COV	Rosella St.	6	Ductile Iron	4	27	0.85 out of 5	\$442	1,856
Transmission Main	733	P-8195	COV	Rosemary St.	12	Ductile Iron	349	31	0.14 out of 5	\$442	154,271
Distribution Main	740	P-7487	COV	Rosemary St.	6	Asbestos Cement	659	57	1.85 out of 5	\$442	291,148
Transmission Main	1267	P-8195	COV	Rosemary St.	12	Ductile Iron	11	31	0.14 out of 5	\$442	4,776
Transmission Main	1268	P-8195	COV	Rosemary St.	12	Ductile Iron	41	28	0.14 out of 5	\$442	18,214
Distribution Main	1095	P-7910	COV	Rosewood Ct.	6	Asbestos Cement	348	38	1.71 out of 5	\$442	153,720
Distribution Main	8304	P-8414	COV	Ross Ct	8	Ductile Iron	322	13	0 out of 5	N/A	\$0
Distribution Main	9748	P-8214	COV	Roundway Dr	8	Ductile Iron	253	8	0 out of 5	N/A	\$0
Distribution Main	9757	P-611	COV	Roundway Dr	8	Ductile Iron	306	8	0 out of 5	N/A	\$0
Distribution Main	10405	P-8214	COV	Roundway Dr	8	Ductile Iron	63	8	0 out of 5	N/A	\$0
Distribution Main	10406	P-8214	COV	Roundway Dr	8	Ductile Iron	35	8	0 out of 5	N/A	\$0
Distribution Main	10865	P-8212	COV	Roundway Dr	8	Ductile Iron	43	8	0 out of 5	N/A	\$0
Distribution Main	10866	P-8212	COV	Roundway Dr	8	Ductile Iron	176	8	0 out of 5	N/A	\$0
Distribution Main	11599	P-612	COV	Roundway Dr	8	Ductile Iron	100	8	0 out of 5	N/A	\$0
Distribution Main	5257	P-7023	COV	Rustic Way	8	Asbestos Cement	386	40	1 out of 5	\$442	170,735
Distribution Main	2190	P-8315	COV	Salvas Ave.	8	Ductile Iron	386	16	0 out of 5	N/A	\$0
Distribution Main	2191	P-8315	COV	Salvas Ave.	8	Ductile Iron	93	16	0 out of 5	N/A	\$0
Distribution Main	3144	P-8315	COV	Salvas Ave.	8	Ductile Iron	74	16	0 out of 5	N/A	\$0
Distribution Main	9052	COV	COV	Salvas Ave.	8	Ductile Iron	5	16	0 out of 5	N/A	\$0
Distribution Main	11202	P-8315	COV	Salvas Ave.	8	Ductile Iron	35	16	0 out of 5	N/A	\$0
Distribution Main	2797	P-7590	COV	Sand St.	6	Asbestos Cement	236	56	1.85 out of 5	\$442	104,093
Distribution Main	515	P-7941	COV	Sandalwood Ct.	6	Asbestos Cement	9	53	1.85 out of 5	\$442	4,144
Distribution Main	2692	P-7942	COV	Sandalwood Ct.	6	Asbestos Cement	43	53	1.85 out of 5	\$442	18,909
Distribution Main	2693	P-8383	COV	Sandalwood Ct.	6	Asbestos Cement	483	53	1.85 out of 5	\$442	213,397
Distribution Main	2744	P-8383	COV	Sandalwood Ct.	6	Asbestos Cement	12	53	1.85 out of 5	\$442	5,493
Distribution Main	1142	COV	COV	Sandlewood Ct	8	Ductile Iron	41	15	0 out of 5	N/A	\$0
Distribution Main	513	P-8381	COV	Sandlewood Ct.	6	Asbestos Cement	152	53	1.85 out of 5	\$442	67,156
Distribution Main	518	P-8381	COV	Sandlewood Ct.	6	Asbestos Cement	176	53	1.85 out of 5	\$442	77,728
Distribution Main	519	P-8382	COV	Sandlewood Ct.	6	Asbestos Cement	107	53	1.85 out of 5	\$442	47,270
Distribution Main	10447	COV	COV	Sandlewood Ct.	6	Asbestos Cement	23	53	1.85 out of 5	\$442	9,978
Distribution Main	11070	P-8381	COV	Sandlewood Ct.	6	Asbestos Cement	46	53	1.85 out of 5	\$442	20,194
Transmission Main	60	P-8930	COV	Sandy Bottom Rd	16	Ductile Iron	523	8	0 out of 5	N/A	\$0
Distribution Main	9577	P-8928	COV	Sandy Bottom Rd	8	Ductile Iron	19	2	0 out of 5	N/A	\$0
Transmission Main	10591	P-8472	COV	Sandy Bottom Rd	12	Ductile Iron	795	2	0 out of 5	N/A	\$0
Transmission Main	10592	P-7843	COV	Sandy Bottom Rd	12	Ductile Iron	436	0	0 out of 5	N/A	\$0
Distribution Main	10593	P-8472	COV	Sandy Bottom Rd	8	Ductile Iron	15	2	0 out of 5	N/A	\$0
Transmission Main	11684	P-8473	COV	Sandy Bottom Rd	12	Ductile Iron	291	0	0 out of 5	N/A	\$0
Transmission Main	11685	P-7843	COV	Sandy Bottom Rd	16	Ductile Iron	22	2	0 out of 5	N/A	\$0
Distribution Main	9573	P-8472	COV	Sandy Bottom Rd.	8	Ductile Iron	29	0	0 out of 5	N/A	\$0
Distribution Main	9574	P-8472	COV	Sandy Bottom Rd.	8	Ductile Iron	24	0	0 out of 5	N/A	\$0
Distribution Main	9575	P-8472	COV	Sandy Bottom Rd.	8	Ductile Iron	143	0	0 out of 5	N/A	\$0
Distribution Main	9576	P-8472	COV	Sandy Bottom Rd.	8	Cast Iron	194	0	1.14 out of 5	N/A	\$0
Distribution Main	8773	P-8901	COV	Sawyer Dr	8	Ductile Iron	52	8	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	8774	P-8901	COV	Sawyer Dr	8	Ductile Iron	3	8	0 out of 5	N/A	\$0
Distribution Main	4908	P-8901	COV	Sawyer Drive	8	Asbestos Cement	216	44	1.14 out of 5	\$442	95,289
Distribution Main	4909	P-8901	COV	Sawyer Drive	8	Asbestos Cement	344	44	1.14 out of 5	\$442	152,049
Distribution Main	7762	P-7228	COV	Second St.	6	Asbestos Cement	168	65	2 out of 5	\$442	74,347
Distribution Main	8353	P-7725	COV	Seneca St.	8	Ductile Iron	305	13	0 out of 5	N/A	\$0
Distribution Main	8354	P-8765	COV	Seneca St.	8	Ductile Iron	197	13	0 out of 5	N/A	\$0
Distribution Main	7459	P-7104	COV	Sharon Dr.	8	Ductile Iron	464	26	0.14 out of 5	\$442	205,200
Distribution Main	7460	P-7104	COV	Sharon Dr.	8	Ductile Iron	798	26	0.14 out of 5	\$442	352,636
Distribution Main	11803	P-7104	COV	Sharon Dr.	8	Ductile Iron	784	26	0.14 out of 5	\$442	346,326
Distribution Main	11804	P-7104	COV	Sharon Dr.	8	Ductile Iron	790	26	0.14 out of 5	\$442	349,055
Distribution Main	2736	P-8284	COV	Sharp St.	6	Asbestos Cement	290	56	1.85 out of 5	\$442	128,248
Distribution Main	9759	P-620	COV	Sheffield Ave	8	Ductile Iron	213	8	0 out of 5	N/A	\$0
Distribution Main	9784	P-618	COV	Sheffield Ave	8	Ductile Iron	193	8	0 out of 5	N/A	\$0
Distribution Main	10407	P-615	COV	Sheffield Ave	8	Ductile Iron	31	8	0 out of 5	N/A	\$0
Distribution Main	10408	P-615	COV	Sheffield Ave	8	Ductile Iron	182	8	0 out of 5	N/A	\$0
Distribution Main	11600	P-618	COV	Sheffield Ave	8	Ductile Iron	128	8	0 out of 5	N/A	\$0
Distribution Main	3044	P-7836	COV	Sheltra Ave	8	Asbestos Cement	793	54	1.14 out of 5	\$442	350,684
Distribution Main	3045	P-7836	COV	Sheltra Ave	8	Asbestos Cement	79	54	1.14 out of 5	\$442	34,752
Distribution Main	9513	P-8285	COV	Sheltra Ave.	8	PVC	603	34	0.43 out of 5	\$442	266,552
Distribution Main	9514	P-8285	COV	Sheltra Ave.	8	PVC	25	34	0.43 out of 5	\$442	10,999
Distribution Main	29	P-7383	COV	Sheri Dr	8	Ductile Iron	5	30	0.14 out of 5	\$442	2,216
Distribution Main	30	P-7383	COV	Sheri Dr	8	Ductile Iron	155	30	0.14 out of 5	\$442	68,322
Distribution Main	450	P-7382	COV	Sheri Dr.	8	Ductile Iron	233	30	0.14 out of 5	\$442	102,968
Distribution Main	451	P-7382	COV	Sheri Dr.	8	Ductile Iron	196	30	0.14 out of 5	\$442	86,812
Distribution Main	1463	P-7381	COV	Sheri Dr.	8	Ductile Iron	119	30	0.14 out of 5	\$442	52,636
Distribution Main	448	P-7374	COV	Short Way Dr.	6	Asbestos Cement	54	48	1.85 out of 5	\$442	23,757
Distribution Main	1473	P-7374	COV	Short Way Dr.	6	Asbestos Cement	237	48	1.85 out of 5	\$442	104,792
Distribution Main	1474	P-7374	COV	Short Way Dr.	6	Asbestos Cement	22	48	1.85 out of 5	\$442	9,789
Distribution Main	9780	P-627	COV	Sidney St	8	Ductile Iron	152	8	0 out of 5	N/A	\$0
Distribution Main	3065	P-7359	COV	Silo Lane	8	Ductile Iron	230	24	0.14 out of 5	N/A	\$0
Distribution Main	4907	P-7105	COV	Silver Maple Dr.	8	Asbestos Cement	333	41	1.14 out of 5	\$442	147,111
Distribution Main	6112	P-7121	COV	Silver Maple Dr.	8	Ductile Iron	292	28	0.14 out of 5	\$442	128,893
Distribution Main	6315	P-7112	COV	Silver Maple Dr.	8	Ductile Iron	199	28	0.14 out of 5	\$442	87,930
Distribution Main	6316	P-7113	COV	Silver Maple Dr.	8	Asbestos Cement	95	41	1.14 out of 5	\$442	42,068
Distribution Main	7455	P-7108	COV	Silver Maple Dr.	8	Asbestos Cement	70	41	1.14 out of 5	\$442	30,827
Distribution Main	7461	P-7108	COV	Silver Maple Dr.	8	Asbestos Cement	552	41	1.14 out of 5	\$442	244,052
Distribution Main	7975	P-7118	COV	Silver Maple Dr.	8	Ductile Iron	380	28	0.14 out of 5	\$442	167,947
Distribution Main	8729	P-7113	COV	Silver Maple Dr.	8	Asbestos Cement	86	41	1.14 out of 5	\$442	38,096
Distribution Main	8730	P-7113	COV	Silver Maple Dr.	8	Asbestos Cement	14	41	1.14 out of 5	\$442	6,047
Distribution Main	10088	P-7121	COV	Silver Maple Dr.	8	Ductile Iron	4	28	0.14 out of 5	\$442	1,654
Distribution Main	10089	P-7121	COV	Silver Maple Dr.	8	Ductile Iron	56	28	0.14 out of 5	\$442	24,965
Distribution Main	10090	P-7118	COV	Silver Maple Dr.	8	Ductile Iron	61	28	0.14 out of 5	\$442	27,004
Distribution Main	2196	P-7749	COV	Sooner Ln.	8	Ductile Iron	334	27	0.14 out of 5	\$442	147,765
Distribution Main	1687	P-604	COV	Sophia'S Way	6	Ductile Iron	213	29	0.85 out of 5	\$442	94,294

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9744	P-1958	COV	Sophia'S Way	8	Ductile Iron	30	8	0 out of 5	N/A	\$0
Distribution Main	9745	P-1958	COV	Sophia'S Way	8	Ductile Iron	4	8	0 out of 5	N/A	\$0
Distribution Main	9746	P-1959	COV	Sophia'S Way	6	Ductile Iron	18	8	0.71 out of 5	N/A	\$0
Distribution Main	556	P-7710	COV	South Glen Dr.	6	Asbestos Cement	259	60	1.85 out of 5	\$442	114,383
Distribution Main	557	P-7710	COV	South Glen Dr.	6	Asbestos Cement	577	60	1.85 out of 5	\$442	254,884
Transmission Main	582	P-7535	COV	South Main St.	16	Cast Iron	345	129	1.86 out of 5	\$442	152,636
Transmission Main	793	P-7586	COV	South Main St.	16	Cast Iron	81	129	1.86 out of 5	\$442	35,905
Transmission Main	794	P-7537	COV	South Main St.	16	Cast Iron	4	129	1.86 out of 5	\$442	1,939
Transmission Main	795	P-7537	COV	South Main St.	16	Cast Iron	347	129	1.86 out of 5	\$442	153,409
Transmission Main	1264	P-7535	COV	South Main St.	16	Cast Iron	8	129	1.86 out of 5	\$442	3,664
Distribution Main	1648	P-7526	COV	South Main St.	8	Asbestos Cement	302	71	1.29 out of 5	\$442	133,485
Distribution Main	1649	P-7526	COV	South Main St.	8	Asbestos Cement	182	71	1.29 out of 5	\$442	80,610
Distribution Main	1846	P-7551	COV	South Main St.	8	Asbestos Cement	41	71	1.29 out of 5	\$442	17,942
Distribution Main	1847	P-7551	COV	South Main St.	8	Asbestos Cement	164	71	1.29 out of 5	\$442	72,325
Distribution Main	1848	P-7550	COV	South Main St.	8	Asbestos Cement	264	71	1.29 out of 5	\$442	116,791
Distribution Main	1869	P-7534	COV	South Main St.	8	Asbestos Cement	405	71	1.29 out of 5	\$442	178,948
Distribution Main	1870	P-7525	COV	South Main St.	8	Asbestos Cement	266	71	1.29 out of 5	\$442	117,598
Transmission Main	2366	P-7535	COV	South Main St.	16	Cast Iron	127	129	1.86 out of 5	\$442	55,981
Transmission Main	2367	P-8933	COV	South Main St.	16	Cast Iron	30	129	1.86 out of 5	\$442	13,042
Transmission Main	2368	P-8933	COV	South Main St.	16	Cast Iron	8	129	1.86 out of 5	\$442	3,383
Transmission Main	2808	P-7536	COV	South Main St.	16	Cast Iron	134	129	1.86 out of 5	\$442	59,056
Transmission Main	2809	P-7586	COV	South Main St.	16	Cast Iron	174	129	1.86 out of 5	\$442	76,768
Transmission Main	2812	P-7257	COV	South Main St.	16	Cast Iron	14	129	1.86 out of 5	\$442	6,019
Distribution Main	5320	P-7511	COV	South Main St.	8	Asbestos Cement	124	71	1.29 out of 5	\$442	55,008
Distribution Main	5328	P-7511	COV	South Main St.	8	Asbestos Cement	28	71	1.29 out of 5	\$442	12,274
Distribution Main	5337	P-7517	COV	South Main St.	8	Asbestos Cement	366	71	1.29 out of 5	\$442	161,787
Distribution Main	5338	P-7517	COV	South Main St.	8	Asbestos Cement	394	71	1.29 out of 5	\$442	174,158
Distribution Main	5347	P-7511	COV	South Main St.	8	Asbestos Cement	194	71	1.29 out of 5	\$442	85,706
Distribution Main	5348	P-7524	COV	South Main St.	8	Asbestos Cement	241	71	1.29 out of 5	\$442	106,617
Distribution Main	5349	P-7524	COV	South Main St.	8	Asbestos Cement	123	71	1.29 out of 5	\$442	54,249
Distribution Main	5350	P-7523	COV	South Main St.	8	Asbestos Cement	206	71	1.29 out of 5	\$442	91,014
Distribution Main	7689	P-7517	COV	South Main St.	8	Asbestos Cement	491	71	1.29 out of 5	\$442	216,860
Transmission Main	11088	P-7586	COV	South Main St.	16	Cast Iron	15	129	1.86 out of 5	\$442	6,605
Distribution Main	386	P-7934	COV	South Pond Dr.	8	Ductile Iron	115	21	0.14 out of 5	N/A	\$0
Distribution Main	387	P-7932	COV	South Pond Dr.	8	Ductile Iron	669	21	0.14 out of 5	N/A	\$0
Distribution Main	782	P-7932	COV	South Pond Dr.	8	Ductile Iron	69	21	0.14 out of 5	N/A	\$0
Distribution Main	783	P-7932	COV	South Pond Dr.	8	Ductile Iron	148	21	0.14 out of 5	N/A	\$0
Transmission Main	784	P-7931	COV	South Pond Dr.	12	Ductile Iron	622	21	0.14 out of 5	N/A	\$0
Distribution Main	785	P-7932	COV	South Pond Dr.	8	Ductile Iron	149	21	0.14 out of 5	N/A	\$0
Distribution Main	1009	P-7934	COV	South Pond Dr.	8	Ductile Iron	534	21	0.14 out of 5	N/A	\$0
Distribution Main	9663	P-7932	COV	South Pond Dr.	8	Ductile Iron	193	21	0.14 out of 5	N/A	\$0
Distribution Main	9664	P-7934	COV	South Pond Dr.	8	Ductile Iron	352	21	0.14 out of 5	N/A	\$0
Distribution Main	9665	P-7934	COV	South Pond Dr.	8	Ductile Iron	35	21	0.14 out of 5	N/A	\$0
Distribution Main	1226	P-8015	COV	South St.	6	Ductile Iron	1	14	0.71 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	1227	P-8015	COV	South St.	6	Asbestos Cement	173	129	2.29 out of 5	\$442	76,388
Distribution Main	2702	P-8015	COV	South St.	6	Cast Iron	512	129	2.57 out of 5	\$442	226,513
Distribution Main	2726	P-8015	COV	South St.	8	Ductile Iron	26	14	0 out of 5	N/A	\$0
Distribution Main	1506	P-7561	COV	Spencer St.	6	Cast Iron	434	129	2.57 out of 5	\$442	191,677
Distribution Main	3494	P-7572	COV	Spencer St.	6	Cast Iron	104	129	2.57 out of 5	\$442	46,002
Distribution Main	1952	P-9032	COV	St Vincent Depaul	6	Asbestos Cement	6	80	2 out of 5	\$442	2,806
Distribution Main	3071	P-9032	COV	St Vincent Depaul	6	Asbestos Cement	8	80	2 out of 5	\$442	3,356
Distribution Main	3073	P-9032	COV	St Vincent Depaul	6	Asbestos Cement	301	80	2 out of 5	\$442	132,980
Distribution Main	3074	P-9032	COV	St Vincent Depaul	6	Asbestos Cement	224	80	2 out of 5	\$442	99,181
Distribution Main	799	P-7262	COV	Station St.	8	Asbestos Cement	126	56	1.14 out of 5	\$442	55,698
Distribution Main	1475	P-8324	COV	Station St.	8	Asbestos Cement	1,044	56	1.14 out of 5	\$442	461,296
Distribution Main	1476	P-8324	COV	Station St.	8	Asbestos Cement	614	56	1.14 out of 5	\$442	271,268
Distribution Main	1477	P-8324	COV	Station St.	8	Asbestos Cement	705	56	1.14 out of 5	\$442	311,415
Distribution Main	2370	P-7262	COV	Station St.	8	Asbestos Cement	588	56	1.85 out of 5	\$442	259,849
Distribution Main	2371	P-7262	COV	Station St.	8	Asbestos Cement	20	56	1.14 out of 5	\$442	8,996
Distribution Main	2373	P-8325	COV	Station St.	8	Asbestos Cement	691	56	1.14 out of 5	\$442	305,334
Distribution Main	2374	P-8325	COV	Station St.	8	Asbestos Cement	2	56	1.14 out of 5	\$442	1,034
Distribution Main	2815	P-8914	COV	Station St.	8	Asbestos Cement	305	56	1.14 out of 5	\$442	134,656
Transmission Main	2818	P-7845	COV	Station St.	12	Asbestos Cement	9	78	1.29 out of 5	\$442	3,922
Distribution Main	3005	P-7269	COV	Station St.	8	Asbestos Cement	228	56	1.14 out of 5	\$442	100,668
Distribution Main	3006	P-7269	COV	Station St.	8	Asbestos Cement	186	56	1.14 out of 5	\$442	82,187
Distribution Main	5047	P-7343	COV	Station St.	8	Asbestos Cement	16	56	1.14 out of 5	\$442	7,046
Distribution Main	5927	P-7343	COV	Station St.	8	Asbestos Cement	409	56	1.14 out of 5	\$442	180,740
Distribution Main	5928	P-7343	COV	Station St.	8	Asbestos Cement	39	56	1.14 out of 5	\$442	17,205
Distribution Main	5929	P-7343	COV	Station St.	8	Asbestos Cement	909	56	1.14 out of 5	\$442	401,858
Distribution Main	5930	P-7343	COV	Station St.	8	Asbestos Cement	463	56	1.14 out of 5	\$442	204,426
Distribution Main	5931	P-8823	COV	Station St.	8	Asbestos Cement	838	56	1.14 out of 5	\$442	370,462
Distribution Main	7839	P-8824	COV	Station St.	8	Asbestos Cement	15	56	1.14 out of 5	\$442	6,752
Distribution Main	7840	P-8824	COV	Station St.	8	Asbestos Cement	311	56	1.14 out of 5	\$442	137,301
Transmission Main	10108	P-7845	COV	Station St.	12	Asbestos Cement	7	78	1.29 out of 5	\$442	3,166
Distribution Main	11972	P-8325	COV	Station St.	8	Asbestos Cement	339	56	1.14 out of 5	\$442	149,716
Distribution Main	7782	P-7420	COV	Steere Ln.	6	Asbestos Cement	115	53	1.85 out of 5	\$442	50,918
Distribution Main	7784	P-7421	COV	Steere Ln.	6	Asbestos Cement	333	53	1.85 out of 5	\$442	146,978
Distribution Main	7785	P-7420	COV	Steere Ln.	6	Asbestos Cement	12	53	1.85 out of 5	\$442	5,523
Distribution Main	1029	P-8879	COV	Stewart Lane	8	Asbestos Cement	3	UNK	0.85 out of 5	\$442	1,161
Distribution Main	2467	P-8879	COV	Stewart Lane	8	Ductile Iron	53	UNK	0 out of 5	N/A	\$0
Distribution Main	1871	P-7529	COV	Stone St.	6	Cast Iron	322	79	2.28 out of 5	\$442	142,254
Distribution Main	5050	P-7530	COV	Stone St.	2	Cast Iron	304	79	3 out of 5	\$442	134,445
Distribution Main	5052	P-8936	COV	Stone St.	6	Cast Iron	90	79	2.28 out of 5	\$442	39,624
Distribution Main	5053	P-8936	COV	Stone St.	6	Cast Iron	56	79	2.28 out of 5	\$442	24,962
Distribution Main	5057	P-8321	COV	Stone St.	6	Cast Iron	103	79	2.28 out of 5	\$442	45,389
Distribution Main	7883	P-7215	COV	Stoney Hill Cir.	8	Ductile Iron	373	29	0.14 out of 5	\$442	164,750
Distribution Main	7884	P-7215	COV	Stoney Hill Cir.	8	Ductile Iron	493	29	0.14 out of 5	\$442	218,018
Distribution Main	7890	P-7217	COV	Stoney Hill Cir.	8	Ductile Iron	132	29	0.14 out of 5	\$442	58,431

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7891	P-7217	COV	Stoney Hill Cir.	8	Ductile Iron	267	29	0.14 out of 5	\$442	118,143
Distribution Main	5229	P-7450	COV	Stratford Dr.	8	Ductile Iron	404	25	0.14 out of 5	N/A	\$0
Distribution Main	5230	P-7450	COV	Stratford Dr.	8	Ductile Iron	35	25	0.14 out of 5	N/A	\$0
Transmission Main	7593	P-7087	COV	Sugar Maple Dr.	12	Ductile Iron	270	28	0.14 out of 5	\$442	119,471
Transmission Main	7595	P-7084	COV	Sugar Maple Dr.	12	Ductile Iron	402	28	0.14 out of 5	\$442	177,591
Transmission Main	7772	P-7085	COV	Sugar Maple Dr.	12	Ductile Iron	275	28	0.14 out of 5	\$442	121,585
Transmission Main	7773	P-7087	COV	Sugar Maple Dr.	12	Ductile Iron	4	28	0.14 out of 5	\$442	1,976
Transmission Main	8297	P-7075	COV	Sugar Maple Dr.	12	Ductile Iron	78	28	0.14 out of 5	\$442	34,663
Transmission Main	8298	P-7085	COV	Sugar Maple Dr.	12	Ductile Iron	58	28	0.14 out of 5	\$442	25,766
Transmission Main	8299	P-7075	COV	Sugar Maple Dr.	12	Ductile Iron	68	28	0.14 out of 5	\$442	30,235
Transmission Main	8301	P-7075	COV	Sugar Maple Dr.	12	Ductile Iron	390	28	0.14 out of 5	\$442	172,347
Transmission Main	8326	P-7073	COV	Sugar Maple Dr.	12	Ductile Iron	366	28	0.14 out of 5	\$442	161,674
Transmission Main	8327	P-7083	COV	Sugar Maple Dr.	12	Ductile Iron	320	28	0.14 out of 5	\$442	141,351
Transmission Main	8328	P-7083	COV	Sugar Maple Dr.	12	Ductile Iron	107	28	0.14 out of 5	\$442	47,440
Transmission Main	11393	P-7087	COV	Sugar Maple Dr.	12	Ductile Iron	14	28	0.14 out of 5	\$442	6,203
Transmission Main	11394	P-7084	COV	Sugar Maple Dr.	12	Ductile Iron	4	28	0.14 out of 5	\$442	1,736
Distribution Main	583	P-7532	COV	Sunapee Ct.	6	Asbestos Cement	22	62	2 out of 5	\$442	9,715
Distribution Main	584	P-7532	COV	Sunapee Ct.	6	Asbestos Cement	135	62	2 out of 5	\$442	59,619
Distribution Main	5051	P-7533	COV	Sunapee Ct.	6	Asbestos Cement	604	62	2 out of 5	\$442	266,764
Distribution Main	9080	P-8979	COV	Sunset Ave	6	Asbestos Cement	41	UNK	1.56 out of 5	\$442	17,927
Distribution Main	9081	P-8979	COV	Sunset Ave	6	Asbestos Cement	152	UNK	1.56 out of 5	\$442	67,326
Distribution Main	1066	P-8987	COV	Sunset Street	2	Copper	254	79	2.43 out of 5	\$442	112,069
Distribution Main	2470	P-8987	COV	Sunset Street	2	Copper	12	79	2.43 out of 5	\$442	5,246
Distribution Main	2640	P-8987	COV	Sunset Street	2	Copper	8	79	2.43 out of 5	\$442	3,395
Distribution Main	8079	P-9023	COV	Sweet Fern Ln	8	Ductile Iron	32	11	0 out of 5	N/A	\$0
Distribution Main	8080	P-9023	COV	Sweet Fern Ln	8	Ductile Iron	836	11	0 out of 5	N/A	\$0
Distribution Main	11791	P-9023	COV	Sweet Fern Ln	8	Ductile Iron	424	11	0 out of 5	N/A	\$0
Distribution Main	7163	P-7296	COV	Sweetwater Dr.	8	Asbestos Cement	22	41	1.14 out of 5	\$442	9,627
Distribution Main	7165	P-7295	COV	Sweetwater Dr.	8	Asbestos Cement	459	41	1.14 out of 5	\$442	202,699
Distribution Main	7905	P-7296	COV	Sweetwater Dr.	8	Asbestos Cement	73	41	1.14 out of 5	\$442	32,257
Distribution Main	7906	P-7296	COV	Sweetwater Dr.	8	Asbestos Cement	936	41	1.14 out of 5	\$442	413,640
Distribution Main	11976	P-7296	COV	Sweetwater Dr.	8	Asbestos Cement	103	41	1.14 out of 5	\$442	45,558
Distribution Main	7570	P-7451	COV	Sycamore Dr.	8	Ductile Iron	328	25	0.14 out of 5	N/A	\$0
Distribution Main	7581	P-7453	COV	Sycamore Dr.	8	Ductile Iron	406	25	0.14 out of 5	N/A	\$0
Distribution Main	7582	P-7453	COV	Sycamore Dr.	8	Ductile Iron	31	25	0.14 out of 5	N/A	\$0
Distribution Main	7583	P-7449	COV	Sycamore Dr.	8	Ductile Iron	426	25	0.14 out of 5	N/A	\$0
Distribution Main	7584	P-7448	COV	Sycamore Dr.	8	Ductile Iron	413	25	0.14 out of 5	N/A	\$0
Distribution Main	7585	P-7448	COV	Sycamore Dr.	8	Ductile Iron	7	25	0.14 out of 5	N/A	\$0
Distribution Main	7652	P-8965	COV	Sycamore Dr.	8	Ductile Iron	36	25	0.14 out of 5	N/A	\$0
Distribution Main	1957	P-7831	COV	Taft St.	6	Cast Iron	548	132	2.57 out of 5	\$442	242,066
Distribution Main	1958	P-7831	COV	Taft St.	6	Cast Iron	136	132	2.57 out of 5	\$442	60,177
Distribution Main	3156	P-7834	COV	Taft St.	6	Asbestos Cement	506	54	1.85 out of 5	\$442	223,831
Distribution Main	3157	P-7834	COV	Taft St.	6	Asbestos Cement	46	54	1.85 out of 5	\$442	20,216
Distribution Main	9515	P-7836	COV	Taft St.	8	Asbestos Cement	485	54	1.14 out of 5	\$442	214,554

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9516	P-7836	COV	Taft St.	8	Asbestos Cement	40	54	1.14 out of 5	\$442	17,624
Distribution Main	853	P-7125	COV	Tallwood Dr.	8	Ductile Iron	62	18	0 out of 5	N/A	\$0
Distribution Main	854	P-7125	COV	Tallwood Dr.	8	Ductile Iron	342	18	0 out of 5	N/A	\$0
Distribution Main	7887	P-7127	COV	Tallwood Dr.	8	Ductile Iron	374	18	0 out of 5	N/A	\$0
Distribution Main	11092	P-7125	COV	Tallwood Dr.	8	Ductile Iron	15	18	0 out of 5	N/A	\$0
Distribution Main	7970	P-7119	COV	Tamarack Tr.	8	Ductile Iron	643	28	0.14 out of 5	\$442	284,166
Distribution Main	7971	P-7119	COV	Tamarack Tr.	8	Ductile Iron	59	28	0.14 out of 5	\$442	26,106
Distribution Main	7972	P-7119	COV	Tamarack Tr.	8	Ductile Iron	199	27	0.14 out of 5	\$442	88,030
Distribution Main	7164	P-7313	COV	Teakwood Dr. East	8	Asbestos Cement	460	40	1 out of 5	\$442	203,244
Distribution Main	7875	P-7298	COV	Teakwood Dr. East	8	Asbestos Cement	112	40	1 out of 5	\$442	49,504
Distribution Main	7876	P-7298	COV	Teakwood Dr. East	8	Asbestos Cement	11	40	1 out of 5	\$442	4,867
Distribution Main	7909	P-7297	COV	Teakwood Dr. East	8	Asbestos Cement	432	40	1 out of 5	\$442	190,943
Distribution Main	7881	P-7309	COV	Teakwood Dr. West	8	Asbestos Cement	150	40	1 out of 5	\$442	66,171
Distribution Main	7892	P-7308	COV	Teakwood Dr. West	8	Asbestos Cement	438	40	1 out of 5	\$442	193,410
Distribution Main	7893	P-7307	COV	Teakwood Dr. West	8	Asbestos Cement	280	40	1 out of 5	\$442	123,944
Distribution Main	7898	P-7309	COV	Teakwood Dr. West	8	Asbestos Cement	13	40	1 out of 5	\$442	5,540
Distribution Main	7899	P-7309	COV	Teakwood Dr. West	8	Asbestos Cement	25	40	1 out of 5	\$442	10,848
Distribution Main	10236	P-8812	COV	Teakwood Drive	8	Ductile Iron	203	5	0 out of 5	N/A	\$0
Distribution Main	10237	P-8812	COV	Teakwood Drive	8	Ductile Iron	63	5	0 out of 5	N/A	\$0
Distribution Main	10238	P-8811	COV	Teakwood Drive	8	Ductile Iron	137	5	0 out of 5	N/A	\$0
Distribution Main	10239	P-8811	COV	Teakwood Drive	8	Ductile Iron	541	5	0 out of 5	N/A	\$0
Distribution Main	10240	P-8811	COV	Teakwood Drive	8	Ductile Iron	33	5	0 out of 5	N/A	\$0
Distribution Main	10241	P-8810	COV	Teakwood Drive	8	Ductile Iron	198	5	0 out of 5	N/A	\$0
Distribution Main	10975	P-8809	COV	Teakwood Drive	8	Ductile Iron	349	5	0 out of 5	N/A	\$0
Distribution Main	11645	P-8811	COV	Teakwood Drive	8	Ductile Iron	36	5	0 out of 5	N/A	\$0
Distribution Main	10804	P-7267	COV	Tero Dr	8	Ductile Iron	344	0	0 out of 5	N/A	\$0
Distribution Main	10805	P-7267	COV	Tero Dr	8	Ductile Iron	218	0	0 out of 5	N/A	\$0
Distribution Main	3004	P-8134	COV	Tero Dr.	6	Asbestos Cement	7	44	1.85 out of 5	\$442	3,178
Distribution Main	3097	P-8134	COV	Terrace Ave.	4	Cast Iron	517	129	3.29 out of 5	\$442	228,700
Distribution Main	9058	P-8134	COV	The Crossroads	4	Ductile Iron	21	18	1.42 out of 5	N/A	\$0
Distribution Main	7156	P-7195	COV	Thompson Dr.	8	Asbestos Cement	554	45	1.14 out of 5	\$442	244,677
Distribution Main	2880	P-8163	COV	Tiffany Rd.	8	Asbestos Cement	235	43	1.14 out of 5	\$442	104,002
Distribution Main	2881	P-8163	COV	Tiffany Rd.	8	Asbestos Cement	52	43	1.14 out of 5	\$442	23,079
Transmission Main	4072	P-8167	COV	Tiffany Rd.	12	PVC	317	32	0.43 out of 5	\$442	140,253
Distribution Main	4771	P-8192	COV	Tiffany Rd.	8	PVC	709	32	0.43 out of 5	\$442	313,486
Distribution Main	4772	P-8192	COV	Tiffany Rd.	8	PVC	267	32	0.43 out of 5	\$442	117,909
Distribution Main	11911	P-8192	COV	Tiffany Rd.	8	PVC	686	32	0.43 out of 5	\$442	303,284
Transmission Main	8064	P-8712	COV	Tiffany Road	12	Ductile Iron	766	11	0 out of 5	N/A	\$0
Distribution Main	8073	P-9027	COV	Tiffany Road	8	Ductile Iron	12	11	0 out of 5	N/A	\$0
Distribution Main	8074	P-9027	COV	Tiffany Road	8	Ductile Iron	2	11	0 out of 5	N/A	\$0
Transmission Main	10140	P-9026	COV	Tiffany Road	12	Ductile Iron	13	11	0 out of 5	N/A	\$0
Distribution Main	9952	P-8401	COV	Timber Tr	8	Ductile Iron	294	9	0 out of 5	N/A	\$0
Distribution Main	9953	P-8403	COV	Timber Tr	8	Ductile Iron	12	9	0 out of 5	N/A	\$0
Distribution Main	9954	P-8403	COV	Timber Tr	8	Ductile Iron	147	9	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9955	P-8403	COV	Timber Tr	8	Ductile Iron	384	9	0 out of 5	N/A	\$0
Distribution Main	9956	P-8403	COV	Timber Tr	8	Ductile Iron	371	9	0 out of 5	N/A	\$0
Distribution Main	9957	P-8402	COV	Timber Tr	8	Ductile Iron	52	9	0 out of 5	N/A	\$0
Distribution Main	9958	P-8402	COV	Timber Tr	8	Ductile Iron	255	9	0 out of 5	N/A	\$0
Distribution Main	10844	P-8405	COV	Timber Tr	8	Ductile Iron	58	9	0 out of 5	N/A	\$0
Distribution Main	10845	P-8405	COV	Timber Tr	8	Ductile Iron	4	9	0 out of 5	N/A	\$0
Distribution Main	10183		COV	Timber Trail	8	Ductile Iron	459	6	0 out of 5	N/A	\$0
Distribution Main	10184		COV	Timber Trail	8	Ductile Iron	151	6	0 out of 5	N/A	\$0
Distribution Main	10185		COV	Timber Trail	8	Ductile Iron	416	6	0 out of 5	N/A	\$0
Distribution Main	10186		COV	Timber Trail	8	Ductile Iron	391	6	0 out of 5	N/A	\$0
Distribution Main	12125		COV	Timber Trail	8	Ductile Iron	114	6	0 out of 5	N/A	\$0
Transmission Main	10683		COV	Tiogue Av	12	Ductile Iron	11	UNK	0 out of 5	N/A	\$0
Transmission Main	8065		COV	Tiogue Ave	12	Ductile Iron	1,133	11	0 out of 5	N/A	\$0
Transmission Main	8066	P-8526	COV	Tiogue Ave	12	Ductile Iron	169	11	0 out of 5	N/A	\$0
Transmission Main	8067	P-8526	COV	Tiogue Ave	12	Ductile Iron	5	11	0 out of 5	N/A	\$0
Transmission Main	8068		COV	Tiogue Ave	12	Ductile Iron	79	11	0 out of 5	N/A	\$0
Transmission Main	8077	P-7745	COV	Tiogue Ave	12	Ductile Iron	20	11	0 out of 5	N/A	\$0
Transmission Main	8344		COV	Tiogue Ave	12	Ductile Iron	10	11	0 out of 5	N/A	\$0
Transmission Main	8345		COV	Tiogue Ave	12	Ductile Iron	5	11	0 out of 5	N/A	\$0
Transmission Main	8346		COV	Tiogue Ave	12	Ductile Iron	22	11	0 out of 5	N/A	\$0
Transmission Main	8347		COV	Tiogue Ave	12	Ductile Iron	4	11	0 out of 5	N/A	\$0
Transmission Main	8348	P-7745	COV	Tiogue Ave	12	Ductile Iron	9	11	0 out of 5	N/A	\$0
Transmission Main	8349	P-7745	COV	Tiogue Ave	12	Ductile Iron	106	11	0 out of 5	N/A	\$0
Transmission Main	8350		COV	Tiogue Ave	12	Ductile Iron	11	11	0 out of 5	N/A	\$0
Transmission Main	8351		COV	Tiogue Ave	12	Ductile Iron	34	11	0 out of 5	N/A	\$0
Distribution Main	9334		COV	Tiogue Ave	2	Copper	22	9	1.99 out of 5	N/A	\$0
Distribution Main	9640		COV	Tiogue Ave	6	Ductile Iron	22	11	0.71 out of 5	N/A	\$0
Distribution Main	9897		COV	Tiogue Ave	4	PVC	51	UNK	1.71 out of 5	\$442	22,704
Distribution Main	10286		COV	Tiogue Ave	8	Ductile Iron	3	25	0.14 out of 5	N/A	\$0
Distribution Main	10292		COV	Tiogue Ave	8	Ductile Iron	7	26	0.14 out of 5	\$442	3,044
Transmission Main	11164		COV	Tiogue Ave	12	Ductile Iron	28	11	0 out of 5	N/A	\$0
Transmission Main	11419		COV	Tiogue Ave	12	Ductile Iron	5	11	0 out of 5	N/A	\$0
Transmission Main	11420	P-8526	COV	Tiogue Ave	12	Ductile Iron	67	11	0 out of 5	N/A	\$0
Transmission Main	11422		COV	Tiogue Ave	12	Ductile Iron	9	11	0 out of 5	N/A	\$0
Transmission Main	11423		COV	Tiogue Ave	12	Ductile Iron	20	11	0 out of 5	N/A	\$0
Transmission Main	526	P-7564	COV	Tiogue Ave.	12	Ductile Iron	65	0	0 out of 5	N/A	\$0
Transmission Main	527	P-7564	COV	Tiogue Ave.	12	Ductile Iron	247	0	0 out of 5	N/A	\$0
Transmission Main	530	P-7717	COV	Tiogue Ave.	12	Ductile Iron	38	0	0 out of 5	N/A	\$0
Transmission Main	532	P-7715	COV	Tiogue Ave.	20	Ductile Iron	1,722	19	0 out of 5	N/A	\$0
Distribution Main	533	P-8298	COV	Tiogue Ave.	8	Cast Iron	312	24	1.14 out of 5	N/A	\$0
Distribution Main	534	P-8298	COV	Tiogue Ave.	8	Cast Iron	6	24	1.14 out of 5	N/A	\$0
Transmission Main	701	P-9006	COV	Tiogue Ave.	16	Ductile Iron	197	19	0 out of 5	N/A	\$0
Transmission Main	702	P-9006	COV	Tiogue Ave.	16	Ductile Iron	449	19	0 out of 5	N/A	\$0
Transmission Main	703	P-7609	COV	Tiogue Ave.	20	Ductile Iron	204	19	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	704	P-7508	COV	Tiogue Ave.	12	Asbestos Cement	7	57	1.14 out of 5	\$442	2,904
Transmission Main	705	P-7508	COV	Tiogue Ave.	12	Asbestos Cement	280	57	1.14 out of 5	\$442	123,748
Transmission Main	708	P-7609	COV	Tiogue Ave.	20	Ductile Iron	90	19	0 out of 5	N/A	\$0
Transmission Main	1290	P-7743	COV	Tiogue Ave.	12	Ductile Iron	402	0	0 out of 5	N/A	\$0
Transmission Main	1291	P-7743	COV	Tiogue Ave.	12	Ductile Iron	279	0	0 out of 5	N/A	\$0
Transmission Main	1292	P-8475	COV	Tiogue Ave.	12	Ductile Iron	947	0	0 out of 5	N/A	\$0
Distribution Main	1294		COV	Tiogue Ave.		Unknown	16	UNK	0 out of 5	N/A	\$0
Transmission Main	1295	P-8296	COV	Tiogue Ave.	16	Ductile Iron	404	19	0 out of 5	N/A	\$0
Transmission Main	1296	P-8296	COV	Tiogue Ave.	16	Ductile Iron	316	19	0 out of 5	N/A	\$0
Transmission Main	1297	P-7563	COV	Tiogue Ave.	12	Ductile Iron	400	0	0 out of 5	N/A	\$0
Transmission Main	1298	P-7563	COV	Tiogue Ave.	12	Ductile Iron	340	0	0 out of 5	N/A	\$0
Distribution Main	1299		COV	Tiogue Ave.	2	Unknown	9	UNK	1.42 out of 5	\$442	4,059
Distribution Main	1300		COV	Tiogue Ave.	2	Unknown	26	UNK	1.42 out of 5	\$442	11,590
Transmission Main	1301	P-8296	COV	Tiogue Ave.	16	Ductile Iron	420	19	0 out of 5	N/A	\$0
Transmission Main	1302	P-8296	COV	Tiogue Ave.	16	Ductile Iron	672	19	0 out of 5	N/A	\$0
Transmission Main	1303		COV	Tiogue Ave.	12	Ductile Iron	6	19	0 out of 5	N/A	\$0
Transmission Main	1304	P-9005	COV	Tiogue Ave.	12	Ductile Iron	218	0	0 out of 5	N/A	\$0
Transmission Main	1305	P-9005	COV	Tiogue Ave.	12	Ductile Iron	197	0	0 out of 5	N/A	\$0
Transmission Main	1308	P-7509	COV	Tiogue Ave.	12	Asbestos Cement	845	57	1.14 out of 5	\$442	373,582
Transmission Main	1309	P-7509	COV	Tiogue Ave.	12	Asbestos Cement	882	57	1.14 out of 5	\$442	389,815
Transmission Main	1310	P-8943	COV	Tiogue Ave.	12	Asbestos Cement	392	57	1.14 out of 5	\$442	173,127
Transmission Main	1311	P-7608	COV	Tiogue Ave.	20	Ductile Iron	404	19	0 out of 5	N/A	\$0
Transmission Main	1715	P-7751	COV	Tiogue Ave.	12	Ductile Iron	157	0	0 out of 5	N/A	\$0
Transmission Main	1716	P-7751	COV	Tiogue Ave.	12	Ductile Iron	750	0	0 out of 5	N/A	\$0
Transmission Main	2295	P-7563	COV	Tiogue Ave.	12	Ductile Iron	357	0	0 out of 5	N/A	\$0
Transmission Main	2296	P-7563	COV	Tiogue Ave.	12	Asbestos Cement	420	0	0.85 out of 5	N/A	\$0
Transmission Main	2298		COV	Tiogue Ave.	12	Unknown	10	UNK	0 out of 5	N/A	\$0
Transmission Main	2299	P-8296	COV	Tiogue Ave.	16	Ductile Iron	226	19	0 out of 5	N/A	\$0
Transmission Main	2300		COV	Tiogue Ave.	12	Unknown	13	UNK	0 out of 5	N/A	\$0
Transmission Main	2303	P-7717	COV	Tiogue Ave.	12	Ductile Iron	287	19	0 out of 5	N/A	\$0
Transmission Main	2304	P-7717	COV	Tiogue Ave.	12	Ductile Iron	409	19	0 out of 5	N/A	\$0
Transmission Main	3272	P-1172	COV	Tiogue Ave.	12	Asbestos Cement	10	54	1.14 out of 5	\$442	4,220
Transmission Main	3273	P-1172	COV	Tiogue Ave.	12	Asbestos Cement	357	54	1.14 out of 5	\$442	157,786
Transmission Main	3274	P-1172	COV	Tiogue Ave.	12	Asbestos Cement	106	54	1.14 out of 5	\$442	46,791
Transmission Main	3275	P-1172	COV	Tiogue Ave.	12	Asbestos Cement	92	54	1.14 out of 5	\$442	40,557
Transmission Main	3679	P-7754	COV	Tiogue Ave.	12	Asbestos Cement	199	54	1.14 out of 5	\$442	87,809
Transmission Main	3680	P-7754	COV	Tiogue Ave.	12	Asbestos Cement	22	54	1.14 out of 5	\$442	9,791
Transmission Main	3681	P-7755	COV	Tiogue Ave.	12	Asbestos Cement	264	54	1.14 out of 5	\$442	116,817
Transmission Main	3812	P-7768	COV	Tiogue Ave.	12	Asbestos Cement	25	54	1.14 out of 5	\$442	11,068
Transmission Main	3813	P-7768	COV	Tiogue Ave.	12	Asbestos Cement	296	54	1.14 out of 5	\$442	130,985
Transmission Main	3814	P-7770	COV	Tiogue Ave.	12	Asbestos Cement	253	54	1.14 out of 5	\$442	111,984
Transmission Main	3815	P-7770	COV	Tiogue Ave.	12	Asbestos Cement	421	54	1.14 out of 5	\$442	186,135
Transmission Main	3818	P-7767	COV	Tiogue Ave.	12	Asbestos Cement	49	54	1.14 out of 5	\$442	21,572
Transmission Main	4571	P-1174	COV	Tiogue Ave.	12	Asbestos Cement	48	54	1.14 out of 5	\$442	21,058

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	4572	P-1174	COV	Tiogue Ave.	12	Asbestos Cement	187	54	1.14 out of 5	\$442	82,761
Transmission Main	4690	P-1172	COV	Tiogue Ave.	12	Asbestos Cement	467	54	1.14 out of 5	\$442	206,527
Transmission Main	4723	P-1172	COV	Tiogue Ave.	12	Asbestos Cement	75	54	1.14 out of 5	\$442	32,974
Transmission Main	4724	P-1172	COV	Tiogue Ave.	12	Asbestos Cement	178	54	1.14 out of 5	\$442	78,672
Transmission Main	4779	P-1577	COV	Tiogue Ave.	12	Asbestos Cement	48	54	1.14 out of 5	\$442	21,309
Transmission Main	4780	P-1577	COV	Tiogue Ave.	12	Asbestos Cement	101	54	1.14 out of 5	\$442	44,531
Distribution Main	4838	P-7505	COV	Tiogue Ave.	10	Asbestos Cement	81	57	1.14 out of 5	\$442	35,882
Transmission Main	4841	P-7160	COV	Tiogue Ave.	12	Ductile Iron	339	30	0.14 out of 5	\$442	149,916
Distribution Main	4842	P-8721	COV	Tiogue Ave.	10	Asbestos Cement	501	57	1.14 out of 5	\$442	221,550
Distribution Main	4843	P-8721	COV	Tiogue Ave.	10	Asbestos Cement	244	57	1.14 out of 5	\$442	107,940
Transmission Main	4844	P-7159	COV	Tiogue Ave.	12	Ductile Iron	33	30	0.14 out of 5	\$442	14,468
Transmission Main	4845	P-7159	COV	Tiogue Ave.	12	Ductile Iron	633	30	0.14 out of 5	\$442	279,655
Distribution Main	4846	P-7502	COV	Tiogue Ave.	8	Asbestos Cement	136	57	1.14 out of 5	\$442	59,963
Transmission Main	4847	P-7506	COV	Tiogue Ave.	12	Asbestos Cement	45	19	0.85 out of 5	N/A	\$0
Distribution Main	4848	P-7505	COV	Tiogue Ave.	10	Asbestos Cement	15	57	1.14 out of 5	\$442	6,537
Distribution Main	5319	P-7503	COV	Tiogue Ave.	8	Asbestos Cement	70	57	1.14 out of 5	\$442	30,967
Transmission Main	5321	P-7507	COV	Tiogue Ave.	12	Asbestos Cement	265	57	1.14 out of 5	\$442	117,257
Transmission Main	5322	P-7507	COV	Tiogue Ave.	12	Asbestos Cement	526	57	1.14 out of 5	\$442	232,556
Distribution Main	5339	P-8513	COV	Tiogue Ave.	8	Asbestos Cement	583	71	1.29 out of 5	\$442	257,699
Distribution Main	5340	P-7496	COV	Tiogue Ave.	8	Asbestos Cement	843	71	1.29 out of 5	\$442	372,628
Distribution Main	6171	P-7496	COV	Tiogue Ave.	8	Asbestos Cement	181	71	1.29 out of 5	\$442	79,998
Distribution Main	6172	P-7496	COV	Tiogue Ave.	8	Asbestos Cement	51	71	1.29 out of 5	\$442	22,587
Transmission Main	7190	P-7159	COV	Tiogue Ave.	12	Ductile Iron	23	30	0.14 out of 5	\$442	10,194
Transmission Main	7191	P-7159	COV	Tiogue Ave.	12	Ductile Iron	752	30	0.14 out of 5	\$442	332,240
Transmission Main	7195	P-7159	COV	Tiogue Ave.	12	Ductile Iron	339	30	0.14 out of 5	\$442	150,017
Transmission Main	7196	P-7159	COV	Tiogue Ave.	12	Ductile Iron	6	30	0.14 out of 5	\$442	2,506
Transmission Main	7197	P-7159	COV	Tiogue Ave.	12	Ductile Iron	132	30	0.14 out of 5	\$442	58,285
Transmission Main	7198	P-7159	COV	Tiogue Ave.	12	Ductile Iron	8	30	0.14 out of 5	\$442	3,657
Transmission Main	7201	P-7159	COV	Tiogue Ave.	12	Ductile Iron	11	30	0.14 out of 5	\$442	5,070
Transmission Main	7202	P-7159	COV	Tiogue Ave.	12	Ductile Iron	463	30	0.14 out of 5	\$442	204,442
Transmission Main	7203	P-7159	COV	Tiogue Ave.	12	Ductile Iron	460	30	0.14 out of 5	\$442	203,358
Distribution Main	7205	P-7503	COV	Tiogue Ave.	8	Asbestos Cement	8	71	1.29 out of 5	\$442	3,622
Transmission Main	7515	P-7159	COV	Tiogue Ave.	12	Ductile Iron	18	30	0.14 out of 5	\$442	7,932
Transmission Main	7516	P-7159	COV	Tiogue Ave.	12	Ductile Iron	19	30	0.14 out of 5	\$442	8,334
Transmission Main	8069	P-8526	COV	Tiogue Ave.	12	Ductile Iron	31	19	0 out of 5	N/A	\$0
Transmission Main	8076	P-7755	COV	Tiogue Ave.	12	Asbestos Cement	37	54	1.14 out of 5	\$442	16,310
Distribution Main	9512		COV	Tiogue Ave.	8	Ductile Iron	12	19	0 out of 5	N/A	\$0
Transmission Main	9549	P-8487	COV	Tiogue Ave.	12	Ductile Iron	216	0	0 out of 5	N/A	\$0
Transmission Main	9553	P-8425	COV	Tiogue Ave.	12	Ductile Iron	448	19	0 out of 5	N/A	\$0
Transmission Main	9554	P-8425	COV	Tiogue Ave.	12	Ductile Iron	483	19	0 out of 5	N/A	\$0
Transmission Main	9555	P-7718	COV	Tiogue Ave.	12	Ductile Iron	104	19	0 out of 5	N/A	\$0
Transmission Main	9559	P-7564	COV	Tiogue Ave.	12	Ductile Iron	76	19	0 out of 5	N/A	\$0
Transmission Main	9560	P-7564	COV	Tiogue Ave.	12	Ductile Iron	26	19	0 out of 5	N/A	\$0
Distribution Main	9561		COV	Tiogue Ave.	6	Asbestos Cement	48	61	2 out of 5	\$442	21,279

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	9566	P-7563	COV	Tiogue Ave.	16	Ductile Iron	30	19	0 out of 5	N/A	\$0
Distribution Main	9567	P-8298	COV	Tiogue Ave.	8	Cast Iron	157	24	1.14 out of 5	N/A	\$0
Distribution Main	9568	P-8298	COV	Tiogue Ave.	8	Cast Iron	274	24	1.14 out of 5	N/A	\$0
Transmission Main	9569	P-7507	COV	Tiogue Ave.	12	Asbestos Cement	189	57	1.14 out of 5	\$442	83,432
Distribution Main	9570	P-7496	COV	Tiogue Ave.	8	Asbestos Cement	197	71	1.29 out of 5	\$442	87,070
Transmission Main	9578	P-8946	COV	Tiogue Ave.	12	Asbestos Cement	360	57	1.14 out of 5	\$442	159,114
Transmission Main	9579	P-7714	COV	Tiogue Ave.	16	Ductile Iron	424	19	0 out of 5	N/A	\$0
Transmission Main	9989	P-8296	COV	Tiogue Ave.	16	Ductile Iron	471	19	0 out of 5	N/A	\$0
Transmission Main	10806	P-7563	COV	Tiogue Ave.	12	Ductile Iron	200	19	0 out of 5	N/A	\$0
Transmission Main	10807	P-7563	COV	Tiogue Ave.	12	Ductile Iron	183	0	0 out of 5	N/A	\$0
Transmission Main	10808	P-7563	COV	Tiogue Ave.	12	Asbestos Cement	216	70	1.29 out of 5	\$442	95,504
Transmission Main	11074	P-7564	COV	Tiogue Ave.	12	Ductile Iron	16	0	0 out of 5	N/A	\$0
Transmission Main	11075	P-7564	COV	Tiogue Ave.	12	Ductile Iron	6	19	0 out of 5	N/A	\$0
Transmission Main	11076	P-7564	COV	Tiogue Ave.	12	Asbestos Cement	31	70	1.29 out of 5	\$442	13,682
Transmission Main	11077	P-7717	COV	Tiogue Ave.	12	Ductile Iron	27	0	0 out of 5	N/A	\$0
Transmission Main	11078	P-7717	COV	Tiogue Ave.	12	Ductile Iron	17	19	0 out of 5	N/A	\$0
Transmission Main	11114	P-8475	COV	Tiogue Ave.	12	Ductile Iron	24	0	0 out of 5	N/A	\$0
Transmission Main	11116	P-7563	COV	Tiogue Ave.	12	Ductile Iron	88	0	0 out of 5	N/A	\$0
Transmission Main	11117	P-7563	COV	Tiogue Ave.	12	Ductile Iron	42	0	0 out of 5	N/A	\$0
Transmission Main	11118	P-9005	COV	Tiogue Ave.	12	Ductile Iron	185	0	0 out of 5	N/A	\$0
Transmission Main	11119	P-9005	COV	Tiogue Ave.	12	Ductile Iron	155	0	0 out of 5	N/A	\$0
Transmission Main	11120	P-9005	COV	Tiogue Ave.	12	Ductile Iron	97	0	0 out of 5	N/A	\$0
Transmission Main	11123	P-7509	COV	Tiogue Ave.	12	Asbestos Cement	202	57	1.14 out of 5	\$442	89,363
Transmission Main	11163	P-7754	COV	Tiogue Ave.	12	Asbestos Cement	5	54	1.14 out of 5	\$442	2,215
Transmission Main	11165	P-7563	COV	Tiogue Ave.	12	Asbestos Cement	108	70	1.29 out of 5	\$442	47,764
Transmission Main	11166	P-8296	COV	Tiogue Ave.	16	Ductile Iron	108	19	0 out of 5	N/A	\$0
Transmission Main	11235	P-7770	COV	Tiogue Ave.	12	Asbestos Cement	42	54	1.14 out of 5	\$442	18,759
Distribution Main	11268	P-7505	COV	Tiogue Ave.	10	Asbestos Cement	30	57	1.14 out of 5	\$442	13,360
Transmission Main	11269	P-7160	COV	Tiogue Ave.	12	Ductile Iron	88	30	0.14 out of 5	\$442	38,903
Distribution Main	11270	P-8721	COV	Tiogue Ave.	10	Asbestos Cement	188	57	1.14 out of 5	\$442	83,241
Transmission Main	11296	P-7507	COV	Tiogue Ave.	12	Asbestos Cement	481	57	1.85 out of 5	\$442	212,466
Transmission Main	11339	P-7159	COV	Tiogue Ave.	12	Ductile Iron	78	30	0.14 out of 5	\$442	34,687
Transmission Main	11587	P-8475	COV	Tiogue Ave.	12	Asbestos Cement	69	61	1.29 out of 5	\$442	30,626
Transmission Main	11736	P-7563	COV	Tiogue Ave.	12	Ductile Iron	51	19	0 out of 5	N/A	\$0
Transmission Main	11737	P-7563	COV	Tiogue Ave.	12	Ductile Iron	3	19	0 out of 5	N/A	\$0
Distribution Main	11738	COV	COV	Tiogue Ave.	2	Unknown	2	UNK	1.42 out of 5	\$442	817
Transmission Main	11784	P-8425	COV	Tiogue Ave.	12	Ductile Iron	19	19	0 out of 5	N/A	\$0
Transmission Main	12068	P-7743	COV	Tiogue Ave.	12	Ductile Iron	96	0	0 out of 5	N/A	\$0
Transmission Main	12075	P-7717	COV	Tiogue Ave.	12	Ductile Iron	104	19	0 out of 5	N/A	\$0
Transmission Main	12079	P-7159	COV	Tiogue Ave.	12	Ductile Iron	34	30	0.14 out of 5	\$442	15,221
Transmission Main	12081	P-7507	COV	Tiogue Ave.	12	Asbestos Cement	229	57	1.14 out of 5	\$442	101,418
Transmission Main	8335	P-8485	COV	Tiogue Tank Connection	12	Asbestos Cement	15	UNK	0.85 out of 5	\$442	6,785
Transmission Main	8336	P-8485	COV	Tiogue Tank Connection	12	Asbestos Cement	16	UNK	0.85 out of 5	\$442	7,161
Transmission Main	8337	P-7730	COV	Tiogue Tank Connection	12	Asbestos Cement	97	UNK	0.85 out of 5	\$442	42,839

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	8338		COV	Tiogue Tank Connection	8	Ductile Iron	26	14	0 out of 5	N/A	\$0
Transmission Main	10455	P-8485	COV	Tiogue Tank Connection	12	Ductile Iron	15	14	0 out of 5	N/A	\$0
Distribution Main	10456		COV	Tiogue Tank Connection	6	Steel	3	UNK	1.28 out of 5	\$442	1,414
Distribution Main	10457		COV	Tiogue Tank Connection	6	Ductile Iron	6	14	0.71 out of 5	N/A	\$0
Transmission Main	11463	P-8485	COV	Tiogue Tank Connection	12	Ductile Iron	4	UNK	0 out of 5	N/A	\$0
Transmission Main	11464	P-8485	COV	Tiogue Tank Connection	12	Ductile Iron	5	14	0 out of 5	N/A	\$0
Distribution Main	9634	P-7572	COV	Tobin St	6	Ductile Iron	193	30	0.85 out of 5	\$442	85,463
Distribution Main	12107	P-7572	COV	Tobin St	6	Ductile Iron	1	30	0.85 out of 5	\$442	479
Distribution Main	4070	P-8165	COV	Trafford Park Dr.	8	Asbestos Cement	470	42	1.14 out of 5	\$442	207,613
Distribution Main	4071	P-8165	COV	Trafford Park Dr.	8	Asbestos Cement	572	42	1.14 out of 5	\$442	252,648
Distribution Main	551	P-7678	COV	Tulip Rd.	6	Asbestos Cement	35	56	1.85 out of 5	\$442	15,299
Distribution Main	552	P-7678	COV	Tulip Rd.	6	Asbestos Cement	410	56	1.85 out of 5	\$442	181,211
Distribution Main	3174	P-7837	COV	Turcotte St.	8	PVC	482	32	0.43 out of 5	\$442	213,230
Distribution Main	1754	P-7656	COV	Twin Lakes Ave.	8	Ductile Iron	171	18	0 out of 5	N/A	\$0
Distribution Main	2785	P-7652	COV	Twin Lakes Ave.	8	Ductile Iron	6	18	0 out of 5	N/A	\$0
Distribution Main	2787		COV	Twin Lakes Ave.	8	Ductile Iron	31	18	0 out of 5	N/A	\$0
Distribution Main	2798	P-7652	COV	Twin Lakes Ave.	8	Ductile Iron	88	18	0 out of 5	N/A	\$0
Distribution Main	2799	P-7652	COV	Twin Lakes Ave.	8	Ductile Iron	555	18	0 out of 5	N/A	\$0
Distribution Main	2802	P-7654	COV	Twin Lakes Ave.	8	Ductile Iron	175	18	0 out of 5	N/A	\$0
Distribution Main	187	P-7662	COV	Vale St.	2	Copper	399	83	2.57 out of 5	\$442	176,457
Distribution Main	709	P-7662	COV	Vale St.	6	Asbestos Cement	62	83	2.14 out of 5	\$442	27,442
Distribution Main	10158		COV	Valley Crest Rd	6	Ductile Iron	9	8	0.71 out of 5	N/A	\$0
Distribution Main	10462		COV	Valley Crest Rd	8	Ductile Iron	152	8	0 out of 5	N/A	\$0
Distribution Main	190	P-723	COV	Valley Crest Rd.	6	Asbestos Cement	730	60	1.85 out of 5	\$442	322,490
Distribution Main	191	P-7289	COV	Valley Crest Rd.	8	Asbestos Cement	124	59	1.14 out of 5	\$442	54,814
Distribution Main	192	P-7289	COV	Valley Crest Rd.	8	Asbestos Cement	103	60	1.14 out of 5	\$442	45,720
Distribution Main	193	P-7288	COV	Valley Crest Rd.	8	Asbestos Cement	9	59	1.14 out of 5	\$442	3,945
Distribution Main	3072	P-7288	COV	Valley Crest Rd.	8	Asbestos Cement	204	59	1.14 out of 5	\$442	90,322
Distribution Main	4956	P-8138	COV	Valrene St.	6	Asbestos Cement	437	52	1.85 out of 5	\$442	193,096
Distribution Main	4957	P-8138	COV	Valrene St.	6	Asbestos Cement	23	52	1.85 out of 5	\$442	10,353
Distribution Main	11277	P-8138	COV	Valrene St.	6	Asbestos Cement	67	52	1.85 out of 5	\$442	29,632
Distribution Main	3168	P-7804	COV	Vanderbilt Ter.	6	Asbestos Cement	481	43	1.85 out of 5	\$442	212,418
Distribution Main	3228	P-7799	COV	Vanderbilt Ter.	6	Asbestos Cement	470	43	1.85 out of 5	\$442	207,750
Distribution Main	2555	P-7673	COV	Vera Rd.	6	Asbestos Cement	23	56	1.85 out of 5	\$442	10,236
Distribution Main	2556	P-7673	COV	Vera Rd.	6	Asbestos Cement	552	56	1.85 out of 5	\$442	243,983
Distribution Main	2615	P-8975	COV	Vera Rd.	6	Asbestos Cement	294	56	1.85 out of 5	\$442	129,843
Distribution Main	2616	P-8975	COV	Vera Rd.	6	Asbestos Cement	44	56	1.85 out of 5	\$442	19,305
Distribution Main	7454	P-7102	COV	Veronica Ct.	6	Asbestos Cement	11	44	1.85 out of 5	\$442	5,024
Distribution Main	7464	P-7102	COV	Veronica Ct.	6	Asbestos Cement	351	44	1.85 out of 5	\$442	155,110
Distribution Main	1455	P-7705	COV	View Rd.	2	Copper	312	60	2.28 out of 5	\$442	137,788
Distribution Main	1456	P-7705	COV	View Rd.	2	Copper	47	60	2.28 out of 5	\$442	20,840
Distribution Main	449	P-7370	COV	Viola St.	6	Asbestos Cement	395	51	1.85 out of 5	\$442	174,621
Distribution Main	1462	P-7372	COV	Viola St.	6	Asbestos Cement	250	51	1.85 out of 5	\$442	110,373
Distribution Main	1471	P-7371	COV	Viola St.	6	Asbestos Cement	312	51	1.85 out of 5	\$442	137,805

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	1472	P-7373	COV	Viola St.	6	Asbestos Cement	284	51	1.85 out of 5	\$442	125,353
Distribution Main	8800		COV	Walker Lane	6	Asbestos Cement	206	UNK	1.56 out of 5	\$442	91,082
Distribution Main	8801		COV	Walker Lane	6	Asbestos Cement	412	UNK	1.56 out of 5	\$442	181,994
Distribution Main	10430		COV	Walker Lane	6	Ductile Iron	35	8	0.71 out of 5	N/A	\$0
Transmission Main	9972		COV	Walker Ln	12	Ductile Iron	39	25	0.14 out of 5	N/A	\$0
Distribution Main	9973		COV	Walker Ln	6	Ductile Iron	4	25	0.85 out of 5	N/A	\$0
Transmission Main	7174	P-7186	COV	Walker Ln.	12	Ductile Iron	271	25	0.14 out of 5	N/A	\$0
Transmission Main	7520	P-7187	COV	Walker Ln.	12	Ductile Iron	415	25	0.14 out of 5	N/A	\$0
Transmission Main	7523	P-7186	COV	Walker Ln.	12	Ductile Iron	262	25	0.14 out of 5	N/A	\$0
Transmission Main	7524	P-7186	COV	Walker Ln.	12	Ductile Iron	344	25	0.14 out of 5	N/A	\$0
Transmission Main	7872	P-7186	COV	Walker Ln.	12	Ductile Iron	593	25	0.14 out of 5	N/A	\$0
Transmission Main	7900	P-7186	COV	Walker Ln.	12	Ductile Iron	220	25	0.14 out of 5	N/A	\$0
Transmission Main	7901	P-7186	COV	Walker Ln.	12	Ductile Iron	494	25	0.14 out of 5	N/A	\$0
Transmission Main	8787	P-8896	COV	Walker Ln.	12	Ductile Iron	4	25	0.14 out of 5	N/A	\$0
Transmission Main	9970	P-7186	COV	Walker Ln.	12	Ductile Iron	1,035	25	0.14 out of 5	N/A	\$0
Transmission Main	9971	P-7186	COV	Walker Ln.	12	Ductile Iron	15	25	0.14 out of 5	N/A	\$0
Transmission Main	11413	P-7186	COV	Walker Ln.	12	Ductile Iron	18	25	0.14 out of 5	N/A	\$0
Transmission Main	11889	P-7186	COV	Walker Ln.	12	Ductile Iron	328	25	0.14 out of 5	N/A	\$0
Distribution Main	998	P-7320	COV	Walnut Hill Rd.	8	Asbestos Cement	547	54	1.14 out of 5	\$442	241,831
Distribution Main	999	P-7320	COV	Walnut Hill Rd.	8	Asbestos Cement	29	54	1.14 out of 5	\$442	12,739
Transmission Main	114	P-7848	COV	Washington St	16	Cast Iron	16	129	1.86 out of 5	\$442	7,062
Distribution Main	9348		COV	Washington St	8	Ductile Iron	32	9	0 out of 5	N/A	\$0
Transmission Main	9947		COV	Washington St	12	Ductile Iron	11	6	0 out of 5	N/A	\$0
Transmission Main	308	P-8762	COV	Washington St.	12	Cast Iron	275	132	1.86 out of 5	\$442	121,624
Transmission Main	309	P-8762	COV	Washington St.	12	Cast Iron	34	132	1.86 out of 5	\$442	14,928
Transmission Main	310	P-8011	COV	Washington St.	12	Cast Iron	90	132	1.86 out of 5	\$442	39,785
Transmission Main	311	P-8011	COV	Washington St.	12	Cast Iron	321	132	1.86 out of 5	\$442	141,933
Transmission Main	401	P-8010	COV	Washington St.	12	Cast Iron	85	132	1.86 out of 5	\$442	37,510
Transmission Main	412	P-8009	COV	Washington St.	12	Cast Iron	400	132	1.86 out of 5	\$442	176,993
Transmission Main	413	P-8009	COV	Washington St.	12	Cast Iron	227	132	1.86 out of 5	\$442	100,507
Transmission Main	830	P-7864	COV	Washington St.	12	Asbestos Cement	308	75	1.29 out of 5	\$442	136,058
Transmission Main	831	P-7864	COV	Washington St.	12	Asbestos Cement	271	75	1.29 out of 5	\$442	119,784
Transmission Main	1038	P-8010	COV	Washington St.	12	Cast Iron	13	132	1.86 out of 5	\$442	5,827
Transmission Main	1262	P-8246	COV	Washington St.	16	Cast Iron	381	133	1.86 out of 5	\$442	168,588
Transmission Main	1263	P-8246	COV	Washington St.	16	Cast Iron	407	133	1.86 out of 5	\$442	179,978
Transmission Main	1288	P-7964	COV	Washington St.	12	Cast Iron	59	132	1.86 out of 5	\$442	26,277
Transmission Main	1405	P-8010	COV	Washington St.	12	Cast Iron	14	132	1.86 out of 5	\$442	6,112
Transmission Main	1406	P-8009	COV	Washington St.	12	Cast Iron	3	132	1.86 out of 5	\$442	1,295
Transmission Main	1497	P-7865	COV	Washington St.	12	Cast Iron	29	132	1.86 out of 5	\$442	12,878
Transmission Main	1498	P-7865	COV	Washington St.	12	Cast Iron	197	132	1.86 out of 5	\$442	87,271
Transmission Main	1499	P-8288	COV	Washington St.	12	Cast Iron	33	132	1.86 out of 5	\$442	14,713
Transmission Main	1950	P-7962	COV	Washington St.	12	Cast Iron	97	132	1.86 out of 5	\$442	43,093
Transmission Main	2194	P-8244	COV	Washington St.	16	Cast Iron	13	133	1.86 out of 5	\$442	5,750
Transmission Main	2195	P-8244	COV	Washington St.	16	Cast Iron	11	133	1.86 out of 5	\$442	4,968

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	2380	P-7964	COV	Washington St.	12	Asbestos Cement	114	75	1.29 out of 5	\$442	50,295
Transmission Main	2381	P-7865	COV	Washington St.	12	Cast Iron	24	132	1.86 out of 5	\$442	10,805
Transmission Main	2700	P-8020	COV	Washington St.	12	Cast Iron	69	132	1.86 out of 5	\$442	30,407
Transmission Main	2701	P-8020	COV	Washington St.	12	Cast Iron	168	132	1.86 out of 5	\$442	74,359
Transmission Main	2706	P-8022	COV	Washington St.	12	Cast Iron	363	132	1.86 out of 5	\$442	160,548
Transmission Main	2707	P-8022	COV	Washington St.	12	Cast Iron	82	132	1.86 out of 5	\$442	36,379
Transmission Main	2807	P-7848	COV	Washington St.	16	Cast Iron	704	129	1.86 out of 5	\$442	311,099
Transmission Main	3007	P-8243	COV	Washington St.	16	Cast Iron	14	129	1.86 out of 5	\$442	5,993
Transmission Main	3021	P-8246	COV	Washington St.	16	Cast Iron	33	133	1.86 out of 5	\$442	14,631
Transmission Main	3022	P-7962	COV	Washington St.	12	Asbestos Cement	591	75	1.29 out of 5	\$442	261,224
Transmission Main	3023	P-7964	COV	Washington St.	12	Cast Iron	295	132	1.86 out of 5	\$442	130,280
Transmission Main	3024	P-7964	COV	Washington St.	12	Cast Iron	212	132	1.86 out of 5	\$442	93,676
Transmission Main	3025	P-8290	COV	Washington St.	16	Cast Iron	8	132	1.86 out of 5	\$442	3,490
Transmission Main	3026	P-8288	COV	Washington St.	12	Cast Iron	238	132	1.86 out of 5	\$442	105,000
Transmission Main	3027	P-8288	COV	Washington St.	12	Cast Iron	451	132	1.86 out of 5	\$442	199,458
Transmission Main	3028	P-8291	COV	Washington St.	16	Cast Iron	245	132	1.86 out of 5	\$442	108,361
Transmission Main	3030	P-8287	COV	Washington St.	12	Cast Iron	213	132	1.86 out of 5	\$442	94,146
Transmission Main	3031	P-7965	COV	Washington St.	12	Cast Iron	20	132	1.86 out of 5	\$442	8,897
Transmission Main	3032	P-7965	COV	Washington St.	12	Cast Iron	131	132	1.86 out of 5	\$442	57,733
Transmission Main	3033	P-7963	COV	Washington St.	12	Asbestos Cement	9	75	1.29 out of 5	\$442	3,947
Transmission Main	3154	P-7863	COV	Washington St.	12	Cast Iron	54	91	1.72 out of 5	\$442	23,681
Transmission Main	3155	P-7863	COV	Washington St.	12	Cast Iron	405	91	1.72 out of 5	\$442	178,806
Transmission Main	3474	P-8290	COV	Washington St.	16	Cast Iron	49	132	1.86 out of 5	\$442	21,785
Transmission Main	3475	P-9029	COV	Washington St.	12	Cast Iron	16	132	1.86 out of 5	\$442	6,966
Transmission Main	3476	P-9029	COV	Washington St.	12	Cast Iron	48	132	1.86 out of 5	\$442	21,119
Transmission Main	6178	P-8777	COV	Washington St.	12	Ductile Iron	670	15	0 out of 5	N/A	\$0
Transmission Main	6179	P-8777	COV	Washington St.	12	Ductile Iron	433	15	0 out of 5	N/A	\$0
Transmission Main	9625	P-8291	COV	Washington St.	16	Cast Iron	242	132	1.86 out of 5	\$442	106,875
Transmission Main	9627	P-7860	COV	Washington St.	12	Ductile Iron	179	15	0 out of 5	N/A	\$0
Transmission Main	10859	P-8291	COV	Washington St.	16	Cast Iron	47	132	1.86 out of 5	\$442	20,712
Transmission Main	10872	P-9045	COV	Washington St.	12	Cast Iron	273	132	1.86 out of 5	\$442	120,564
Transmission Main	10873	P-9045	COV	Washington St.	12	Cast Iron	325	132	1.86 out of 5	\$442	143,825
Transmission Main	11185	P-8020	COV	Washington St.	12	Cast Iron	10	132	1.86 out of 5	\$442	4,272
Transmission Main	11199	P-8288	COV	Washington St.	12	Cast Iron	139	132	1.86 out of 5	\$442	61,306
Transmission Main	11756	P-7964	COV	Washington St.	12	Cast Iron	58	132	1.86 out of 5	\$442	25,631
Transmission Main	11757	P-8288	COV	Washington St.	12	Cast Iron	373	132	1.86 out of 5	\$442	165,057
Transmission Main	11758	P-8288	COV	Washington St.	12	Cast Iron	99	132	1.86 out of 5	\$442	43,781
Transmission Main	11774	P-8009	COV	Washington St.	12	Cast Iron	64	132	1.86 out of 5	\$442	28,334
Transmission Main	11775	P-8246	COV	Washington St.	16	Cast Iron	101	133	1.86 out of 5	\$442	44,545
Transmission Main	11776	P-8246	COV	Washington St.	16	Cast Iron	276	133	1.86 out of 5	\$442	121,958
Transmission Main	12066	P-8246	COV	Washington St.	16	Cast Iron	51	133	1.86 out of 5	\$442	22,705
Distribution Main	6169	P-7301	COV	Watercress Ct.	8	Asbestos Cement	455	40	1 out of 5	\$442	201,116
Distribution Main	7691	P-7312	COV	Watercress Ct.	8	Asbestos Cement	275	40	1 out of 5	\$442	121,373
Distribution Main	7692	P-7312	COV	Watercress Ct.	8	Asbestos Cement	632	40	1 out of 5	\$442	279,355

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7693	P-7300	COV	Watercress Ct.	8	Asbestos Cement	493	40	1 out of 5	\$442	218,079
Distribution Main	7694	P-7300	COV	Watercress Ct.	8	Asbestos Cement	138	40	1 out of 5	\$442	61,216
Distribution Main	7695	P-7311	COV	Watercress Ct.	8	Asbestos Cement	159	40	1 out of 5	\$442	70,090
Distribution Main	10139		COV	Waterman Rd	2	Copper	129	58	2.28 out of 5	\$442	56,838
Distribution Main	2193	P-7568	COV	Wendell St.	6	Asbestos Cement	244	65	2 out of 5	\$442	107,686
Distribution Main	1598	P-8152	COV	Wendy Dr.	8	Asbestos Cement	19	46	1.14 out of 5	\$442	8,314
Distribution Main	2534		COV	Wendy Dr.	8	Asbestos Cement	95	46	1.14 out of 5	\$442	41,923
Distribution Main	2535	P-8158	COV	Wendy Dr.	8	Asbestos Cement	18	46	1.14 out of 5	\$442	7,902
Distribution Main	2537	P-8157	COV	Wendy Dr.	8	Asbestos Cement	8	46	1.14 out of 5	\$442	3,739
Distribution Main	2538	P-8157	COV	Wendy Dr.	8	Asbestos Cement	156	46	1.14 out of 5	\$442	68,822
Distribution Main	2873	P-8152	COV	Wendy Dr.	8	Asbestos Cement	186	46	1.14 out of 5	\$442	82,251
Distribution Main	4563	P-8158	COV	Wendy Dr.	8	Asbestos Cement	400	46	1.14 out of 5	\$442	176,886
Distribution Main	1491	P-7817	COV	Wesleyan Ave.	6	Asbestos Cement	18	52	1.85 out of 5	\$442	7,997
Distribution Main	1492	P-7817	COV	Wesleyan Ave.	6	Asbestos Cement	596	52	1.85 out of 5	\$442	263,465
Distribution Main	2843	P-7815	COV	Wesleyan Ave.	6	Asbestos Cement	263	52	1.85 out of 5	\$442	116,257
Distribution Main	3170	P-7806	COV	Wesleyan Ave.	8	Asbestos Cement	606	52	1.14 out of 5	\$442	267,885
Distribution Main	3171	P-7806	COV	Wesleyan Ave.	8	Asbestos Cement	720	52	1.14 out of 5	\$442	318,188
Distribution Main	3232	P-7798	COV	Wesleyan Ave.	8	Asbestos Cement	29	52	1.14 out of 5	\$442	12,777
Distribution Main	3233	P-7798	COV	Wesleyan Ave.	8	Asbestos Cement	225	52	1.14 out of 5	\$442	99,259
Distribution Main	11131	P-7817	COV	Wesleyan Ave.	6	Asbestos Cement	2	52	1.85 out of 5	\$442	979
Distribution Main	747	P-7628	COV	West Lake Dr.	6	Asbestos Cement	435	58	1.85 out of 5	\$442	192,281
Distribution Main	9939	P-8996	COV	West Shore Dr	8	Ductile Iron	34	11	0 out of 5	N/A	\$0
Distribution Main	10977	P-8997	COV	West Shore Dr	8	Ductile Iron	22	11	0 out of 5	N/A	\$0
Distribution Main	11627		COV	West Shore Dr	6	Ductile Iron	17	18	0.71 out of 5	N/A	\$0
Distribution Main	1090	P-7689	COV	West Shore Dr.	6	Asbestos Cement	90	53	1.85 out of 5	\$442	39,964
Distribution Main	1091	P-7689	COV	West Shore Dr.	6	Asbestos Cement	414	53	1.85 out of 5	\$442	182,974
Distribution Main	711	P-8309	COV	West Shore Drive	6	Asbestos Cement	208	65	2 out of 5	\$442	91,751
Distribution Main	712	P-8993	COV	West Shore Drive	6	Ductile Iron	31	18	0.71 out of 5	N/A	\$0
Distribution Main	713	P-8994	COV	West Shore Drive	1	Copper	202	65	2.43 out of 5	\$442	89,447
Distribution Main	1458	P-7661	COV	West Shore Drive	1	Copper	231	83	2.57 out of 5	\$442	102,167
Distribution Main	9509		COV	West Shore Drive	6	Asbestos Cement	30	65	2 out of 5	\$442	13,210
Distribution Main	12063	P-8309	COV	West Shore Drive	6	Ductile Iron	5	18	0.71 out of 5	N/A	\$0
Distribution Main	5250	P-7067	COV	West View Dr.	8	Asbestos Cement	56	46	1.14 out of 5	\$442	24,932
Distribution Main	5251	P-7067	COV	West View Dr.	8	Asbestos Cement	468	46	1.14 out of 5	\$442	206,940
Distribution Main	5252	P-7066	COV	West View Dr.	8	Asbestos Cement	30	32	1 out of 5	\$442	13,294
Distribution Main	7214	P-7057	COV	West View Dr.	8	Asbestos Cement	190	46	1.14 out of 5	\$442	83,777
Distribution Main	7215	P-7057	COV	West View Dr.	8	Asbestos Cement	134	46	1.14 out of 5	\$442	59,346
Distribution Main	7216	P-7058	COV	West View Dr.	8	Asbestos Cement	267	46	1.14 out of 5	\$442	118,076
Distribution Main	7745	P-7056	COV	West View Dr.	8	Asbestos Cement	12	46	1.14 out of 5	\$442	5,380
Distribution Main	7810	P-7066	COV	West View Dr.	8	Asbestos Cement	232	46	1.14 out of 5	\$442	102,381
Distribution Main	7811	P-7066	COV	West View Dr.	8	Asbestos Cement	373	32	1 out of 5	\$442	165,082
Distribution Main	7812	P-7066	COV	West View Dr.	8	Asbestos Cement	216	32	1 out of 5	\$442	95,670
Distribution Main	7825	P-7056	COV	West View Dr.	8	Asbestos Cement	304	46	1.14 out of 5	\$442	134,457
Distribution Main	11364	P-7057	COV	West View Dr.	8	Asbestos Cement	4	46	1.14 out of 5	\$442	1,618

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11410	P-7066	COV	West View Dr.	8	Asbestos Cement	7	46	1.14 out of 5	\$442	3,201
Distribution Main	2364		COV	Whipple Court	6	Ductile Iron	8	30	0.85 out of 5	\$442	3,610
Distribution Main	2365		COV	Whipple Court	6	Ductile Iron	473	30	0.85 out of 5	\$442	209,075
Distribution Main	6319	P-7133	COV	White Oak Ct.	8	Ductile Iron	200	20	0 out of 5	N/A	\$0
Distribution Main	6320	P-7132	COV	White Oak Ct.	8	Ductile Iron	813	20	0 out of 5	N/A	\$0
Distribution Main	6321	P-7132	COV	White Oak Ct.	8	Ductile Iron	69	20	0 out of 5	N/A	\$0
Distribution Main	1915	P-7906	COV	White Pine Rd.	8	Asbestos Cement	417	39	1 out of 5	\$442	184,479
Distribution Main	1916	P-7904	COV	White Pine Rd.	8	Asbestos Cement	77	39	1 out of 5	\$442	34,149
Distribution Main	1917	P-7904	COV	White Pine Rd.	8	Asbestos Cement	675	39	1 out of 5	\$442	298,528
Distribution Main	595	P-7881	COV	White Rock Dr.	8	Asbestos Cement	663	54	1.14 out of 5	\$442	292,888
Distribution Main	596	P-7881	COV	White Rock Dr.	8	Asbestos Cement	19	54	1.14 out of 5	\$442	8,531
Distribution Main	2115	P-7322	COV	White Rock Dr.	8	Asbestos Cement	776	54	1.14 out of 5	\$442	342,861
Distribution Main	9964	P-7321	COV	White Rock Dr.	8	Asbestos Cement	4	54	1.14 out of 5	\$442	1,794
Distribution Main	12171		COV	White Rock Dr.	8	Asbestos Cement	175	54	1.14 out of 5	\$442	77,158
Distribution Main	12172		COV	White Rock Dr.	8	Asbestos Cement	16	54	1.14 out of 5	\$442	7,130
Distribution Main	1584	P-8764	COV	Whitford St.	8	Ductile Iron	827	14	0 out of 5	N/A	\$0
Distribution Main	1059	P-7565	COV	Whitman St.	6	Asbestos Cement	14	50	1.85 out of 5	\$442	6,276
Distribution Main	1060	P-7565	COV	Whitman St.	6	Asbestos Cement	395	50	1.85 out of 5	\$442	174,712
Distribution Main	2262	P-8161	COV	Whittier Dr.	8	Asbestos Cement	198	46	1.14 out of 5	\$442	87,497
Distribution Main	4562	P-8160	COV	Whittier Dr.	8	Asbestos Cement	11	46	1.14 out of 5	\$442	4,836
Distribution Main	4963	P-8160	COV	Whittier Dr.	8	Asbestos Cement	427	46	1.14 out of 5	\$442	188,590
Distribution Main	3058	P-7356	COV	Wildflower Dr.	8	Ductile Iron	10	24	0.14 out of 5	N/A	\$0
Distribution Main	3060	P-7356	COV	Wildflower Dr.	8	Ductile Iron	706	24	0.14 out of 5	N/A	\$0
Distribution Main	3061	P-7356	COV	Wildflower Dr.	8	Ductile Iron	42	24	0.14 out of 5	N/A	\$0
Distribution Main	2647	P-7549	COV	Wildwood St.	6	Asbestos Cement	302	69	2 out of 5	\$442	133,587
Distribution Main	1063	P-7559	COV	Williams St.	6	Asbestos Cement	298	69	2 out of 5	\$442	131,607
Distribution Main	2475	P-7559	COV	Williams St.	2	Galvanized Iron	102	87	3.43 out of 5	\$442	45,203
Distribution Main	2636	P-7559	COV	Williams St.	2	Galvanized Iron	18	87	3.43 out of 5	\$442	7,850
Distribution Main	2646	P-7560	COV	Williams St.	6	Asbestos Cement	575	69	2 out of 5	\$442	254,248
Distribution Main	9766	P-1384	COV	Wilshire Way	8	Ductile Iron	441	8	0 out of 5	N/A	\$0
Distribution Main	9785	P-628	COV	Wilshire Way	8	Ductile Iron	282	8	0 out of 5	N/A	\$0
Distribution Main	9786	P-628	COV	Wilshire Way	8	Ductile Iron	135	8	0 out of 5	N/A	\$0
Distribution Main	11603	P-628	COV	Wilshire Way	8	Ductile Iron	35	8	0 out of 5	N/A	\$0
Distribution Main	9736	P-8203	COV	Windsor Park Dr	8	Ductile Iron	540	8	0 out of 5	N/A	\$0
Distribution Main	9737	P-8204	COV	Windsor Park Dr	8	Ductile Iron	354	8	0 out of 5	N/A	\$0
Distribution Main	9739	P-8206	COV	Windsor Park Dr	8	Ductile Iron	121	8	0 out of 5	N/A	\$0
Distribution Main	9740	P-8206	COV	Windsor Park Dr	8	Ductile Iron	104	8	0 out of 5	N/A	\$0
Distribution Main	9742	P-1961	COV	Windsor Park Dr	8	Ductile Iron	234	8	0 out of 5	N/A	\$0
Distribution Main	9743	P-1961	COV	Windsor Park Dr	8	Ductile Iron	2	8	0 out of 5	N/A	\$0
Distribution Main	9747	P-9070	COV	Windsor Park Dr	8	Ductile Iron	70	8	0 out of 5	N/A	\$0
Distribution Main	9750	P-8213	COV	Windsor Park Dr	8	Ductile Iron	370	8	0 out of 5	N/A	\$0
Distribution Main	9755	P-8213	COV	Windsor Park Dr	8	Ductile Iron	97	8	0 out of 5	N/A	\$0
Distribution Main	9756	P-8213	COV	Windsor Park Dr	8	Ductile Iron	119	8	0 out of 5	N/A	\$0
Distribution Main	10863	P-8209	COV	Windsor Park Dr	8	Ductile Iron	150	8	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10864	P-8207	COV	Windsor Park Dr	8	Ductile Iron	194	8	0 out of 5	N/A	\$0
Distribution Main	10867	P-8210	COV	Windsor Park Dr	8	Ductile Iron	86	8	0 out of 5	N/A	\$0
Distribution Main	10868	P-8210	COV	Windsor Park Dr	8	Ductile Iron	256	8	0 out of 5	N/A	\$0
Distribution Main	11595	P-8209	COV	Windsor Park Dr	8	Ductile Iron	24	8	0 out of 5	N/A	\$0
Distribution Main	11596	P-1960	COV	Windsor Park Dr	8	Ductile Iron	54	8	0 out of 5	N/A	\$0
Distribution Main	11597	P-603	COV	Windsor Park Dr	8	Ductile Iron	28	8	0 out of 5	N/A	\$0
Distribution Main	11598	P-8207	COV	Windsor Park Dr	8	Ductile Iron	62	8	0 out of 5	N/A	\$0
Distribution Main	7213	P-7068	COV	Winterberry Dr.	6	Asbestos Cement	19	46	1.85 out of 5	\$442	8,271
Distribution Main	7809	P-7068	COV	Winterberry Dr.	6	Asbestos Cement	583	46	1.85 out of 5	\$442	257,523
Distribution Main	7814	P-7070	COV	Winterberry Dr.	6	Asbestos Cement	48	46	1.85 out of 5	\$442	21,355
Distribution Main	7826	P-7070	COV	Winterberry Dr.	6	Asbestos Cement	416	46	1.85 out of 5	\$442	183,725
Distribution Main	1016	P-7896	COV	Wintergreen Ct.	6	Asbestos Cement	243	38	1.71 out of 5	\$442	107,387
Distribution Main	4457	P-7055	COV	Wisteria Dr.	8	Asbestos Cement	16	57	1.14 out of 5	\$442	7,169
Distribution Main	7217	P-7054	COV	Wisteria Dr.	8	Asbestos Cement	28	57	1.14 out of 5	\$442	12,591
Distribution Main	7218	P-7054	COV	Wisteria Dr.	8	Asbestos Cement	426	57	1.14 out of 5	\$442	188,245
Distribution Main	7219	P-7039	COV	Wisteria Dr.	8	Asbestos Cement	491	57	1.14 out of 5	\$442	217,064
Distribution Main	7220	P-7040	COV	Wisteria Dr.	8	Asbestos Cement	48	57	1.14 out of 5	\$442	21,284
Distribution Main	7221	P-7040	COV	Wisteria Dr.	8	Asbestos Cement	160	57	1.14 out of 5	\$442	70,931
Distribution Main	7222	P-7041	COV	Wisteria Dr.	8	Asbestos Cement	216	57	1.14 out of 5	\$442	95,447
Distribution Main	7223	P-7037	COV	Wisteria Dr.	8	Asbestos Cement	60	57	1.14 out of 5	\$442	26,654
Distribution Main	7224	P-7037	COV	Wisteria Dr.	8	Asbestos Cement	559	57	1.14 out of 5	\$442	246,964
Distribution Main	7225	P-7030	COV	Wisteria Dr.	8	Asbestos Cement	683	57	1.14 out of 5	\$442	301,918
Distribution Main	7547	P-7055	COV	Wisteria Dr.	8	Asbestos Cement	8	57	1.14 out of 5	\$442	3,676
Distribution Main	7590	P-7011	COV	Wisteria Dr.	8	Asbestos Cement	113	57	1.14 out of 5	\$442	50,114
Distribution Main	7591	P-7011	COV	Wisteria Dr.	8	Asbestos Cement	895	57	1.14 out of 5	\$442	395,410
Distribution Main	7725	P-7026	COV	Wisteria Dr.	8	Asbestos Cement	314	57	1.14 out of 5	\$442	138,567
Distribution Main	7726	P-7017	COV	Wisteria Dr.	8	Asbestos Cement	9	57	1.14 out of 5	\$442	4,035
Distribution Main	7727	P-7017	COV	Wisteria Dr.	8	Asbestos Cement	367	57	1.14 out of 5	\$442	162,219
Distribution Main	7734	P-7030	COV	Wisteria Dr.	8	Asbestos Cement	16	57	1.14 out of 5	\$442	7,065
Distribution Main	7743	P-7055	COV	Wisteria Dr.	8	Asbestos Cement	179	57	1.14 out of 5	\$442	78,923
Distribution Main	7744	P-7055	COV	Wisteria Dr.	8	Asbestos Cement	251	57	1.14 out of 5	\$442	110,877
Distribution Main	8181	P-7025	COV	Wisteria Dr.	8	Asbestos Cement	454	57	1.14 out of 5	\$442	200,848
Distribution Main	11365	P-7054	COV	Wisteria Dr.	8	Asbestos Cement	3	57	1.14 out of 5	\$442	1,516
Distribution Main	11366	P-7039	COV	Wisteria Dr.	8	Asbestos Cement	7	57	1.14 out of 5	\$442	2,987
Distribution Main	11367	P-7040	COV	Wisteria Dr.	8	Asbestos Cement	20	57	1.14 out of 5	\$442	8,620
Distribution Main	11368	P-7041	COV	Wisteria Dr.	8	Asbestos Cement	6	57	1.14 out of 5	\$442	2,791
Distribution Main	11407	P-7026	COV	Wisteria Dr.	8	Asbestos Cement	13	57	1.14 out of 5	\$442	5,901
Distribution Main	11798	P-7011	COV	Wisteria Dr.	8	Asbestos Cement	647	57	1.14 out of 5	\$442	286,086
Distribution Main	1667	P-8932	COV	Woburn Street	6	Asbestos Cement	277	60	1.85 out of 5	\$442	122,413
Distribution Main	8324	P-7082	COV	Wolfe Ct.	6	Ductile Iron	45	29	0.85 out of 5	\$442	20,016
Distribution Main	8325	P-7082	COV	Wolfe Ct.	6	Ductile Iron	222	29	0.85 out of 5	\$442	98,311
Distribution Main	9261	P-7013	COV	Wood Cove Dr		Unknown	58	UNK	0 out of 5	N/A	\$0
Distribution Main	7209	P-7052	COV	Wood Cove Dr.	8	Asbestos Cement	43	51	1.14 out of 5	\$442	19,013
Distribution Main	7210	P-7052	COV	Wood Cove Dr.	8	Asbestos Cement	165	51	1.14 out of 5	\$442	72,799

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7456	P-7090	COV	Wood Cove Dr.	8	Asbestos Cement	571	51	1.14 out of 5	\$442	252,539
Distribution Main	7457	P-7090	COV	Wood Cove Dr.	8	Asbestos Cement	54	51	1.14 out of 5	\$442	23,801
Distribution Main	7601	P-7088	COV	Wood Cove Dr.	8	Asbestos Cement	79	51	1.14 out of 5	\$442	34,863
Distribution Main	7602	P-7088	COV	Wood Cove Dr.	8	Asbestos Cement	540	51	1.14 out of 5	\$442	238,772
Distribution Main	7709	P-7012	COV	Wood Cove Dr.	8	Asbestos Cement	142	51	1.14 out of 5	\$442	62,549
Distribution Main	7710	P-7012	COV	Wood Cove Dr.	8	Asbestos Cement	492	51	1.14 out of 5	\$442	217,362
Distribution Main	7715	P-7015	COV	Wood Cove Dr.	8	Asbestos Cement	41	51	1.14 out of 5	\$442	18,262
Distribution Main	7716	P-7015	COV	Wood Cove Dr.	8	Asbestos Cement	5	51	1.14 out of 5	\$442	2,192
Distribution Main	7717	P-7015	COV	Wood Cove Dr.	8	Asbestos Cement	767	51	1.14 out of 5	\$442	339,082
Distribution Main	7718	P-7029	COV	Wood Cove Dr.	8	Asbestos Cement	383	51	1.14 out of 5	\$442	169,232
Distribution Main	7719	P-7033	COV	Wood Cove Dr.	8	Asbestos Cement	251	51	1.14 out of 5	\$442	110,780
Distribution Main	7730	P-7013	COV	Wood Cove Dr.	8	Asbestos Cement	690	51	1.14 out of 5	\$442	305,073
Distribution Main	7731	P-7013	COV	Wood Cove Dr.	8	Asbestos Cement	221	51	1.14 out of 5	\$442	97,861
Distribution Main	7739	P-7079	COV	Wood Cove Dr.	8	Asbestos Cement	15	51	1.14 out of 5	\$442	6,502
Distribution Main	7817	P-7051	COV	Wood Cove Dr.	6	Asbestos Cement	418	51	1.85 out of 5	\$442	184,817
Distribution Main	7818	P-7051	COV	Wood Cove Dr.	6	Asbestos Cement	257	51	1.85 out of 5	\$442	113,814
Distribution Main	7823	P-7049	COV	Wood Cove Dr.	6	Asbestos Cement	453	51	1.85 out of 5	\$442	200,029
Distribution Main	7824	P-7049	COV	Wood Cove Dr.	6	Asbestos Cement	395	51	1.85 out of 5	\$442	174,379
Distribution Main	7833	P-7047	COV	Wood Cove Dr.	6	Asbestos Cement	54	51	1.85 out of 5	\$442	23,844
Distribution Main	7834	P-7047	COV	Wood Cove Dr.	6	Asbestos Cement	221	51	1.85 out of 5	\$442	97,838
Distribution Main	7837	P-7079	COV	Wood Cove Dr.	8	Asbestos Cement	32	51	1.14 out of 5	\$442	14,311
Distribution Main	7838	P-7079	COV	Wood Cove Dr.	8	Asbestos Cement	405	51	1.14 out of 5	\$442	179,215
Distribution Main	8853	P-8960	COV	Wood Cove Dr.	8	Ductile Iron	8	13	0 out of 5	N/A	\$0
Distribution Main	8854	P-8961	COV	Wood Cove Dr.	8	Ductile Iron	6	13	0 out of 5	N/A	\$0
Distribution Main	8855	P-8961	COV	Wood Cove Dr.	6	Ductile Iron	2	13	0.71 out of 5	N/A	\$0
Distribution Main	11404	P-7015	COV	Wood Cove Dr.	8	Asbestos Cement	8	51	1.14 out of 5	\$442	3,327
Distribution Main	11405	P-7015	COV	Wood Cove Dr.	8	Asbestos Cement	11	51	1.14 out of 5	\$442	4,836
Distribution Main	11795	P-7015	COV	Wood Cove Dr.	8	Asbestos Cement	613	51	1.14 out of 5	\$442	271,109
Distribution Main	11797	P-7088	COV	Wood Cove Dr.	8	Asbestos Cement	532	51	1.14 out of 5	\$442	235,032
Distribution Main	9332		COV	Wood St.	6	Ductile Iron	19	10	0.71 out of 5	N/A	\$0
Transmission Main	581	P-8931	COV	Wood St.	16	Cast Iron	37	129	1.86 out of 5	\$442	16,388
Transmission Main	1039	P-7557	COV	Wood St.	16	Cast Iron	126	129	1.86 out of 5	\$442	55,691
Transmission Main	1040	P-7557	COV	Wood St.	16	Cast Iron	227	129	1.86 out of 5	\$442	100,534
Transmission Main	1307	P-7558	COV	Wood St.	16	Cast Iron	186	129	1.86 out of 5	\$442	82,415
Transmission Main	2473	P-7555	COV	Wood St.	16	Cast Iron	72	129	1.86 out of 5	\$442	31,614
Transmission Main	2474	P-7555	COV	Wood St.	16	Cast Iron	52	129	1.86 out of 5	\$442	22,862
Transmission Main	2628	P-7555	COV	Wood St.	16	Cast Iron	702	129	1.86 out of 5	\$442	310,488
Transmission Main	2632	P-7558	COV	Wood St.	16	Cast Iron	215	129	1.86 out of 5	\$442	95,017
Transmission Main	2825		COV	Wood St.	12	Unknown	14	UNK	0 out of 5	N/A	\$0
Transmission Main	2987	P-8931	COV	Wood St.	16	Cast Iron	129	129	1.86 out of 5	\$442	56,829
Transmission Main	2988	P-8931	COV	Wood St.	16	Cast Iron	506	129	1.86 out of 5	\$442	223,595
Transmission Main	2989		COV	Wood St.	12	Unknown	67	UNK	0 out of 5	N/A	\$0
Transmission Main	11098	P-7557	COV	Wood St.	16	Cast Iron	68	129	1.86 out of 5	\$442	30,239
Transmission Main	11121	P-7558	COV	Wood St.	16	Cast Iron	23	129	1.86 out of 5	\$442	10,094

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11122	P-7558	COV	Wood St.	16	Cast Iron	11	129	1.86 out of 5	\$442	4,671
Transmission Main	11198	P-8931	COV	Wood St.	16	Cast Iron	144	129	1.86 out of 5	\$442	63,725
Transmission Main	12182		COV	Wood St.	16	Cast Iron	51	129	1.86 out of 5	\$442	22,427
Transmission Main	12183		COV	Wood St.	16	Cast Iron	58	129	1.86 out of 5	\$442	25,768
Distribution Main	476		COV	Woodland Ave.	6	Asbestos Cement	61	69	2 out of 5	\$442	27,045
Distribution Main	1642	P-7547	COV	Woodland Ave.	6	Asbestos Cement	212	69	2 out of 5	\$442	93,502
Distribution Main	1643	P-7547	COV	Woodland Ave.	6	Asbestos Cement	363	69	2 out of 5	\$442	160,624
Distribution Main	1858	P-7548	COV	Woodland Ave.	6	Asbestos Cement	240	69	2 out of 5	\$442	106,130
Distribution Main	407	P-8067	COV	Woodmist Cir.	8	Ductile Iron	1,054	18	0 out of 5	N/A	\$0
Distribution Main	408	P-8067	COV	Woodmist Cir.	8	Ductile Iron	1,164	18	0 out of 5	N/A	\$0
Distribution Main	11746	P-8067	COV	Woodmist Cir.	8	Ductile Iron	795	18	0 out of 5	N/A	\$0
Distribution Main	10342		COV	Wright Way		Unknown	19	UNK	0 out of 5	N/A	\$0
Distribution Main	1719	P-7780	COV	Yale Dr.	6	Asbestos Cement	579	60	1.85 out of 5	\$442	255,699
Distribution Main	2204	P-7791	COV	Yale Dr.	6	Asbestos Cement	441	60	1.85 out of 5	\$442	194,920
Distribution Main	2205	P-7791	COV	Yale Dr.	6	Asbestos Cement	285	60	1.85 out of 5	\$442	126,054
Distribution Main	3175	P-7792	COV	Yale Dr.	6	Asbestos Cement	197	60	1.85 out of 5	\$442	87,222
Distribution Main	9946	P-7780	COV	Yale Dr.	6	Asbestos Cement	23	60	1.85 out of 5	\$442	10,044
Distribution Main	404	P-7982	COV	Yates Ave.	6	Asbestos Cement	23	70	2 out of 5	\$442	10,157
Distribution Main	405	P-7982	COV	Yates Ave.	6	Asbestos Cement	211	70	2 out of 5	\$442	93,309
Distribution Main	942	P-9063	COV	Yates Ave.	1	Copper	339	UNK	1.99 out of 5	\$442	149,980
Distribution Main	9222	P-8076	COV	Yeaton St	8	Ductile Iron	609	8	0 out of 5	N/A	\$0
Distribution Main	1862	P-7621	COV	York Dr.	8	Asbestos Cement	46	53	1.14 out of 5	\$442	20,150
Distribution Main	1863	P-7621	COV	York Dr.	8	Asbestos Cement	740	53	1.14 out of 5	\$442	327,234
Distribution Main	1864	P-7601	COV	York Dr.	8	Asbestos Cement	464	53	1.14 out of 5	\$442	205,118
Distribution Main	2560	P-7627	COV	York Dr.	8	Asbestos Cement	34	53	1.14 out of 5	\$442	15,238
Distribution Main	2604	P-7626	COV	York Dr.	8	Asbestos Cement	825	53	1.14 out of 5	\$442	364,735
Distribution Main	2605	P-7626	COV	York Dr.	8	Asbestos Cement	660	53	1.14 out of 5	\$442	291,589
Distribution Main	2407	P-8048	COV	Youngs Ave.	8	Asbestos Cement	196	63	1.29 out of 5	\$442	86,597
Distribution Main	2929	P-8048	COV	Youngs Ave.	8	Asbestos Cement	15	63	1.29 out of 5	\$442	6,455
Distribution Main	8891	P-5026	CRA	Allard St	8	Ductile Iron	53	9	0 out of 5	N/A	\$0
Distribution Main	8892	P-5026	CRA	Allard St	8	Ductile Iron	541	9	0 out of 5	N/A	\$0
Distribution Main	8893	P-5027	CRA	Allard St	8	Ductile Iron	468	9	0 out of 5	N/A	\$0
Distribution Main	11806	P-5026	CRA	Allard St	8	Ductile Iron	4	9	0 out of 5	N/A	\$0
Distribution Main	8867	P-5042	CRA	Amanda Ct	8	Ductile Iron	247	9	0 out of 5	N/A	\$0
Distribution Main	8869	P-5040	CRA	Amanda St	8	Ductile Iron	200	9	0 out of 5	N/A	\$0
Distribution Main	8870	P-5040	CRA	Amanda St	8	Ductile Iron	124	9	0 out of 5	N/A	\$0
Distribution Main	8872	P-5039	CRA	Amanda St	8	Ductile Iron	407	9	0 out of 5	N/A	\$0
Distribution Main	8873	P-5039	CRA	Amanda St	8	Ductile Iron	131	9	0 out of 5	N/A	\$0
Distribution Main	8875	P-5039	CRA	Amanda St	8	Ductile Iron	461	9	0 out of 5	N/A	\$0
Distribution Main	8876	P-5167	CRA	Amanda St	8	Ductile Iron	390	9	0 out of 5	N/A	\$0
Distribution Main	11520	P-5040	CRA	Amanda St	8	Ductile Iron	102	9	0 out of 5	N/A	\$0
Distribution Main	7401	P-5005	CRA	Angell Ave.	8	Ductile Iron	349	15	0 out of 5	N/A	\$0
Distribution Main	7410	P-5151	CRA	Angell Ave.	8	Ductile Iron	7	15	0 out of 5	N/A	\$0
Distribution Main	7419	P-5153	CRA	Angell Ave.	8	Ductile Iron	30	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7424	P-5153	CRA	Angell Ave.	8	Ductile Iron	159	15	0 out of 5	N/A	\$0
Distribution Main	7466	P-5005	CRA	Angell Ave.	8	Ductile Iron	116	15	0 out of 5	N/A	\$0
Distribution Main	8701	P-5153	CRA	Angell Ave.	8	Ductile Iron	140	15	0 out of 5	N/A	\$0
Distribution Main	8702	P-5006	CRA	Angell Ave.	8	Ductile Iron	27	15	0 out of 5	N/A	\$0
Distribution Main	10988	P-5006	CRA	Angell Ave.	8	Ductile Iron	91	15	0 out of 5	N/A	\$0
Distribution Main	10989	P-5015	CRA	Angell Ave.	8	Ductile Iron	256	15	0 out of 5	N/A	\$0
Distribution Main	11376	P-5003	CRA	Angell Ave.	8	Ductile Iron	481	15	0 out of 5	N/A	\$0
Distribution Main	11377	P-5151	CRA	Angell Ave.	8	Ductile Iron	4	15	0 out of 5	N/A	\$0
Distribution Main	10321		CRA	Bald Hill Rd	8	Ductile Iron	322	5	0 out of 5	N/A	\$0
Distribution Main	10322		CRA	Bald Hill Rd	8	Ductile Iron	29	5	0 out of 5	N/A	\$0
Distribution Main	10323	P-5101	CRA	Bald Hill Rd	10	Ductile Iron	12	5	0 out of 5	N/A	\$0
Distribution Main	11805		CRA	Bald Hill Rd	8	Ductile Iron	18	5	0 out of 5	N/A	\$0
Distribution Main	12130		CRA	Bald Hill Rd	8	Ductile Iron	4	5	0 out of 5	N/A	\$0
Distribution Main	4591		CRA	Bald Hill Rd.	6	Asbestos Cement	6	51	1.85 out of 5	\$442	2,798
Distribution Main	4592	P-5099	CRA	Bald Hill Rd.	6	Asbestos Cement	9	51	1.85 out of 5	\$442	4,088
Distribution Main	4593	P-5099	CRA	Bald Hill Rd.	6	Asbestos Cement	151	51	1.85 out of 5	\$442	66,527
Distribution Main	4594	P-5095	CRA	Bald Hill Rd.	10	Asbestos Cement	543	51	1.14 out of 5	\$442	239,965
Distribution Main	5380	P-5101	CRA	Bald Hill Rd.	10	Asbestos Cement	220	51	1.14 out of 5	\$442	97,115
Distribution Main	5382	P-5100	CRA	Bald Hill Rd.	6	Asbestos Cement	114	51	1.85 out of 5	\$442	50,191
Distribution Main	5387	P-5101	CRA	Bald Hill Rd.	10	Asbestos Cement	138	51	1.14 out of 5	\$442	61,043
Distribution Main	5388	P-5100	CRA	Bald Hill Rd.	6	Unknown	11	UNK	0.71 out of 5	\$442	5,033
Distribution Main	5389	P-5100	CRA	Bald Hill Rd.	6	Asbestos Cement	62	UNK	1.56 out of 5	\$442	27,620
Distribution Main	5646	P-5095	CRA	Bald Hill Rd.	6	Asbestos Cement	345	51	1.85 out of 5	\$442	152,351
Distribution Main	5647	P-5099	CRA	Bald Hill Rd.	6	Asbestos Cement	4	51	1.85 out of 5	\$442	1,793
Distribution Main	7411	P-5101	CRA	Bald Hill Rd.	10	Asbestos Cement	150	51	1.14 out of 5	\$442	66,129
Distribution Main	7412	P-5099	CRA	Bald Hill Rd.	6	Asbestos Cement	17	51	1.85 out of 5	\$442	7,456
Distribution Main	10532	P-5095	CRA	Bald Hill Rd.	6	Asbestos Cement	49	51	1.85 out of 5	\$442	21,658
Distribution Main	10533		CRA	Bald Hill Rd.	6	Asbestos Cement	53	51	1.85 out of 5	\$442	23,508
Distribution Main	10828	P-5097	CRA	Bald Hill Rd.	10	Asbestos Cement	36	51	1.14 out of 5	\$442	15,703
Distribution Main	10829	P-5097	CRA	Bald Hill Rd.	10	Asbestos Cement	239	51	1.14 out of 5	\$442	105,833
Distribution Main	11258	P-5097	CRA	Bald Hill Rd.	10	Asbestos Cement	113	51	1.14 out of 5	\$442	50,115
Distribution Main	11300	P-5100	CRA	Bald Hill Rd.	6	Asbestos Cement	6	51	1.85 out of 5	\$442	2,595
Distribution Main	11378	P-5101	CRA	Bald Hill Rd.	10	Asbestos Cement	24	51	1.14 out of 5	\$442	10,477
Distribution Main	9034	P-5033	CRA	Benjamin Ave	8	Ductile Iron	18	9	0 out of 5	N/A	\$0
Distribution Main	8874	P-5033	CRA	Benjamin Ave.	8	Ductile Iron	252	9	0 out of 5	N/A	\$0
Distribution Main	8884	P-5034	CRA	Benjamin Ave.	8	Ductile Iron	61	9	0 out of 5	N/A	\$0
Distribution Main	10826	P-5034	CRA	Benjamin Ave.	8	Ductile Iron	185	9	0 out of 5	N/A	\$0
Distribution Main	10827	P-5168	CRA	Benjamin Ave.	8	Ductile Iron	18	9	0 out of 5	N/A	\$0
Distribution Main	4170		CRA	Briarwood Rd.	6	Asbestos Cement	7	62	2 out of 5	\$442	2,976
Distribution Main	4171		CRA	Briarwood Rd.	6	Asbestos Cement	5	62	2 out of 5	\$442	2,076
Distribution Main	4934	P-5072	CRA	Briarwood Rd.	6	Asbestos Cement	20	62	2 out of 5	\$442	8,887
Distribution Main	6544	P-5079	CRA	Briarwood Rd.	6	Asbestos Cement	190	62	2 out of 5	\$442	84,105
Distribution Main	7488	P-5072	CRA	Briarwood Rd.	6	Asbestos Cement	6	62	2 out of 5	\$442	2,626
Distribution Main	4939	P-5080	CRA	Brookfield Dr.	6	Asbestos Cement	435	64	2 out of 5	\$442	192,317

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6535	P-5080	CRA	Brookfield Dr.	6	Asbestos Cement	415	64	2 out of 5	\$442	183,361
Distribution Main	6536	P-5080	CRA	Brookfield Dr.	6	Asbestos Cement	77	64	2 out of 5	\$442	33,884
Distribution Main	6540	P-5074	CRA	Brookfield Dr.	6	Asbestos Cement	7	64	2 out of 5	\$442	3,148
Distribution Main	6541	P-5074	CRA	Brookfield Dr.	6	Asbestos Cement	350	64	2 out of 5	\$442	154,506
Distribution Main	6545	P-5079	CRA	Brookfield Dr.	6	Asbestos Cement	5	64	2 out of 5	\$442	2,256
Distribution Main	10981	P-5080	CRA	Brookfield Dr.	6	Asbestos Cement	3	64	2 out of 5	\$442	1,220
Distribution Main	8866	P-5090	CRA	Burdick Dr	8	Ductile Iron	6	9	0 out of 5	N/A	\$0
Distribution Main	10994	P-5092	CRA	Burdick Dr	8	Ductile Iron	3	9	0 out of 5	N/A	\$0
Distribution Main	3278	P-5081	CRA	Burdick Dr.	8	Asbestos Cement	34	49	1.14 out of 5	\$442	15,076
Distribution Main	3279	P-5081	CRA	Burdick Dr.	8	Asbestos Cement	180	49	1.14 out of 5	\$442	79,420
Distribution Main	5990	P-5092	CRA	Burdick Dr.	8	Asbestos Cement	90	49	1.14 out of 5	\$442	39,928
Distribution Main	5991	P-5089	CRA	Burdick Dr.	8	Asbestos Cement	126	49	1.14 out of 5	\$442	55,856
Distribution Main	5992	P-5089	CRA	Burdick Dr.	8	Asbestos Cement	551	49	1.14 out of 5	\$442	243,723
Distribution Main	5993	P-5092	CRA	Burdick Dr.	8	Asbestos Cement	958	49	1.14 out of 5	\$442	423,338
Distribution Main	5994	P-5092	CRA	Burdick Dr.	8	Asbestos Cement	132	49	1.14 out of 5	\$442	58,347
Distribution Main	5997	P-5090	CRA	Burdick Dr.	8	Asbestos Cement	269	49	1.14 out of 5	\$442	118,763
Distribution Main	5999	P-5083	CRA	Burdick Dr.	8	Asbestos Cement	255	49	1.14 out of 5	\$442	112,799
Distribution Main	7372	P-5092	CRA	Burdick Dr.	8	Asbestos Cement	25	49	1.14 out of 5	\$442	11,119
Distribution Main	7373	P-5085	CRA	Burdick Dr.	8	Asbestos Cement	30	49	1.14 out of 5	\$442	13,439
Distribution Main	7374	P-5085	CRA	Burdick Dr.	8	Asbestos Cement	247	49	1.14 out of 5	\$442	109,031
Distribution Main	4947	P-5110	CRA	Candle Dr.	8	Asbestos Cement	297	42	1.14 out of 5	\$442	131,338
Distribution Main	4948	P-5110	CRA	Candle Dr.	8	Asbestos Cement	102	42	1.14 out of 5	\$442	44,944
Distribution Main	7487	P-5110	CRA	Candle Dr.	8	Asbestos Cement	18	42	1.14 out of 5	\$442	7,755
Distribution Main	762	P-5049	CRA	Capeway Rd.	6	Asbestos Cement	127	70	2 out of 5	\$442	55,926
Distribution Main	763	P-5049	CRA	Capeway Rd.	6	Asbestos Cement	92	70	2 out of 5	\$442	40,548
Distribution Main	3317	P-5049	CRA	Capeway Rd.	6	Asbestos Cement	8	70	2 out of 5	\$442	3,575
Distribution Main	3281	P-5117	CRA	Carriage Rd.	8	Asbestos Cement	10	42	1.14 out of 5	\$442	4,261
Distribution Main	3282	P-5113	CRA	Carriage Rd.	8	Asbestos Cement	170	44	1.14 out of 5	\$442	74,992
Distribution Main	4520	P-5111	CRA	Carriage Rd.	8	Asbestos Cement	39	44	1.14 out of 5	\$442	17,390
Distribution Main	4521		CRA	Carriage Rd.	8	Asbestos Cement	57	44	1.14 out of 5	\$442	25,075
Distribution Main	4522	P-5109	CRA	Carriage Rd.	8	Asbestos Cement	276	44	1.14 out of 5	\$442	121,919
Distribution Main	4936	P-5117	CRA	Carriage Rd.	8	Asbestos Cement	145	42	1.14 out of 5	\$442	64,237
Distribution Main	5296	P-5111	CRA	Carriage Rd.	8	Asbestos Cement	207	44	1.14 out of 5	\$442	91,685
Distribution Main	7483	P-1	CRA	Carriage Rd.	8	Asbestos Cement	259	44	1.14 out of 5	\$442	114,683
Distribution Main	5905	P-5115	CRA	Chapel Dr.	6	PVC	137	31	1.14 out of 5	\$442	60,614
Distribution Main	5906	P-5115	CRA	Chapel Dr.	6	PVC	202	31	1.14 out of 5	\$442	89,403
Distribution Main	8871	P-5038	CRA	Ellison St	8	Ductile Iron	11	17	0 out of 5	N/A	\$0
Distribution Main	5907	P-5038	CRA	Ellison St.	8	Ductile Iron	393	17	0 out of 5	N/A	\$0
Distribution Main	5908	P-5038	CRA	Ellison St.	8	Ductile Iron	452	17	0 out of 5	N/A	\$0
Distribution Main	5909	P-5038	CRA	Ellison St.	8	Ductile Iron	3	17	0 out of 5	N/A	\$0
Distribution Main	5910	P-5032	CRA	Ellison St.	8	Ductile Iron	228	17	0 out of 5	N/A	\$0
Distribution Main	5911	P-5032	CRA	Ellison St.	8	Ductile Iron	24	17	0 out of 5	N/A	\$0
Distribution Main	9033	P-5038	CRA	Ellison St.	8	Ductile Iron	389	17	0 out of 5	N/A	\$0
Distribution Main	8885	P-5036	CRA	Esther St	8	Ductile Iron	19	9	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	8886	P-5036	CRA	Esther St	8	Ductile Iron	216	9	0 out of 5	N/A	\$0
Distribution Main	8688	P-5019	CRA	Exchange St.	8	Ductile Iron	157	15	0 out of 5	N/A	\$0
Distribution Main	8689	P-5019	CRA	Exchange St.	8	Ductile Iron	96	15	0 out of 5	N/A	\$0
Distribution Main	10383	P-5019	CRA	Exchange St.	8	Ductile Iron	3	17	0 out of 5	N/A	\$0
Distribution Main	10384	P-5019	CRA	Exchange St.	8	Ductile Iron	32	15	0 out of 5	N/A	\$0
Distribution Main	4269	P-5060	CRA	Fairway Dr.	8	Ductile Iron	274	15	0 out of 5	N/A	\$0
Distribution Main	4270	P-5060	CRA	Fairway Dr.	8	Ductile Iron	249	15	0 out of 5	N/A	\$0
Distribution Main	4271		CRA	Fairway Dr.	8	Ductile Iron	6	16	0 out of 5	N/A	\$0
Distribution Main	4272	P-5061	CRA	Fairway Dr.	8	Ductile Iron	145	16	0 out of 5	N/A	\$0
Distribution Main	4273		CRA	Fairway Dr.	4	Unknown	29	UNK	1.42 out of 5	\$442	12,876
Distribution Main	5366	P-5057	CRA	Fairway Dr.	8	Ductile Iron	29	15	0 out of 5	N/A	\$0
Distribution Main	5368	p-5057	CRA	Fairway Dr.	8	Ductile Iron	127	15	0 out of 5	N/A	\$0
Distribution Main	11003	P-5061	CRA	Fairway Dr.	8	Ductile Iron	2	16	0 out of 5	N/A	\$0
Distribution Main	11004	p-5060	CRA	Fairway Dr.	8	Ductile Iron	2	15	0 out of 5	N/A	\$0
Distribution Main	11249	P-5061	CRA	Fairway Dr.	8	Ductile Iron	7	16	0 out of 5	N/A	\$0
Distribution Main	8682	P-5162	CRA	Fruit St.	8	Ductile Iron	29	17	0 out of 5	N/A	\$0
Distribution Main	8898	P-5022	CRA	Fruit St.	8	Ductile Iron	16	9	0 out of 5	N/A	\$0
Distribution Main	8899	P-5022	CRA	Fruit St.	8	Ductile Iron	214	9	0 out of 5	N/A	\$0
Distribution Main	11524	P-5163	CRA	Fruit St.	8	Ductile Iron	109	9	0 out of 5	N/A	\$0
Distribution Main	5295	P-5075	CRA	Gaunt Dr.	6	Asbestos Cement	236	65	2 out of 5	\$442	104,455
Distribution Main	6546	P-5075	CRA	Gaunt Dr.	6	Asbestos Cement	7	65	2 out of 5	\$442	3,274
Distribution Main	9987	P-5076	CRA	Gaunt Dr.	8	Ductile Iron	178	6	0 out of 5	N/A	\$0
Distribution Main	9988	P-5187	CRA	Gaunt Dr.	6	Ductile Iron	4	6	0.71 out of 5	N/A	\$0
Distribution Main	5370	P-5059	CRA	Green Ct.	8	Ductile Iron	328	16	0 out of 5	N/A	\$0
Distribution Main	5371	P-5059	CRA	Green Ct.	8	Ductile Iron	19	16	0 out of 5	N/A	\$0
Distribution Main	3092	P-5118	CRA	Greenview Rd.	8	Asbestos Cement	336	44	1.14 out of 5	\$442	148,592
Distribution Main	3280	P-5105	CRA	Greenview Rd.	8	Asbestos Cement	229	44	1.14 out of 5	\$442	101,308
Distribution Main	4945	P-5118	CRA	Greenview Rd.	8	Asbestos Cement	82	44	1.14 out of 5	\$442	36,316
Distribution Main	4946	P-5118	CRA	Greenview Rd.	8	Asbestos Cement	18	44	1.14 out of 5	\$442	8,089
Distribution Main	5369	P-5058	CRA	Hagen Ave.	8	Ductile Iron	3	16	0 out of 5	N/A	\$0
Distribution Main	5372	P-5185	CRA	Hagen Ave.	8	Ductile Iron	86	46	0.29 out of 5	\$442	37,924
Distribution Main	5373	P-5058	CRA	Hagen Ave.	8	Ductile Iron	281	15	0 out of 5	N/A	\$0
Distribution Main	2283	P-5142	CRA	Hall Ave.	6	Asbestos Cement	80	46	1.85 out of 5	\$442	35,554
Distribution Main	2284	P-5142	CRA	Hall Ave.	6	PVC	555	34	1.14 out of 5	\$442	245,166
Distribution Main	9821	P-5195	CRA	Hall Ln	8	Ductile Iron	27	7	0 out of 5	N/A	\$0
Distribution Main	9822	P-5123	CRA	Hall Ln	6	Ductile Iron	5	7	0.71 out of 5	N/A	\$0
Distribution Main	10133		CRA	Hall Ln	8	Ductile Iron	36	6	0 out of 5	N/A	\$0
Distribution Main	7486	P-5112	CRA	Hard Point Rd.	8	Asbestos Cement	436	43	1.14 out of 5	\$442	192,845
Distribution Main	7388	P-5008	CRA	Harrison Ave.	8	Ductile Iron	243	15	0 out of 5	N/A	\$0
Distribution Main	7396	P-5007	CRA	Harrison Ave.	8	Ductile Iron	233	15	0 out of 5	N/A	\$0
Distribution Main	8700	P-5007	CRA	Harrison Ave.	8	Ductile Iron	3	15	0 out of 5	N/A	\$0
Distribution Main	9818	P-5121	CRA	Hope Rd	8	Ductile Iron	634	7	0 out of 5	N/A	\$0
Distribution Main	9819	P-5122	CRA	Hope Rd	8	Ductile Iron	737	7	0 out of 5	N/A	\$0
Transmission Main	9820	P-5121	CRA	Hope Rd	12	Ductile Iron	1	7	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9823	P-5127	CRA	Hope Rd	8	Ductile Iron	367	7	0 out of 5	N/A	\$0
Distribution Main	9824	P-5127	CRA	Hope Rd	8	Ductile Iron	1,727	7	0 out of 5	N/A	\$0
Distribution Main	11614	P-5124	CRA	Hope Rd	8	Ductile Iron	25	7	0 out of 5	N/A	\$0
Distribution Main	8915	P-164	CRA	Hopedale Dr	8	Ductile Iron	457	9	0 out of 5	N/A	\$0
Distribution Main	8916	P-164	CRA	Hopedale Dr	8	Ductile Iron	18	9	0 out of 5	N/A	\$0
Distribution Main	9405	P-169	CRA	Hopedale Dr	8	Ductile Iron	78	9	0 out of 5	N/A	\$0
Distribution Main	10131	P-6114	CRA	Jackson Flat Rd	8	Ductile Iron	41	6	0 out of 5	N/A	\$0
Distribution Main	7385	P-5159	CRA	Lincoln Park Ave.	8	Asbestos Cement	232	15	0.85 out of 5	N/A	\$0
Distribution Main	7426	P-5009	CRA	Lincoln Park Ave.	8	Ductile Iron	3	15	0 out of 5	N/A	\$0
Distribution Main	8035	P-5009	CRA	Lincoln Park Ave.	8	Asbestos Cement	23	48	1.14 out of 5	\$442	9,967
Distribution Main	8170	P-5009	CRA	Lincoln Park Ave.	6	Asbestos Cement	153	48	1.85 out of 5	\$442	67,795
Distribution Main	8703	P-5009	CRA	Lincoln Park Ave.	6	Asbestos Cement	989	48	2.57 out of 5	\$442	437,102
Distribution Main	8877	P-5029	CRA	Loring St.	8	Ductile Iron	248	9	0 out of 5	N/A	\$0
Distribution Main	8878	P-5029	CRA	Loring St.	8	Ductile Iron	113	9	0 out of 5	N/A	\$0
Distribution Main	8887	P-5029	CRA	Loring St.	8	Ductile Iron	96	9	0 out of 5	N/A	\$0
Distribution Main	11521	P-5029	CRA	Loring St.	8	Ductile Iron	46	9	0 out of 5	N/A	\$0
Distribution Main	10129	P-5125	CRA	Main St	8	Ductile Iron	414	6	0 out of 5	N/A	\$0
Distribution Main	10130	P-5125	CRA	Main St	8	Ductile Iron	571	6	0 out of 5	N/A	\$0
Distribution Main	11641	P-5125	CRA	Main St	8	Ductile Iron	558	6	0 out of 5	N/A	\$0
Distribution Main	11642	P-5125	CRA	Main St	8	Ductile Iron	17	6	0 out of 5	N/A	\$0
Distribution Main	11808	P-5125	CRA	Main St	8	Ductile Iron	63	6	0 out of 5	N/A	\$0
Distribution Main	11809	P-5125	CRA	Main St	8	Ductile Iron	33	6	0 out of 5	N/A	\$0
Distribution Main	11810	P-5125	CRA	Main St	8	Ductile Iron	10	6	0 out of 5	N/A	\$0
Distribution Main	12124	P-5125	CRA	Main St	8	Ductile Iron	13	6	0 out of 5	N/A	\$0
Transmission Main	1181	P-5193	CRA	Main St.	12	Cast Iron	329	133	1.86 out of 5	\$442	145,615
Transmission Main	1182	P-5193	CRA	Main St.	12	Cast Iron	475	133	1.86 out of 5	\$442	209,833
Distribution Main	1183	P-5193	CRA	Main St.	6	Unknown	13	UNK	0.71 out of 5	\$442	5,782
Transmission Main	1315	P-5193	CRA	Main St.	12	Cast Iron	393	133	1.86 out of 5	\$442	173,843
Transmission Main	1316	P-5193	CRA	Main St.	12	Cast Iron	47	133	1.86 out of 5	\$442	20,966
Transmission Main	2112		CRA	Main St.	12	Cast Iron	22	133	1.86 out of 5	\$442	9,862
Transmission Main	8599	P-5121	CRA	Main St.	12	Ductile Iron	8	20	0 out of 5	N/A	\$0
Transmission Main	9817		CRA	Main St.	12	Cast Iron	14	133	1.86 out of 5	\$442	6,120
Transmission Main	10128		CRA	Main St.	12	Cast Iron	6	133	1.86 out of 5	\$442	2,492
Transmission Main	11484	P-5121	CRA	Main St.	12	Ductile Iron	6	20	0 out of 5	N/A	\$0
Transmission Main	11613		CRA	Main St.	12	Cast Iron	2	133	1.86 out of 5	\$442	758
Transmission Main	11807	P-5193	CRA	Main St.	12	Cast Iron	56	133	1.86 out of 5	\$442	24,845
Distribution Main	6542	P-5077	CRA	Manor Rd.	6	Asbestos Cement	299	65	2 out of 5	\$442	131,972
Distribution Main	6543	P-5077	CRA	Manor Rd.	6	Asbestos Cement	489	65	2 out of 5	\$442	216,228
Distribution Main	8918	P-157	CRA	Maywood Dr	8	Ductile Iron	472	9	0 out of 5	N/A	\$0
Distribution Main	8919	P-157	CRA	Maywood Dr	8	Ductile Iron	33	9	0 out of 5	N/A	\$0
Distribution Main	8036	P-5098	CRA	Moon Ave.	6	Cast Iron	20	91	2.43 out of 5	\$442	9,045
Distribution Main	8037	P-5098	CRA	Moon Ave.	6	Cast Iron	116	91	2.43 out of 5	\$442	51,249
Transmission Main	873	P-5188	CRA	New London Ave.	12	Ductile Iron	48	15	0 out of 5	N/A	\$0
Transmission Main	874	P-5188	CRA	New London Ave.	12	Ductile Iron	294	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	2419	P-5062	CRA	New London Ave.	12	Ductile Iron	264	15	0 out of 5	N/A	\$0
Transmission Main	3589	P-5062	CRA	New London Ave.	12	Ductile Iron	555	15	0 out of 5	N/A	\$0
Transmission Main	4274	P-5103	CRA	New London Ave.	12	Ductile Iron	475	15	0 out of 5	N/A	\$0
Transmission Main	4275	P-5103	CRA	New London Ave.	12	Ductile Iron	122	15	0 out of 5	N/A	\$0
Transmission Main	5375	P-5188	CRA	New London Ave.	12	Ductile Iron	154	15	0 out of 5	N/A	\$0
Transmission Main	8160	P-5062	CRA	New London Ave.	12	Ductile Iron	41	15	0 out of 5	N/A	\$0
Distribution Main	3314	P-5182	CRA	Normandy Dr.	6	Asbestos Cement	272	69	2 out of 5	\$442	120,313
Distribution Main	3315	P-5138	CRA	Normandy Dr.	6	Asbestos Cement	324	69	2 out of 5	\$442	143,092
Distribution Main	3316	P-5138	CRA	Normandy Dr.	6	Asbestos Cement	268	69	2 out of 5	\$442	118,450
Distribution Main	11213	P-5138	CRA	Normandy Dr.	6	Asbestos Cement	33	69	2 out of 5	\$442	14,378
Distribution Main	3690	P-5184	CRA	Normandy Drive	1	Copper	147	UNK	1.99 out of 5	\$442	65,087
Distribution Main	8907	P-212	CRA	Oakland Dr	6	Ductile Iron	6	9	0.71 out of 5	N/A	\$0
Transmission Main	9412	P-5174	CRA	Oaklawn Ave	12	Ductile Iron	27	17	0 out of 5	N/A	\$0
Distribution Main	9413	P-5175	CRA	Oaklawn Ave	8	Ductile Iron	29	17	0 out of 5	N/A	\$0
Distribution Main	10211	P-5093	CRA	Oaklawn Ave	6	Ductile Iron	9	13	0.71 out of 5	N/A	\$0
Transmission Main	1231	P-5044	CRA	Oaklawn Ave.	12	Cast Iron	188	91	1.72 out of 5	\$442	83,059
Transmission Main	4590	P-5173	CRA	Oaklawn Ave.	12	Ductile Iron	272	17	0 out of 5	N/A	\$0
Transmission Main	5360	P-5050	CRA	Oaklawn Ave.	12	Ductile Iron	410	17	0 out of 5	N/A	\$0
Transmission Main	5362	P-5052	CRA	Oaklawn Ave.	12	Ductile Iron	171	17	0 out of 5	N/A	\$0
Transmission Main	5365	P-5056	CRA	Oaklawn Ave.	12	Ductile Iron	4	15	0 out of 5	N/A	\$0
Transmission Main	5367	P-5056	CRA	Oaklawn Ave.	12	Ductile Iron	221	15	0 out of 5	N/A	\$0
Transmission Main	5457	P-5055	CRA	Oaklawn Ave.	12	Ductile Iron	1,348	15	0 out of 5	N/A	\$0
Transmission Main	5458	P-5173	CRA	Oaklawn Ave.	12	Ductile Iron	24	17	0 out of 5	N/A	\$0
Transmission Main	5459	P-5173	CRA	Oaklawn Ave.	12	Ductile Iron	85	17	0 out of 5	N/A	\$0
Distribution Main	6667	P-5156	CRA	Oaklawn Ave.	10	Cast Iron	103	91	1.72 out of 5	\$442	45,704
Distribution Main	7376	P-5093	CRA	Oaklawn Ave.	10	Asbestos Cement	259	51	1.14 out of 5	\$442	114,260
Transmission Main	7413	P-5155	CRA	Oaklawn Ave.	12	Cast Iron	265	91	1.72 out of 5	\$442	117,321
Transmission Main	7414	P-5155	CRA	Oaklawn Ave.	12	Cast Iron	61	91	1.72 out of 5	\$442	26,982
Distribution Main	7415	P-5166	CRA	Oaklawn Ave.	10	Cast Iron	102	91	1.72 out of 5	\$442	44,870
Transmission Main	7418	P-5155	CRA	Oaklawn Ave.	12	Cast Iron	319	91	1.72 out of 5	\$442	141,210
Transmission Main	7468	P-5045	CRA	Oaklawn Ave.	12	Ductile Iron	289	17	0 out of 5	N/A	\$0
Transmission Main	8161	P-5139	CRA	Oaklawn Ave.	12	Ductile Iron	293	15	0 out of 5	N/A	\$0
Transmission Main	8162	P-5139	CRA	Oaklawn Ave.	12	Ductile Iron	322	15	0 out of 5	N/A	\$0
Transmission Main	8163	P-5054	CRA	Oaklawn Ave.	12	Cast Iron	106	91	1.72 out of 5	\$442	46,681
Transmission Main	8164	P-5155	CRA	Oaklawn Ave.	12	Cast Iron	80	91	1.72 out of 5	\$442	35,417
Transmission Main	8165	P-5155	CRA	Oaklawn Ave.	12	Cast Iron	67	91	1.72 out of 5	\$442	29,496
Transmission Main	8166	P-5155	CRA	Oaklawn Ave.	12	Cast Iron	179	91	1.72 out of 5	\$442	79,000
Transmission Main	9035	P-5050	CRA	Oaklawn Ave.	12	Ductile Iron	297	17	0 out of 5	N/A	\$0
Transmission Main	9036	P-5137	CRA	Oaklawn Ave.	12	Ductile Iron	3	17	0 out of 5	N/A	\$0
Transmission Main	9037	P-5137	CRA	Oaklawn Ave.	12	Ductile Iron	14	17	0 out of 5	N/A	\$0
Transmission Main	9389	P-5052	CRA	Oaklawn Ave.	12	Ductile Iron	47	17	0 out of 5	N/A	\$0
Transmission Main	9390	P-5052	CRA	Oaklawn Ave.	12	Ductile Iron	4	17	0 out of 5	N/A	\$0
Transmission Main	9391	P-5056	CRA	Oaklawn Ave.	12	Ductile Iron	21	15	0 out of 5	N/A	\$0
Transmission Main	9392	P-5052	CRA	Oaklawn Ave.	12	Ductile Iron	35	17	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10121	P-5095	CRA	Oaklawn Ave.	6	Ductile Iron	35	13	0.71 out of 5	N/A	\$0
Distribution Main	11374	P-5093	CRA	Oaklawn Ave.	10	Asbestos Cement	117	51	1.14 out of 5	\$442	51,697
Transmission Main	11578	P-5050	CRA	Oaklawn Ave.	12	Ductile Iron	15	17	0 out of 5	N/A	\$0
Transmission Main	11579	P-5052	CRA	Oaklawn Ave.	12	Ductile Iron	4	17	0 out of 5	N/A	\$0
Transmission Main	5461	P-5177	CRA	Old Spring Rd.	12	Ductile Iron	85	17	0 out of 5	N/A	\$0
Transmission Main	5462	P-5176	CRA	Old Spring Rd.	12	Cast Iron	49	91	1.72 out of 5	\$442	21,452
Transmission Main	7408	P-5178	CRA	Old Spring Rd.	12	Cast Iron	184	91	1.72 out of 5	\$442	81,441
Transmission Main	7409	P-5178	CRA	Old Spring Rd.	12	Cast Iron	30	91	1.72 out of 5	\$442	13,321
Distribution Main	7420	P-5181	CRA	Old Spring Rd.	1.5	Copper	94	UNK	1.99 out of 5	\$442	41,424
Distribution Main	7421	P-5180	CRA	Old Spring Rd.	1.5	Copper	132	UNK	1.99 out of 5	\$442	58,151
Distribution Main	7422	P-5179	CRA	Old Spring Rd.	1.5	Copper	144	UNK	1.99 out of 5	\$442	63,632
Transmission Main	7423	P-5046	CRA	Old Spring Rd.	12	Cast Iron	574	91	1.72 out of 5	\$442	253,670
Transmission Main	7425	P-5048	CRA	Old Spring Rd.	12	Cast Iron	501	91	1.72 out of 5	\$442	221,447
Distribution Main	7391	P-5010	CRA	Olive St.	8	Ductile Iron	6	15	0 out of 5	N/A	\$0
Distribution Main	7392	P-5150	CRA	Olive St.	8	Ductile Iron	6	15	0 out of 5	N/A	\$0
Distribution Main	8032	P-5150	CRA	Olive St.	8	Ductile Iron	232	15	0 out of 5	N/A	\$0
Distribution Main	8695	P-5010	CRA	Olive St.	8	Ductile Iron	55	15	0 out of 5	N/A	\$0
Distribution Main	8696	P-5010	CRA	Olive St.	8	Ductile Iron	174	15	0 out of 5	N/A	\$0
Distribution Main	4940	P-5067	CRA	Ontario Ave.	6	Asbestos Cement	234	60	1.85 out of 5	\$442	103,380
Distribution Main	7371	P-5082	CRA	Ontario Ave.	6	Asbestos Cement	329	49	1.85 out of 5	\$442	145,563
Distribution Main	7397	P-5159	CRA	Oriole Ave.	8	Ductile Iron	13	15	0 out of 5	N/A	\$0
Distribution Main	7398	P-5004	CRA	Oriole Ave.	8	Ductile Iron	13	15	0 out of 5	N/A	\$0
Distribution Main	7399	P-5004	CRA	Oriole Ave.	8	Ductile Iron	214	15	0 out of 5	N/A	\$0
Distribution Main	7402	P-5002	CRA	Oriole Ave.	8	Ductile Iron	236	15	0 out of 5	N/A	\$0
Distribution Main	7403	P-5004	CRA	Oriole Ave.	8	Ductile Iron	3	15	0 out of 5	N/A	\$0
Distribution Main	7404	P-5002	CRA	Oriole Ave.	8	Ductile Iron	3	15	0 out of 5	N/A	\$0
Distribution Main	7469	P-5001	CRA	Oriole Ave.	8	Ductile Iron	253	15	0 out of 5	N/A	\$0
Distribution Main	8704	P-5159	CRA	Oriole Ave.	6	Ductile Iron	3	15	0.71 out of 5	N/A	\$0
Distribution Main	490	P-8853	CRA	Paulette Dr.	8	Ductile Iron	36	15	0 out of 5	N/A	\$0
Distribution Main	7375	P-5084	CRA	Rainbow Rd.	6	Asbestos Cement	193	49	1.85 out of 5	\$442	85,331
Distribution Main	3062	P-7351	CRA	Red Barn Ct.	8	Ductile Iron	454	24	0.14 out of 5	N/A	\$0
Distribution Main	3066	P-7352	CRA	Red Barn Ct.	8	Ductile Iron	126	24	0.14 out of 5	N/A	\$0
Distribution Main	4168	P-5116	CRA	Red Barn Ct.	8	Asbestos Cement	170	42	1.14 out of 5	\$442	74,956
Distribution Main	5298	P-5114	CRA	Red Barn Ct.	8	Asbestos Cement	309	42	1.14 out of 5	\$442	136,537
Distribution Main	8868	P-5172	CRA	Redfern Dr	8	Ductile Iron	224	9	0 out of 5	N/A	\$0
Distribution Main	10132	P-5172	CRA	Roberts Ave	8	Ductile Iron	38	6	0 out of 5	N/A	\$0
Distribution Main	7407	P-5016	CRA	Searle Ave.	8	Ductile Iron	34	15	0 out of 5	N/A	\$0
Distribution Main	7416	P-5160	CRA	Searle Ave.	8	Ductile Iron	83	15	0 out of 5	N/A	\$0
Distribution Main	7417	P-5160	CRA	Searle Ave.	8	Ductile Iron	193	15	0 out of 5	N/A	\$0
Distribution Main	7467	P-5016	CRA	Searle Ave.	8	Ductile Iron	235	15	0 out of 5	N/A	\$0
Distribution Main	8034	P-5151	CRA	Searle Ave.	8	Ductile Iron	266	15	0 out of 5	N/A	\$0
Distribution Main	8691	P-5018	CRA	Searle Ave.	8	Ductile Iron	26	15	0 out of 5	N/A	\$0
Distribution Main	8692	P-5018	CRA	Searle Ave.	8	Ductile Iron	285	15	0 out of 5	N/A	\$0
Distribution Main	8693	P-5151	CRA	Searle Ave.	8	Ductile Iron	33	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	8694	P-5151	CRA	Searle Ave.	8	Ductile Iron	35	15	0 out of 5	N/A	\$0
Distribution Main	11493	P-5151	CRA	Searle Ave.	8	Ductile Iron	3	15	0 out of 5	N/A	\$0
Transmission Main	8597	P-5120	CRA	Seven Mile Rd	16	Ductile Iron	940	20	0 out of 5	N/A	\$0
Transmission Main	8598	P-5120	CRA	Seven Mile Rd	16	Ductile Iron	807	20	0 out of 5	N/A	\$0
Transmission Main	8600	P-5120	CRA	Seven Mile Rd	12	Ductile Iron	9	20	0 out of 5	N/A	\$0
Transmission Main	8595	P-5197	CRA	Seven Mile Rd.	16	Ductile Iron	372	20	0 out of 5	N/A	\$0
Transmission Main	8596	P-5197	CRA	Seven Mile Rd.	16	Ductile Iron	1,077	20	0 out of 5	N/A	\$0
Transmission Main	9912	P-5198	CRA	Seven Mile Rd.	16	Ductile Iron	9	20	0 out of 5	N/A	\$0
Transmission Main	11901	P-5197	CRA	Seven Mile Rd.	16	Ductile Iron	790	20	0 out of 5	N/A	\$0
Distribution Main	8902	P-5166	CRA	Stoneham	6	Ductile Iron	13	9	0.71 out of 5	N/A	\$0
Distribution Main	8900	P-5167	CRA	Stoneham Ct.	6	Asbestos Cement	67	UNK	1.56 out of 5	\$442	29,756
Distribution Main	8901	P-5166	CRA	Stoneham Ct.	8	Ductile Iron	22	9	0 out of 5	N/A	\$0
Distribution Main	8896	P-5023	CRA	Stoneham St	8	Ductile Iron	290	9	0 out of 5	N/A	\$0
Distribution Main	8897	P-5023	CRA	Stoneham St	8	Ductile Iron	293	9	0 out of 5	N/A	\$0
Distribution Main	5998	P-5087	CRA	Sunkist Cir.	8	Asbestos Cement	124	47	1.14 out of 5	\$442	54,875
Distribution Main	5995	P-5086	CRA	Sunrise Road	8	Asbestos Cement	276	47	1.14 out of 5	\$442	122,046
Distribution Main	5996	P-5088	CRA	Sunrise Road	8	Asbestos Cement	335	47	1.14 out of 5	\$442	148,143
Distribution Main	7389	P-5000	CRA	Turner Ave.	8	Ductile Iron	510	15	0 out of 5	N/A	\$0
Distribution Main	7390	P-5000	CRA	Turner Ave.	8	Ductile Iron	36	15	0 out of 5	N/A	\$0
Distribution Main	7393	P-5014	CRA	Turner Ave.	8	Ductile Iron	6	15	0 out of 5	N/A	\$0
Distribution Main	7394	P-5014	CRA	Turner Ave.	8	Ductile Iron	455	15	0 out of 5	N/A	\$0
Distribution Main	7395	P-5014	CRA	Turner Ave.	8	Ductile Iron	38	15	0 out of 5	N/A	\$0
Distribution Main	7405	P-5012	CRA	Turner Ave.	8	Ductile Iron	367	15	0 out of 5	N/A	\$0
Distribution Main	7406	P-5012	CRA	Turner Ave.	8	Ductile Iron	68	15	0 out of 5	N/A	\$0
Distribution Main	7432	P-5011	CRA	Turner Ave.	8	Ductile Iron	7	15	0 out of 5	N/A	\$0
Distribution Main	7433	P-5002	CRA	Turner Ave.	8	Ductile Iron	15	15	0 out of 5	N/A	\$0
Distribution Main	8698	P-5011	CRA	Turner Ave.	8	Ductile Iron	69	15	0 out of 5	N/A	\$0
Distribution Main	8699	P-5011	CRA	Turner Ave.	8	Ductile Iron	346	15	0 out of 5	N/A	\$0
Distribution Main	11375	P-5014	CRA	Turner Ave.	8	Ductile Iron	27	15	0 out of 5	N/A	\$0
Distribution Main	3091	P-5107	CRA	Verdant Dr.	8	Asbestos Cement	39	43	1.14 out of 5	\$442	17,108
Distribution Main	4937	P-5108	CRA	Verdant Dr.	8	Asbestos Cement	336	43	1.14 out of 5	\$442	148,683
Distribution Main	4938	P-5108	CRA	Verdant Dr.	8	Asbestos Cement	206	43	1.14 out of 5	\$442	91,222
Distribution Main	4950	P-5107	CRA	Verdant Dr.	8	Asbestos Cement	202	43	1.14 out of 5	\$442	89,214
Distribution Main	5294	P-5108	CRA	Verdant Dr.	8	Asbestos Cement	34	43	1.14 out of 5	\$442	15,055
Distribution Main	6550	P-5108	CRA	Verdant Dr.	8	Asbestos Cement	13	43	1.14 out of 5	\$442	5,773
Distribution Main	7484	P-5106	CRA	Verdant Dr.	8	Asbestos Cement	213	43	1.14 out of 5	\$442	94,187
Distribution Main	7485	P-5106	CRA	Verdant Dr.	8	Asbestos Cement	148	43	1.14 out of 5	\$442	65,439
Distribution Main	10987	P-5106	CRA	Verdant Dr.	8	Asbestos Cement	5	43	1.14 out of 5	\$442	2,241
Distribution Main	6539	P-5069	CRA	Versailles St.	6	Asbestos Cement	522	50	1.85 out of 5	\$442	230,631
Distribution Main	6551	P-5070	CRA	Versailles St.	6	Asbestos Cement	154	50	1.85 out of 5	\$442	68,012
Distribution Main	6552	P-5070	CRA	Versailles St.	6	Asbestos Cement	320	50	1.85 out of 5	\$442	141,371
Distribution Main	7492	P-5068	CRA	Versailles St.	6	Asbestos Cement	274	50	1.85 out of 5	\$442	120,903
Distribution Main	7493	P-5071	CRA	Versailles St.	6	Asbestos Cement	22	50	1.85 out of 5	\$442	9,752
Distribution Main	5381	P-5149	CRA	Vinton Ave.	8	Ductile Iron	3	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7386	P-5013	CRA	Vinton Ave.	8	Ductile Iron	590	15	0 out of 5	N/A	\$0
Distribution Main	7387	P-5013	CRA	Vinton Ave.	8	Ductile Iron	102	15	0 out of 5	N/A	\$0
Distribution Main	7400	P-5148	CRA	Vinton Ave.	8	Ductile Iron	352	15	0 out of 5	N/A	\$0
Distribution Main	8003	P-5149	CRA	Vinton Ave.	8	Ductile Iron	57	15	0 out of 5	N/A	\$0
Distribution Main	8004	P-5149	CRA	Vinton Ave.	8	Ductile Iron	393	15	0 out of 5	N/A	\$0
Distribution Main	8033	P-5148	CRA	Vinton Ave.	8	Ductile Iron	3	15	0 out of 5	N/A	\$0
Distribution Main	8690	P-5013	CRA	Vinton Ave.	8	Ductile Iron	8	15	0 out of 5	N/A	\$0
Distribution Main	8697	P-5148	CRA	Vinton Ave.	8	Ductile Iron	91	15	0 out of 5	N/A	\$0
Distribution Main	4943	P-5065	CRA	Warfield Ave.	6	Asbestos Cement	98	66	2 out of 5	\$442	43,478
Distribution Main	6553	P-5063	CRA	Warfield Ave.	6	Cast Iron	155	83	2.43 out of 5	\$442	68,408
Distribution Main	6554	P-5063	CRA	Warfield Ave.	6	Cast Iron	58	83	2.43 out of 5	\$442	25,683
Distribution Main	7489	P-5064	CRA	Warfield Ave.	6	Asbestos Cement	197	66	2 out of 5	\$442	87,191
Distribution Main	8883	P-5035	CRA	Warren Ave	8	Ductile Iron	226	9	0 out of 5	N/A	\$0
Distribution Main	8890	P-5028	CRA	Warren Ave	8	Ductile Iron	89	9	0 out of 5	N/A	\$0
Distribution Main	8895	P-5025	CRA	Warren Ave	8	Ductile Iron	337	9	0 out of 5	N/A	\$0
Distribution Main	9386	P-5037	CRA	Warren Ave	8	Ductile Iron	215	9	0 out of 5	N/A	\$0
Distribution Main	9387	P-5037	CRA	Warren Ave	8	Ductile Iron	557	9	0 out of 5	N/A	\$0
Distribution Main	9388	P-5170	CRA	Warren Ave	8	Ductile Iron	61	9	0 out of 5	N/A	\$0
Distribution Main	10821	P-5164	CRA	Warren Ave	8	Ductile Iron	247	9	0 out of 5	N/A	\$0
Distribution Main	10822	P-5028	CRA	Warren Ave	8	Ductile Iron	178	9	0 out of 5	N/A	\$0
Distribution Main	10823	P-5141	CRA	Warren Ave	8	Ductile Iron	78	9	0 out of 5	N/A	\$0
Distribution Main	10824	P-5170	CRA	Warren Ave	8	Ductile Iron	154	9	0 out of 5	N/A	\$0
Distribution Main	10825	P-5037	CRA	Warren Ave	8	Ductile Iron	50	9	0 out of 5	N/A	\$0
Distribution Main	11523	P-5165	CRA	Warren Ave	8	Ductile Iron	16	9	0 out of 5	N/A	\$0
Distribution Main	8894	P-5024	CRA	Warren Ave.	8	Ductile Iron	41	17	0 out of 5	N/A	\$0
Distribution Main	5634	P-5171	CRA	Warren Ct.	6	Unknown	136	UNK	0.71 out of 5	\$442	59,931
Distribution Main	8888	P-5171	CRA	Warren Ct.	6	Ductile Iron	15	9	0.71 out of 5	N/A	\$0
Distribution Main	8889	P-5171	CRA	Warren Ct.	8	Ductile Iron	12	9	0 out of 5	N/A	\$0
Distribution Main	5363	P-5053	CRA	Westbrook Rd.	8	Ductile Iron	35	15	0 out of 5	N/A	\$0
Distribution Main	5364	P-5053	CRA	Westbrook Rd.	8	Ductile Iron	293	15	0 out of 5	N/A	\$0
Distribution Main	9038	P-5053	CRA	Westbrook Rd.	8	Ductile Iron	33	15	0 out of 5	N/A	\$0
Distribution Main	2221	P-5152	CRA	Wheelock Ave.	8	Ductile Iron	486	15	0 out of 5	N/A	\$0
Transmission Main	8677	P-5161	CRA	Wilbur Ave.	12	Ductile Iron	237	17	0 out of 5	N/A	\$0
Transmission Main	8678	P-5161	CRA	Wilbur Ave.	12	Ductile Iron	12	17	0 out of 5	N/A	\$0
Distribution Main	8679	P-5152	CRA	Wilbur Ave.	8	Ductile Iron	31	15	0 out of 5	N/A	\$0
Transmission Main	8680	P-5021	CRA	Wilbur Ave.	12	Ductile Iron	8	17	0 out of 5	N/A	\$0
Transmission Main	8681	P-5021	CRA	Wilbur Ave.	12	Ductile Iron	220	17	0 out of 5	N/A	\$0
Transmission Main	8683	P-5020	CRA	Wilbur Ave.	12	Ductile Iron	491	17	0 out of 5	N/A	\$0
Transmission Main	8684	P-5043	CRA	Wilbur Ave.	12	Ductile Iron	112	17	0 out of 5	N/A	\$0
Transmission Main	8685	P-5043	CRA	Wilbur Ave.	12	Ductile Iron	6	17	0 out of 5	N/A	\$0
Transmission Main	8686	P-5043	CRA	Wilbur Ave.	12	Ductile Iron	92	17	0 out of 5	N/A	\$0
Transmission Main	8687	P-5043	CRA	Wilbur Ave.	12	Ductile Iron	111	17	0 out of 5	N/A	\$0
Transmission Main	11492	P-5043	CRA	Wilbur Ave.	12	Ductile Iron	43	17	0 out of 5	N/A	\$0
Distribution Main	5361	P-5051	CRA	Willow Rd.	8	Ductile Iron	235	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9039	P-5051	CRA	Willow Rd.	8	Ductile Iron	9	15	0 out of 5	N/A	\$0
Distribution Main	4941	P-5066	CRA	Woodlawn Dr.	6	Asbestos Cement	381	65	2 out of 5	\$442	168,490
Distribution Main	4942	P-5066	CRA	Woodlawn Dr.	6	Asbestos Cement	433	65	2 out of 5	\$442	191,485
Distribution Main	7490	P-5073	CRA	Woodlawn Dr.	6	Asbestos Cement	274	65	2 out of 5	\$442	121,100
Distribution Main	7491	P-5073	CRA	Woodlawn Dr.	6	Asbestos Cement	233	65	2 out of 5	\$442	102,788
Distribution Main	5504	P-4103	EG	Adirondack Dr	8	Asbestos Cement	50	43	1.14 out of 5	\$442	22,049
Distribution Main	5505	P-4103	EG	Adirondack Dr	8	Asbestos Cement	488	43	1.14 out of 5	\$442	215,805
Distribution Main	5519	P-4090	EG	Adirondack Dr	8	Ductile Iron	55	38	0.14 out of 5	\$442	24,377
Distribution Main	5520	P-4090	EG	Adirondack Dr	8	Ductile Iron	227	38	0.14 out of 5	\$442	100,419
Distribution Main	5522	P-4095	EG	Adirondack Dr	8	Ductile Iron	521	38	0.14 out of 5	\$442	230,151
Distribution Main	5523	P-4095	EG	Adirondack Dr	8	Ductile Iron	45	38	0.14 out of 5	\$442	19,864
Distribution Main	5526	P-4094	EG	Adirondack Dr	8	Ductile Iron	436	38	0.14 out of 5	\$442	192,496
Distribution Main	5533	P-4101	EG	Adirondack Dr	8	Asbestos Cement	118	43	1.14 out of 5	\$442	51,997
Distribution Main	5534	P-4101	EG	Adirondack Dr	8	Asbestos Cement	304	43	1.14 out of 5	\$442	134,360
Distribution Main	5654	P-4097	EG	Adirondack Dr	8	Ductile Iron	691	38	0.14 out of 5	\$442	305,590
Distribution Main	5659	P-4094	EG	Adirondack Dr	8	Ductile Iron	15	38	0.14 out of 5	\$442	6,412
Distribution Main	5876	P-4102	EG	Adirondack Dr	8	Asbestos Cement	11	43	1.14 out of 5	\$442	4,855
Distribution Main	5877	P-4102	EG	Adirondack Dr	8	Asbestos Cement	696	43	1.14 out of 5	\$442	307,582
Distribution Main	5878	P-4101	EG	Adirondack Dr	8	Asbestos Cement	14	43	1.14 out of 5	\$442	6,223
Distribution Main	6696	P-4103	EG	Adirondack Dr	8	Asbestos Cement	4	43	1.14 out of 5	\$442	1,588
Distribution Main	9320	P-4102	EG	Adirondack Dr	8	Asbestos Cement	13	43	1.14 out of 5	\$442	5,892
Distribution Main	9321	P-4101	EG	Adirondack Dr	8	Asbestos Cement	13	43	1.14 out of 5	\$442	5,619
Distribution Main	9322	P-4097	EG	Adirondack Dr	8	Ductile Iron	6	38	0.14 out of 5	\$442	2,561
Distribution Main	9323	P-4097	EG	Adirondack Dr	8	Ductile Iron	4	38	0.14 out of 5	\$442	1,574
Distribution Main	11309	P-4094	EG	Adirondack Dr	8	Ductile Iron	4	38	0.14 out of 5	\$442	1,631
Distribution Main	11833	P-4095	EG	Adirondack Dr	8	Ductile Iron	447	38	0.14 out of 5	\$442	197,355
Distribution Main	11839	P-4095	EG	Adirondack Dr	8	Ductile Iron	447	38	0.14 out of 5	\$442	197,656
Distribution Main	5624	P-4448	EG	Alder Ct	6	Asbestos Cement	215	48	1.85 out of 5	\$442	95,143
Distribution Main	4034	P-4358	EG	Allen Dr	6	Asbestos Cement	409	51	1.85 out of 5	\$442	180,895
Distribution Main	4990	P-4358	EG	Allen Dr	6	Asbestos Cement	28	51	1.85 out of 5	\$442	12,515
Distribution Main	5589	P-4380	EG	Allen Dr	8	Asbestos Cement	392	51	1.14 out of 5	\$442	173,147
Distribution Main	6395	P-4379	EG	Allen Dr	6	Asbestos Cement	465	51	1.85 out of 5	\$442	205,342
Distribution Main	6404	P-4374	EG	Allen Dr	6	Asbestos Cement	198	51	1.85 out of 5	\$442	87,561
Distribution Main	6405	P-4374	EG	Allen Dr	6	Asbestos Cement	33	51	1.85 out of 5	\$442	14,515
Distribution Main	10373	P-4380	EG	Allen Dr	8	Ductile Iron	19	51	0.29 out of 5	\$442	8,608
Distribution Main	6056	P-4480	EG	Apple Tree Ct.	6	Asbestos Cement	341	48	2.57 out of 5	\$442	150,794
Distribution Main	5392	P-4051	EG	Arbor Way	8	Asbestos Cement	596	49	1.14 out of 5	\$442	263,583
Distribution Main	4373	P-4715	EG	Arrowhead Trail	8	Asbestos Cement	69	46	1.14 out of 5	\$442	30,499
Distribution Main	4374		EG	Arrowhead Trail	8	Ductile Iron	68	22	0.14 out of 5	N/A	\$0
Distribution Main	4375	P-4714	EG	Arrowhead Trail	8	Asbestos Cement	1,000	46	1.14 out of 5	\$442	441,968
Distribution Main	4376	P-4714	EG	Arrowhead Trail	8	Asbestos Cement	78	46	1.14 out of 5	\$442	34,338
Distribution Main	11253	P-4714	EG	Arrowhead Trail	8	Asbestos Cement	11	46	1.14 out of 5	\$442	4,694
Distribution Main	3662	P-4704	EG	Ashbrook Run	8	Ductile Iron	434	30	0.14 out of 5	\$442	191,823
Distribution Main	3663	P-4704	EG	Ashbrook Run	8	Ductile Iron	94	30	0.14 out of 5	\$442	41,337

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5594	P-4369	EG	Atherton Rd.	8	Ductile Iron	19	62	0.43 out of 5	\$442	8,478
Distribution Main	6391	P-4369	EG	Atherton Rd.	6	Asbestos Cement	9	62	2 out of 5	\$442	3,773
Distribution Main	6392	P-4369	EG	Atherton Rd.	6	Asbestos Cement	824	62	2 out of 5	\$442	364,322
Distribution Main	11814	P-4369	EG	Atherton Rd.	6	Asbestos Cement	115	62	2.71 out of 5	\$442	50,944
Distribution Main	9229	P-4196	EG	Ayrault Rd	8	Ductile Iron	364	8	0 out of 5	N/A	\$0
Distribution Main	10966	P-4193	EG	Ayrault Rd	8	Ductile Iron	317	8	0 out of 5	N/A	\$0
Distribution Main	6197	P-4445	EG	Balsam Dr.	6	Asbestos Cement	571	50	1.85 out of 5	\$442	252,586
Distribution Main	6198	P-4445	EG	Balsam Dr.	6	Asbestos Cement	598	50	1.85 out of 5	\$442	264,249
Distribution Main	6570	P-4446	EG	Balsam Dr.	6	Asbestos Cement	224	50	1.85 out of 5	\$442	98,988
Distribution Main	5622	P-4979	EG	Barrows Dr.	6	Unknown	75	58	1 out of 5	\$442	33,256
Distribution Main	6193	P-4451	EG	Barrows Dr.	6	Asbestos Cement	61	58	1.85 out of 5	\$442	26,932
Distribution Main	6194	P-4451	EG	Barrows Dr.	6	Asbestos Cement	616	58	1.85 out of 5	\$442	272,287
Distribution Main	6195	P-4979	EG	Barrows Dr.	6	Unknown	4	58	1 out of 5	\$442	1,771
Transmission Main	5782	P-4132	EG	Bassett Circle	20	Ductile Iron	299	36	0.14 out of 5	\$442	132,138
Transmission Main	6004	P-4132	EG	Bassett Circle	20	Ductile Iron	22	36	0.14 out of 5	\$442	9,539
Transmission Main	6005	P-4132	EG	Bassett Circle	20	Ductile Iron	470	36	0.14 out of 5	\$442	207,554
Transmission Main	10440	P-4132	EG	Bassett Circle	20	Ductile Iron	259	36	0.14 out of 5	\$442	114,299
Transmission Main	10441	P-4132	EG	Bassett Circle	20	Ductile Iron	182	36	0.14 out of 5	\$442	80,303
Distribution Main	2476	P-4427	EG	Bayberry Lane	6	Asbestos Cement	1,159	50	1.85 out of 5	\$442	512,494
Distribution Main	5279	P-4004	EG	Bear Swamp Rd.	8	Asbestos Cement	478	41	1.14 out of 5	\$442	211,057
Distribution Main	5280	P-4004	EG	Bear Swamp Rd.	8	Asbestos Cement	216	41	1.14 out of 5	\$442	95,606
Distribution Main	6367	P-4004	EG	Bear Swamp Rd.	8	Asbestos Cement	6	41	1.14 out of 5	\$442	2,845
Distribution Main	8312	P-4815	EG	Beechcrest Rd	8	Ductile Iron	51	14	0 out of 5	N/A	\$0
Distribution Main	8313	P-4815	EG	Beechcrest Rd	8	Ductile Iron	747	14	0 out of 5	N/A	\$0
Distribution Main	11459	P-4815	EG	Beechcrest Rd	8	Ductile Iron	116	14	0 out of 5	N/A	\$0
Transmission Main	9165	P-4621	EG	Bicknell Ave	12	Ductile Iron	190	8	0 out of 5	N/A	\$0
Transmission Main	9166	P-4621	EG	Bicknell Ave	12	Ductile Iron	128	8	0 out of 5	N/A	\$0
Transmission Main	9167	P-4621	EG	Bicknell Ave	12	Ductile Iron	24	8	0 out of 5	N/A	\$0
Distribution Main	6064	P-4418	EG	Birchwood Way	6	Asbestos Cement	350	50	1.85 out of 5	\$442	154,541
Distribution Main	6065	P-4418	EG	Birchwood Way	6	Asbestos Cement	18	50	1.85 out of 5	\$442	7,982
Distribution Main	6487	P-4423	EG	Birchwood Way	6	Asbestos Cement	289	50	1.85 out of 5	\$442	127,946
Distribution Main	6500	P-4424	EG	Birchwood Way	6	Asbestos Cement	43	50	1.85 out of 5	\$442	19,119
Distribution Main	6501	P-4424	EG	Birchwood Way	6	Asbestos Cement	211	50	1.85 out of 5	\$442	93,316
Distribution Main	4026	P-4450	EG	Blueberry Dr	6	Asbestos Cement	1,056	58	1.85 out of 5	\$442	466,745
Distribution Main	5959	P-4452	EG	Blueberry Dr	6	Asbestos Cement	545	58	1.85 out of 5	\$442	240,761
Distribution Main	9474	P-40035	EG	Bond St	0.75	Copper	312	UNK	1.99 out of 5	\$442	137,749
Transmission Main	967	P-4992	EG	Boulder Way	20	Ductile Iron	13	36	0.14 out of 5	\$442	5,553
Transmission Main	2025	P-4879	EG	Boulder Way	20	Ductile Iron	728	36	0.14 out of 5	\$442	321,933
Transmission Main	2026	P-4879	EG	Boulder Way	20	Ductile Iron	15	36	0.14 out of 5	\$442	6,731
Transmission Main	2028	P-4992	EG	Boulder Way	20	Ductile Iron	904	36	0.14 out of 5	\$442	399,379
Transmission Main	2029	P-4992	EG	Boulder Way	20	Ductile Iron	519	36	0.14 out of 5	\$442	229,445
Distribution Main	6793	P-4330	EG	Bow St.	8	Asbestos Cement	346	50	1.14 out of 5	\$442	152,757
Distribution Main	6794	P-4330	EG	Bow St.	8	Asbestos Cement	64	50	1.14 out of 5	\$442	28,478
Distribution Main	6809	P-4329	EG	Bow St.	8	Asbestos Cement	1,060	50	1.14 out of 5	\$442	468,443

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	12186		EG	Bow St.	8	Asbestos Cement	741	50	1.14 out of 5	\$442	327,477
Distribution Main	12187		EG	Bow St.	8	Asbestos Cement	190	50	1.14 out of 5	\$442	83,902
Distribution Main	6800	P-4301	EG	Boxwood Dr.	6	Asbestos Cement	471	51	1.85 out of 5	\$442	208,268
Distribution Main	6801	P-4301	EG	Boxwood Dr.	6	Asbestos Cement	516	51	1.85 out of 5	\$442	227,908
Distribution Main	4511	P-4568	EG	Brayton St.	8	Ductile Iron	333	17	0 out of 5	N/A	\$0
Distribution Main	4512	P-4568	EG	Brayton St.	8	Ductile Iron	391	17	0 out of 5	N/A	\$0
Distribution Main	6271	P-4568	EG	Brayton St.	8	Ductile Iron	145	17	0 out of 5	N/A	\$0
Distribution Main	3321	P-4597	EG	Bridge St.	8	Ductile Iron	12	17	0 out of 5	N/A	\$0
Distribution Main	3322	P-4597	EG	Bridge St.	8	Ductile Iron	187	17	0 out of 5	N/A	\$0
Distribution Main	4259	P-4693	EG	Bridge St.	8	Ductile Iron	237	17	0 out of 5	N/A	\$0
Distribution Main	361	P-4519	EG	Brisas Cir.	8	Asbestos Cement	190	52	1.14 out of 5	\$442	83,793
Distribution Main	362	P-4520	EG	Brisas Cir.	8	Asbestos Cement	717	52	1.14 out of 5	\$442	316,880
Distribution Main	363	P-4520	EG	Brisas Cir.	8	Asbestos Cement	69	52	1.14 out of 5	\$442	30,498
Distribution Main	3218	P-4517	EG	Brisas Cir.	8	Asbestos Cement	18	52	1.14 out of 5	\$442	7,789
Distribution Main	4176	P-4518	EG	Brisas Cir.	8	Asbestos Cement	270	52	1.14 out of 5	\$442	119,432
Distribution Main	4177	P-4518	EG	Brisas Cir.	8	Asbestos Cement	443	52	1.14 out of 5	\$442	195,827
Distribution Main	6346	P-4517	EG	Brisas Cir.	8	Asbestos Cement	334	52	1.14 out of 5	\$442	147,537
Distribution Main	5895	P-4151	EG	Brookfield Dr.	8	Ductile Iron	57	25	0.14 out of 5	N/A	\$0
Distribution Main	5896	P-4151	EG	Brookfield Dr.	8	Ductile Iron	616	25	0.14 out of 5	N/A	\$0
Distribution Main	189	P-4508	EG	Brookside Dr.	6	Asbestos Cement	720	69	2 out of 5	\$442	318,439
Distribution Main	375	P-4509	EG	Brookside Dr.	6	Asbestos Cement	243	69	2 out of 5	\$442	107,420
Distribution Main	6149	P-4349	EG	Bunker Hill Ln.	8	Asbestos Cement	588	55	1.14 out of 5	\$442	259,948
Distribution Main	9240	P-4203	EG	Canonchet Tr	8	Ductile Iron	316	8	0 out of 5	N/A	\$0
Distribution Main	9237	P-4201	EG	Canonicus Tr	8	Ductile Iron	3	20	0 out of 5	N/A	\$0
Distribution Main	9239	P-4201	EG	Canonicus Tr	8	Ductile Iron	13	20	0 out of 5	N/A	\$0
Distribution Main	9243	P-4205	EG	Canonicus Tr	8	Ductile Iron	413	8	0 out of 5	N/A	\$0
Distribution Main	9247	P-4205	EG	Canonicus Tr	8	Ductile Iron	53	8	0 out of 5	N/A	\$0
Distribution Main	6386	P-4201	EG	Canonicus Tr.	8	Ductile Iron	491	20	0 out of 5	N/A	\$0
Distribution Main	6591	P-4059	EG	Cardinal Lane Easement	8	Asbestos Cement	20	42	1.14 out of 5	\$442	8,711
Distribution Main	10346	P-4059	EG	Cardinal Lane Easement	8	Asbestos Cement	11	42	1.14 out of 5	\$442	4,937
Distribution Main	11653	P-4068	EG	Cardinal Lane Easement	8	Asbestos Cement	6	42	1.14 out of 5	\$442	2,798
Distribution Main	4360	P-4068	EG	Cardinal Ln.	8	Asbestos Cement	31	47	1.14 out of 5	\$442	13,487
Distribution Main	5796	P-4049	EG	Cardinal Ln.	8	Asbestos Cement	742	47	1.14 out of 5	\$442	327,758
Distribution Main	6778	P-4047	EG	Cardinal Ln.	8	Asbestos Cement	30	47	1.14 out of 5	\$442	13,427
Distribution Main	6779	P-4047	EG	Cardinal Ln.	8	Asbestos Cement	357	47	1.14 out of 5	\$442	157,857
Distribution Main	9439	P-4068	EG	Cardinal Ln.	8	Asbestos Cement	73	47	1.14 out of 5	\$442	32,487
Distribution Main	5655	P-4096	EG	Cartier Ct.	6	Ductile Iron	366	33	0.85 out of 5	\$442	161,907
Distribution Main	5656	P-4096	EG	Cartier Ct.	6	Ductile Iron	94	33	0.85 out of 5	\$442	41,396
Distribution Main	5406	P-4654	EG	Castle St.	8	Ductile Iron	3	19	0 out of 5	N/A	\$0
Distribution Main	5407	P-4650	EG	Castle St.	8	Ductile Iron	138	19	0 out of 5	N/A	\$0
Distribution Main	5408	P-4650	EG	Castle St.	8	Ductile Iron	106	19	0 out of 5	N/A	\$0
Distribution Main	5419	P-4654	EG	Castle St.	8	Ductile Iron	326	19	0 out of 5	N/A	\$0
Distribution Main	6233	P-4649	EG	Castle St.	8	Ductile Iron	11	19	0 out of 5	N/A	\$0
Distribution Main	6649	P-4650	EG	Castle St.	8	Ductile Iron	3	19	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10361	P-4649	EG	Castle St.	8	Ductile Iron	160	19	0 out of 5	N/A	\$0
Distribution Main	10522	P-4649	EG	Castle St.	8	Ductile Iron	71	19	0 out of 5	N/A	\$0
Distribution Main	5524	P-4091	EG	Cavalier Dr.	8	Ductile Iron	350	38	0.14 out of 5	\$442	154,695
Distribution Main	5525	P-4091	EG	Cavalier Dr.	8	Ductile Iron	508	38	0.14 out of 5	\$442	224,688
Distribution Main	5527	P-4093	EG	Cavalier Dr.	8	Ductile Iron	405	38	0.14 out of 5	\$442	179,142
Distribution Main	5528	P-4093	EG	Cavalier Dr.	8	Ductile Iron	128	38	0.14 out of 5	\$442	56,574
Distribution Main	5529	P-4093	EG	Cavalier Dr.	8	Ductile Iron	508	38	0.14 out of 5	\$442	224,315
Distribution Main	5530	P-4093	EG	Cavalier Dr.	8	Ductile Iron	46	38	0.14 out of 5	\$442	20,508
Distribution Main	5532	P-4093	EG	Cavalier Dr.	8	Ductile Iron	14	38	0.14 out of 5	\$442	6,192
Distribution Main	5657	P-4091	EG	Cavalier Dr.	8	Ductile Iron	14	38	0.14 out of 5	\$442	6,089
Distribution Main	5658	P-4093	EG	Cavalier Dr.	8	Ductile Iron	14	38	0.14 out of 5	\$442	6,272
Distribution Main	116		EG	Cedar Ave		Unknown	70	UNK	0 out of 5	N/A	\$0
Distribution Main	9378	P-40031	EG	Cedar Ave	8	Ductile Iron	13	7	0 out of 5	N/A	\$0
Distribution Main	9379	P-40031	EG	Cedar Ave	8	Ductile Iron	18	7	0 out of 5	N/A	\$0
Distribution Main	117	P-4527	EG	Cedar Ave.	8	Asbestos Cement	79	53	1.14 out of 5	\$442	34,718
Distribution Main	357	P-4696	EG	Cedar Ave.	8	Ductile Iron	260	23	0.14 out of 5	N/A	\$0
Distribution Main	358	P-4437	EG	Cedar Ave.	8	Asbestos Cement	482	53	1.14 out of 5	\$442	213,075
Distribution Main	359	P-40030	EG	Cedar Ave.	8	Asbestos Cement	20	53	1.14 out of 5	\$442	8,800
Distribution Main	373	P-4499	EG	Cedar Ave.	8	Asbestos Cement	37	53	1.14 out of 5	\$442	16,303
Distribution Main	661	P-4524	EG	Cedar Ave.	8	Asbestos Cement	169	53	1.14 out of 5	\$442	74,744
Distribution Main	4023	P-4503	EG	Cedar Ave.	8	Ductile Iron	448	40	0.14 out of 5	\$442	197,923
Distribution Main	4156	P-4499	EG	Cedar Ave.	8	Asbestos Cement	602	53	1.14 out of 5	\$442	266,248
Distribution Main	4157	P-4499	EG	Cedar Ave.	8	Asbestos Cement	5	53	1.14 out of 5	\$442	2,261
Distribution Main	4181	P-4523	EG	Cedar Ave.	8	Ductile Iron	749	40	0.14 out of 5	\$442	331,076
Distribution Main	4186	P-40030	EG	Cedar Ave.	8	Asbestos Cement	1,085	53	1.14 out of 5	\$442	479,533
Distribution Main	5615	P-4503	EG	Cedar Ave.	8	Ductile Iron	22	40	0.14 out of 5	\$442	9,939
Distribution Main	5616	P-4503	EG	Cedar Ave.	8	Ductile Iron	325	40	0.14 out of 5	\$442	143,511
Distribution Main	5617	P-4503	EG	Cedar Ave.	8	Ductile Iron	10	40	0.14 out of 5	\$442	4,305
Distribution Main	6196	P-4523	EG	Cedar Ave.	8	Ductile Iron	811	40	0.14 out of 5	\$442	358,620
Distribution Main	6206	P-4524	EG	Cedar Ave.	8	Asbestos Cement	12	53	1.14 out of 5	\$442	5,493
Distribution Main	6207	P-4524	EG	Cedar Ave.	8	Asbestos Cement	135	53	1.14 out of 5	\$442	59,531
Distribution Main	6564	P-4501	EG	Cedar Ave.	8	Asbestos Cement	237	53	1.14 out of 5	\$442	104,584
Distribution Main	6565	P-4501	EG	Cedar Ave.	8	Asbestos Cement	869	53	1.14 out of 5	\$442	384,212
Distribution Main	6720	P-4523	EG	Cedar Ave.	8	Ductile Iron	27	40	0.14 out of 5	\$442	11,834
Distribution Main	11247	P-40030	EG	Cedar Ave.	8	Asbestos Cement	371	53	1.14 out of 5	\$442	164,183
Distribution Main	3845	P-4270	EG	Chestnut Dr.	8	Asbestos Cement	549	51	1.14 out of 5	\$442	242,844
Distribution Main	4893	P-4271	EG	Chestnut Dr.	8	Asbestos Cement	379	51	1.14 out of 5	\$442	167,510
Distribution Main	4894	P-4258	EG	Chestnut Dr.	8	Asbestos Cement	418	51	1.14 out of 5	\$442	184,854
Distribution Main	4897	P-4261	EG	Chestnut Dr.	8	Asbestos Cement	97	51	1.14 out of 5	\$442	42,889
Distribution Main	4898	P-4261	EG	Chestnut Dr.	8	Asbestos Cement	818	51	1.14 out of 5	\$442	361,384
Distribution Main	5585	P-4261	EG	Chestnut Dr.	8	Asbestos Cement	166	51	1.14 out of 5	\$442	73,390
Distribution Main	5662	P-4041	EG	Chestnut Dr.	8	Asbestos Cement	361	51	1.14 out of 5	\$442	159,459
Distribution Main	5665	P-4055	EG	Chestnut Dr.	8	Asbestos Cement	165	51	1.14 out of 5	\$442	72,866
Distribution Main	6781		EG	Chestnut Dr.	6	Asbestos Cement	473	51	1.85 out of 5	\$442	209,129

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6782		EG	Chestnut Dr.	6	Asbestos Cement	575	51	1.85 out of 5	\$442	254,043
Distribution Main	6788	P-4257	EG	Chestnut Dr.	8	Asbestos Cement	21	51	1.14 out of 5	\$442	9,376
Distribution Main	6789	P-4257	EG	Chestnut Dr.	8	Asbestos Cement	466	51	1.14 out of 5	\$442	205,843
Distribution Main	11273	P-4258	EG	Chestnut Dr.	8	Asbestos Cement	13	51	1.14 out of 5	\$442	5,541
Distribution Main	11825	P-4261	EG	Chestnut Dr.	8	Asbestos Cement	13	51	1.14 out of 5	\$442	5,951
Distribution Main	3830	P-4161	EG	Chief Botelho Dr.	8	Ductile Iron	65	25	0.14 out of 5	N/A	\$0
Distribution Main	3831	P-4161	EG	Chief Botelho Dr.	8	Ductile Iron	313	25	0.14 out of 5	N/A	\$0
Distribution Main	3832	P-4161	EG	Chief Botelho Dr.	8	Ductile Iron	80	25	0.14 out of 5	N/A	\$0
Distribution Main	904	P-4686	EG	Church St.	8	Ductile Iron	23	17	0 out of 5	N/A	\$0
Distribution Main	3856	P-4570	EG	Church St.	8	Ductile Iron	98	17	0 out of 5	N/A	\$0
Distribution Main	3858	P-4965	EG	Church St.	8	Ductile Iron	29	17	0 out of 5	N/A	\$0
Distribution Main	4502	P-4688	EG	Church St.	8	Ductile Iron	304	17	0 out of 5	N/A	\$0
Distribution Main	4503	P-4686	EG	Church St.	8	Ductile Iron	115	17	0 out of 5	N/A	\$0
Distribution Main	4504	P-4686	EG	Church St.	8	Ductile Iron	216	17	0 out of 5	N/A	\$0
Distribution Main	4505	P-4686	EG	Church St.	8	Ductile Iron	415	17	0 out of 5	N/A	\$0
Distribution Main	4513	P-4684	EG	Church St.	8	Ductile Iron	301	17	0 out of 5	N/A	\$0
Distribution Main	6272	P-4969	EG	Church St.	8	Ductile Iron	204	17	0 out of 5	N/A	\$0
Distribution Main	6758	P-4570	EG	Church St.	8	Ductile Iron	23	17	0 out of 5	N/A	\$0
Distribution Main	9014	P-4569	EG	Church St.	8	Ductile Iron	65	17	0 out of 5	N/A	\$0
Distribution Main	9015	P-4570	EG	Church St.	8	Ductile Iron	123	17	0 out of 5	N/A	\$0
Transmission Main	9023	P-4686	EG	Church St.	12	Ductile Iron	3	17	0 out of 5	N/A	\$0
Transmission Main	9024	P-4570	EG	Church St.	12	Ductile Iron	4	17	0 out of 5	N/A	\$0
Distribution Main	455	P-4387	EG	Cindyann Dr.	8	Asbestos Cement	948	56	1.14 out of 5	\$442	418,876
Distribution Main	456	P-4387	EG	Cindyann Dr.	8	Asbestos Cement	50	56	1.14 out of 5	\$442	21,931
Distribution Main	5247	P-4479	EG	Cindyann Dr.	8	Asbestos Cement	155	56	1.14 out of 5	\$442	68,631
Distribution Main	5248	P-4982	EG	Cindyann Dr.	8	Asbestos Cement	47	56	1.14 out of 5	\$442	20,777
Distribution Main	5249	P-4982	EG	Cindyann Dr.	8	Asbestos Cement	636	56	1.14 out of 5	\$442	281,009
Distribution Main	5413	P-4477	EG	Cindyann Dr.	8	Asbestos Cement	322	56	1.14 out of 5	\$442	142,315
Distribution Main	5414	P-4477	EG	Cindyann Dr.	8	Asbestos Cement	524	56	1.14 out of 5	\$442	231,792
Distribution Main	5949	P-4345	EG	Cindyann Dr.	8	Asbestos Cement	44	56	1.14 out of 5	\$442	19,660
Distribution Main	5950	P-4345	EG	Cindyann Dr.	8	Asbestos Cement	469	56	1.14 out of 5	\$442	207,514
Distribution Main	6332	P-4481	EG	Cindyann Dr.	8	Asbestos Cement	257	56	1.14 out of 5	\$442	113,608
Distribution Main	6333	P-4482	EG	Cindyann Dr.	8	Asbestos Cement	394	56	1.14 out of 5	\$442	174,158
Distribution Main	6376	P-4980	EG	Cindyann Dr.	8	Asbestos Cement	202	56	1.14 out of 5	\$442	89,276
Distribution Main	6380	P-4388	EG	Cindyann Dr.	8	Asbestos Cement	830	56	1.14 out of 5	\$442	366,704
Distribution Main	6381	P-4388	EG	Cindyann Dr.	8	Asbestos Cement	961	56	1.14 out of 5	\$442	424,705
Distribution Main	11829	P-4982	EG	Cindyann Dr.	8	Asbestos Cement	31	56	1.14 out of 5	\$442	13,655
Transmission Main	4494	P-4149	EG	Clauson Court	16	Ductile Iron	359	25	0.14 out of 5	N/A	\$0
Transmission Main	5894	P-4149	EG	Clauson Court	16	Ductile Iron	136	25	0.14 out of 5	N/A	\$0
Distribution Main	4200	P-4117	EG	Clemente Dr.	6	Asbestos Cement	10	56	1.85 out of 5	\$442	4,312
Distribution Main	4203	P-4142	EG	Clemente Dr.	6	Asbestos Cement	58	56	1.85 out of 5	\$442	25,696
Distribution Main	4204	P-4142	EG	Clemente Dr.	6	Asbestos Cement	157	56	1.85 out of 5	\$442	69,251
Distribution Main	6136	P-4117	EG	Clemente Dr.	6	Asbestos Cement	482	56	1.85 out of 5	\$442	212,949
Transmission Main	4260	P-4591	EG	Cliff St.	12	Ductile Iron	73	23	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	5401	P-4591	EG	Cliff St.	12	Ductile Iron	382	23	0.14 out of 5	N/A	\$0
Transmission Main	6719	P-4947	EG	Cliff St.	12	Ductile Iron	116	23	0.14 out of 5	N/A	\$0
Transmission Main	10905	P-4947	EG	Cliff St.	12	Ductile Iron	148	23	0.14 out of 5	N/A	\$0
Distribution Main	118	P-4485	EG	Clover Hill Ct.	6	Asbestos Cement	163	43	1.85 out of 5	\$442	72,227
Distribution Main	6495	P-4430	EG	Coddington Ct.	6	Asbestos Cement	173	49	1.85 out of 5	\$442	76,457
Distribution Main	2510	P-4988	EG	Cole Circle	8	Ductile Iron	309	15	0 out of 5	N/A	\$0
Distribution Main	4051	P-4405	EG	Cora St.	8	Ductile Iron	351	20	0 out of 5	N/A	\$0
Distribution Main	4052	P-4405	EG	Cora St.	8	Ductile Iron	735	20	0 out of 5	N/A	\$0
Distribution Main	8603	P-40023	EG	Cora St.	6	Ductile Iron	15	20	0.71 out of 5	N/A	\$0
Distribution Main	8606	P-40025	EG	Cora St.	6	Ductile Iron	17	20	0.71 out of 5	N/A	\$0
Distribution Main	11239	P-4405	EG	Cora St.	8	Ductile Iron	146	20	0 out of 5	N/A	\$0
Distribution Main	6494	P-4433	EG	Country Ct.	6	Asbestos Cement	94	49	1.85 out of 5	\$442	41,468
Distribution Main	6282	P-4804	EG	Court House Ln	6	Ductile Iron	202	24	0.85 out of 5	N/A	\$0
Distribution Main	5005	P-4341	EG	Crest Ridge Dr.	8	Asbestos Cement	522	50	1.14 out of 5	\$442	230,868
Distribution Main	5006	P-4990	EG	Crest Ridge Dr.	8	Asbestos Cement	121	50	1.14 out of 5	\$442	53,367
Distribution Main	5947	P-4340	EG	Crest Ridge Dr.	8	Asbestos Cement	32	50	1.14 out of 5	\$442	14,081
Distribution Main	5948	P-4340	EG	Crest Ridge Dr.	8	Asbestos Cement	834	50	1.85 out of 5	\$442	368,712
Distribution Main	2505	P-4461	EG	Cresthill Dr.	6	Asbestos Cement	345	61	2 out of 5	\$442	152,302
Distribution Main	5620	P-4459	EG	Cresthill Dr.	6	Asbestos Cement	345	61	2 out of 5	\$442	152,316
Distribution Main	5621	P-4459	EG	Cresthill Dr.	6	Asbestos Cement	287	61	2 out of 5	\$442	126,867
Transmission Main	2046		EG	Cricket Cir	12	Unknown	38	17	0 out of 5	N/A	\$0
Distribution Main	9706		EG	Cricket Cir	8	Unknown	35	17	0 out of 5	N/A	\$0
Distribution Main	5463	P-4660	EG	Crompton Ave.	6	Ductile Iron	675	32	0.85 out of 5	\$442	298,251
Distribution Main	5464	P-4660	EG	Crompton Ave.	6	Ductile Iron	280	32	0.85 out of 5	\$442	123,885
Distribution Main	5465	P-4660	EG	Crompton Ave.	6	Ductile Iron	186	32	0.85 out of 5	\$442	82,042
Distribution Main	6733	P-4660	EG	Crompton Ave.	6	Ductile Iron	12	32	0.85 out of 5	\$442	5,487
Distribution Main	9444	P-4660	EG	Crompton Ave.	6	Ductile Iron	198	32	0.85 out of 5	\$442	87,652
Distribution Main	9445	P-4660	EG	Crompton Ave.	6	Ductile Iron	161	32	0.85 out of 5	\$442	70,958
Distribution Main	11817	P-4660	EG	Crompton Ave.	6	Ductile Iron	429	32	0.85 out of 5	\$442	189,796
Transmission Main	262	P-4185	EG	Crompton Rd.	16	Ductile Iron	443	28	0.14 out of 5	\$442	196,025
Transmission Main	263	P-4185	EG	Crompton Rd.	16	Ductile Iron	364	28	0.14 out of 5	\$442	160,754
Transmission Main	264	P-4185	EG	Crompton Rd.	16	Ductile Iron	181	28	0.14 out of 5	\$442	80,150
Transmission Main	265	P-4185	EG	Crompton Rd.	16	Ductile Iron	430	28	0.14 out of 5	\$442	190,131
Transmission Main	275	P-4673	EG	Crompton Rd.	16	Ductile Iron	218	28	0.14 out of 5	\$442	96,324
Transmission Main	1034	P-4185	EG	Crompton Rd.	16	Ductile Iron	478	28	0.14 out of 5	\$442	211,422
Transmission Main	1628	P-4184	EG	Crompton Rd.	16	Ductile Iron	303	28	0.14 out of 5	\$442	133,869
Transmission Main	1629	P-4184	EG	Crompton Rd.	16	Ductile Iron	409	28	0.14 out of 5	\$442	180,825
Transmission Main	11846	P-4185	EG	Crompton Rd.	16	Ductile Iron	251	28	0.14 out of 5	\$442	110,964
Transmission Main	11847	P-4185	EG	Crompton Rd.	16	Ductile Iron	522	28	0.14 out of 5	\$442	230,524
Transmission Main	11848	P-4185	EG	Crompton Rd.	16	Ductile Iron	467	28	0.14 out of 5	\$442	206,373
Transmission Main	9168	P-4619	EG	Crop St	12	Ductile Iron	6	8	0 out of 5	N/A	\$0
Transmission Main	9169	P-4619	EG	Crop St	12	Ductile Iron	297	8	0 out of 5	N/A	\$0
Distribution Main	3656	P-4415	EG	Crossways Rd.	6	Asbestos Cement	147	60	1.85 out of 5	\$442	65,085
Distribution Main	5290	P-4415	EG	Crossways Rd.	6	Asbestos Cement	34	60	1.85 out of 5	\$442	15,056

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6141	P-4700	EG	Crossways Rd.	6	Ductile Iron	191	22	0.85 out of 5	N/A	\$0
Distribution Main	6473	P-4393	EG	Crossways Rd.	6	Ductile Iron	98	30	0.85 out of 5	\$442	43,471
Distribution Main	12174		EG	Crossways Rd.	6	Ductile Iron	66	22	0.85 out of 5	N/A	\$0
Distribution Main	12175		EG	Crossways Rd.	6	Ductile Iron	19	22	0.85 out of 5	N/A	\$0
Distribution Main	6345	P-4122	EG	Crystal Ct.	6	Asbestos Cement	157	44	1.85 out of 5	\$442	69,242
Distribution Main	6022	P-4121	EG	Crystal Dr.	8	Asbestos Cement	953	44	1.14 out of 5	\$442	421,218
Distribution Main	6023	P-4121	EG	Crystal Dr.	8	Asbestos Cement	3	44	1.14 out of 5	\$442	1,444
Distribution Main	6573	P-4123	EG	Crystal Dr.	8	Asbestos Cement	647	44	1.14 out of 5	\$442	285,897
Distribution Main	3929	P-4256	EG	Cypress Court	6	Asbestos Cement	369	51	1.85 out of 5	\$442	163,302
Distribution Main	2506	P-4455	EG	Dalehill Dr.	8	Asbestos Cement	212	59	1.14 out of 5	\$442	93,824
Distribution Main	2507	P-4455	EG	Dalehill Dr.	8	Asbestos Cement	8	59	1.14 out of 5	\$442	3,346
Distribution Main	4027	P-4502	EG	Dalehill Dr.	8	Asbestos Cement	6	59	1.14 out of 5	\$442	2,546
Distribution Main	4996	P-4502	EG	Dalehill Dr.	8	Asbestos Cement	535	59	1.14 out of 5	\$442	236,576
Distribution Main	4997	P-4502	EG	Dalehill Dr.	8	Asbestos Cement	55	59	1.14 out of 5	\$442	24,382
Distribution Main	5619	P-4456	EG	Dalehill Dr.	6	Asbestos Cement	448	59	1.85 out of 5	\$442	198,203
Distribution Main	5957	P-4453	EG	Dalehill Dr.	6	Asbestos Cement	404	59	1.85 out of 5	\$442	178,611
Distribution Main	5960	P-4462	EG	Dalehill Dr.	8	Asbestos Cement	41	59	1.14 out of 5	\$442	17,979
Distribution Main	5961	P-4462	EG	Dalehill Dr.	8	Asbestos Cement	406	59	1.14 out of 5	\$442	179,519
Distribution Main	6578	P-4136	EG	Darl Ct.	8	PVC	362	33	0.43 out of 5	\$442	159,922
Distribution Main	6579	P-4136	EG	Darl Ct.	8	PVC	13	33	0.43 out of 5	\$442	5,605
Distribution Main	6228	P-4607	EG	Dedford St.	6	Asbestos Cement	148	49	1.85 out of 5	\$442	65,625
Distribution Main	6690	P-4607	EG	Dedford St.	6	Asbestos Cement	5	49	1.85 out of 5	\$442	2,284
Distribution Main	3911	P-4476	EG	Deep Meadow Drive	8	Ductile Iron	45	19	0 out of 5	N/A	\$0
Distribution Main	4989	P-4476	EG	Deep Meadow Drive	8	Ductile Iron	54	19	0 out of 5	N/A	\$0
Distribution Main	5236	P-4476	EG	Deep Meadow Drive	8	Ductile Iron	253	19	0 out of 5	N/A	\$0
Distribution Main	10442	P-4476	EG	Deep Meadow Drive	8	Ductile Iron	252	19	0 out of 5	N/A	\$0
Distribution Main	5833	P-4037	EG	Deerfield Dr	8	Asbestos Cement	8	45	1.14 out of 5	\$442	3,710
Distribution Main	6589	P-4037	EG	Deerfield Dr	8	Asbestos Cement	284	45	1.14 out of 5	\$442	125,699
Distribution Main	6590	P-4037	EG	Deerfield Dr	8	Asbestos Cement	234	45	1.14 out of 5	\$442	103,447
Distribution Main	3303	P-4038	EG	Deerfield Dr.	8	Asbestos Cement	67	45	1.14 out of 5	\$442	29,536
Distribution Main	5816	P-4022	EG	Deerfield Dr.	8	PVC	533	32	0.43 out of 5	\$442	235,710
Distribution Main	5820	P-4036	EG	Deerfield Dr.	8	PVC	100	32	0.43 out of 5	\$442	44,043
Distribution Main	5821	P-4033	EG	Deerfield Dr.	8	PVC	534	32	0.43 out of 5	\$442	235,898
Distribution Main	5823	P-4035	EG	Deerfield Dr.	8	PVC	56	32	0.43 out of 5	\$442	24,548
Distribution Main	5824	P-4035	EG	Deerfield Dr.	8	PVC	581	32	0.43 out of 5	\$442	256,878
Distribution Main	6582	P-4022	EG	Deerfield Dr.	8	PVC	61	32	0.43 out of 5	\$442	27,131
Distribution Main	6583	P-4022	EG	Deerfield Dr.	8	PVC	224	32	0.43 out of 5	\$442	98,875
Distribution Main	6588	P-4039	EG	Deerfield Dr.	8	Asbestos Cement	550	45	1.14 out of 5	\$442	243,231
Distribution Main	6713	P-4036	EG	Deerfield Dr.	8	PVC	581	32	0.43 out of 5	\$442	256,590
Distribution Main	6714	P-4036	EG	Deerfield Dr.	8	PVC	23	32	0.43 out of 5	\$442	10,019
Distribution Main	3853	P-4331	EG	Devon Court	6	Asbestos Cement	691	50	1.85 out of 5	\$442	305,216
Distribution Main	3854	P-4331	EG	Devon Court	6	Asbestos Cement	25	50	1.85 out of 5	\$442	11,046
Distribution Main	2047		EG	Division Rd	8	Ductile Iron	55	19	0 out of 5	N/A	\$0
Distribution Main	9003	P-4881	EG	Division Rd	8	Ductile Iron	16	13	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	9091	P-4758	EG	Division Rd	16	Ductile Iron	394	13	0 out of 5	N/A	\$0
Transmission Main	9092	P-4758	EG	Division Rd	16	Ductile Iron	252	13	0 out of 5	N/A	\$0
Transmission Main	9093	P-4849	EG	Division Rd	12	Ductile Iron	32	13	0 out of 5	N/A	\$0
Transmission Main	9094	P-4882	EG	Division Rd	16	Ductile Iron	283	13	0 out of 5	N/A	\$0
Transmission Main	9095	P-4882	EG	Division Rd	16	Ductile Iron	37	13	0 out of 5	N/A	\$0
Distribution Main	9351		EG	Division Rd	6	Ductile Iron	53	8	0.71 out of 5	N/A	\$0
Transmission Main	11539	P-4882	EG	Division Rd	16	Ductile Iron	158	13	0 out of 5	N/A	\$0
Transmission Main	11856	P-4882	EG	Division Rd	16	Ductile Iron	72	13	0 out of 5	N/A	\$0
Transmission Main	12101	P-4758	EG	Division Rd	16	Ductile Iron	322	13	0 out of 5	N/A	\$0
Transmission Main	12102	P-4758	EG	Division Rd	16	Ductile Iron	127	13	0 out of 5	N/A	\$0
Transmission Main	12103	P-4882	EG	Division Rd	16	Ductile Iron	6	13	0 out of 5	N/A	\$0
Transmission Main	33	P-4754	EG	Division Road	16	Ductile Iron	26	24	0.14 out of 5	N/A	\$0
Transmission Main	64		EG	Division Road	16	Ductile Iron	9	24	0.14 out of 5	N/A	\$0
Transmission Main	461	P-4705	EG	Division Road	12	Asbestos Cement	22	48	1.14 out of 5	\$442	9,715
Transmission Main	511	P-4706	EG	Division Road	12	Asbestos Cement	774	48	1.14 out of 5	\$442	342,042
Transmission Main	512	P-4706	EG	Division Road	12	Asbestos Cement	576	48	1.14 out of 5	\$442	254,729
Transmission Main	776	P-4780	EG	Division Road	12	Asbestos Cement	397	48	1.14 out of 5	\$442	175,582
Transmission Main	777	P-4706	EG	Division Road	12	Asbestos Cement	3	48	1.14 out of 5	\$442	1,455
Transmission Main	778	P-4706	EG	Division Road	12	Asbestos Cement	613	48	1.14 out of 5	\$442	271,147
Transmission Main	779	P-4706	EG	Division Road	12	Asbestos Cement	577	48	1.14 out of 5	\$442	254,833
Transmission Main	780	P-4706	EG	Division Road	12	Asbestos Cement	215	48	1.14 out of 5	\$442	95,048
Transmission Main	781	P-4706	EG	Division Road	12	Asbestos Cement	310	48	1.14 out of 5	\$442	137,187
Transmission Main	965	P-4706	EG	Division Road	12	Asbestos Cement	281	48	1.14 out of 5	\$442	124,140
Transmission Main	975	P-4180	EG	Division Road	12	Asbestos Cement	16	62	1.29 out of 5	\$442	7,268
Transmission Main	976		EG	Division Road	12	Asbestos Cement	46	62	1.29 out of 5	\$442	20,197
Transmission Main	977	P-4706	EG	Division Road	12	Asbestos Cement	65	48	1.14 out of 5	\$442	28,551
Transmission Main	1674	P-4754	EG	Division Road	16	Ductile Iron	422	24	0.14 out of 5	N/A	\$0
Transmission Main	1675	P-4754	EG	Division Road	16	Ductile Iron	882	24	0.14 out of 5	N/A	\$0
Transmission Main	1676	P-4754	EG	Division Road	16	Ductile Iron	529	24	0.14 out of 5	N/A	\$0
Transmission Main	1677	P-4168	EG	Division Road	16	Ductile Iron	29	24	0.14 out of 5	N/A	\$0
Transmission Main	1678	P-4168	EG	Division Road	16	Ductile Iron	588	24	0.14 out of 5	N/A	\$0
Transmission Main	1679	P-4168	EG	Division Road	16	Ductile Iron	232	24	0.14 out of 5	N/A	\$0
Transmission Main	1680	P-4168	EG	Division Road	16	Ductile Iron	751	24	0.14 out of 5	N/A	\$0
Transmission Main	1681	P-4168	EG	Division Road	16	Ductile Iron	4	24	0.14 out of 5	N/A	\$0
Transmission Main	2045		EG	Division Road	12	Asbestos Cement	18	62	1.29 out of 5	\$442	8,064
Transmission Main	2048	P-4780	EG	Division Road	12	Asbestos Cement	350	48	1.14 out of 5	\$442	154,807
Transmission Main	6340	P-4705	EG	Division Road	12	Asbestos Cement	582	48	1.14 out of 5	\$442	257,128
Transmission Main	119	P-4678	EG	Division St.	12	Asbestos Cement	415	62	1.29 out of 5	\$442	183,233
Transmission Main	120	P-4678	EG	Division St.	12	Asbestos Cement	379	62	1.29 out of 5	\$442	167,500
Distribution Main	303	P-4568	EG	Division St.	8	Ductile Iron	18	17	0 out of 5	N/A	\$0
Distribution Main	2253	P-4561	EG	Division St.	8	Cast Iron	39	129	1.86 out of 5	\$442	17,099
Transmission Main	2523	P-4560	EG	Division St.	12	Asbestos Cement	468	62	1.29 out of 5	\$442	206,957
Distribution Main	2912	P-4713	EG	Division St.	8	Cast Iron	215	129	1.86 out of 5	\$442	95,142
Distribution Main	2913	P-4713	EG	Division St.	8	Cast Iron	74	129	1.86 out of 5	\$442	32,491

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2914	P-4567	EG	Division St.	8	Cast Iron	120	129	1.86 out of 5	\$442	52,957
Transmission Main	3222	P-4583	EG	Division St.	12	Asbestos Cement	12	62	1.29 out of 5	\$442	5,194
Distribution Main	3223	P-4885	EG	Division St.	2	Copper	453	UNK	1.99 out of 5	\$442	200,319
Transmission Main	3460	P-4497	EG	Division St.	12	Asbestos Cement	605	62	1.14 out of 5	\$442	267,309
Transmission Main	3912	P-4674	EG	Division St.	12	Asbestos Cement	919	62	1.29 out of 5	\$442	406,412
Transmission Main	3913	P-4674	EG	Division St.	12	Asbestos Cement	800	62	2 out of 5	\$442	353,666
Transmission Main	3914	P-4674	EG	Division St.	12	Asbestos Cement	49	62	1.29 out of 5	\$442	21,556
Transmission Main	3915	P-4674	EG	Division St.	12	Asbestos Cement	22	62	1.29 out of 5	\$442	9,753
Transmission Main	3938	P-4526	EG	Division St.	12	Asbestos Cement	818	62	1.29 out of 5	\$442	361,492
Transmission Main	4155	P-4498	EG	Division St.	12	Asbestos Cement	563	62	1.29 out of 5	\$442	248,980
Distribution Main	4525	P-4550	EG	Division St.	6	Cast Iron	412	133	2.57 out of 5	\$442	182,212
Distribution Main	4526	P-4550	EG	Division St.	6	Cast Iron	305	133	2.57 out of 5	\$442	134,644
Distribution Main	4533		EG	Division St.	8	Cast Iron	66	129	1.86 out of 5	\$442	28,989
Distribution Main	4534	P-4564	EG	Division St.	8	Cast Iron	238	129	1.86 out of 5	\$442	105,105
Distribution Main	4535	P-4539	EG	Division St.	6	Cast Iron	333	129	2.57 out of 5	\$442	147,172
Transmission Main	4539	P-4602	EG	Division St.	12	Asbestos Cement	14	62	1.29 out of 5	\$442	5,985
Distribution Main	5035	P-4567	EG	Division St.	8	Cast Iron	125	129	1.86 out of 5	\$442	55,418
Distribution Main	5036	P-4567	EG	Division St.	8	Cast Iron	7	129	1.86 out of 5	\$442	3,268
Distribution Main	5039	P-4886	EG	Division St.	8	Asbestos Cement	88	UNK	0.85 out of 5	\$442	38,925
Transmission Main	5040	P-4583	EG	Division St.	12	Asbestos Cement	342	62	1.29 out of 5	\$442	151,253
Transmission Main	5410	P-4463	EG	Division St.	12	Asbestos Cement	472	62	1.29 out of 5	\$442	208,486
Transmission Main	5411	P-4463	EG	Division St.	12	Asbestos Cement	15	62	1.14 out of 5	\$442	6,630
Transmission Main	5412	P-4676	EG	Division St.	12	Asbestos Cement	16	62	1.29 out of 5	\$442	7,080
Transmission Main	5428	P-4538	EG	Division St.	12	Asbestos Cement	936	62	1.29 out of 5	\$442	413,575
Transmission Main	5787	P-4676	EG	Division St.	12	Asbestos Cement	31	62	1.29 out of 5	\$442	13,543
Transmission Main	5966	P-4497	EG	Division St.	12	Asbestos Cement	14	62	1.29 out of 5	\$442	6,049
Transmission Main	5967	P-4463	EG	Division St.	12	Asbestos Cement	41	62	1.29 out of 5	\$442	18,247
Transmission Main	6288	P-4602	EG	Division St.	12	Asbestos Cement	14	62	1.29 out of 5	\$442	5,993
Distribution Main	6289	P-4563	EG	Division St.	8	Cast Iron	249	129	1.86 out of 5	\$442	110,184
Distribution Main	6290	P-4562	EG	Division St.	8	Cast Iron	21	129	1.86 out of 5	\$442	9,164
Transmission Main	6304	P-4521	EG	Division St.	12	Asbestos Cement	1,053	62	1.14 out of 5	\$442	465,467
Transmission Main	6305	P-4583	EG	Division St.	12	Asbestos Cement	508	62	1.29 out of 5	\$442	224,372
Distribution Main	6306	P-4885	EG	Division St.	2	Copper	61	UNK	1.99 out of 5	\$442	26,816
Transmission Main	6324	P-4674	EG	Division St.	12	Asbestos Cement	518	62	1.29 out of 5	\$442	229,016
Transmission Main	6327	P-4465	EG	Division St.	12	Asbestos Cement	107	62	1.29 out of 5	\$442	47,121
Transmission Main	6328	P-4465	EG	Division St.	12	Asbestos Cement	492	62	1.29 out of 5	\$442	217,501
Transmission Main	6329	P-4674	EG	Division St.	12	Asbestos Cement	325	62	1.29 out of 5	\$442	143,686
Transmission Main	6330	P-4674	EG	Division St.	12	Asbestos Cement	294	62	1.29 out of 5	\$442	130,143
Transmission Main	6334	P-4676	EG	Division St.	12	Asbestos Cement	8	62	1.29 out of 5	\$442	3,476
Transmission Main	6335	P-4676	EG	Division St.	12	Asbestos Cement	5	62	1.29 out of 5	\$442	2,201
Transmission Main	6336	P-4674	EG	Division St.	12	Asbestos Cement	14	48	1.14 out of 5	\$442	6,143
Transmission Main	6338	P-4466	EG	Division St.	12	Asbestos Cement	457	62	1.29 out of 5	\$442	202,060
Transmission Main	6566	P-4701	EG	Division St.	12	Asbestos Cement	124	62	1.14 out of 5	\$442	54,853
Transmission Main	6567	P-4701	EG	Division St.	12	Asbestos Cement	701	62	1.29 out of 5	\$442	309,840

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	6715	P-4702	EG	Division St.	12	Asbestos Cement	250	62	1.29 out of 5	\$442	110,580
Distribution Main	6764	P-4563	EG	Division St.	8	Cast Iron	30	129	1.86 out of 5	\$442	13,186
Distribution Main	6765	P-4563	EG	Division St.	8	Cast Iron	13	129	1.86 out of 5	\$442	5,719
Distribution Main	6768	P-4562	EG	Division St.	8	Cast Iron	30	129	1.86 out of 5	\$442	13,192
Distribution Main	6769	P-4562	EG	Division St.	8	Cast Iron	232	129	1.86 out of 5	\$442	102,441
Distribution Main	6770	P-4560	EG	Division St.	8	Cast Iron	15	129	1.86 out of 5	\$442	6,582
Distribution Main	6771	P-4560	EG	Division St.	8	Cast Iron	402	129	1.86 out of 5	\$442	177,487
Transmission Main	9010	P-4583	EG	Division St.	12	Asbestos Cement	229	62	1.29 out of 5	\$442	101,090
Transmission Main	9011	P-4583	EG	Division St.	12	Asbestos Cement	182	62	1.29 out of 5	\$442	80,397
Transmission Main	9012	P-4583	EG	Division St.	12	Asbestos Cement	168	62	1.29 out of 5	\$442	74,300
Transmission Main	9013	P-4583	EG	Division St.	12	Asbestos Cement	65	62	1.29 out of 5	\$442	28,566
Distribution Main	9137		EG	Division St.	8	Cast Iron	60	129	1.86 out of 5	\$442	26,594
Distribution Main	9138	P-4893	EG	Division St.	6	Cast Iron	229	129	2.57 out of 5	\$442	101,093
Distribution Main	9308	P-4559	EG	Division St.	8	Cast Iron	4	129	1.86 out of 5	\$442	1,878
Distribution Main	9309	P-4559	EG	Division St.	8	Cast Iron	251	129	1.86 out of 5	\$442	110,924
Distribution Main	9484	P-4558	EG	Division St.	6	Cast Iron	102	131	2.57 out of 5	\$442	45,118
Distribution Main	9485	P-4558	EG	Division St.	6	Cast Iron	12	133	2.57 out of 5	\$442	5,279
Distribution Main	11255	P-4539	EG	Division St.	6	Cast Iron	6	129	2.57 out of 5	\$442	2,733
Distribution Main	11271	P-4561	EG	Division St.	8	Cast Iron	11	129	1.86 out of 5	\$442	4,987
Transmission Main	11350	P-4702	EG	Division St.	12	Asbestos Cement	51	62	1.14 out of 5	\$442	22,545
Distribution Main	11548		EG	Division St.	8	Cast Iron	4	129	1.86 out of 5	\$442	1,551
Distribution Main	11951	P-4713	EG	Division St.	8	Cast Iron	36	129	1.86 out of 5	\$442	15,792
Distribution Main	12106	P-4558	EG	Division St.	6	Cast Iron	68	133	2.57 out of 5	\$442	29,984
Distribution Main	372		EG	Division St. Prv	8	Ductile Iron	10	25	0.14 out of 5	N/A	\$0
Distribution Main	4499		EG	Division St. Prv	8	Ductile Iron	18	25	0.14 out of 5	N/A	\$0
Distribution Main	5415		EG	Division St. Prv	8	Ductile Iron	24	25	0.14 out of 5	N/A	\$0
Distribution Main	6339		EG	Division St. Prv	8	Ductile Iron	4	25	0.14 out of 5	N/A	\$0
Distribution Main	6043	P-4324	EG	Downing Street	8	Asbestos Cement	406	50	1.14 out of 5	\$442	179,531
Distribution Main	6044	P-4324	EG	Downing Street	8	Asbestos Cement	1,001	50	1.14 out of 5	\$442	442,321
Distribution Main	11827	P-4324	EG	Downing Street	8	Asbestos Cement	22	50	1.14 out of 5	\$442	9,745
Distribution Main	9162	P-4616	EG	Duke St	8	Ductile Iron	208	8	0 out of 5	N/A	\$0
Distribution Main	9174	P-4628	EG	Duke St	8	Ductile Iron	424	8	0 out of 5	N/A	\$0
Distribution Main	9179	P-4646	EG	Duke St	8	Ductile Iron	119	8	0 out of 5	N/A	\$0
Distribution Main	9180	P-4644	EG	Duke St	8	Ductile Iron	366	8	0 out of 5	N/A	\$0
Distribution Main	9181	P-4644	EG	Duke St	8	Ductile Iron	18	8	0 out of 5	N/A	\$0
Distribution Main	9192	P-4904	EG	Duke St	8	Ductile Iron	227	8	0 out of 5	N/A	\$0
Distribution Main	9193	P-4904	EG	Duke St	8	Ductile Iron	49	8	0 out of 5	N/A	\$0
Distribution Main	9200	P-4644	EG	Duke St	8	Ductile Iron	16	8	0 out of 5	N/A	\$0
Distribution Main	11553	P-4904	EG	Duke St	8	Ductile Iron	137	8	0 out of 5	N/A	\$0
Distribution Main	1893	P-4627	EG	Duke St.	8	Ductile Iron	100	19	0 out of 5	N/A	\$0
Distribution Main	9199	P-4646	EG	Duke St.	8	Ductile Iron	230	8	0 out of 5	N/A	\$0
Distribution Main	9304	P-4646	EG	Duke St.	8	Ductile Iron	3	17	0 out of 5	N/A	\$0
Distribution Main	5822	P-4034	EG	Eagle Ln.	8	PVC	390	32	0.43 out of 5	\$442	172,530
Transmission Main	4486	P-4027	EG	Easement	16	Ductile Iron	290	25	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	4489	P-4027	EG	Easement	16	Ductile Iron	32	25	0.14 out of 5	N/A	\$0
Transmission Main	4490	P-4027	EG	Easement	16	Ductile Iron	573	25	0.14 out of 5	N/A	\$0
Transmission Main	4589	P-4005	EG	Easement	12	Ductile Iron	460	30	0.14 out of 5	\$442	203,466
Transmission Main	5724	P-4149	EG	Easement	16	Ductile Iron	703	25	0.14 out of 5	N/A	\$0
Transmission Main	5725	P-4149	EG	Easement	16	Ductile Iron	513	25	0.14 out of 5	N/A	\$0
Transmission Main	5729	P-4027	EG	Easement	16	Ductile Iron	316	25	0.14 out of 5	N/A	\$0
Transmission Main	5732	P-4149	EG	Easement	16	Ductile Iron	8	25	0.14 out of 5	N/A	\$0
Transmission Main	5733	P-4149	EG	Easement	16	Ductile Iron	142	25	0.14 out of 5	N/A	\$0
Transmission Main	5734	P-4027	EG	Easement	16	Ductile Iron	6	25	0.14 out of 5	N/A	\$0
Distribution Main	6119	P-4252	EG	Edward Road	6	Asbestos Cement	27	56	1.85 out of 5	\$442	11,933
Distribution Main	6120	P-4252	EG	Edward Road	6	Asbestos Cement	509	56	1.85 out of 5	\$442	225,015
Distribution Main	11325	P-4252	EG	Edward Road	6	Asbestos Cement	4	56	1.85 out of 5	\$442	1,568
Transmission Main	6712		EG	Eg Well Station 1	12	Ductile Iron	240	22	0.14 out of 5	N/A	\$0
Distribution Main	3916	P-4553	EG	Eldredge Ave.	8	Ductile Iron	312	17	0 out of 5	N/A	\$0
Distribution Main	4514	P-4683	EG	Eldredge Ave.	8	Ductile Iron	81	17	0 out of 5	N/A	\$0
Distribution Main	4515	P-4683	EG	Eldredge Ave.	8	Ductile Iron	414	17	0 out of 5	N/A	\$0
Distribution Main	10381	P-4557	EG	Eldredge Ave.	8	Ductile Iron	209	17	0 out of 5	N/A	\$0
Distribution Main	4207	P-4272	EG	Eugene St.	6	Asbestos Cement	731	51	1.85 out of 5	\$442	323,018
Distribution Main	4208	P-4272	EG	Eugene St.	6	Asbestos Cement	438	51	1.85 out of 5	\$442	193,543
Transmission Main	6122	P-4229	EG	Eugene St.	20	Asbestos Cement	1,478	55	1.14 out of 5	\$442	653,462
Distribution Main	1894	P-4629	EG	Exchange St.	8	Ductile Iron	464	19	0 out of 5	N/A	\$0
Distribution Main	5518	P-4098	EG	Ezechial Carrie Rd.	8	PVC	1,130	35	0.43 out of 5	\$442	499,359
Distribution Main	5653	P-4098	EG	Ezechial Carrie Rd.	8	PVC	20	35	0.43 out of 5	\$442	8,784
Distribution Main	5875	P-498	EG	Ezechial Carrie Rd.	8	PVC	29	35	0.43 out of 5	\$442	12,762
Distribution Main	3654	P-4342	EG	Fairfield Ave.	6	Ductile Iron	190	21	0.85 out of 5	N/A	\$0
Distribution Main	4194	P-4350	EG	Fairfield Ave.	6	Ductile Iron	195	21	0.85 out of 5	N/A	\$0
Distribution Main	5468		EG	Fairfield Ave.	6	Ductile Iron	6	21	0.85 out of 5	N/A	\$0
Distribution Main	5469	P-4353	EG	Fairfield Ave.	6	Ductile Iron	59	21	0.85 out of 5	N/A	\$0
Distribution Main	5470	P-4353	EG	Fairfield Ave.	6	Ductile Iron	27	UNK	0.71 out of 5	\$442	11,862
Distribution Main	6482	P-4335	EG	Fairfield Ave.	6	Ductile Iron	180	21	0.85 out of 5	N/A	\$0
Distribution Main	6483	P-4335	EG	Fairfield Ave.	6	Ductile Iron	24	21	0.85 out of 5	N/A	\$0
Distribution Main	6484	P-4348	EG	Fairfield Ave.	6	Ductile Iron	200	21	0.85 out of 5	N/A	\$0
Distribution Main	5834	P-4038	EG	Falcon Cir.	8	Asbestos Cement	1,018	45	1.14 out of 5	\$442	450,145
Distribution Main	5835	P-4038	EG	Falcon Cir.	8	Asbestos Cement	996	45	1.14 out of 5	\$442	440,299
Distribution Main	5836	P-4038	EG	Falcon Cir.	8	Asbestos Cement	15	45	1.14 out of 5	\$442	6,575
Distribution Main	6481	P-4338	EG	Fairfield Ave.	6	Ductile Iron	217	21	0.85 out of 5	N/A	\$0
Distribution Main	5650	P-4133	EG	Fernwood Dr	6	Ductile Iron	17	36	0.85 out of 5	\$442	7,335
Distribution Main	6017	P-4133	EG	Fernwood Dr	6	Ductile Iron	220	36	0.85 out of 5	\$442	97,155
Transmission Main	6003	P-4132	EG	Fernwood Dr.	20	Ductile Iron	55	36	0.14 out of 5	\$442	24,140
Transmission Main	6011	P-4132	EG	Fernwood Dr.	20	Ductile Iron	60	36	0.14 out of 5	\$442	26,554
Transmission Main	6014	P-4134	EG	Fernwood Dr.	20	Ductile Iron	41	36	0.14 out of 5	\$442	18,034
Transmission Main	6341	P-4134	EG	Fernwood Dr.	20	Ductile Iron	39	36	0.14 out of 5	\$442	17,232
Transmission Main	6342	P-4134	EG	Fernwood Dr.	20	Ductile Iron	885	36	0.14 out of 5	\$442	391,336
Transmission Main	6572	P-4994	EG	Fernwood Dr.	20	Ductile Iron	198	36	0.14 out of 5	\$442	87,681

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6155	P-4468	EG	Field Stone Dr.	6	Ductile Iron	376	19	0.71 out of 5	N/A	\$0
Distribution Main	4265	P-4946	EG	Fifth Av	6	Asbestos Cement	30	51	1.85 out of 5	\$442	13,236
Distribution Main	5673	P-4946	EG	Fifth Av	6	Asbestos Cement	211	51	1.85 out of 5	\$442	93,144
Distribution Main	9314		EG	First Ave	6	Ductile Iron	26	9	0.71 out of 5	N/A	\$0
Distribution Main	666	P-4515	EG	First Ave.	8	Asbestos Cement	486	52	1.14 out of 5	\$442	214,994
Transmission Main	1076	P-4662	EG	First Ave.	12	Ductile Iron	75	23	0.14 out of 5	N/A	\$0
Distribution Main	1899	P-4586	EG	First Ave.	6	Cast Iron	166	133	2.57 out of 5	\$442	73,373
Distribution Main	1900	P-4969	EG	First Ave.	8	Ductile Iron	15	17	0 out of 5	N/A	\$0
Distribution Main	4174	P-4532	EG	First Ave.	6	Cast Iron	272	133	2.57 out of 5	\$442	120,012
Distribution Main	4175	P-4532	EG	First Ave.	6	Cast Iron	23	133	2.57 out of 5	\$442	10,256
Distribution Main	4261	P-4593	EG	First Ave.	6	Cast Iron	54	133	2.57 out of 5	\$442	23,948
Distribution Main	5418	P-4590	EG	First Ave.	6	Cast Iron	686	133	2.57 out of 5	\$442	303,315
Distribution Main	5425	P-4532	EG	First Ave.	6	Cast Iron	8	133	2.57 out of 5	\$442	3,621
Distribution Main	6268	P-4586	EG	First Ave.	6	Cast Iron	25	133	2.57 out of 5	\$442	11,137
Distribution Main	6347		EG	First Ave.	8	Asbestos Cement	7	52	1.14 out of 5	\$442	3,250
Distribution Main	6350	P-4703	EG	First Ave.	8	Asbestos Cement	558	52	1.14 out of 5	\$442	246,643
Distribution Main	6630	P-4581	EG	First Ave.	6	Cast Iron	236	133	2.57 out of 5	\$442	104,303
Distribution Main	6632	P-4588	EG	First Ave.	6	Cast Iron	14	133	2.57 out of 5	\$442	6,199
Distribution Main	6633	P-4588	EG	First Ave.	6	Cast Iron	183	133	2.57 out of 5	\$442	80,756
Transmission Main	6642		EG	First Ave.	12	Ductile Iron	15	23	0.14 out of 5	N/A	\$0
Distribution Main	6718	P-4585	EG	First Ave.	6	Cast Iron	199	131	2.57 out of 5	\$442	88,081
Transmission Main	6724	P-4940	EG	First Ave.	12	Ductile Iron	63	23	0.14 out of 5	N/A	\$0
Distribution Main	6727	P-4703	EG	First Ave.	8	Asbestos Cement	247	52	1.14 out of 5	\$442	109,106
Distribution Main	9443	P-4593	EG	First Ave.	6	Cast Iron	362	133	2.57 out of 5	\$442	160,163
Distribution Main	11005	P-4970	EG	First Ave.	8	Ductile Iron	14	17	0 out of 5	N/A	\$0
Distribution Main	11151	P-4586	EG	First Ave.	6	Cast Iron	51	133	2.57 out of 5	\$442	22,560
Distribution Main	11332	P-4703	EG	First Ave.	8	Asbestos Cement	5	52	1.14 out of 5	\$442	2,169
Distribution Main	11347	P-4581	EG	First Ave.	6	Cast Iron	6	133	2.57 out of 5	\$442	2,761
Distribution Main	6784	P-4280	EG	Flintstone Court	6	Asbestos Cement	5	51	1.85 out of 5	\$442	2,017
Distribution Main	6785	P-4280	EG	Flintstone Court	6	Asbestos Cement	335	51	1.85 out of 5	\$442	148,153
Distribution Main	5209	P-4941	EG	Fourth Ave.	6	PVC	701	36	1.14 out of 5	\$442	309,839
Distribution Main	5399	P-4664	EG	Fourth Ave.	6	Asbestos Cement	240	68	2 out of 5	\$442	106,058
Distribution Main	5400	P-4664	EG	Fourth Ave.	6	Asbestos Cement	6	68	2 out of 5	\$442	2,505
Distribution Main	5422	P-4666	EG	Fourth Ave.	6	PVC	332	36	1.14 out of 5	\$442	146,960
Distribution Main	6639	P-4941	EG	Fourth Ave.	6	PVC	59	36	1.14 out of 5	\$442	26,016
Distribution Main	3939	P-4944	EG	Fourth St	6	Unknown	254	68	1.14 out of 5	\$442	112,118
Distribution Main	5417	P-4945	EG	Fourth St	6	Unknown	179	68	1.14 out of 5	\$442	79,125
Distribution Main	970	P-4172	EG	Fox Run	8	Asbestos Cement	14	39	1 out of 5	\$442	6,249
Distribution Main	974	P-4171	EG	Fox Run	8	Asbestos Cement	608	39	1 out of 5	\$442	268,926
Distribution Main	2037	P-4172	EG	Fox Run	8	Asbestos Cement	606	39	1 out of 5	\$442	268,038
Distribution Main	2038	P-4172	EG	Fox Run	8	Asbestos Cement	976	39	1 out of 5	\$442	431,565
Distribution Main	5666	P-4057	EG	Franklin Rd.	8	Asbestos Cement	439	51	1.14 out of 5	\$442	194,241
Distribution Main	5667	P-4057	EG	Franklin Rd.	8	Asbestos Cement	271	51	1.14 out of 5	\$442	119,771
Distribution Main	5788	P-4072	EG	Frederick T. Miller Way	8	Ductile Iron	14	19	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5789	P-4072	EG	Frederick T. Miller Way	8	Ductile Iron	411	19	0 out of 5	N/A	\$0
Transmission Main	9062	P-40005	EG	Frenchtown Rd.	12	Asbestos Cement	9	55	1.14 out of 5	\$442	3,769
Transmission Main	749	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	96	55	1.14 out of 5	\$442	42,502
Transmission Main	750	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	159	55	1.14 out of 5	\$442	70,207
Transmission Main	751		EG	Frenchtown Rd.	12	Ductile Iron	15	21	0.14 out of 5	N/A	\$0
Transmission Main	752	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	677	55	1.14 out of 5	\$442	299,035
Transmission Main	753	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	21	55	1.14 out of 5	\$442	9,464
Transmission Main	754	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	410	21	0.14 out of 5	N/A	\$0
Transmission Main	755		EG	Frenchtown Rd.	12	Asbestos Cement	4	55	1.14 out of 5	\$442	1,555
Transmission Main	756	P-4371	EG	Frenchtown Rd.	16	Ductile Iron	32	21	0.14 out of 5	N/A	\$0
Transmission Main	758	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	732	55	1.14 out of 5	\$442	323,537
Transmission Main	1929	P-40019	EG	Frenchtown Rd.	12	Asbestos Cement	15	55	1.14 out of 5	\$442	6,495
Transmission Main	1930	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	130	55	1.14 out of 5	\$442	57,336
Transmission Main	1931	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	48	21	0.14 out of 5	N/A	\$0
Transmission Main	1932	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	13	21	0.14 out of 5	N/A	\$0
Transmission Main	1933		EG	Frenchtown Rd.	12	Asbestos Cement	39	55	1.14 out of 5	\$442	17,446
Transmission Main	1934	P-4728	EG	Frenchtown Rd.	12	Asbestos Cement	355	55	1.14 out of 5	\$442	157,031
Transmission Main	1935	P-4728	EG	Frenchtown Rd.	12	Asbestos Cement	662	55	1.14 out of 5	\$442	292,692
Transmission Main	1936	P-4730	EG	Frenchtown Rd.	16	Ductile Iron	187	21	0.14 out of 5	N/A	\$0
Transmission Main	1937	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	579	22	0.14 out of 5	N/A	\$0
Transmission Main	1938	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	460	22	0.14 out of 5	N/A	\$0
Transmission Main	1939	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	574	22	0.14 out of 5	N/A	\$0
Transmission Main	1942	P-4728	EG	Frenchtown Rd.	12	Asbestos Cement	73	55	1.14 out of 5	\$442	32,190
Transmission Main	1943	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	659	55	1.14 out of 5	\$442	291,358
Transmission Main	1944	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	18	21	0.14 out of 5	N/A	\$0
Transmission Main	1945	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	359	55	1.14 out of 5	\$442	158,867
Transmission Main	1946	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	5	55	1.14 out of 5	\$442	2,124
Transmission Main	1947	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	179	21	0.14 out of 5	N/A	\$0
Transmission Main	1948	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	487	21	0.14 out of 5	N/A	\$0
Transmission Main	2915	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	31	55	1.14 out of 5	\$442	13,735
Transmission Main	2975	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	704	21	0.14 out of 5	N/A	\$0
Transmission Main	2976	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	80	21	0.14 out of 5	N/A	\$0
Transmission Main	3301	P-4063	EG	Frenchtown Rd.	12	Ductile Iron	30	22	0.14 out of 5	N/A	\$0
Transmission Main	4139	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	349	21	0.14 out of 5	N/A	\$0
Transmission Main	4140	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	88	21	0.14 out of 5	N/A	\$0
Transmission Main	4141	P-4831	EG	Frenchtown Rd.	16	Ductile Iron	526	22	0.14 out of 5	N/A	\$0
Transmission Main	4142	P-4730	EG	Frenchtown Rd.	16	Ductile Iron	546	22	0.14 out of 5	N/A	\$0
Transmission Main	4143		EG	Frenchtown Rd.	12	Asbestos Cement	4	55	1.14 out of 5	\$442	1,594
Transmission Main	4355	P-4743	EG	Frenchtown Rd.	16	Ductile Iron	7	21	0.14 out of 5	N/A	\$0
Transmission Main	4356	P-4843	EG	Frenchtown Rd.	12	Ductile Iron	773	22	0.14 out of 5	N/A	\$0
Transmission Main	4361	P-4056	EG	Frenchtown Rd.	12	Ductile Iron	47	22	0.14 out of 5	N/A	\$0
Transmission Main	4362	P-4056	EG	Frenchtown Rd.	12	Ductile Iron	390	22	0.14 out of 5	N/A	\$0
Transmission Main	4363	P-4060	EG	Frenchtown Rd.	16	Asbestos Cement	749	49	1.14 out of 5	\$442	331,127
Transmission Main	4366	P-40071	EG	Frenchtown Rd.	12	Ductile Iron	887	22	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	4382	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	754	55	1.14 out of 5	\$442	333,051
Transmission Main	4383	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	692	55	1.14 out of 5	\$442	305,819
Transmission Main	4925		EG	Frenchtown Rd.	16	Ductile Iron	27	17	0 out of 5	N/A	\$0
Transmission Main	4926		EG	Frenchtown Rd.	16	Ductile Iron	5	17	0 out of 5	N/A	\$0
Transmission Main	4927		EG	Frenchtown Rd.	16	Ductile Iron	8	17	0 out of 5	N/A	\$0
Transmission Main	4985		EG	Frenchtown Rd.	16	PVC	471	32	0.43 out of 5	\$442	208,032
Transmission Main	4986	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	336	55	1.14 out of 5	\$442	148,427
Transmission Main	4987	P-4855	EG	Frenchtown Rd.	12	Asbestos Cement	511	55	1.14 out of 5	\$442	226,013
Transmission Main	5278	P-4001	EG	Frenchtown Rd.	16	Ductile Iron	369	17	0 out of 5	N/A	\$0
Transmission Main	5281	P-4001	EG	Frenchtown Rd.	16	Ductile Iron	975	17	0 out of 5	N/A	\$0
Transmission Main	5282	P-4001	EG	Frenchtown Rd.	16	Ductile Iron	39	17	0 out of 5	N/A	\$0
Transmission Main	5283	P-4001	EG	Frenchtown Rd.	16	Ductile Iron	3	17	0 out of 5	N/A	\$0
Transmission Main	5284	P-4001	EG	Frenchtown Rd.	16	Ductile Iron	699	17	0 out of 5	N/A	\$0
Transmission Main	5670	P-4105	EG	Frenchtown Rd.	12	Asbestos Cement	252	55	1.14 out of 5	\$442	111,294
Transmission Main	5706	P-4113	EG	Frenchtown Rd.	12	Asbestos Cement	446	49	1.14 out of 5	\$442	197,017
Transmission Main	5707	P-4113	EG	Frenchtown Rd.	12	Asbestos Cement	203	49	1.14 out of 5	\$442	89,808
Transmission Main	5708	P-4722	EG	Frenchtown Rd.	20	Asbestos Cement	103	49	1.14 out of 5	\$442	45,399
Transmission Main	5709	P-4722	EG	Frenchtown Rd.	20	Asbestos Cement	314	49	1.14 out of 5	\$442	138,810
Transmission Main	5719	P-4371	EG	Frenchtown Rd.	16	Ductile Iron	472	21	0.14 out of 5	N/A	\$0
Transmission Main	5720	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	218	21	0.14 out of 5	N/A	\$0
Transmission Main	5721	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	346	21	0.14 out of 5	N/A	\$0
Transmission Main	5722	P-4731	EG	Frenchtown Rd.	12	Ductile Iron	6	21	0.14 out of 5	N/A	\$0
Transmission Main	5723	P-40019	EG	Frenchtown Rd.	12	Asbestos Cement	339	55	1.14 out of 5	\$442	149,654
Transmission Main	5799	P-4075	EG	Frenchtown Rd.	20	Asbestos Cement	723	49	1.14 out of 5	\$442	319,780
Transmission Main	5800	P-4075	EG	Frenchtown Rd.	20	Asbestos Cement	833	49	1.14 out of 5	\$442	368,097
Transmission Main	5801	P-4721	EG	Frenchtown Rd.	20	Asbestos Cement	99	49	1.14 out of 5	\$442	43,850
Transmission Main	5802	P-4721	EG	Frenchtown Rd.	20	Asbestos Cement	845	49	1.14 out of 5	\$442	373,551
Transmission Main	5873	P-4114	EG	Frenchtown Rd.	12	Asbestos Cement	45	55	1.14 out of 5	\$442	19,861
Transmission Main	5874	P-4114	EG	Frenchtown Rd.	12	Asbestos Cement	940	55	1.14 out of 5	\$442	415,475
Transmission Main	5880	P-4859	EG	Frenchtown Rd.	12	Asbestos Cement	97	55	1.14 out of 5	\$442	42,980
Transmission Main	5881	P-4859	EG	Frenchtown Rd.	12	Asbestos Cement	1,029	55	1.14 out of 5	\$442	454,851
Transmission Main	5888	P-4114	EG	Frenchtown Rd.	12	Asbestos Cement	8	55	1.14 out of 5	\$442	3,644
Transmission Main	6360	P-4003	EG	Frenchtown Rd.	16	Asbestos Cement	10	49	1.14 out of 5	\$442	4,395
Transmission Main	6361	P-4003	EG	Frenchtown Rd.	16	Asbestos Cement	745	49	1.14 out of 5	\$442	329,499
Transmission Main	6362		EG	Frenchtown Rd.	16	Ductile Iron	2	17	0 out of 5	N/A	\$0
Transmission Main	6366	P-4002	EG	Frenchtown Rd.	16	Asbestos Cement	437	49	1.14 out of 5	\$442	193,254
Transmission Main	6691	P-4104	EG	Frenchtown Rd.	12	Asbestos Cement	7	55	1.14 out of 5	\$442	2,989
Transmission Main	6692	P-4104	EG	Frenchtown Rd.	12	Asbestos Cement	407	55	1.14 out of 5	\$442	180,062
Transmission Main	9060	P-40005	EG	Frenchtown Rd.	20	Asbestos Cement	38	49	1.14 out of 5	\$442	16,862
Transmission Main	9061	P-40005	EG	Frenchtown Rd.	20	Asbestos Cement	408	49	1.14 out of 5	\$442	180,152
Transmission Main	9063	P-4075	EG	Frenchtown Rd.	20	Asbestos Cement	37	49	1.14 out of 5	\$442	16,532
Transmission Main	10432	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	428	22	0.14 out of 5	N/A	\$0
Transmission Main	10433	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	344	21	0.14 out of 5	N/A	\$0
Transmission Main	10434	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	84	22	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	10435	P-4731	EG	Frenchtown Rd.	16	Ductile Iron	220	21	0.14 out of 5	N/A	\$0
Transmission Main	11152	P-4728	EG	Frenchtown Rd.	12	Asbestos Cement	64	55	1.14 out of 5	\$442	28,354
Transmission Main	11207	P-4060	EG	Frenchtown Rd.	16	Asbestos Cement	11	49	1.14 out of 5	\$442	4,723
Transmission Main	11208	P-4063	EG	Frenchtown Rd.	12	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Transmission Main	11209	P-40005	EG	Frenchtown Rd.	20	Asbestos Cement	11	49	1.14 out of 5	\$442	4,810
Transmission Main	11246	P-4730	EG	Frenchtown Rd.	16	Ductile Iron	48	21	0.14 out of 5	N/A	\$0
Transmission Main	11314	P-4721	EG	Frenchtown Rd.	20	Asbestos Cement	35	49	1.14 out of 5	\$442	15,518
Transmission Main	11315	P-4721	EG	Frenchtown Rd.	20	Asbestos Cement	7	49	1.14 out of 5	\$442	3,047
Transmission Main	11828	P-4721	EG	Frenchtown Rd.	20	Asbestos Cement	532	49	1.14 out of 5	\$442	235,131
Transmission Main	11873	P-4728	EG	Frenchtown Rd.	12	Asbestos Cement	237	55	1.14 out of 5	\$442	104,730
Transmission Main	11874	P-4728	EG	Frenchtown Rd.	12	Asbestos Cement	292	55	1.14 out of 5	\$442	129,060
Transmission Main	4357		EG	Frenchtown Road Tank Ease	16	Asbestos Cement	5	49	1.14 out of 5	\$442	2,170
Transmission Main	4358	P-4059	EG	Frenchtown Road Tank Ease	12	Ductile Iron	754	20	0 out of 5	N/A	\$0
Transmission Main	4359	P-4058	EG	Frenchtown Road Tank Ease	12	Ductile Iron	9	20	0 out of 5	N/A	\$0
Transmission Main	4364	P-4059	EG	Frenchtown Road Tank Ease	12	Ductile Iron	13	20	0 out of 5	N/A	\$0
Transmission Main	5045	P-4066	EG	Frenchtown Road Tank Ease	16	Asbestos Cement	7	49	1.14 out of 5	\$442	2,915
Transmission Main	5046	P-4066	EG	Frenchtown Road Tank Ease	16	Asbestos Cement	22	49	1.14 out of 5	\$442	9,801
Transmission Main	5793	P-4066	EG	Frenchtown Road Tank Ease	16	Asbestos Cement	5	49	1.14 out of 5	\$442	2,152
Transmission Main	5794	P-4066	EG	Frenchtown Road Tank Ease	16	Asbestos Cement	7	49	1.14 out of 5	\$442	3,056
Distribution Main	5795	P-4066	EG	Frenchtown Road Tank Ease	8	Ductile Iron	12	20	0 out of 5	N/A	\$0
Transmission Main	5797	P-4064	EG	Frenchtown Road Tank Ease	20	Asbestos Cement	650	49	1.14 out of 5	\$442	287,283
Transmission Main	5798	P-4064	EG	Frenchtown Road Tank Ease	20	Asbestos Cement	77	49	1.14 out of 5	\$442	34,145
Transmission Main	6586	P-4059	EG	Frenchtown Road Tank Ease	20	Asbestos Cement	8	49	1.14 out of 5	\$442	3,555
Distribution Main	6773	P-4066	EG	Frenchtown Road Tank Ease	8	Ductile Iron	24	20	0 out of 5	N/A	\$0
Transmission Main	6774	P-4066	EG	Frenchtown Road Tank Ease	16	Asbestos Cement	31	49	1.14 out of 5	\$442	13,559
Transmission Main	10345	P-4065	EG	Frenchtown Road Tank Ease	12	Ductile Iron	5	20	0 out of 5	N/A	\$0
Distribution Main	4053	P-4414	EG	Friendly Rd.	6	Ductile Iron	55	31	0.85 out of 5	\$442	24,458
Distribution Main	4054	P-4414	EG	Friendly Rd.	6	Ductile Iron	645	31	0.85 out of 5	\$442	284,933
Distribution Main	6411	P-4377	EG	Friendly Rd.	6	Ductile Iron	460	31	0.85 out of 5	\$442	203,477
Distribution Main	1897	P-4577	EG	Friendship St.	6	Asbestos Cement	28	69	2 out of 5	\$442	12,333
Distribution Main	1898	P-4577	EG	Friendship St.	6	Asbestos Cement	220	69	2 out of 5	\$442	97,330
Transmission Main	5416	P-4592	EG	Friendship St.	12	Ductile Iron	260	23	0.14 out of 5	N/A	\$0
Distribution Main	6226	P-4579	EG	Friendship St.	4	Cast Iron	14	133	3.29 out of 5	\$442	6,045
Distribution Main	6227	P-4579	EG	Friendship St.	4	Cast Iron	221	133	3.29 out of 5	\$442	97,564
Transmission Main	6716	P-4947	EG	Friendship St.	12	Ductile Iron	252	23	0.14 out of 5	N/A	\$0
Distribution Main	9890		EG	Fry Brook Dr	8	Ductile Iron	1	13	0 out of 5	N/A	\$0
Distribution Main	5625	P-4460	EG	Gladridge Dr.	6	Asbestos Cement	174	61	2 out of 5	\$442	76,766
Distribution Main	5626	P-4460	EG	Gladridge Dr.	6	Asbestos Cement	196	61	2 out of 5	\$442	86,845
Distribution Main	3840	P-40027	EG	Glenn Dr.	8	Ductile Iron	23	18	0 out of 5	N/A	\$0
Distribution Main	3841	P-4396	EG	Glenn Dr.	6	Asbestos Cement	12	59	1.85 out of 5	\$442	5,108
Distribution Main	3842	P-4396	EG	Glenn Dr.	6	Asbestos Cement	114	59	1.85 out of 5	\$442	50,422
Distribution Main	6409	P-4396	EG	Glenn Dr.	6	Asbestos Cement	1,037	59	1.85 out of 5	\$442	458,448
Distribution Main	4035	P-4365	EG	Gould Pl.	6	Asbestos Cement	56	61	2 out of 5	\$442	24,611
Distribution Main	4036	P-4365	EG	Gould Pl.	6	Asbestos Cement	679	61	2 out of 5	\$442	300,210

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3298	P-4723	EG	Graham Way	8	Ductile Iron	314	30	0.14 out of 5	\$442	138,650
Distribution Main	3299	P-4723	EG	Graham Way	8	Ductile Iron	525	30	0.14 out of 5	\$442	231,858
Distribution Main	5863	P-4725	EG	Graham Way	8	Ductile Iron	115	30	0.14 out of 5	\$442	50,904
Distribution Main	5866	P-4725	EG	Graham Way	8	Ductile Iron	211	30	0.14 out of 5	\$442	93,181
Distribution Main	5867	P-4725	EG	Graham Way	8	Ductile Iron	181	30	0.14 out of 5	\$442	79,950
Distribution Main	3846	P-4316	EG	Grandview Road	6	Asbestos Cement	573	51	1.85 out of 5	\$442	253,387
Distribution Main	3847	P-4316	EG	Grandview Road	6	Asbestos Cement	36	51	1.85 out of 5	\$442	15,752
Distribution Main	3848	P-4317	EG	Grandview Road	6	Asbestos Cement	377	51	1.85 out of 5	\$442	166,769
Distribution Main	4889	P-4402	EG	Grandview Road	6	Asbestos Cement	252	51	1.85 out of 5	\$442	111,409
Distribution Main	4890	P-4274	EG	Grandview Road	6	Asbestos Cement	188	51	1.85 out of 5	\$442	82,957
Distribution Main	4895	P-4260	EG	Grandview Road	6	Asbestos Cement	431	51	1.85 out of 5	\$442	190,361
Distribution Main	4899	P-4316	EG	Grandview Road	6	Asbestos Cement	121	51	1.85 out of 5	\$442	53,458
Distribution Main	5612	P-4268	EG	Grandview Road	6	Asbestos Cement	629	58	1.85 out of 5	\$442	278,192
Distribution Main	5613	P-4288	EG	Grandview Road	6	Asbestos Cement	270	58	1.85 out of 5	\$442	119,261
Distribution Main	5614	P-4288	EG	Grandview Road	6	Asbestos Cement	440	51	1.85 out of 5	\$442	194,632
Distribution Main	6464	P-4403	EG	Grandview Road	6	Asbestos Cement	104	51	1.85 out of 5	\$442	45,969
Distribution Main	10233	P-4274	EG	Grandview Road	6	Asbestos Cement	138	51	1.85 out of 5	\$442	61,100
Distribution Main	968	P-4129	EG	Granite Dr.	6	Asbestos Cement	516	44	1.85 out of 5	\$442	227,949
Distribution Main	969	P-4129	EG	Granite Dr.	6	Asbestos Cement	282	44	1.85 out of 5	\$442	124,809
Distribution Main	3463	P-4127	EG	Granite Dr.	6	Asbestos Cement	399	44	1.85 out of 5	\$442	176,247
Distribution Main	6024	P-4127	EG	Granite Dr.	6	Asbestos Cement	13	44	1.85 out of 5	\$442	5,906
Distribution Main	2906	P-4375	EG	Grassland Road	6	Ductile Iron	241	31	0.85 out of 5	\$442	106,636
Distribution Main	2907	P-4375	EG	Grassland Road	6	Ductile Iron	19	31	0.85 out of 5	\$442	8,465
Distribution Main	2478	P-4436	EG	Grasslands Rd	8	Cast Iron	6	82	1.72 out of 5	\$442	2,613
Distribution Main	6491	P-40029	EG	Grasslands Rd	8	Cast Iron	111	82	1.72 out of 5	\$442	49,128
Distribution Main	6492	P-40029	EG	Grasslands Rd	8	Cast Iron	3	82	1.72 out of 5	\$442	1,342
Distribution Main	6374	P-4391	EG	Great Rd.	8	Asbestos Cement	813	50	1.14 out of 5	\$442	359,132
Distribution Main	2511	P-4989	EG	Great Road	8	Ductile Iron	627	15	0 out of 5	N/A	\$0
Distribution Main	2512	P-4989	EG	Great Road	8	Ductile Iron	329	15	0 out of 5	N/A	\$0
Distribution Main	11175	P-4989	EG	Great Road	8	Ductile Iron	37	15	0 out of 5	N/A	\$0
Distribution Main	6325	P-4464	EG	Green Bush Rd.	8	Ductile Iron	9	25	0.14 out of 5	N/A	\$0
Transmission Main	6326	P-4464	EG	Green Bush Rd.	12	Ductile Iron	13	25	0.14 out of 5	N/A	\$0
Distribution Main	9497	P-4464	EG	Green Bush Rd.	8	Ductile Iron	31	25	0.14 out of 5	N/A	\$0
Distribution Main	9498	P-4464	EG	Green Bush Rd.	8	Ductile Iron	38	25	0.14 out of 5	N/A	\$0
Distribution Main	9136		EG	Greene St	4	Ductile Iron	19	9	1.42 out of 5	N/A	\$0
Distribution Main	4256	P-4599	EG	Greene St.	8	Ductile Iron	26	17	0 out of 5	N/A	\$0
Distribution Main	6241	P-4600	EG	Greene St.	8	Ductile Iron	565	17	0 out of 5	N/A	\$0
Distribution Main	6242	P-4600	EG	Greene St.	8	Ductile Iron	37	17	0 out of 5	N/A	\$0
Distribution Main	6244	P-4599	EG	Greene St.	8	Ductile Iron	313	17	0 out of 5	N/A	\$0
Distribution Main	12089	P-4600	EG	Greene St.	8	Ductile Iron	56	17	0 out of 5	N/A	\$0
Distribution Main	12090	P-4600	EG	Greene St.	8	Ductile Iron	27	17	0 out of 5	N/A	\$0
Distribution Main	3941		EG	Greenwich Blvd	2	Unknown	56	41	1.71 out of 5	\$442	24,640
Distribution Main	6255		EG	Greenwich Blvd	2	Unknown	5	41	1.71 out of 5	\$442	2,018
Distribution Main	9475	P-40037	EG	Greenwich Blvd	1.5	Galvanized Iron	397	41	3.14 out of 5	\$442	175,628

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	908	P-4483	EG	Greenwich Blvd.	2	PVC	433	49	2 out of 5	\$442	191,224
Distribution Main	3943	P-4410	EG	Greenwich Blvd.	2	PVC	151	41	2 out of 5	\$442	66,619
Distribution Main	6261	P-4410	EG	Greenwich Blvd.	2	PVC	25	41	2 out of 5	\$442	11,227
Distribution Main	6059	P-4266	EG	Hamilton Dr.	6	Asbestos Cement	805	51	1.85 out of 5	\$442	355,714
Distribution Main	6060	P-4266	EG	Hamilton Dr.	6	Asbestos Cement	900	51	1.85 out of 5	\$442	397,671
Distribution Main	11830	P-4266	EG	Hamilton Dr.	6	Asbestos Cement	341	51	1.85 out of 5	\$442	150,801
Distribution Main	4992	P-4364	EG	Hanaford Dr.	6	Asbestos Cement	199	51	1.85 out of 5	\$442	88,032
Distribution Main	4993	P-4364	EG	Hanaford Dr.	6	Asbestos Cement	7	51	1.85 out of 5	\$442	2,919
Distribution Main	4994	P-4366	EG	Hanaford Dr.	6	Asbestos Cement	876	51	1.85 out of 5	\$442	387,218
Distribution Main	6394	P-4363	EG	Hanaford Dr.	6	Asbestos Cement	453	51	1.85 out of 5	\$442	200,358
Distribution Main	6029	P-4356	EG	Hanaford Drive	6	Asbestos Cement	505	50	1.85 out of 5	\$442	223,247
Distribution Main	3214	P-4235	EG	Harwood Rd.	6	Cast Iron	638	87	2.43 out of 5	\$442	281,860
Distribution Main	3215	P-4235	EG	Harwood Rd.	6	Cast Iron	450	87	2.43 out of 5	\$442	198,736
Distribution Main	4024	P-4458	EG	Hemlock Dr.	8	Asbestos Cement	850	50	1.14 out of 5	\$442	375,659
Distribution Main	4025	P-4458	EG	Hemlock Dr.	8	Asbestos Cement	38	50	1.14 out of 5	\$442	16,667
Distribution Main	4028	P-4458	EG	Hemlock Dr.	8	Asbestos Cement	49	50	1.14 out of 5	\$442	21,852
Distribution Main	4029	P-4449	EG	Hemlock Dr.	8	Asbestos Cement	57	50	1.14 out of 5	\$442	25,338
Distribution Main	4152		EG	Hemlock Dr.	8	Asbestos Cement	34	50	1.14 out of 5	\$442	15,182
Distribution Main	5623	P-4447	EG	Hemlock Dr.	8	Asbestos Cement	36	50	1.14 out of 5	\$442	15,936
Distribution Main	5627	P-4458	EG	Hemlock Dr.	6	Asbestos Cement	58	50	1.85 out of 5	\$442	25,570
Distribution Main	5958	P-4449	EG	Hemlock Dr.	8	Asbestos Cement	716	50	1.14 out of 5	\$442	316,586
Distribution Main	6191	P-4447	EG	Hemlock Dr.	8	Asbestos Cement	212	50	1.14 out of 5	\$442	93,912
Distribution Main	6192	P-4447	EG	Hemlock Dr.	8	Asbestos Cement	188	50	1.14 out of 5	\$442	83,234
Distribution Main	11768	P-4458	EG	Hemlock Dr.	8	Asbestos Cement	536	50	1.14 out of 5	\$442	237,008
Distribution Main	4903	P-4299	EG	Hickory Dr.	8	Asbestos Cement	67	51	1.14 out of 5	\$442	29,523
Distribution Main	4904	P-4300	EG	Hickory Dr.	8	Asbestos Cement	270	51	1.14 out of 5	\$442	119,351
Distribution Main	4905	P-4295	EG	Hickory Dr.	8	Asbestos Cement	261	51	1.14 out of 5	\$442	115,312
Distribution Main	4906	P-4295	EG	Hickory Dr.	8	Asbestos Cement	134	51	1.14 out of 5	\$442	59,276
Distribution Main	8317	P-4809	EG	Hidden Lane	8	Ductile Iron	716	14	0 out of 5	N/A	\$0
Distribution Main	8318	P-4809	EG	Hidden Lane	8	Ductile Iron	15	14	0 out of 5	N/A	\$0
Distribution Main	10106	P-4811	EG	Hidden Lane	8	Ductile Iron	398	14	0 out of 5	N/A	\$0
Distribution Main	11460	P-4809	EG	Hidden Lane	8	Ductile Iron	170	14	0 out of 5	N/A	\$0
Distribution Main	855	P-4050	EG	High Hawk Rd.	8	Asbestos Cement	511	49	1.14 out of 5	\$442	225,793
Distribution Main	856	P-4046	EG	High Hawk Rd.	8	Asbestos Cement	9	49	1.14 out of 5	\$442	3,838
Distribution Main	4365	P-40004	EG	High Hawk Rd.	8	Asbestos Cement	38	49	1.14 out of 5	\$442	16,917
Distribution Main	5043	P-4052	EG	High Hawk Rd.	8	Asbestos Cement	77	49	1.14 out of 5	\$442	34,048
Distribution Main	5044	P-4052	EG	High Hawk Rd.	8	Asbestos Cement	366	49	1.14 out of 5	\$442	161,750
Transmission Main	5811	P-4023	EG	High Hawk Rd.	12	PVC	307	33	0.43 out of 5	\$442	135,837
Transmission Main	5812	P-4023	EG	High Hawk Rd.	12	PVC	18	33	0.43 out of 5	\$442	8,036
Transmission Main	5813	P-4019	EG	High Hawk Rd.	12	PVC	366	33	0.43 out of 5	\$442	161,930
Distribution Main	5837	P-4053	EG	High Hawk Rd.	8	Asbestos Cement	989	49	1.14 out of 5	\$442	437,286
Transmission Main	5838	P-4040	EG	High Hawk Rd.	12	PVC	712	33	0.43 out of 5	\$442	314,808
Transmission Main	5839	P-4040	EG	High Hawk Rd.	12	PVC	13	33	0.43 out of 5	\$442	5,606
Distribution Main	5858	P-4042	EG	High Hawk Rd.	8	Asbestos Cement	493	49	1.14 out of 5	\$442	217,831

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5859	P-4042	EG	High Hawk Rd.	8	Asbestos Cement	884	49	1.14 out of 5	\$442	390,899
Transmission Main	5917	P-4029	EG	High Hawk Rd.	12	PVC	213	33	0.43 out of 5	\$442	94,281
Transmission Main	6292	P-4018	EG	High Hawk Rd.	12	PVC	283	33	0.43 out of 5	\$442	124,916
Transmission Main	6293	P-4018	EG	High Hawk Rd.	12	PVC	200	33	0.43 out of 5	\$442	88,253
Distribution Main	6587	P-4053	EG	High Hawk Rd.	8	Asbestos Cement	943	49	1.14 out of 5	\$442	416,811
Distribution Main	6592	P-4046	EG	High Hawk Rd.	8	Asbestos Cement	135	49	1.14 out of 5	\$442	59,604
Distribution Main	6777	P-4042	EG	High Hawk Rd.	8	Asbestos Cement	56	49	1.14 out of 5	\$442	24,872
Distribution Main	12085	P-4042	EG	High Hawk Rd.	8	Asbestos Cement	24	49	1.14 out of 5	\$442	10,801
Distribution Main	6006	P-4995	EG	Hill Dr	6	Ductile Iron	527	27	0.85 out of 5	\$442	233,126
Distribution Main	6008	P-4995	EG	Hill Dr	6	Ductile Iron	6	27	0.85 out of 5	\$442	2,727
Distribution Main	5244	P-4217	EG	Holly Hill Ct.	6	Asbestos Cement	155	51	1.85 out of 5	\$442	68,314
Distribution Main	5474	P-4500	EG	Howland Farms	8	Ductile Iron	467	29	0.14 out of 5	\$442	206,579
Distribution Main	5475	P-4500	EG	Howland Farms	8	Ductile Iron	1,331	29	0.14 out of 5	\$442	588,278
Distribution Main	11824	P-4500	EG	Howland Farms	8	Ductile Iron	46	29	0.14 out of 5	\$442	20,406
Distribution Main	374	P-4373	EG	Howland Rd.	8	Asbestos Cement	48	57	1.14 out of 5	\$442	21,297
Distribution Main	3837	P-4382	EG	Howland Rd.	8	Ductile Iron	296	42	0.29 out of 5	\$442	130,888
Distribution Main	4995	P-4978	EG	Howland Rd.	8	Asbestos Cement	148	57	1.14 out of 5	\$442	65,605
Distribution Main	5962	P-4454	EG	Howland Rd.	8	Asbestos Cement	299	57	1.14 out of 5	\$442	132,136
Distribution Main	5963	P-4488	EG	Howland Rd.	8	Asbestos Cement	559	57	1.14 out of 5	\$442	247,171
Distribution Main	6186	P-4373	EG	Howland Rd.	8	Asbestos Cement	847	57	1.14 out of 5	\$442	374,396
Distribution Main	6187	P-4373	EG	Howland Rd.	8	Asbestos Cement	1,094	57	1.14 out of 5	\$442	483,686
Distribution Main	6190	P-4487	EG	Howland Rd.	8	Asbestos Cement	170	57	1.14 out of 5	\$442	75,196
Distribution Main	6399	P-4376	EG	Howland Rd.	8	Ductile Iron	107	42	0.29 out of 5	\$442	47,223
Distribution Main	6400	P-4376	EG	Howland Rd.	8	Ductile Iron	241	42	0.29 out of 5	\$442	106,629
Distribution Main	6401	P-4381	EG	Howland Rd.	8	Ductile Iron	468	42	0.29 out of 5	\$442	207,002
Distribution Main	6402	P-4382	EG	Howland Rd.	8	Ductile Iron	21	42	0.29 out of 5	\$442	9,111
Distribution Main	6568	P-4978	EG	Howland Rd.	8	Asbestos Cement	453	57	1.14 out of 5	\$442	200,343
Distribution Main	6569	P-4978	EG	Howland Rd.	8	Asbestos Cement	605	57	1.14 out of 5	\$442	267,347
Distribution Main	5668	P-4106	EG	Hugenot Dr.	8	Asbestos Cement	36	43	1.14 out of 5	\$442	16,024
Distribution Main	5669	P-4106	EG	Hugenot Dr.	8	Asbestos Cement	548	43	1.14 out of 5	\$442	242,377
Distribution Main	6699	P-4107	EG	Hugenot Dr.	8	Asbestos Cement	300	44	1.14 out of 5	\$442	132,445
Distribution Main	6700	P-4107	EG	Hugenot Dr.	8	Asbestos Cement	257	44	1.14 out of 5	\$442	113,527
Distribution Main	5879	P-4100	EG	Huling Ln.	8	Ductile Iron	15	35	0.14 out of 5	\$442	6,478
Distribution Main	6693	P-4099	EG	Huling Ln.	8	Ductile Iron	375	35	0.14 out of 5	\$442	165,932
Distribution Main	6694	P-4099	EG	Huling Ln.	8	Ductile Iron	80	35	0.14 out of 5	\$442	35,578
Distribution Main	6695	P-4100	EG	Huling Ln.	8	Ductile Iron	596	35	0.14 out of 5	\$442	263,273
Transmission Main	5276	P-4008	EG	Hunters Crossing Rd.	12	Ductile Iron	69	30	0.14 out of 5	\$442	30,536
Transmission Main	5277	P-4008	EG	Hunters Crossing Rd.	12	Ductile Iron	475	30	0.14 out of 5	\$442	209,907
Transmission Main	11845	P-4008	EG	Hunters Crossing Rd.	12	Ductile Iron	277	30	0.14 out of 5	\$442	122,628
Distribution Main	9472	P-4977	EG	Hutchins Court	1.5	Copper	256	67	2.43 out of 5	\$442	113,030
Distribution Main	300	P-4679	EG	Hyland Ave.	8	Ductile Iron	26	17	0 out of 5	N/A	\$0
Distribution Main	1235	P-4679	EG	Hyland Ave.	8	Ductile Iron	105	17	0 out of 5	N/A	\$0
Distribution Main	1236	P-4679	EG	Hyland Ave.	8	Ductile Iron	483	17	0 out of 5	N/A	\$0
Distribution Main	1237	P-4543	EG	Hyland Ave.	8	Ductile Iron	185	17	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6152	P-4471	EG	Ivy Guarded Way	6	Ductile Iron	47	19	0.71 out of 5	N/A	\$0
Distribution Main	6153	P-4471	EG	Ivy Guarded Way	6	Ductile Iron	195	19	0.71 out of 5	N/A	\$0
Distribution Main	3924	P-4251	EG	Jefferson Dr.	8	Asbestos Cement	915	51	1.14 out of 5	\$442	404,651
Distribution Main	3925	P-4251	EG	Jefferson Dr.	8	Asbestos Cement	700	51	1.14 out of 5	\$442	309,320
Distribution Main	11826	P-4251	EG	Jefferson Dr.	8	Asbestos Cement	144	51	1.14 out of 5	\$442	63,820
Distribution Main	5671	P-4111	EG	Jodie Beth Cir.	8	Ductile Iron	18	24	0.14 out of 5	N/A	\$0
Distribution Main	5862	P-4111	EG	Jodie Beth Cir.	8	Ductile Iron	6	24	0.14 out of 5	N/A	\$0
Distribution Main	5864	P-4111	EG	Jodie Beth Cir.	8	Ductile Iron	463	24	0.14 out of 5	N/A	\$0
Distribution Main	5865	P-4111	EG	Jodie Beth Cir.	8	Ductile Iron	218	24	0.14 out of 5	N/A	\$0
Distribution Main	5868	P-4111	EG	Jodie Beth Cir.	8	Ductile Iron	6	24	0.14 out of 5	N/A	\$0
Distribution Main	5882	P-4109	EG	Jodie Beth Cir.	8	Asbestos Cement	798	46	1.14 out of 5	\$442	352,573
Distribution Main	5883	P-4109	EG	Jodie Beth Cir.	8	Asbestos Cement	572	46	1.14 out of 5	\$442	252,868
Distribution Main	6697	P-4109	EG	Jodie Beth Cir.	8	Asbestos Cement	22	46	1.14 out of 5	\$442	9,881
Distribution Main	5951	P-4386	EG	John Alden Rd.	6	Asbestos Cement	253	49	1.85 out of 5	\$442	111,747
Distribution Main	8820	P-4826	EG	Judge Torres Ln	8	Ductile Iron	573	14	0 out of 5	N/A	\$0
Distribution Main	8821	P-4826	EG	Judge Torres Ln	8	Ductile Iron	99	14	0 out of 5	N/A	\$0
Distribution Main	11515	P-4826	EG	Judge Torres Ln	8	Ductile Iron	356	14	0 out of 5	N/A	\$0
Distribution Main	11854	P-4826	EG	Judge Torres Ln	8	Ductile Iron	27	14	0 out of 5	N/A	\$0
Transmission Main	3302	P-4006	EG	Juniper Drive	12	Ductile Iron	8	30	0.14 out of 5	\$442	3,546
Transmission Main	3461	P-4011	EG	Juniper Drive	12	Ductile Iron	14	27	0.14 out of 5	\$442	6,075
Transmission Main	4587	P-4006	EG	Juniper Drive	12	Ductile Iron	222	30	0.14 out of 5	\$442	98,246
Transmission Main	4588	P-4006	EG	Juniper Drive	12	Ductile Iron	489	30	0.14 out of 5	\$442	216,118
Distribution Main	5267	P-4013	EG	Juniper Drive	8	Ductile Iron	321	27	0.14 out of 5	\$442	141,838
Transmission Main	5268	P-4009	EG	Juniper Drive	12	Ductile Iron	415	27	0.14 out of 5	\$442	183,530
Transmission Main	5269	P-4009	EG	Juniper Drive	12	Ductile Iron	5	27	0.14 out of 5	\$442	2,201
Transmission Main	5272	P-4011	EG	Juniper Drive	12	Ductile Iron	166	27	0.14 out of 5	\$442	73,590
Transmission Main	5273	P-4011	EG	Juniper Drive	12	Ductile Iron	210	27	0.14 out of 5	\$442	92,615
Transmission Main	5274	P-4009	EG	Juniper Drive	12	Ductile Iron	61	27	0.14 out of 5	\$442	26,799
Transmission Main	5275	P-4009	EG	Juniper Drive	12	Ductile Iron	365	27	0.14 out of 5	\$442	161,184
Transmission Main	1233	P-4007	EG	Juniper Rd.	12	Ductile Iron	135	30	0.14 out of 5	\$442	59,794
Transmission Main	1234	P-4007	EG	Juniper Rd.	12	Ductile Iron	403	30	0.14 out of 5	\$442	178,010
Distribution Main	4182	P-4976	EG	Kenson Dr.	6	Asbestos Cement	514	69	2 out of 5	\$442	227,179
Distribution Main	4183	P-4976	EG	Kenson Dr.	6	Asbestos Cement	59	69	2 out of 5	\$442	25,985
Distribution Main	12184		EG	Kenson Dr.	6	Asbestos Cement	483	69	2 out of 5	\$442	213,488
Distribution Main	454	P-4389	EG	Kent Dr.	8	Asbestos Cement	830	51	1.14 out of 5	\$442	367,056
Distribution Main	457	P-4387	EG	Kent Dr.	8	Asbestos Cement	49	51	1.14 out of 5	\$442	21,772
Distribution Main	2508	P-4390	EG	Kent Dr.	8	Asbestos Cement	423	51	1.14 out of 5	\$442	187,054
Distribution Main	2509	P-4390	EG	Kent Dr.	8	Asbestos Cement	60	51	1.14 out of 5	\$442	26,560
Distribution Main	4037	P-4352	EG	Kent Dr.	6	Asbestos Cement	443	51	1.85 out of 5	\$442	195,619
Distribution Main	4038	P-4352	EG	Kent Dr.	6	Asbestos Cement	550	51	1.85 out of 5	\$442	243,301
Distribution Main	4991	P-4361	EG	Kent Dr.	6	Asbestos Cement	10	51	1.85 out of 5	\$442	4,487
Distribution Main	6375	P-4389	EG	Kent Dr.	8	Asbestos Cement	29	51	1.14 out of 5	\$442	12,747
Distribution Main	6377	P-4984	EG	Kent Dr.	8	Asbestos Cement	137	51	1.14 out of 5	\$442	60,405
Distribution Main	6378	P-4984	EG	Kent Dr.	8	Asbestos Cement	32	51	1.14 out of 5	\$442	14,258

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6396	P-4362	EG	Kent Dr.	6	Asbestos Cement	676	51	1.85 out of 5	\$442	298,916
Distribution Main	6397	P-4362	EG	Kent Dr.	6	Asbestos Cement	511	51	1.85 out of 5	\$442	225,765
Distribution Main	6398	P-4361	EG	Kent Dr.	6	Asbestos Cement	330	51	1.85 out of 5	\$442	145,915
Distribution Main	10206	P-4986	EG	Kent Dr.	8	Asbestos Cement	8	51	1.14 out of 5	\$442	3,755
Distribution Main	9350		EG	Kenyon Ave	4	Ductile Iron	30	8	1.42 out of 5	N/A	\$0
Distribution Main	360	P-4544	EG	Kenyon Ave.	6	Cast Iron	308	133	2.57 out of 5	\$442	136,040
Distribution Main	665	P-4527	EG	Kenyon Ave.	8	Asbestos Cement	350	70	1.29 out of 5	\$442	154,596
Distribution Main	913	P-4540	EG	Kenyon Ave.	6	Cast Iron	180	133	2.57 out of 5	\$442	79,415
Distribution Main	2394	P-4544	EG	Kenyon Ave.	6	Cast Iron	21	133	2.57 out of 5	\$442	9,281
Distribution Main	3933	P-4545	EG	Kenyon Ave.	6	Cast Iron	244	133	2.57 out of 5	\$442	107,709
Distribution Main	3936	P-4549	EG	Kenyon Ave.	6	Cast Iron	36	133	2.57 out of 5	\$442	15,776
Distribution Main	4164	P-4542	EG	Kenyon Ave.	6	Cast Iron	118	133	2.57 out of 5	\$442	52,020
Distribution Main	4165	P-4542	EG	Kenyon Ave.	6	Cast Iron	51	133	2.57 out of 5	\$442	22,557
Distribution Main	4180	P-4527	EG	Kenyon Ave.	8	Asbestos Cement	243	53	1.14 out of 5	\$442	107,569
Distribution Main	4184	P-4527	EG	Kenyon Ave.	8	Asbestos Cement	292	70	1.29 out of 5	\$442	128,860
Distribution Main	5424	P-4531	EG	Kenyon Ave.	8	Asbestos Cement	10	70	1.29 out of 5	\$442	4,636
Transmission Main	5426	P-4234	EG	Kenyon Ave.	20	Asbestos Cement	23	55	1.14 out of 5	\$442	10,345
Transmission Main	5427	P-4234	EG	Kenyon Ave.	20	Asbestos Cement	1,619	55	1.14 out of 5	\$442	715,813
Distribution Main	5688	P-4975	EG	Kenyon Ave.	8	Ductile Iron	5	17	0 out of 5	N/A	\$0
Distribution Main	5689	P-4975	EG	Kenyon Ave.	8	Ductile Iron	18	17	0 out of 5	N/A	\$0
Distribution Main	6199	P-4973	EG	Kenyon Ave.	8	Ductile Iron	20	17	0 out of 5	N/A	\$0
Distribution Main	6210	P-4531	EG	Kenyon Ave.	8	Asbestos Cement	1,027	70	2 out of 5	\$442	454,069
Distribution Main	6211	P-4531	EG	Kenyon Ave.	8	Asbestos Cement	14	70	1.29 out of 5	\$442	6,115
Transmission Main	6212	P-4234	EG	Kenyon Ave.	20	Asbestos Cement	72	55	1.14 out of 5	\$442	32,021
Transmission Main	6213	P-4234	EG	Kenyon Ave.	20	Asbestos Cement	35	55	1.14 out of 5	\$442	15,585
Distribution Main	6276	P-4549	EG	Kenyon Ave.	6	Cast Iron	565	133	2.57 out of 5	\$442	249,671
Distribution Main	9448	P-4542	EG	Kenyon Ave.	6	Cast Iron	114	133	2.57 out of 5	\$442	50,184
Transmission Main	9449	P-2649	EG	Kenyon Ave.	20	Asbestos Cement	79	55	1.14 out of 5	\$442	34,844
Transmission Main	9450	P-4235	EG	Kenyon Ave.	20	Asbestos Cement	712	55	1.14 out of 5	\$442	314,668
Transmission Main	9451	P-4235	EG	Kenyon Ave.	20	Asbestos Cement	609	55	1.14 out of 5	\$442	269,366
Transmission Main	9452	P-4235	EG	Kenyon Ave.	20	Asbestos Cement	381	55	1.14 out of 5	\$442	168,252
Distribution Main	11326	P-4973	EG	Kenyon Ave.	8	Ductile Iron	16	17	0 out of 5	N/A	\$0
Distribution Main	9238	P-4202	EG	King Philip Tr	8	Ductile Iron	197	8	0 out of 5	N/A	\$0
Distribution Main	9241	P-4200	EG	King Philip Tr	8	Ductile Iron	61	8	0 out of 5	N/A	\$0
Distribution Main	9242	P-4200	EG	King Philip Tr	8	Ductile Iron	157	8	0 out of 5	N/A	\$0
Distribution Main	10969	P-40011	EG	King Philip Tr	8	Ductile Iron	97	8	0 out of 5	N/A	\$0
Distribution Main	11561	P-4200	EG	King Philip Tr	8	Ductile Iron	38	8	0 out of 5	N/A	\$0
Distribution Main	6388	P-4211	EG	King Philip Tr.	8	Ductile Iron	233	8	0 out of 5	N/A	\$0
Transmission Main	9170	P-4900	EG	King St	12	Ductile Iron	49	8	0 out of 5	N/A	\$0
Distribution Main	9172	P-4618	EG	King St	6	Ductile Iron	13	8	0.71 out of 5	N/A	\$0
Distribution Main	9175	P-4908	EG	King St	6	Ductile Iron	10	8	0.71 out of 5	N/A	\$0
Distribution Main	9176	P-4908	EG	King St	6	Ductile Iron	8	8	0.71 out of 5	N/A	\$0
Distribution Main	9177	P-4906	EG	King St	6	Ductile Iron	7	8	0.71 out of 5	N/A	\$0
Distribution Main	9178	P-4906	EG	King St	6	Ductile Iron	1	8	0.71 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9194	P-4906	EG	King St	8	Ductile Iron	6	8	0 out of 5	N/A	\$0
Distribution Main	9195	P-4628	EG	King St	8	Ductile Iron	5	8	0 out of 5	N/A	\$0
Transmission Main	11551	P-4900	EG	King St	12	Ductile Iron	6	8	0 out of 5	N/A	\$0
Distribution Main	1895	P-4618	EG	King St.	6	Cast Iron	13	133	2.57 out of 5	\$442	5,825
Distribution Main	1896	P-4618	EG	King St.	6	Cast Iron	16	133	2.57 out of 5	\$442	6,883
Distribution Main	2410	P-4617	EG	King St.	6	Cast Iron	110	133	2.57 out of 5	\$442	48,745
Distribution Main	4849	P-4622	EG	King St.	6	Cast Iron	12	32	1.99 out of 5	\$442	5,513
Distribution Main	4850	P-4622	EG	King St.	6	Cast Iron	19	32	1.99 out of 5	\$442	8,224
Distribution Main	4851	P-4622	EG	King St.	6	Cast Iron	8	32	1.99 out of 5	\$442	3,503
Distribution Main	5535	P-4902	EG	King St.	2	Copper	70	32	2.14 out of 5	\$442	30,761
Distribution Main	5537	P-4901	EG	King St.	6	Cast Iron	73	32	1.99 out of 5	\$442	32,352
Distribution Main	5676	P-4615	EG	King St.	6	Cast Iron	209	133	2.57 out of 5	\$442	92,405
Distribution Main	6277	P-4613	EG	King St.	6	Cast Iron	224	133	2.57 out of 5	\$442	99,023
Distribution Main	6686	P-4910	EG	King St.	8	Cast Iron	13	133	1.86 out of 5	\$442	5,859
Distribution Main	6717	P-4618	EG	King St.	6	Cast Iron	57	133	2.57 out of 5	\$442	25,029
Distribution Main	6732	P-4622	EG	King St.	6	Cast Iron	287	32	1.99 out of 5	\$442	126,823
Distribution Main	6734	P-4901	EG	King St.	6	Ductile Iron	2	4	0.71 out of 5	N/A	\$0
Distribution Main	6736	P-4902	EG	King St.	2	Copper	2	32	2.14 out of 5	\$442	934
Distribution Main	6761	P-4613	EG	King St.	6	Cast Iron	22	133	2.57 out of 5	\$442	9,612
Distribution Main	6763	P-4910	EG	King St.	8	Cast Iron	6	133	1.86 out of 5	\$442	2,680
Distribution Main	9446	P-4615	EG	King St.	6	Cast Iron	5	133	2.57 out of 5	\$442	2,084
Distribution Main	9447	P-4615	EG	King St.	6	Cast Iron	11	133	2.57 out of 5	\$442	4,740
Distribution Main	5506	P-4110	EG	Kirker Dr.	8	Asbestos Cement	393	46	1.14 out of 5	\$442	173,609
Distribution Main	5507	P-4110	EG	Kirker Dr.	8	Asbestos Cement	540	46	1.14 out of 5	\$442	238,736
Distribution Main	664	P-4529	EG	Knollwood Ave.	6	Asbestos Cement	170	69	2 out of 5	\$442	75,211
Distribution Main	4187	P-4529	EG	Knollwood Ave.	6	Asbestos Cement	32	69	2 out of 5	\$442	13,923
Distribution Main	4188	P-4528	EG	Knollwood Ave.	6	Asbestos Cement	1,128	69	2 out of 5	\$442	498,425
Distribution Main	4189	P-4528	EG	Knollwood Ave.	6	Asbestos Cement	116	69	2 out of 5	\$442	51,484
Distribution Main	6208	P-4529	EG	Knollwood Ave.	6	Asbestos Cement	662	69	2 out of 5	\$442	292,433
Distribution Main	6209	P-4528	EG	Knollwood Ave.	6	Asbestos Cement	29	69	2 out of 5	\$442	12,850
Distribution Main	2908	P-4422	EG	Lafayette Dr.	6	Asbestos Cement	27	50	1.85 out of 5	\$442	11,785
Distribution Main	6142	P-4422	EG	Lafayette Dr.	6	Asbestos Cement	456	50	1.85 out of 5	\$442	201,646
Distribution Main	6143	P-4422	EG	Lafayette Dr.	6	Asbestos Cement	614	50	1.85 out of 5	\$442	271,440
Distribution Main	6476	P-4419	EG	Landover Dr.	6	Asbestos Cement	310	60	1.85 out of 5	\$442	137,204
Distribution Main	6477	P-4421	EG	Landover Dr.	6	Asbestos Cement	278	60	1.85 out of 5	\$442	122,702
Distribution Main	5600	P-4326	EG	Larch Rd.	6	Asbestos Cement	418	50	1.85 out of 5	\$442	184,949
Distribution Main	5606	P-4327	EG	Larch Rd.	6	Asbestos Cement	355	50	1.85 out of 5	\$442	156,773
Distribution Main	5607	P-4327	EG	Larch Rd.	6	Asbestos Cement	680	50	1.85 out of 5	\$442	300,438
Distribution Main	5601	P-4310	EG	Laurel Hill Rd.	6	Asbestos Cement	932	60	1.85 out of 5	\$442	412,104
Distribution Main	5602	P-4310	EG	Laurel Hill Rd.	6	Asbestos Cement	29	60	1.85 out of 5	\$442	12,637
Distribution Main	6407	P-4304	EG	Laurel Hill Rd.	6	Asbestos Cement	849	60	1.85 out of 5	\$442	375,374
Distribution Main	9230	P-40016	EG	Laurel Ln	8	Ductile Iron	258	8	0 out of 5	N/A	\$0
Distribution Main	5841	P-4086	EG	Laurel Woods Dr.	8	Ductile Iron	352	24	0.14 out of 5	N/A	\$0
Distribution Main	5842	P-4087	EG	Laurel Woods Dr.	8	Ductile Iron	647	24	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5843	P-4087	EG	Laurel Woods Dr.	8	Ductile Iron	28	24	0.14 out of 5	N/A	\$0
Distribution Main	5845	P-4087	EG	Laurel Woods Dr.	8	Ductile Iron	18	24	0.14 out of 5	N/A	\$0
Distribution Main	5846	P-4087	EG	Laurel Woods Dr.	8	Ductile Iron	342	24	0.14 out of 5	N/A	\$0
Distribution Main	5847	P-4088	EG	Laurel Woods Dr.	8	Ductile Iron	1,211	24	0.14 out of 5	N/A	\$0
Distribution Main	5848	P-4086	EG	Laurel Woods Dr.	8	Ductile Iron	447	24	0.14 out of 5	N/A	\$0
Distribution Main	5844	P-4089	EG	Laurel Woods Easement	8	Ductile Iron	423	24	0.14 out of 5	N/A	\$0
Distribution Main	4146	P-4426	EG	Le Baron Dr.	6	Asbestos Cement	269	51	1.85 out of 5	\$442	119,095
Distribution Main	4190	P-40028	EG	Le Baron Dr.	6	Asbestos Cement	127	51	1.85 out of 5	\$442	55,954
Distribution Main	4191		EG	Le Baron Dr.	6	Unknown	87	UNK	0.71 out of 5	\$442	38,601
Transmission Main	6063	P-4232	EG	Le Baron Dr.	20	Asbestos Cement	998	55	1.14 out of 5	\$442	441,258
Distribution Main	6144	P-4426	EG	Le Baron Dr.	6	Asbestos Cement	12	51	1.85 out of 5	\$442	5,125
Distribution Main	6468	P-4420	EG	Le Baron Dr.	6	Asbestos Cement	182	51	1.85 out of 5	\$442	80,329
Distribution Main	6485	P-4425	EG	Le Baron Dr.	6	Asbestos Cement	76	51	1.85 out of 5	\$442	33,773
Distribution Main	6486	P-4438	EG	Le Baron Dr.	6	Asbestos Cement	185	51	1.85 out of 5	\$442	81,805
Distribution Main	11340	P-4420	EG	Le Baron Dr.	6	Asbestos Cement	5	51	1.85 out of 5	\$442	2,140
Distribution Main	6490	P-4436	EG	Lebaron Dr.	6	Asbestos Cement	120	65	2 out of 5	\$442	53,131
Distribution Main	6200	P-4541	EG	Ledge Rd.	8	Ductile Iron	72	17	0 out of 5	N/A	\$0
Distribution Main	6201	P-4541	EG	Ledge Rd.	8	Ductile Iron	352	17	0 out of 5	N/A	\$0
Distribution Main	6202	P-4541	EG	Ledge Rd.	8	Ductile Iron	222	17	0 out of 5	N/A	\$0
Distribution Main	9004	P-4541	EG	Ledge Rd.	8	Ductile Iron	35	17	0 out of 5	N/A	\$0
Distribution Main	3651	P-4154	EG	Lenihan Lane	8	Ductile Iron	488	17	0 out of 5	N/A	\$0
Distribution Main	3652	P-4154	EG	Lenihan Lane	8	Ductile Iron	636	17	0 out of 5	N/A	\$0
Distribution Main	5728	P-4824	EG	Lenihan Lane	8	Ductile Iron	958	17	0 out of 5	N/A	\$0
Distribution Main	9994	P-4154	EG	Lenihan Lane	8	Ductile Iron	320	17	0 out of 5	N/A	\$0
Distribution Main	11223	P-4154	EG	Lenihan Lane	8	Ductile Iron	128	17	0 out of 5	N/A	\$0
Distribution Main	8819	P-4155	EG	Lenihan Ln	8	Ductile Iron	591	14	0 out of 5	N/A	\$0
Distribution Main	9051		EG	Lenihan Ln	2	Ductile Iron	19	17	1.42 out of 5	N/A	\$0
Distribution Main	9993	P-4824	EG	Lenihan Ln	8	Ductile Iron	136	14	0 out of 5	N/A	\$0
Distribution Main	10295		EG	Lenihan Ln	8	Ductile Iron	247	4	0 out of 5	N/A	\$0
Distribution Main	893	P-4604	EG	Liberty St.	8	Ductile Iron	18	17	0 out of 5	N/A	\$0
Distribution Main	894	P-4604	EG	Liberty St.	8	Ductile Iron	397	17	0 out of 5	N/A	\$0
Distribution Main	895	P-4604	EG	Liberty St.	8	Ductile Iron	19	17	0 out of 5	N/A	\$0
Distribution Main	6243	P-4950	EG	Liberty St.	8	Ductile Iron	273	17	0 out of 5	N/A	\$0
Distribution Main	10904	P-4953	EG	Liberty St.	8	Ductile Iron	49	17	0 out of 5	N/A	\$0
Distribution Main	2477	P-4351	EG	Lilian Street	6	Asbestos Cement	475	57	1.85 out of 5	\$442	210,013
Distribution Main	3659	P-4428	EG	Lillibridge Dr.	6	Asbestos Cement	616	57	1.85 out of 5	\$442	272,125
Distribution Main	6052	P-4128	EG	Limerock Dr.	6	Asbestos Cement	776	42	1.85 out of 5	\$442	343,073
Distribution Main	6053	P-4128	EG	Limerock Dr.	6	Asbestos Cement	243	42	1.85 out of 5	\$442	107,271
Distribution Main	6230	P-4691	EG	Lincoln St.	8	Ductile Iron	268	17	0 out of 5	N/A	\$0
Distribution Main	9028	P-4691	EG	Lincoln St.	8	Ductile Iron	174	17	0 out of 5	N/A	\$0
Distribution Main	10382		EG	Lincoln St.	8	Ductile Iron	33	17	0 out of 5	N/A	\$0
Distribution Main	899	P-4648	EG	Lion St.	6	Ductile Iron	4	19	0.71 out of 5	N/A	\$0
Distribution Main	5786	P-4653	EG	Lion St.	8	Ductile Iron	230	19	0 out of 5	N/A	\$0
Distribution Main	6236	P-4648	EG	Lion St.	8	Ductile Iron	5	19	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6239	P-4648	EG	Lion St.	6	Ductile Iron	31	19	0.71 out of 5	N/A	\$0
Distribution Main	6760	P-4648	EG	Lion St.	8	Ductile Iron	152	19	0 out of 5	N/A	\$0
Distribution Main	4900	P-4277	EG	Locust Drive	6	Asbestos Cement	724	51	1.85 out of 5	\$442	319,967
Distribution Main	4901	P-4277	EG	Locust Drive	6	Asbestos Cement	32	51	1.85 out of 5	\$442	14,064
Distribution Main	4250		EG	London St	4	Unknown	4	UNK	1.42 out of 5	\$442	1,643
Distribution Main	4264	P-4647	EG	London St	6	Ductile Iron	120	32	0.85 out of 5	\$442	53,204
Distribution Main	6752	P-4647	EG	London St	6	Ductile Iron	4	32	0.85 out of 5	\$442	1,663
Distribution Main	9182	P-4642	EG	London St	8	Ductile Iron	154	8	0 out of 5	N/A	\$0
Transmission Main	9183	P-4926	EG	London St	12	Ductile Iron	2	8	0 out of 5	N/A	\$0
Transmission Main	9184	P-4926	EG	London St	12	Ductile Iron	18	8	0 out of 5	N/A	\$0
Distribution Main	9305	P-4643	EG	London St	6	Ductile Iron	12	8	0.71 out of 5	N/A	\$0
Distribution Main	10910	P-4636	EG	London St	8	Ductile Iron	55	8	0 out of 5	N/A	\$0
Distribution Main	11552	P-4642	EG	London St	8	Ductile Iron	12	8	0 out of 5	N/A	\$0
Distribution Main	12105	P-4642	EG	London St	8	Ductile Iron	12	8	0 out of 5	N/A	\$0
Distribution Main	4263	P-4929	EG	London St.	6	Cast Iron	15	133	2.57 out of 5	\$442	6,472
Distribution Main	6237	P-4930	EG	London St.	6	Ductile Iron	66	32	0.85 out of 5	\$442	29,231
Distribution Main	6238	P-4930	EG	London St.	6	Ductile Iron	37	32	0.85 out of 5	\$442	16,409
Transmission Main	6245	P-4638	EG	London St.	12	Asbestos Cement	173	60	1.14 out of 5	\$442	76,251
Distribution Main	6247		EG	London St.	6	Cast Iron	38	133	2.57 out of 5	\$442	16,783
Distribution Main	6643	P-4643	EG	London St.	6	Cast Iron	55	133	2.57 out of 5	\$442	24,329
Transmission Main	6722	P-4635	EG	London St.	12	Asbestos Cement	63	60	1.14 out of 5	\$442	27,657
Transmission Main	6738	P-4638	EG	London St.	12	Asbestos Cement	6	60	1.14 out of 5	\$442	2,867
Distribution Main	6751	P-4930	EG	London St.	6	Ductile Iron	3	32	0.85 out of 5	\$442	1,449
Distribution Main	6753	P-4929	EG	London St.	6	Cast Iron	16	133	2.57 out of 5	\$442	7,215
Transmission Main	9202	P-4638	EG	London St.	12	Ductile Iron	23	8	0 out of 5	N/A	\$0
Distribution Main	884	P-4645	EG	Long St.	8	Ductile Iron	225	17	0 out of 5	N/A	\$0
Distribution Main	5403	P-4651	EG	Long St.	8	Ductile Iron	125	19	0 out of 5	N/A	\$0
Distribution Main	5405	P-4652	EG	Long St.	8	Ductile Iron	5	19	0 out of 5	N/A	\$0
Distribution Main	5409	P-4651	EG	Long St.	8	Ductile Iron	8	19	0 out of 5	N/A	\$0
Distribution Main	6234	P-4652	EG	Long St.	8	Ductile Iron	242	19	0 out of 5	N/A	\$0
Distribution Main	6235	P-4652	EG	Long St.	8	Ductile Iron	23	19	0 out of 5	N/A	\$0
Distribution Main	6759	P-4651	EG	Long St.	8	Ductile Iron	3	19	0 out of 5	N/A	\$0
Distribution Main	3875		EG	Longmeadow Dr.	8	Ductile Iron	19	UNK	0 out of 5	N/A	\$0
Distribution Main	3876		EG	Longmeadow Dr.	8	Ductile Iron	4	UNK	0 out of 5	N/A	\$0
Distribution Main	3877		EG	Longmeadow Dr.	8	Ductile Iron	223	UNK	0 out of 5	N/A	\$0
Distribution Main	3878		EG	Longmeadow Dr.	8	Ductile Iron	485	UNK	0 out of 5	N/A	\$0
Distribution Main	4092		EG	Longmeadow Dr.	8	Ductile Iron	195	UNK	0 out of 5	N/A	\$0
Distribution Main	4093		EG	Longmeadow Dr.	8	Ductile Iron	412	16	0 out of 5	N/A	\$0
Distribution Main	4094		EG	Longmeadow Dr.	8	Ductile Iron	44	16	0 out of 5	N/A	\$0
Distribution Main	4928	P-4000	EG	Longmeadow Dr.	8	Ductile Iron	745	16	0 out of 5	N/A	\$0
Distribution Main	4929	P-4000	EG	Longmeadow Dr.	8	Ductile Iron	275	16	0 out of 5	N/A	\$0
Distribution Main	6353	P-4000	EG	Longmeadow Dr.	8	Ductile Iron	366	16	0 out of 5	N/A	\$0
Distribution Main	6354	P-4000	EG	Longmeadow Dr.	8	Ductile Iron	11	16	0 out of 5	N/A	\$0
Distribution Main	6355	P-4000	EG	Longmeadow Dr.	8	Ductile Iron	40	16	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6356	P-4000	EG	Longmeadow Dr.	8	Ductile Iron	121	16	0 out of 5	N/A	\$0
Distribution Main	6357	P-4000	EG	Longmeadow Dr.	8	Ductile Iron	83	16	0 out of 5	N/A	\$0
Distribution Main	6363	P-4000	EG	Longmeadow Dr.	8	Ductile Iron	65	16	0 out of 5	N/A	\$0
Distribution Main	8822	P-4829	EG	Lovegreen Ln	8	Ductile Iron	386	14	0 out of 5	N/A	\$0
Distribution Main	8823	P-4829	EG	Lovegreen Ln	8	Ductile Iron	414	14	0 out of 5	N/A	\$0
Distribution Main	6574	P-4137	EG	Lynn Cir.	8	PVC	24	33	0.43 out of 5	\$442	10,806
Distribution Main	6575	P-4137	EG	Lynn Cir.	8	PVC	172	33	0.43 out of 5	\$442	75,850
Distribution Main	6580	P-4135	EG	Lynn Cir.	8	PVC	583	33	0.43 out of 5	\$442	257,492
Distribution Main	6581	P-4135	EG	Lynn Cir.	8	PVC	701	33	0.43 out of 5	\$442	310,040
Distribution Main	11837	P-4135	EG	Lynn Cir.	8	PVC	369	33	0.43 out of 5	\$442	163,236
Distribution Main	11838	P-4135	EG	Lynn Cir.	8	PVC	552	33	0.43 out of 5	\$442	244,177
Distribution Main	10178		EG	Main St	4	Ductile Iron	1	17	1.42 out of 5	N/A	\$0
Distribution Main	883	P-4935	EG	Main St.	10	Ductile Iron	24	17	0 out of 5	N/A	\$0
Distribution Main	885	P-4932	EG	Main St.	10	Ductile Iron	6	17	0 out of 5	N/A	\$0
Distribution Main	886	P-4641	EG	Main St.	10	Cast Iron	3	133	1.86 out of 5	\$442	1,434
Distribution Main	887	P-4641	EG	Main St.	10	Cast Iron	320	133	1.86 out of 5	\$442	141,477
Distribution Main	890	P-4598	EG	Main St.	10	Cast Iron	169	133	1.86 out of 5	\$442	74,844
Distribution Main	891	P-4949	EG	Main St.	10	Ductile Iron	14	17	0 out of 5	N/A	\$0
Distribution Main	892	P-4657	EG	Main St.	10	Cast Iron	290	133	1.86 out of 5	\$442	128,323
Distribution Main	4251	P-4279	EG	Main St.	10	Cast Iron	245	133	1.86 out of 5	\$442	108,125
Distribution Main	4253	P-4937	EG	Main St.	10	Ductile Iron	22	17	0 out of 5	N/A	\$0
Distribution Main	4257	P-4633	EG	Main St.	8	Cast Iron	413	133	1.86 out of 5	\$442	182,595
Distribution Main	4258	P-4633	EG	Main St.	8	Cast Iron	342	133	1.86 out of 5	\$442	150,979
Distribution Main	4423	P-4594	EG	Main St.	10	Cast Iron	399	133	1.86 out of 5	\$442	176,296
Distribution Main	4578	P-4692	EG	Main St.	10	Cast Iron	6	133	1.86 out of 5	\$442	2,847
Distribution Main	4579	P-4692	EG	Main St.	10	Cast Iron	234	133	1.86 out of 5	\$442	103,567
Distribution Main	5674	P-4612	EG	Main St.	8	Cast Iron	5	133	1.86 out of 5	\$442	2,421
Distribution Main	5675	P-4612	EG	Main St.	8	Cast Iron	18	133	1.86 out of 5	\$442	8,055
Distribution Main	5677	P-4687	EG	Main St.	8	Cast Iron	194	133	1.86 out of 5	\$442	85,921
Distribution Main	5680	P-4263	EG	Main St.	10	Ductile Iron	250	33	0.14 out of 5	\$442	110,488
Distribution Main	5681	P-4263	EG	Main St.	10	Ductile Iron	93	33	0.14 out of 5	\$442	41,120
Distribution Main	5684	P-4924	EG	Main St.	10	Cast Iron	19	133	1.86 out of 5	\$442	8,395
Distribution Main	5685	P-4924	EG	Main St.	10	Cast Iron	49	133	1.86 out of 5	\$442	21,839
Distribution Main	5686	P-4633	EG	Main St.	8	Cast Iron	2	133	1.86 out of 5	\$442	743
Distribution Main	6248	P-40036	EG	Main St.	10	Ductile Iron	327	33	0.14 out of 5	\$442	144,589
Distribution Main	6257	P-4279	EG	Main St.	10	Cast Iron	197	133	1.86 out of 5	\$442	87,130
Distribution Main	6259	P-4594	EG	Main St.	10	Cast Iron	19	133	1.86 out of 5	\$442	8,420
Distribution Main	6273	P-4612	EG	Main St.	8	Cast Iron	113	133	1.86 out of 5	\$442	49,993
Distribution Main	6274	P-4612	EG	Main St.	8	Cast Iron	228	133	1.86 out of 5	\$442	100,577
Distribution Main	6275	P-4612	EG	Main St.	8	Cast Iron	157	133	1.86 out of 5	\$442	69,194
Distribution Main	6281	P-4612	EG	Main St.	8	Cast Iron	53	133	1.86 out of 5	\$442	23,547
Distribution Main	6638	P-40036	EG	Main St.	10	Ductile Iron	14	33	0.14 out of 5	\$442	6,071
Distribution Main	6641	P-4279	EG	Main St.	10	Cast Iron	10	133	1.86 out of 5	\$442	4,317
Distribution Main	6688	P-4279	EG	Main St.	10	Cast Iron	23	133	1.86 out of 5	\$442	10,154

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6689	P-4279	EG	Main St.	10	Cast Iron	25	133	1.86 out of 5	\$442	10,838
Distribution Main	6729	P-4623	EG	Main St.	8	Cast Iron	31	133	1.86 out of 5	\$442	13,827
Distribution Main	6730	P-4623	EG	Main St.	8	Cast Iron	255	133	1.86 out of 5	\$442	112,554
Distribution Main	6766	P-4891	EG	Main St.	8	Cast Iron	15	133	1.86 out of 5	\$442	6,808
Distribution Main	6767	P-4892	EG	Main St.	8	Cast Iron	5	133	1.86 out of 5	\$442	2,034
Distribution Main	9006	P-4657	EG	Main St.	10	Cast Iron	4	133	1.86 out of 5	\$442	1,758
Distribution Main	9027	P-4911	EG	Main St.	10	Ductile Iron	6	17	0 out of 5	N/A	\$0
Distribution Main	9312	P-4598	EG	Main St.	10	Ductile Iron	13	17	0 out of 5	N/A	\$0
Distribution Main	9442	P-4939	EG	Main St.	10	Cast Iron	67	133	1.86 out of 5	\$442	29,741
Distribution Main	10906	P-4657	EG	Main St.	10	Ductile Iron	10	17	0 out of 5	N/A	\$0
Distribution Main	10980	P-4931	EG	Main St.	10	Ductile Iron	5	17	0 out of 5	N/A	\$0
Distribution Main	11007	P-4623	EG	Main St.	10	Ductile Iron	4	17	0 out of 5	N/A	\$0
Distribution Main	11008	P-4936	EG	Main St.	10	Ductile Iron	15	17	0 out of 5	N/A	\$0
Distribution Main	11311	P-4612	EG	Main St.	8	Cast Iron	10	133	1.86 out of 5	\$442	4,488
Distribution Main	11312	P-4612	EG	Main St.	8	Cast Iron	3	133	1.86 out of 5	\$442	1,302
Distribution Main	11815	P-4623	EG	Main St.	8	Cast Iron	14	133	1.86 out of 5	\$442	6,074
Distribution Main	12091	P-4612	EG	Main St.	8	Cast Iron	64	133	1.86 out of 5	\$442	28,429
Transmission Main	5270	P-4010	EG	Mallard Way	12	Ductile Iron	450	27	0.14 out of 5	\$442	199,043
Transmission Main	5271	P-4010	EG	Mallard Way	12	Ductile Iron	297	27	0.14 out of 5	\$442	131,057
Distribution Main	1814	P-4394	EG	Maplewood Dr.	8	Asbestos Cement	478	59	1.14 out of 5	\$442	211,261
Distribution Main	4891	P-4395	EG	Maplewood Dr.	8	Asbestos Cement	728	59	1.14 out of 5	\$442	321,766
Distribution Main	4892	P-4395	EG	Maplewood Dr.	8	Asbestos Cement	232	59	1.14 out of 5	\$442	102,481
Distribution Main	4902	P-4290	EG	Maplewood Dr.	8	Asbestos Cement	790	59	1.14 out of 5	\$442	348,981
Distribution Main	6145	P-4290	EG	Maplewood Dr.	8	Asbestos Cement	22	59	1.14 out of 5	\$442	9,700
Distribution Main	11811	P-4395	EG	Maplewood Dr.	8	Asbestos Cement	26	59	1.14 out of 5	\$442	11,660
Distribution Main	5783	P-4918	EG	Marion St.	6	Unknown	159	UNK	0.71 out of 5	\$442	70,371
Distribution Main	5784	P-4918	EG	Marion St.	4	Cast Iron	12	133	3.29 out of 5	\$442	5,390
Distribution Main	5785	P-4918	EG	Marion St.	4	Cast Iron	162	133	3.29 out of 5	\$442	71,558
Distribution Main	6278	P-4610	EG	Marion St.	4	Cast Iron	404	133	3.29 out of 5	\$442	178,721
Distribution Main	6755	P-4918	EG	Marion St.	4	Cast Iron	3	133	3.29 out of 5	\$442	1,460
Distribution Main	6757	P-4610	EG	Marion St.	4	Cast Iron	18	133	3.29 out of 5	\$442	8,001
Distribution Main	10380		EG	Marlborough St	4	Ductile Iron	25	UNK	1.42 out of 5	\$442	11,126
Distribution Main	889	P-4656	EG	Marlborough St.	8	Ductile Iron	550	17	0 out of 5	N/A	\$0
Distribution Main	4424	P-4695	EG	Marlborough St.	8	Ductile Iron	66	16	0 out of 5	N/A	\$0
Distribution Main	5678	P-4659	EG	Marlborough St.	8	Ductile Iron	235	17	0 out of 5	N/A	\$0
Distribution Main	5679	P-4659	EG	Marlborough St.	8	Ductile Iron	38	17	0 out of 5	N/A	\$0
Distribution Main	6231	P-4596	EG	Marlborough St.	8	Ductile Iron	21	17	0 out of 5	N/A	\$0
Distribution Main	6232	P-4596	EG	Marlborough St.	8	Ductile Iron	255	17	0 out of 5	N/A	\$0
Transmission Main	6240	P-4639	EG	Marlborough St.	12	Ductile Iron	386	17	0 out of 5	N/A	\$0
Distribution Main	6246	P-4595	EG	Marlborough St.	8	Ductile Iron	140	17	0 out of 5	N/A	\$0
Transmission Main	6647	P-4625	EG	Marlborough St.	12	Asbestos Cement	492	63	1.29 out of 5	\$442	217,544
Transmission Main	6648	P-4625	EG	Marlborough St.	12	Asbestos Cement	18	63	1.29 out of 5	\$442	7,888
Distribution Main	9029	P-4659	EG	Marlborough St.	8	Ductile Iron	7	17	0 out of 5	N/A	\$0
Distribution Main	9030	P-4659	EG	Marlborough St.	8	Ductile Iron	55	17	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9031	P-4656	EG	Marlborough St.	8	Ductile Iron	6	17	0 out of 5	N/A	\$0
Distribution Main	9481	P-4656	EG	Marlborough St.	8	Ductile Iron	45	17	0 out of 5	N/A	\$0
Transmission Main	9482	P-4639	EG	Marlborough St.	12	Ductile Iron	26	17	0 out of 5	N/A	\$0
Transmission Main	9483	P-4639	EG	Marlborough St.	12	Ductile Iron	4	17	0 out of 5	N/A	\$0
Transmission Main	10848	P-4614	EG	Marlborough St.	12	Asbestos Cement	614	63	1.29 out of 5	\$442	271,387
Transmission Main	10849	P-4928	EG	Marlborough St.	12	Asbestos Cement	332	63	1.29 out of 5	\$442	146,690
Transmission Main	10907	P-4928	EG	Marlborough St.	12	Ductile Iron	5	17	0 out of 5	N/A	\$0
Transmission Main	10908	P-4928	EG	Marlborough St.	12	Ductile Iron	3	17	0 out of 5	N/A	\$0
Distribution Main	11329	P-4595	EG	Marlborough St.	8	Ductile Iron	93	16	0 out of 5	N/A	\$0
Distribution Main	9888	P-40003	EG	Mary Elizabeth Way	8	Ductile Iron	509	15	0 out of 5	N/A	\$0
Distribution Main	9889	P-40003	EG	Mary Elizabeth Way	8	Ductile Iron	10	15	0 out of 5	N/A	\$0
Distribution Main	5898	P-4139	EG	Mawney Brook Dr.	8	Ductile Iron	44	25	0.14 out of 5	N/A	\$0
Distribution Main	5899	P-4139	EG	Mawney Brook Dr.	8	Ductile Iron	160	25	0.14 out of 5	N/A	\$0
Distribution Main	5900	P-4139	EG	Mawney Brook Dr.	8	Ductile Iron	363	25	0.14 out of 5	N/A	\$0
Distribution Main	3667	P-4578	EG	Mawney St.	4	Cast Iron	23	133	3.29 out of 5	\$442	10,347
Distribution Main	6634	P-4587	EG	Mawney St.	4	Cast Iron	449	133	3.29 out of 5	\$442	198,602
Distribution Main	12185		EG	Mawney St.	4	Cast Iron	820	133	3.29 out of 5	\$442	362,289
Distribution Main	5008	P-4384	EG	Mayflower Dr.	6	Asbestos Cement	274	50	1.85 out of 5	\$442	121,315
Distribution Main	5009	P-4384	EG	Mayflower Dr.	6	Asbestos Cement	178	50	1.85 out of 5	\$442	78,793
Distribution Main	5010	P-4357	EG	Mayflower Dr.	6	Asbestos Cement	193	50	1.85 out of 5	\$442	85,085
Distribution Main	5246	P-4385	EG	Mayflower Dr.	6	Asbestos Cement	419	50	1.85 out of 5	\$442	185,055
Distribution Main	6150	P-4385	EG	Mayflower Dr.	6	Asbestos Cement	16	50	1.85 out of 5	\$442	7,088
Distribution Main	10075	P-4273	EG	Mcgraw Ct.	6	Ductile Iron	13	28	0.85 out of 5	\$442	5,642
Distribution Main	10076	P-4273	EG	Mcgraw Ct.	6	Ductile Iron	268	28	0.85 out of 5	\$442	118,315
Distribution Main	3645	P-4144	EG	Mcpartland Way	8	Ductile Iron	39	15	0 out of 5	N/A	\$0
Distribution Main	3646	P-4144	EG	Mcpartland Way	8	Ductile Iron	146	15	0 out of 5	N/A	\$0
Distribution Main	3647	P-4144	EG	Mcpartland Way	8	Ductile Iron	507	15	0 out of 5	N/A	\$0
Distribution Main	3648	P-4144	EG	Mcpartland Way	8	Ductile Iron	35	15	0 out of 5	N/A	\$0
Distribution Main	9981	P-4145	EG	Mcpartland Way	8	Ductile Iron	933	15	0 out of 5	N/A	\$0
Distribution Main	10125	P-4145	EG	Mcpartland Way	8	Ductile Iron	27	15	0 out of 5	N/A	\$0
Distribution Main	10126	P-4145	EG	Mcpartland Way	8	Ductile Iron	746	15	0 out of 5	N/A	\$0
Distribution Main	757		EG	Meadowbrook Road	6	PVC	3	55	1.28 out of 5	\$442	1,536
Distribution Main	1808	P-40021	EG	Meadowbrook Road	6	Ductile Iron	19	18	0.71 out of 5	N/A	\$0
Distribution Main	1812	P-40020	EG	Meadowbrook Road	6	PVC	480	55	1.28 out of 5	\$442	212,227
Distribution Main	3639	P-40020	EG	Meadowbrook Road	6	PVC	533	55	1.28 out of 5	\$442	235,749
Distribution Main	5508	P-40022	EG	Meadowbrook Road	6	Ductile Iron	126	18	0.71 out of 5	N/A	\$0
Distribution Main	5515	P-40022	EG	Meadowbrook Road	6	Ductile Iron	4	18	0.71 out of 5	N/A	\$0
Distribution Main	5718	P-40020	EG	Meadowbrook Road	6	PVC	15	55	1.28 out of 5	\$442	6,782
Distribution Main	6389	P-40022	EG	Meadowbrook Road	6	Ductile Iron	4	18	0.71 out of 5	N/A	\$0
Transmission Main	6	P-4671	EG	Middle Rd	12	Asbestos Cement	122	57	1.14 out of 5	\$442	53,896
Distribution Main	4173		EG	Middle Rd	8	Unknown	13	UNK	0 out of 5	N/A	\$0
Distribution Main	9666		EG	Middle Rd	6	Ductile Iron	10	7	0.71 out of 5	N/A	\$0
Distribution Main	10179	P-4212	EG	Middle Rd	4	Ductile Iron	7	18	1.42 out of 5	N/A	\$0
Distribution Main	10180	P-4212	EG	Middle Rd	4	Ductile Iron	44	18	1.42 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10374		EG	Middle Rd	6	Ductile Iron	15	18	0.71 out of 5	N/A	\$0
Distribution Main	5	P-4672	EG	Middle Rd Prv	8	Ductile Iron	11	18	0 out of 5	N/A	\$0
Transmission Main	561		EG	Middle Rd.	12	Ductile Iron	29	25	0.14 out of 5	N/A	\$0
Transmission Main	564	P-4806	EG	Middle Rd.	12	Ductile Iron	21	14	0 out of 5	N/A	\$0
Distribution Main	660	P-4527	EG	Middle Rd.	8	Ductile Iron	25	32	0.14 out of 5	\$442	11,101
Transmission Main	3649	P-4143	EG	Middle Rd.	16	Ductile Iron	538	16	0 out of 5	N/A	\$0
Transmission Main	3650		EG	Middle Rd.	16	Ductile Iron	10	16	0 out of 5	N/A	\$0
Transmission Main	3653	P-4148	EG	Middle Rd.	16	Ductile Iron	1,136	16	0 out of 5	N/A	\$0
Transmission Main	3901	P-4807	EG	Middle Rd.	12	Ductile Iron	901	14	0 out of 5	N/A	\$0
Transmission Main	3902	P-4807	EG	Middle Rd.	12	Ductile Iron	9	14	0 out of 5	N/A	\$0
Transmission Main	4096	P-4806	EG	Middle Rd.	16	Ductile Iron	756	14	0 out of 5	N/A	\$0
Transmission Main	4097	P-4806	EG	Middle Rd.	16	Ductile Iron	53	14	0 out of 5	N/A	\$0
Transmission Main	4098	P-4806	EG	Middle Rd.	12	Ductile Iron	8	14	0 out of 5	N/A	\$0
Transmission Main	4100	P-4807	EG	Middle Rd.	12	Ductile Iron	10	14	0 out of 5	N/A	\$0
Distribution Main	4150	P-4444	EG	Middle Rd.	8	Ductile Iron	493	32	0.14 out of 5	\$442	218,003
Distribution Main	4151	P-4444	EG	Middle Rd.	8	Ductile Iron	379	32	0.14 out of 5	\$442	167,308
Transmission Main	4172	P-4233	EG	Middle Rd.	20	Asbestos Cement	879	55	1.14 out of 5	\$442	388,632
Distribution Main	4178	P-4525	EG	Middle Rd.	8	Ductile Iron	41	32	0.14 out of 5	\$442	18,054
Distribution Main	4179	P-4525	EG	Middle Rd.	8	Ductile Iron	614	32	0.14 out of 5	\$442	271,566
Distribution Main	4243	P-4525	EG	Middle Rd.	8	Ductile Iron	211	32	0.14 out of 5	\$442	93,145
Distribution Main	4244	P-4525	EG	Middle Rd.	8	Ductile Iron	555	32	0.14 out of 5	\$442	245,525
Transmission Main	4245	P-4233	EG	Middle Rd.	20	Asbestos Cement	1,188	55	1.14 out of 5	\$442	525,030
Transmission Main	4487	P-4138	EG	Middle Rd.	16	Ductile Iron	816	25	0.14 out of 5	N/A	\$0
Transmission Main	4488	P-4138	EG	Middle Rd.	16	Ductile Iron	49	25	0.14 out of 5	N/A	\$0
Transmission Main	4492	P-4158	EG	Middle Rd.	16	Ductile Iron	235	26	0.14 out of 5	\$442	103,811
Transmission Main	4493	P-4158	EG	Middle Rd.	16	Ductile Iron	61	26	0.14 out of 5	\$442	27,041
Transmission Main	4497	P-4157	EG	Middle Rd.	16	Ductile Iron	820	26	0.14 out of 5	\$442	362,349
Transmission Main	4498	P-4157	EG	Middle Rd.	16	Ductile Iron	112	18	0 out of 5	N/A	\$0
Transmission Main	5001	P-4213	EG	Middle Rd.	12	Asbestos Cement	641	57	1.14 out of 5	\$442	283,337
Transmission Main	5002	P-4213	EG	Middle Rd.	12	Asbestos Cement	591	57	1.14 out of 5	\$442	261,213
Transmission Main	5003	P-4344	EG	Middle Rd.	12	Asbestos Cement	224	57	1.14 out of 5	\$442	99,050
Transmission Main	5004	P-4344	EG	Middle Rd.	12	Asbestos Cement	485	57	1.14 out of 5	\$442	214,243
Transmission Main	5007	P-4336	EG	Middle Rd.	12	Asbestos Cement	599	57	1.14 out of 5	\$442	264,927
Distribution Main	5586	P-4337	EG	Middle Rd.	8	Ductile Iron	21	18	0 out of 5	N/A	\$0
Distribution Main	5587	P-4398	EG	Middle Rd.	8	Ductile Iron	121	32	0.14 out of 5	\$442	53,667
Distribution Main	5588	P-4398	EG	Middle Rd.	8	Ductile Iron	72	32	0.14 out of 5	\$442	31,972
Distribution Main	5590	P-4392	EG	Middle Rd.	8	Ductile Iron	305	18	0 out of 5	N/A	\$0
Distribution Main	5591	P-4392	EG	Middle Rd.	8	Ductile Iron	22	18	0 out of 5	N/A	\$0
Distribution Main	5592	P-4397	EG	Middle Rd.	8	Ductile Iron	322	18	0 out of 5	N/A	\$0
Distribution Main	5593	P-4367	EG	Middle Rd.	8	Ductile Iron	79	18	0 out of 5	N/A	\$0
Distribution Main	5595	P-4368	EG	Middle Rd.	8	Ductile Iron	481	18	0 out of 5	N/A	\$0
Distribution Main	5596	P-4339	EG	Middle Rd.	8	Ductile Iron	325	18	0 out of 5	N/A	\$0
Transmission Main	5648	P-4118	EG	Middle Rd.	12	Asbestos Cement	611	46	1.14 out of 5	\$442	270,118
Transmission Main	5649	P-4118	EG	Middle Rd.	12	Asbestos Cement	309	46	1.14 out of 5	\$442	136,556

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	5730	P-4138	EG	Middle Rd.	16	Ductile Iron	7	25	0.14 out of 5	N/A	\$0
Transmission Main	5731		EG	Middle Rd.	16	Ductile Iron	3	16	0 out of 5	N/A	\$0
Transmission Main	6002	P-4719	EG	Middle Rd.	12	Ductile Iron	47	36	0.14 out of 5	\$442	20,737
Transmission Main	6007	P-4116	EG	Middle Rd.	20	Ductile Iron	1,164	36	0.14 out of 5	\$442	514,682
Transmission Main	6009	P-4726	EG	Middle Rd.	12	Ductile Iron	640	28	0.14 out of 5	\$442	282,703
Transmission Main	6010	P-4726	EG	Middle Rd.	12	Ductile Iron	444	28	0.14 out of 5	\$442	196,208
Transmission Main	6018	P-4727	EG	Middle Rd.	12	Asbestos Cement	649	46	1.14 out of 5	\$442	286,739
Transmission Main	6025	P-4671	EG	Middle Rd.	12	Steel	379	18	0.57 out of 5	N/A	\$0
Transmission Main	6026	P-4671	EG	Middle Rd.	12	Steel	8	18	0.57 out of 5	N/A	\$0
Transmission Main	6030	P-4118	EG	Middle Rd.	12	Asbestos Cement	6	46	1.14 out of 5	\$442	2,614
Transmission Main	6031	P-4213	EG	Middle Rd.	12	Asbestos Cement	7	57	1.14 out of 5	\$442	3,014
Distribution Main	6188	P-4371	EG	Middle Rd.	8	Ductile Iron	10	32	0.14 out of 5	\$442	4,289
Distribution Main	6189	P-4371	EG	Middle Rd.	8	Ductile Iron	721	32	0.14 out of 5	\$442	318,523
Distribution Main	6390	P-4368	EG	Middle Rd.	8	Ductile Iron	440	18	0 out of 5	N/A	\$0
Distribution Main	6403	P-4371	EG	Middle Rd.	8	Ductile Iron	585	32	0.14 out of 5	\$442	258,558
Distribution Main	6406	P-4398	EG	Middle Rd.	8	Ductile Iron	183	32	0.14 out of 5	\$442	80,947
Transmission Main	6571	P-4719	EG	Middle Rd.	20	Ductile Iron	21	36	0.14 out of 5	\$442	9,365
Transmission Main	8882	P-4157	EG	Middle Rd.	16	Ductile Iron	175	18	0 out of 5	N/A	\$0
Transmission Main	9072		EG	Middle Rd.	16	Ductile Iron	17	16	0 out of 5	N/A	\$0
Transmission Main	9438	P-4140	EG	Middle Rd.	16	Ductile Iron	244	14	0 out of 5	N/A	\$0
Transmission Main	10107	P-4130	EG	Middle Rd.	20	Ductile Iron	3	28	0.14 out of 5	\$442	1,215
Transmission Main	10244	P-4343	EG	Middle Rd.	12	Ductile Iron	12	18	0 out of 5	N/A	\$0
Transmission Main	10245	P-4343	EG	Middle Rd.	12	Ductile Iron	9	18	0 out of 5	N/A	\$0
Transmission Main	10250	P-4233	EG	Middle Rd.	20	Asbestos Cement	129	55	1.14 out of 5	\$442	56,921
Distribution Main	10354		EG	Middle Rd.	6	PVC	14	35	1.14 out of 5	\$442	6,196
Distribution Main	10372	P-4397	EG	Middle Rd.	8	Ductile Iron	89	UNK	0 out of 5	N/A	\$0
Distribution Main	10375	P-4337	EG	Middle Rd.	8	Ductile Iron	12	18	0 out of 5	N/A	\$0
Transmission Main	11079		EG	Middle Rd.	12	Ductile Iron	23	25	0.14 out of 5	N/A	\$0
Transmission Main	11254	P-4158	EG	Middle Rd.	16	Ductile Iron	41	26	0.14 out of 5	\$442	18,340
Transmission Main	11279	P-4213	EG	Middle Rd.	12	Asbestos Cement	273	57	1.14 out of 5	\$442	120,516
Transmission Main	11280	P-4213	EG	Middle Rd.	12	Asbestos Cement	226	57	1.14 out of 5	\$442	99,759
Distribution Main	11333	P-4368	EG	Middle Rd.	8	Ductile Iron	48	18	0 out of 5	N/A	\$0
Transmission Main	11514	P-4148	EG	Middle Rd.	16	Ductile Iron	14	25	0.14 out of 5	N/A	\$0
Transmission Main	11646	P-4343	EG	Middle Rd.	12	Ductile Iron	1	18	0 out of 5	N/A	\$0
Transmission Main	11647	P-4344	EG	Middle Rd.	12	Ductile Iron	2	18	0 out of 5	N/A	\$0
Transmission Main	11813	P-4726	EG	Middle Rd.	12	Ductile Iron	501	28	0.14 out of 5	\$442	221,661
Transmission Main	11818	P-4213	EG	Middle Rd.	12	Asbestos Cement	136	57	1.14 out of 5	\$442	60,083
Transmission Main	11822	P-4726	EG	Middle Rd.	12	Ductile Iron	283	28	0.14 out of 5	\$442	125,256
Transmission Main	11823	P-4726	EG	Middle Rd.	12	Ductile Iron	428	28	0.14 out of 5	\$442	189,124
Transmission Main	11849	P-4726	EG	Middle Rd.	12	Ductile Iron	71	28	0.14 out of 5	\$442	31,280
Transmission Main	12084	P-4118	EG	Middle Rd.	12	Asbestos Cement	172	46	1.14 out of 5	\$442	76,113
Transmission Main	12232		EG	Middle Rd.	16	Ductile Iron	76	25	0.14 out of 5	N/A	\$0
Transmission Main	12234		EG	Middle Rd.	16	Ductile Iron	88	17	0 out of 5	N/A	\$0
Distribution Main	10246	P-4672	EG	Middle Rd. Prv	8	Ductile Iron	7	18	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10247	P-4224	EG	Middle Rd. Prv	8	Ductile Iron	11	18	0 out of 5	N/A	\$0
Distribution Main	3661	P-4440	EG	Midlands Dr.	6	Asbestos Cement	540	45	1.85 out of 5	\$442	238,841
Transmission Main	3821	P-4160	EG	Miss Fry Dr.	16	Ductile Iron	43	26	0.14 out of 5	\$442	18,984
Transmission Main	3822	P-4167	EG	Miss Fry Dr.	16	Ductile Iron	330	26	0.14 out of 5	\$442	145,944
Transmission Main	3823	P-4167	EG	Miss Fry Dr.	16	Ductile Iron	126	26	0.14 out of 5	\$442	55,756
Transmission Main	3826	P-4160	EG	Miss Fry Dr.	16	Ductile Iron	540	26	0.14 out of 5	\$442	238,760
Transmission Main	3827	P-4160	EG	Miss Fry Dr.	16	Ductile Iron	8	26	0.14 out of 5	\$442	3,465
Transmission Main	3828	P-4162	EG	Miss Fry Dr.	16	Ductile Iron	445	26	0.14 out of 5	\$442	196,787
Transmission Main	3829	P-4162	EG	Miss Fry Dr.	16	Ductile Iron	522	26	0.14 out of 5	\$442	230,596
Transmission Main	4491	P-4160	EG	Miss Fry Dr.	16	Ductile Iron	24	26	0.14 out of 5	\$442	10,729
Transmission Main	4854	P-4167	EG	Miss Fry Dr.	16	Ductile Iron	471	26	0.14 out of 5	\$442	208,270
Transmission Main	10092	P-4167	EG	Miss Fry Dr.	16	Ductile Iron	396	26	0.14 out of 5	\$442	175,180
Distribution Main	3843	P-4281	EG	Misty Oak Dr.	8	PVC	486	35	0.43 out of 5	\$442	214,646
Distribution Main	3844	P-4282	EG	Misty Oak Dr.	8	PVC	23	35	0.43 out of 5	\$442	10,338
Distribution Main	6783	P-4275	EG	Misty Oak Dr.	8	Asbestos Cement	273	54	1.14 out of 5	\$442	120,781
Distribution Main	6786	P-4282	EG	Misty Oak Dr.	8	PVC	13	35	0.43 out of 5	\$442	5,705
Distribution Main	6787	P-4282	EG	Misty Oak Dr.	8	PVC	462	35	0.43 out of 5	\$442	204,023
Distribution Main	5884	P-4108	EG	Monroe Dr.	6	Asbestos Cement	20	44	1.85 out of 5	\$442	9,051
Distribution Main	6698	P-4108	EG	Monroe Dr.	6	Asbestos Cement	504	44	1.85 out of 5	\$442	222,667
Distribution Main	6756	P-4919	EG	Montrose St.	4	Cast Iron	266	133	3.29 out of 5	\$442	117,755
Transmission Main	3640	P-40040	EG	Moosehorn Rd.	16	Ductile Iron	75	26	0.14 out of 5	\$442	33,322
Transmission Main	3641	P-4159	EG	Moosehorn Rd.	16	Ductile Iron	476	26	0.14 out of 5	\$442	210,586
Transmission Main	3642	P-4159	EG	Moosehorn Rd.	16	Ductile Iron	467	26	0.14 out of 5	\$442	206,542
Transmission Main	3643	P-4159	EG	Moosehorn Rd.	16	Ductile Iron	438	26	0.14 out of 5	\$442	193,425
Transmission Main	3644	P-4159	EG	Moosehorn Rd.	16	Ductile Iron	13	26	0.14 out of 5	\$442	5,755
Transmission Main	5735	P-40040	EG	Moosehorn Rd.	16	Ductile Iron	12	26	0.14 out of 5	\$442	5,226
Distribution Main	458	P-4983	EG	Moss Ln	8	Unknown	182	35	0.14 out of 5	\$442	80,438
Distribution Main	6780	P-4283	EG	Mullberry Ct.	6	PVC	212	35	1.14 out of 5	\$442	93,906
Distribution Main	6710	P-4259	EG	New Castle Drive	8	PVC	441	41	0.57 out of 5	\$442	194,974
Distribution Main	6711	P-4267	EG	New Castle Drive	8	PVC	134	41	0.57 out of 5	\$442	59,159
Distribution Main	9659		EG	New London	2	Unknown	51	7	1.42 out of 5	N/A	\$0
Distribution Main	4032	P-4378	EG	Nichols Ln	6	Asbestos Cement	211	51	1.85 out of 5	\$442	93,373
Distribution Main	4033	P-4378	EG	Nichols Ln	6	Asbestos Cement	832	51	1.85 out of 5	\$442	367,661
Distribution Main	5503	P-4322	EG	North Gate Dr.	8	Asbestos Cement	274	50	1.14 out of 5	\$442	121,257
Distribution Main	6054	P-4221	EG	Oak Dell Cir.	8	Asbestos Cement	845	51	1.14 out of 5	\$442	373,499
Distribution Main	6055	P-4221	EG	Oak Dell Cir.	8	Asbestos Cement	261	51	1.14 out of 5	\$442	115,418
Distribution Main	6709	P-4991	EG	Oak Dell Cir.	8	Asbestos Cement	143	51	1.14 out of 5	\$442	63,227
Distribution Main	5628	P-4457	EG	Oakwood Dr.	6	Asbestos Cement	220	60	1.85 out of 5	\$442	97,251
Distribution Main	5629	P-4457	EG	Oakwood Dr.	6	Asbestos Cement	975	60	1.85 out of 5	\$442	430,768
Distribution Main	8813	P-4808	EG	Old Farm Road	8	Ductile Iron	758	14	0 out of 5	N/A	\$0
Distribution Main	8814	P-4808	EG	Old Farm Road	8	Ductile Iron	70	14	0 out of 5	N/A	\$0
Distribution Main	3664	P-4491	EG	Old Greenwich Dr.	6	Asbestos Cement	236	47	1.85 out of 5	\$442	104,093
Distribution Main	3665	P-4490	EG	Old Greenwich Dr.	6	Asbestos Cement	75	47	1.85 out of 5	\$442	33,053
Distribution Main	4149	P-4489	EG	Old Greenwich Dr.	6	Asbestos Cement	54	47	1.85 out of 5	\$442	23,869

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4999	P-4491	EG	Old Greenwich Dr.	6	Asbestos Cement	9	47	1.85 out of 5	\$442	3,937
Transmission Main	9096	P-4755	EG	Old Quaker Ln	16	Ductile Iron	595	13	0 out of 5	N/A	\$0
Transmission Main	9099	P-4755	EG	Old Quaker Ln	16	Ductile Iron	123	13	0 out of 5	N/A	\$0
Transmission Main	9100	P-4755	EG	Old Quaker Ln	16	Ductile Iron	146	13	0 out of 5	N/A	\$0
Distribution Main	5809	P-4030	EG	Osprey Dr.	8	PVC	684	32	0.43 out of 5	\$442	302,192
Distribution Main	5810	P-4030	EG	Osprey Dr.	8	PVC	357	32	0.43 out of 5	\$442	157,717
Distribution Main	6372	P-4031	EG	Osprey Dr.	8	PVC	427	32	0.43 out of 5	\$442	188,903
Distribution Main	11844	P-4030	EG	Osprey Dr.	8	PVC	445	32	0.43 out of 5	\$442	196,593
Distribution Main	2395	P-4533	EG	Overbrook Ln.	6	Asbestos Cement	672	64	2.71 out of 5	\$442	297,202
Distribution Main	3934	P-4534	EG	Overbrook Ln.	6	Asbestos Cement	154	64	2 out of 5	\$442	68,180
Distribution Main	3935	P-4534	EG	Overbrook Ln.	6	Asbestos Cement	72	64	2 out of 5	\$442	31,666
Distribution Main	3937	P-4533	EG	Overbrook Ln.	6	Asbestos Cement	3	64	2 out of 5	\$442	1,343
Distribution Main	2905	P-4354	EG	Overfield Rd.	6	Ductile Iron	392	30	0.85 out of 5	\$442	173,226
Distribution Main	3657	P-4697	EG	Overfield Rd.	6	Ductile Iron	31	30	0.85 out of 5	\$442	13,558
Distribution Main	3658	P-4697	EG	Overfield Rd.	6	Ductile Iron	739	30	0.85 out of 5	\$442	326,669
Distribution Main	4185	P-4697	EG	Overfield Rd.	6	Ductile Iron	77	30	0.85 out of 5	\$442	33,877
Distribution Main	6131	P-4354	EG	Overfield Rd.	6	Ductile Iron	269	30	0.85 out of 5	\$442	118,756
Distribution Main	6132	P-4354	EG	Overfield Rd.	6	Ductile Iron	17	30	0.85 out of 5	\$442	7,362
Distribution Main	6133	P-4354	EG	Overfield Rd.	6	Ductile Iron	264	30	0.85 out of 5	\$442	116,636
Distribution Main	6474	P-4698	EG	Overfield Rd.	6	Ductile Iron	433	30	0.85 out of 5	\$442	191,399
Distribution Main	6475	P-4354	EG	Overfield Rd.	6	Ductile Iron	6	30	0.85 out of 5	\$442	2,518
Distribution Main	5390	P-4044	EG	Owl Tree Ln.	8	Ductile Iron	26	19	0 out of 5	N/A	\$0
Distribution Main	5391	P-4044	EG	Owl Tree Ln.	8	Ductile Iron	362	19	0 out of 5	N/A	\$0
Distribution Main	9959	P-4044	EG	Owl Tree Ln.	8	Asbestos Cement	54	47	1.14 out of 5	\$442	23,666
Distribution Main	9960	P-4044	EG	Owl Tree Ln.	8	Ductile Iron	40	19	0 out of 5	N/A	\$0
Distribution Main	4856	P-4073	EG	Pardon'S Wood Ln.	8	Ductile Iron	284	26	0.14 out of 5	\$442	125,694
Distribution Main	4857	P-4073	EG	Pardon'S Wood Ln.	8	Ductile Iron	45	26	0.14 out of 5	\$442	19,692
Distribution Main	5869	P-4073	EG	Pardon'S Wood Ln.	8	Ductile Iron	70	26	0.14 out of 5	\$442	30,994
Distribution Main	5870	P-4073	EG	Pardon'S Wood Ln.	8	Ductile Iron	380	26	0.14 out of 5	\$442	167,902
Distribution Main	4804	P-4164	EG	Partridge Run	8	Ductile Iron	322	24	0.14 out of 5	N/A	\$0
Distribution Main	4805	P-4164	EG	Partridge Run	8	Ductile Iron	579	24	0.14 out of 5	N/A	\$0
Distribution Main	4855		EG	Partridge Run	8	Ductile Iron	6	26	0.14 out of 5	\$442	2,660
Distribution Main	4861		EG	Partridge Run	8	Ductile Iron	3	26	0.14 out of 5	\$442	1,314
Distribution Main	6295	P-40042	EG	Partridge Run	8	Ductile Iron	367	26	0.14 out of 5	\$442	162,238
Distribution Main	10096	P-40042	EG	Partridge Run	8	Ductile Iron	546	26	0.14 out of 5	\$442	241,374
Distribution Main	10097	P-40042	EG	Partridge Run	8	Ductile Iron	199	26	0.14 out of 5	\$442	87,988
Distribution Main	10098		EG	Partridge Run	8	Ductile Iron	23	24	0.14 out of 5	N/A	\$0
Distribution Main	11266	P-4164	EG	Partridge Run	8	Ductile Iron	46	24	0.14 out of 5	N/A	\$0
Distribution Main	11852	P-40042	EG	Partridge Run	8	Ductile Iron	17	26	0.14 out of 5	\$442	7,696
Distribution Main	11853	P-4164	EG	Partridge Run	8	Ductile Iron	365	24	0.14 out of 5	N/A	\$0
Distribution Main	3859	P-4967	EG	Pearl St.	1.5	Copper	87	UNK	1.99 out of 5	\$442	38,518
Distribution Main	9016	P-4966	EG	Pearl St.	8	Ductile Iron	20	17	0 out of 5	N/A	\$0
Distribution Main	4153	P-4493	EG	Pegwin Dr.	6	Asbestos Cement	24	55	1.85 out of 5	\$442	10,449
Distribution Main	4154	P-4493	EG	Pegwin Dr.	6	Asbestos Cement	435	55	1.85 out of 5	\$442	192,101

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4998	P-4493	EG	Pegwin Dr.	6	Asbestos Cement	7	55	1.85 out of 5	\$442	3,266
Distribution Main	5964	P-4494	EG	Pegwin Dr.	6	Asbestos Cement	729	55	1.85 out of 5	\$442	322,157
Distribution Main	5965	P-4494	EG	Pegwin Dr.	6	Asbestos Cement	17	55	1.85 out of 5	\$442	7,666
Distribution Main	9226	P-4194	EG	Pequot Tr	8	Ductile Iron	43	8	0 out of 5	N/A	\$0
Distribution Main	9227	P-4194	EG	Pequot Tr	8	Ductile Iron	898	8	0 out of 5	N/A	\$0
Distribution Main	9233	P-4199	EG	Pequot Tr	8	Ductile Iron	128	8	0 out of 5	N/A	\$0
Distribution Main	9244	P-4202	EG	Pequot Tr	8	Ductile Iron	511	8	0 out of 5	N/A	\$0
Distribution Main	9245	P-4199	EG	Pequot Tr	8	Ductile Iron	594	8	0 out of 5	N/A	\$0
Distribution Main	9246	P-4206	EG	Pequot Tr	8	Ductile Iron	631	8	0 out of 5	N/A	\$0
Distribution Main	11556	P-4194	EG	Pequot Tr	8	Ductile Iron	155	8	0 out of 5	N/A	\$0
Distribution Main	11557	P-4191	EG	Pequot Tr	8	Ductile Iron	127	8	0 out of 5	N/A	\$0
Distribution Main	11560	P-4190	EG	Pequot Tr	8	Ductile Iron	89	8	0 out of 5	N/A	\$0
Distribution Main	12160	P-4202	EG	Pequot Tr	8	Ductile Iron	113	8	0 out of 5	N/A	\$0
Distribution Main	5467	P-4353	EG	Pettine St.	1	Copper	331	66	2.43 out of 5	\$442	146,257
Distribution Main	11303	P-4353	EG	Pettine St.	1	Copper	18	66	2.43 out of 5	\$442	7,786
Transmission Main	5805	P-40000	EG	Pheasant Dr.	12	PVC	334	30	0.43 out of 5	\$442	147,724
Transmission Main	5806	P-40000	EG	Pheasant Dr.	12	PVC	103	30	0.43 out of 5	\$442	45,625
Transmission Main	5807	P-4024	EG	Pheasant Dr.	16	Ductile Iron	688	26	0.14 out of 5	\$442	304,150
Transmission Main	5808	P-4024	EG	Pheasant Dr.	16	Ductile Iron	712	26	0.14 out of 5	\$442	314,587
Transmission Main	5814	P-4024	EG	Pheasant Dr.	16	Ductile Iron	110	26	0.14 out of 5	\$442	48,786
Transmission Main	5815	P-4024	EG	Pheasant Dr.	16	Ductile Iron	231	26	0.14 out of 5	\$442	101,883
Transmission Main	5901	P-4026	EG	Pheasant Dr.	16	Ductile Iron	558	26	0.14 out of 5	\$442	246,439
Distribution Main	5946	P-4999	EG	Pheasant Dr.	8	Ductile Iron	32	26	0.14 out of 5	\$442	14,184
Transmission Main	11318	P-4026	EG	Pheasant Dr.	16	Ductile Iron	6	26	0.14 out of 5	\$442	2,520
Distribution Main	2903	P-4429	EG	Phillips Dr.	6	Asbestos Cement	465	49	1.85 out of 5	\$442	205,659
Distribution Main	2909	P-4412	EG	Phillips Dr.	6	Asbestos Cement	8	49	1.85 out of 5	\$442	3,478
Distribution Main	4192	P-4411	EG	Phillips Dr.	6	Asbestos Cement	240	49	1.85 out of 5	\$442	105,996
Distribution Main	6467	P-4412	EG	Phillips Dr.	6	Asbestos Cement	281	49	1.85 out of 5	\$442	124,216
Distribution Main	6488	P-4432	EG	Phillips Dr.	6	Asbestos Cement	285	49	1.85 out of 5	\$442	125,938
Distribution Main	6489	P-4436	EG	Phillips Dr.	6	Asbestos Cement	37	49	1.85 out of 5	\$442	16,188
Distribution Main	6496	P-4431	EG	Phillips Dr.	6	Asbestos Cement	57	49	1.85 out of 5	\$442	25,404
Distribution Main	6497	P-4431	EG	Phillips Dr.	6	Asbestos Cement	391	49	1.85 out of 5	\$442	172,828
Distribution Main	11191	P-4429	EG	Phillips Dr.	6	Asbestos Cement	7	49	1.85 out of 5	\$442	3,248
Distribution Main	301	P-4922	EG	Pierce St	8	Ductile Iron	11	17	0 out of 5	N/A	\$0
Distribution Main	9007	P-4921	EG	Pierce St	6	Ductile Iron	8	17	0.71 out of 5	N/A	\$0
Distribution Main	9008	P-4923	EG	Pierce St	6	Ductile Iron	5	17	0.71 out of 5	N/A	\$0
Distribution Main	9153	P-4889	EG	Pierce St	6	Ductile Iron	11	8	0.71 out of 5	N/A	\$0
Distribution Main	9311	P-4921	EG	Pierce St	8	Ductile Iron	9	17	0 out of 5	N/A	\$0
Distribution Main	11575	P-4922	EG	Pierce St	8	Ductile Iron	6	17	0 out of 5	N/A	\$0
Distribution Main	900	P-4685	EG	Pierce St.	6	Cast Iron	316	133	2.57 out of 5	\$442	139,530
Distribution Main	901	P-4685	EG	Pierce St.	6	Cast Iron	181	133	2.57 out of 5	\$442	80,051
Distribution Main	902	P-4608	EG	Pierce St.	6	Cast Iron	23	133	2.57 out of 5	\$442	10,215
Distribution Main	903	P-4608	EG	Pierce St.	6	Cast Iron	186	133	2.57 out of 5	\$442	82,025
Distribution Main	2409	P-4611	EG	Pierce St.	6	Cast Iron	4	133	2.57 out of 5	\$442	1,786

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3860	P-4608	EG	Pierce St.	8	Ductile Iron	8	17	0 out of 5	N/A	\$0
Distribution Main	3861	P-4685	EG	Pierce St.	8	Ductile Iron	6	17	0 out of 5	N/A	\$0
Distribution Main	6220	P-4606	EG	Pierce St.	6	Cast Iron	283	133	2.57 out of 5	\$442	125,171
Distribution Main	6279	P-4611	EG	Pierce St.	6	Cast Iron	392	133	2.57 out of 5	\$442	173,299
Distribution Main	6280	P-4611	EG	Pierce St.	6	Cast Iron	191	133	2.57 out of 5	\$442	84,411
Distribution Main	6739	P-4611	EG	Pierce St.	6	Cast Iron	7	133	2.57 out of 5	\$442	3,130
Distribution Main	9025	P-4608	EG	Pierce St.	6	Ductile Iron	2	17	0.71 out of 5	N/A	\$0
Distribution Main	9026	P-4685	EG	Pierce St.	6	Ductile Iron	2	17	0.71 out of 5	N/A	\$0
Distribution Main	5245	P-4214	EG	Pine Hill Dr.	8	Asbestos Cement	34	51	1.14 out of 5	\$442	15,097
Distribution Main	6028	P-4214	EG	Pine Hill Dr.	8	Asbestos Cement	457	51	1.14 out of 5	\$442	201,820
Distribution Main	112	P-4736	EG	Post Rd	10	Cast Iron	324	133	1.86 out of 5	\$442	143,052
Distribution Main	9612		EG	Post Rd	2	Copper	47	7	1.99 out of 5	N/A	\$0
Transmission Main	304	P-4241	EG	Post Rd.	16	Ductile Iron	472	22	0.14 out of 5	N/A	\$0
Distribution Main	376	P-4736	EG	Post Rd.	10	Cast Iron	876	133	1.86 out of 5	\$442	387,318
Distribution Main	377	P-4736	EG	Post Rd.	10	Cast Iron	47	133	1.86 out of 5	\$442	20,559
Transmission Main	1940	P-4241	EG	Post Rd.	16	Ductile Iron	14	22	0.14 out of 5	N/A	\$0
Transmission Main	1941	P-4241	EG	Post Rd.	16	Ductile Iron	280	22	0.14 out of 5	N/A	\$0
Distribution Main	2904	P-4292	EG	Post Rd.	10	Ductile Iron	7	23	0.14 out of 5	N/A	\$0
Distribution Main	2977	P-4067	EG	Post Rd.	10	Ductile Iron	691	23	0.14 out of 5	N/A	\$0
Distribution Main	2978	P-4067	EG	Post Rd.	10	Ductile Iron	301	23	0.14 out of 5	N/A	\$0
Distribution Main	3449	P-4067	EG	Post Rd.	10	Ductile Iron	192	23	0.14 out of 5	N/A	\$0
Distribution Main	3689	P-4736	EG	Post Rd.	10	Cast Iron	242	133	1.86 out of 5	\$442	107,040
Distribution Main	3940		EG	Post Rd.	10	Ductile Iron	40	23	0.14 out of 5	N/A	\$0
Distribution Main	3942	P-4306	EG	Post Rd.	10	Ductile Iron	646	23	0.14 out of 5	N/A	\$0
Distribution Main	3944	P-40072	EG	Post Rd.	10	Ductile Iron	611	23	0.14 out of 5	N/A	\$0
Distribution Main	4039	P-4276	EG	Post Rd.	10	Cast Iron	465	133	1.86 out of 5	\$442	205,542
Distribution Main	4040	P-40032	EG	Post Rd.	10	Ductile Iron	199	23	0.14 out of 5	N/A	\$0
Distribution Main	4045	P-4272	EG	Post Rd.	10	Cast Iron	340	133	1.86 out of 5	\$442	150,462
Distribution Main	4046	P-4272	EG	Post Rd.	10	Cast Iron	638	133	1.86 out of 5	\$442	282,091
Distribution Main	4147	P-4739	EG	Post Rd.	10	Ductile Iron	528	23	0.14 out of 5	N/A	\$0
Transmission Main	4193	P-4735	EG	Post Rd.	20	Ductile Iron	647	22	0.14 out of 5	N/A	\$0
Transmission Main	4195	P-4227	EG	Post Rd.	20	Asbestos Cement	426	55	1.14 out of 5	\$442	188,211
Transmission Main	4196	P-4227	EG	Post Rd.	20	Asbestos Cement	54	55	1.14 out of 5	\$442	23,901
Distribution Main	4197	P-4735	EG	Post Rd.	10	Cast Iron	382	133	1.86 out of 5	\$442	168,928
Distribution Main	4198	P-4737	EG	Post Rd.	10	Cast Iron	5	133	1.86 out of 5	\$442	1,991
Distribution Main	4199	P-4278	EG	Post Rd.	10	Ductile Iron	296	23	0.14 out of 5	N/A	\$0
Distribution Main	4205		EG	Post Rd.	6	Ductile Iron	9	23	0.85 out of 5	N/A	\$0
Distribution Main	4206	P-4289	EG	Post Rd.	10	Ductile Iron	408	23	0.14 out of 5	N/A	\$0
Distribution Main	4246	P-4737	EG	Post Rd.	10	Cast Iron	493	133	1.86 out of 5	\$442	217,716
Distribution Main	4247	P-4737	EG	Post Rd.	10	Cast Iron	29	133	1.86 out of 5	\$442	12,676
Transmission Main	4983		EG	Post Rd.	12	Ductile Iron	27	23	0.14 out of 5	N/A	\$0
Distribution Main	4984	P-4269	EG	Post Rd.	10	Cast Iron	304	133	1.86 out of 5	\$442	134,288
Transmission Main	4988	P-4241	EG	Post Rd.	16	Ductile Iron	74	22	0.14 out of 5	N/A	\$0
Distribution Main	5429	P-4865	EG	Post Rd.	10	Ductile Iron	6	23	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	5582	P-4734	EG	Post Rd.	20	Ductile Iron	138	22	0.14 out of 5	N/A	\$0
Transmission Main	5583	P-4734	EG	Post Rd.	20	Ductile Iron	397	22	0.14 out of 5	N/A	\$0
Transmission Main	5584	P-4734	EG	Post Rd.	20	Ductile Iron	106	22	0.14 out of 5	N/A	\$0
Transmission Main	5717	P-4241	EG	Post Rd.	16	Ductile Iron	69	22	0.14 out of 5	N/A	\$0
Distribution Main	6118	P-4278	EG	Post Rd.	10	Ductile Iron	973	23	0.14 out of 5	N/A	\$0
Distribution Main	6121	P-4272	EG	Post Rd.	10	Cast Iron	230	133	1.86 out of 5	\$442	101,551
Distribution Main	6134	P-4272	EG	Post Rd.	10	Cast Iron	119	133	1.86 out of 5	\$442	52,762
Distribution Main	6135	P-4272	EG	Post Rd.	10	Cast Iron	653	133	1.86 out of 5	\$442	288,631
Distribution Main	6138	P-4269	EG	Post Rd.	10	Cast Iron	655	133	1.86 out of 5	\$442	289,661
Distribution Main	6139	P-4269	EG	Post Rd.	10	Cast Iron	31	133	1.86 out of 5	\$442	13,645
Distribution Main	6140	P-4699	EG	Post Rd.	10	Ductile Iron	963	23	0.14 out of 5	N/A	\$0
Distribution Main	6251	P-4865	EG	Post Rd.	10	Ductile Iron	193	23	0.14 out of 5	N/A	\$0
Distribution Main	6252	P-4865	EG	Post Rd.	10	Ductile Iron	388	23	0.14 out of 5	N/A	\$0
Distribution Main	6253		EG	Post Rd.	10	Ductile Iron	3	23	0.14 out of 5	N/A	\$0
Distribution Main	6254	P-4321	EG	Post Rd.	10	Ductile Iron	566	23	0.14 out of 5	N/A	\$0
Distribution Main	6256	P-4321	EG	Post Rd.	10	Ductile Iron	93	23	0.14 out of 5	N/A	\$0
Distribution Main	6260	P-4312	EG	Post Rd.	10	Ductile Iron	28	23	0.14 out of 5	N/A	\$0
Distribution Main	6469	P-4303	EG	Post Rd.	10	Ductile Iron	51	23	0.14 out of 5	N/A	\$0
Distribution Main	6470	P-4303	EG	Post Rd.	10	Ductile Iron	145	23	0.14 out of 5	N/A	\$0
Distribution Main	6471	P-4294	EG	Post Rd.	10	Ductile Iron	192	23	0.14 out of 5	N/A	\$0
Distribution Main	6472	P-4292	EG	Post Rd.	10	Ductile Iron	204	23	0.14 out of 5	N/A	\$0
Distribution Main	6635	P-4312	EG	Post Rd.	10	Ductile Iron	18	23	0.14 out of 5	N/A	\$0
Transmission Main	9882	P-4734	EG	Post Rd.	16	Ductile Iron	16	22	0.14 out of 5	N/A	\$0
Transmission Main	9883	P-4239	EG	Post Rd.	12	Ductile Iron	56	22	0.14 out of 5	N/A	\$0
Transmission Main	9885	P-4239	EG	Post Rd.	12	Ductile Iron	50	22	0.14 out of 5	N/A	\$0
Transmission Main	9887		EG	Post Rd.	12	Ductile Iron	69	23	0.14 out of 5	N/A	\$0
Distribution Main	10272		EG	Post Rd.	6	Ductile Iron	32	23	0.85 out of 5	N/A	\$0
Transmission Main	10282	P-4734	EG	Post Rd.	16	Ductile Iron	8	22	0.14 out of 5	N/A	\$0
Distribution Main	10283	P-40052	EG	Post Rd.	10	Cast Iron	256	133	1.86 out of 5	\$442	113,313
Distribution Main	10284	P-4067	EG	Post Rd.	10	Ductile Iron	386	23	0.14 out of 5	N/A	\$0
Distribution Main	10285	P-4067	EG	Post Rd.	10	Ductile Iron	36	23	0.14 out of 5	N/A	\$0
Transmission Main	11050		EG	Post Rd.	16	Ductile Iron	48	22	0.14 out of 5	N/A	\$0
Distribution Main	11051	P-4067	EG	Post Rd.	10	Ductile Iron	34	23	0.14 out of 5	N/A	\$0
Distribution Main	11052	P-4269	EG	Post Rd.	10	Cast Iron	7	133	1.86 out of 5	\$442	2,954
Distribution Main	11053	P-4067	EG	Post Rd.	10	Ductile Iron	21	23	0.14 out of 5	N/A	\$0
Transmission Main	11197	P-4734	EG	Post Rd.	16	Ductile Iron	4	22	0.14 out of 5	N/A	\$0
Distribution Main	11219	P-4067	EG	Post Rd.	10	Ductile Iron	78	23	0.14 out of 5	N/A	\$0
Distribution Main	11816	P-4736	EG	Post Rd.	10	Cast Iron	106	133	1.86 out of 5	\$442	46,980
Distribution Main	12176		EG	Post Rd.	10	Ductile Iron	376	23	0.14 out of 5	N/A	\$0
Distribution Main	2911	P-4346	EG	Power St.	6	PVC	301	36	1.14 out of 5	\$442	133,011
Distribution Main	5630	P-4504	EG	Pricewood Dr.	6	Asbestos Cement	690	61	2 out of 5	\$442	305,037
Distribution Main	4254	P-4682	EG	Proctor Ave.	8	Ductile Iron	404	17	0 out of 5	N/A	\$0
Distribution Main	4255	P-4680	EG	Proctor Ave.	8	Ductile Iron	237	17	0 out of 5	N/A	\$0
Distribution Main	6351	P-4548	EG	Proctor Ave.	6	Cast Iron	333	133	2.57 out of 5	\$442	147,070

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9005	P-4548	EG	Proctor Ave.	8	Ductile Iron	18	17	0 out of 5	N/A	\$0
Distribution Main	11001	P-4680	EG	Proctor Ave.	8	Ductile Iron	5	17	0 out of 5	N/A	\$0
Distribution Main	5690	P-4580	EG	Prospect St.	6	Asbestos Cement	42	70	2 out of 5	\$442	18,635
Transmission Main	6225	P-4955	EG	Prospect St.	12	Ductile Iron	6	17	0 out of 5	N/A	\$0
Transmission Main	6229	P-4580	EG	Prospect St.	12	Ductile Iron	426	17	0 out of 5	N/A	\$0
Distribution Main	6264	P-4589	EG	Prospect St.	6	Asbestos Cement	250	70	2 out of 5	\$442	110,576
Distribution Main	6265	P-4589	EG	Prospect St.	6	Asbestos Cement	202	70	2 out of 5	\$442	89,072
Transmission Main	6645	P-4580	EG	Prospect St.	12	Ductile Iron	7	23	0.14 out of 5	N/A	\$0
Transmission Main	6646	P-4580	EG	Prospect St.	12	Ductile Iron	7	23	0.14 out of 5	N/A	\$0
Transmission Main	6723	P-4581	EG	Prospect St.	12	Ductile Iron	250	23	0.14 out of 5	N/A	\$0
Transmission Main	6744	P-4955	EG	Prospect St.	12	Ductile Iron	244	23	0.14 out of 5	N/A	\$0
Transmission Main	6745	P-4955	EG	Prospect St.	12	Ductile Iron	25	17	0 out of 5	N/A	\$0
Transmission Main	11328	P-4955	EG	Prospect St.	12	Ductile Iron	4	17	0 out of 5	N/A	\$0
Distribution Main	5840	P-4082	EG	Quail Ct.	8	PVC	247	40	0.43 out of 5	\$442	109,366
Transmission Main	9098	P-4755	EG	Quaker Ln	16	Ductile Iron	1,071	13	0 out of 5	N/A	\$0
Transmission Main	9101	P-10006	EG	Quaker Ln	16	Ductile Iron	1,202	13	0 out of 5	N/A	\$0
Distribution Main	10329	P-4631	EG	Queen St	8	Ductile Iron	41	4	0 out of 5	N/A	\$0
Distribution Main	10330	P-4631	EG	Queen St	8	Ductile Iron	10	4	0 out of 5	N/A	\$0
Distribution Main	10331	P-4631	EG	Queen St	6	Ductile Iron	2	4	0.71 out of 5	N/A	\$0
Distribution Main	897	P-4930	EG	Queen St.	6	Cast Iron	454	133	2.57 out of 5	\$442	200,791
Distribution Main	898	P-4930	EG	Queen St.	6	Cast Iron	8	133	2.57 out of 5	\$442	3,755
Distribution Main	5402	P-4624	EG	Queen St.	6	Cast Iron	428	133	2.57 out of 5	\$442	189,183
Distribution Main	5536	P-4917	EG	Queen St.	8	Asbestos Cement	10	44	1.14 out of 5	\$442	4,400
Distribution Main	6291	P-4916	EG	Queen St.	8	Cast Iron	9	133	1.86 out of 5	\$442	4,136
Distribution Main	6737	P-4631	EG	Queen St.	6	Asbestos Cement	297	44	1.85 out of 5	\$442	131,334
Distribution Main	6762	P-4624	EG	Queen St.	6	Cast Iron	29	133	2.57 out of 5	\$442	12,824
Distribution Main	9196	P-4912	EG	Queen St.	8	Ductile Iron	24	19	0 out of 5	N/A	\$0
Distribution Main	9197	P-4913	EG	Queen St.	6	Ductile Iron	4	19	0.71 out of 5	N/A	\$0
Distribution Main	9198	P-4914	EG	Queen St.	6	Ductile Iron	4	19	0.71 out of 5	N/A	\$0
Distribution Main	10909	P-4914	EG	Queen St.	8	Ductile Iron	15	19	0 out of 5	N/A	\$0
Distribution Main	11748	P-4930	EG	Queen St.	6	Cast Iron	8	133	2.57 out of 5	\$442	3,495
Distribution Main	5826	P-4032	EG	Rabbit Run	8	PVC	193	32	0.43 out of 5	\$442	85,371
Distribution Main	5827	P-4032	EG	Rabbit Run	8	PVC	487	32	0.43 out of 5	\$442	215,427
Transmission Main	302	P-4571	EG	Rector St.	12	Ductile Iron	40	22	0.14 out of 5	N/A	\$0
Transmission Main	3857	P-4571	EG	Rector St.	12	Ductile Iron	47	22	0.14 out of 5	N/A	\$0
Transmission Main	4506	P-4572	EG	Rector St.	12	Ductile Iron	10	17	0 out of 5	N/A	\$0
Transmission Main	4507	P-4601	EG	Rector St.	12	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Transmission Main	4508	P-4601	EG	Rector St.	12	Ductile Iron	744	22	0.14 out of 5	N/A	\$0
Transmission Main	4509	P-4571	EG	Rector St.	12	Ductile Iron	11	22	0.14 out of 5	N/A	\$0
Transmission Main	4510	P-4571	EG	Rector St.	12	Ductile Iron	2	22	0.14 out of 5	N/A	\$0
Transmission Main	4586	P-4603	EG	Rector St.	12	Ductile Iron	67	22	0.14 out of 5	N/A	\$0
Transmission Main	5672	P-4572	EG	Rector St.	12	Ductile Iron	49	22	0.14 out of 5	N/A	\$0
Transmission Main	6217	P-4572	EG	Rector St.	12	Ductile Iron	383	22	0.14 out of 5	N/A	\$0
Transmission Main	6721	P-4601	EG	Rector St.	12	Ductile Iron	12	17	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3909	P-4486	EG	Red Barn Ln.	8	Asbestos Cement	55	46	1.14 out of 5	\$442	24,517
Distribution Main	3910	P-4486	EG	Red Barn Ln.	8	Asbestos Cement	418	46	1.14 out of 5	\$442	184,566
Distribution Main	6384	P-4484	EG	Red Barn Ln.	8	Asbestos Cement	167	46	1.14 out of 5	\$442	73,623
Distribution Main	6385	P-4484	EG	Red Barn Ln.	8	Asbestos Cement	869	46	1.14 out of 5	\$442	384,171
Distribution Main	10231	P-4484	EG	Red Barn Ln.	8	Asbestos Cement	399	46	1.14 out of 5	\$442	176,506
Distribution Main	11831	P-4486	EG	Red Barn Ln.	8	Asbestos Cement	46	46	1.14 out of 5	\$442	20,423
Distribution Main	6804	P-4318	EG	Red Oak Rd.	6	Asbestos Cement	809	51	1.85 out of 5	\$442	357,421
Distribution Main	6498	P-4434	EG	Reed Place	6	Asbestos Cement	5	50	1.85 out of 5	\$442	2,236
Distribution Main	6499	P-4434	EG	Reed Place	6	Asbestos Cement	281	50	1.85 out of 5	\$442	124,019
Distribution Main	9476	P-4942	EG	Reilly Av	1	Copper	261	63	2.43 out of 5	\$442	115,547
Distribution Main	5521	P-4092	EG	Remy Place	8	Ductile Iron	8	38	0.14 out of 5	\$442	3,409
Distribution Main	5531	P-4092	EG	Remy Place	8	Ductile Iron	293	38	0.14 out of 5	\$442	129,547
Distribution Main	5660	P-4092	EG	Remy Place	8	Ductile Iron	3	38	0.14 out of 5	\$442	1,485
Distribution Main	5661	P-4092	EG	Remy Place	8	Ductile Iron	10	38	0.14 out of 5	\$442	4,232
Distribution Main	3862	P-4609	EG	Revolution St.	6	Asbestos Cement	345	75	2 out of 5	\$442	152,620
Distribution Main	3863	P-4609	EG	Revolution St.	6	Unknown	351	UNK	0.71 out of 5	\$442	155,149
Distribution Main	1901	P-4576	EG	Reynolds St.	4	Cast Iron	607	133	3.29 out of 5	\$442	268,177
Distribution Main	6214	P-4584	EG	Reynolds St.	4	Cast Iron	416	133	3.29 out of 5	\$442	183,825
Distribution Main	6221	P-4576	EG	Reynolds St.	4	Cast Iron	19	133	3.29 out of 5	\$442	8,285
Distribution Main	6631	P-4584	EG	Reynolds St.	4	Cast Iron	8	133	3.29 out of 5	\$442	3,427
Distribution Main	5860	P-4724	EG	Rhodes Way	8	Ductile Iron	3	17	0 out of 5	N/A	\$0
Distribution Main	5861	P-4724	EG	Rhodes Way	8	Ductile Iron	331	17	0 out of 5	N/A	\$0
Distribution Main	9234	P-4188	EG	Ridge Rd	8	Ductile Iron	60	8	0 out of 5	N/A	\$0
Distribution Main	9235	P-4187	EG	Ridge Rd	8	Ductile Iron	227	8	0 out of 5	N/A	\$0
Distribution Main	9236	P-4187	EG	Ridge Rd	8	Ductile Iron	165	8	0 out of 5	N/A	\$0
Distribution Main	10968	P-4188	EG	Ridge Rd	8	Ductile Iron	203	8	0 out of 5	N/A	\$0
Distribution Main	3660	P-4441	EG	Ridgefield Dr.	8	Asbestos Cement	157	45	1.14 out of 5	\$442	69,455
Distribution Main	4020	P-4441	EG	Ridgefield Dr.	8	Asbestos Cement	262	45	1.14 out of 5	\$442	115,758
Distribution Main	4201	P-4439	EG	Ridgefield Dr.	8	Asbestos Cement	423	45	1.14 out of 5	\$442	187,002
Distribution Main	4202	P-4439	EG	Ridgefield Dr.	8	Asbestos Cement	74	45	1.14 out of 5	\$442	32,759
Distribution Main	6297	P-4443	EG	Ridgefield Dr.	8	Asbestos Cement	408	45	1.14 out of 5	\$442	180,460
Distribution Main	3917	P-4250	EG	River Farm Drive	8	Ductile Iron	204	24	0.14 out of 5	N/A	\$0
Distribution Main	3918	P-4249	EG	River Farm Drive	8	Ductile Iron	445	24	0.14 out of 5	N/A	\$0
Distribution Main	3919	P-4249	EG	River Farm Drive	8	Ductile Iron	472	24	0.14 out of 5	N/A	\$0
Distribution Main	3920	P-4249	EG	River Farm Drive	8	Ductile Iron	129	24	0.14 out of 5	N/A	\$0
Distribution Main	3921	P-4247	EG	River Farm Drive	8	Ductile Iron	328	21	0.14 out of 5	N/A	\$0
Distribution Main	3922	P-4247	EG	River Farm Drive	8	Ductile Iron	411	21	0.14 out of 5	N/A	\$0
Distribution Main	3926	P-4250	EG	River Farm Drive	8	Ductile Iron	251	24	0.14 out of 5	N/A	\$0
Distribution Main	5663	P-4248	EG	River Farm Drive	8	Asbestos Cement	5	51	1.14 out of 5	\$442	2,196
Distribution Main	5664	P-4248	EG	River Farm Drive	8	Asbestos Cement	427	51	1.14 out of 5	\$442	188,927
Distribution Main	6057	P-4249	EG	River Farm Drive	8	Ductile Iron	125	24	0.14 out of 5	N/A	\$0
Distribution Main	6058	P-4249	EG	River Farm Drive	8	Ductile Iron	424	24	0.14 out of 5	N/A	\$0
Distribution Main	11850	P-4247	EG	River Farm Drive	8	Ductile Iron	396	21	0.14 out of 5	N/A	\$0
Distribution Main	11851	P-4247	EG	River Farm Drive	8	Ductile Iron	6	21	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3452	P-4083	EG	River Run	8	PVC	35	40	0.43 out of 5	\$442	15,259
Distribution Main	3453	P-4083	EG	River Run	8	PVC	708	40	0.43 out of 5	\$442	312,995
Distribution Main	3454	P-4081	EG	River Run	8	PVC	115	40	0.43 out of 5	\$442	50,847
Distribution Main	3455	P-4081	EG	River Run	8	PVC	1,058	40	0.43 out of 5	\$442	467,832
Distribution Main	3457	P-4084	EG	River Run	8	PVC	554	40	0.43 out of 5	\$442	244,713
Distribution Main	6584	P-4080	EG	River Run	8	PVC	1,089	40	0.43 out of 5	\$442	481,202
Distribution Main	6585	P-4080	EG	River Run	8	PVC	66	40	0.43 out of 5	\$442	29,175
Distribution Main	11834	P-4080	EG	River Run	8	PVC	85	40	0.43 out of 5	\$442	37,679
Distribution Main	6373	P-4048	EG	Robin Circle	6	Asbestos Cement	398	47	1.85 out of 5	\$442	175,900
Distribution Main	8314	P-4816	EG	Rock Way	8	Ductile Iron	642	14	0 out of 5	N/A	\$0
Distribution Main	8315	P-4816	EG	Rock Way	8	Ductile Iron	97	14	0 out of 5	N/A	\$0
Distribution Main	8316	P-4816	EG	Rock Way	8	Ductile Iron	580	14	0 out of 5	N/A	\$0
Distribution Main	11855	P-4816	EG	Rock Way	8	Ductile Iron	44	14	0 out of 5	N/A	\$0
Distribution Main	906	P-4594	EG	Rocky Hollow Rd.	6	Ductile Iron	18	17	0.71 out of 5	N/A	\$0
Distribution Main	6258	P-4694	EG	Rocky Hollow Rd.	6	Ductile Iron	25	17	0.71 out of 5	N/A	\$0
Distribution Main	6746	P-4661	EG	Rocky Hollow Rd.	8	Ductile Iron	143	17	0 out of 5	N/A	\$0
Distribution Main	6747	P-4661	EG	Rocky Hollow Rd.	8	Ductile Iron	52	17	0 out of 5	N/A	\$0
Distribution Main	6748	P-4938	EG	Rocky Hollow Rd.	8	Ductile Iron	74	17	0 out of 5	N/A	\$0
Distribution Main	6754	P-4694	EG	Rocky Hollow Rd.	8	Ductile Iron	152	17	0 out of 5	N/A	\$0
Distribution Main	11351	P-4694	EG	Rocky Hollow Rd.	8	Ductile Iron	34	17	0 out of 5	N/A	\$0
Distribution Main	9997		EG	Rocky Hollow Road	4	Ductile Iron	25	13	1.42 out of 5	N/A	\$0
Distribution Main	5726	P-4156	EG	Romano Ct.	8	Ductile Iron	32	17	0 out of 5	N/A	\$0
Distribution Main	5727	P-4156	EG	Romano Ct.	8	Ductile Iron	629	17	0 out of 5	N/A	\$0
Distribution Main	3456	P-4085	EG	Rosewood Ct.	8	PVC	139	40	0.43 out of 5	\$442	61,593
Distribution Main	966	P-4993	EG	Round Hill Ct	6	Unknown	275	35	0.85 out of 5	\$442	121,439
Distribution Main	459	P-4981	EG	Salley Ann Dr.	8	Asbestos Cement	226	35	1 out of 5	\$442	100,074
Distribution Main	121	P-4467	EG	Sanctuary Dr.	8	Ductile Iron	428	19	0 out of 5	N/A	\$0
Distribution Main	122	P-4467	EG	Sanctuary Dr.	8	Ductile Iron	44	19	0 out of 5	N/A	\$0
Distribution Main	4158	P-4473	EG	Sanctuary Dr.	8	Ductile Iron	96	19	0 out of 5	N/A	\$0
Distribution Main	4159	P-4473	EG	Sanctuary Dr.	8	Ductile Iron	75	19	0 out of 5	N/A	\$0
Distribution Main	4160	P-4474	EG	Sanctuary Dr.	8	Ductile Iron	406	19	0 out of 5	N/A	\$0
Distribution Main	4161	P-4473	EG	Sanctuary Dr.	8	Ductile Iron	506	19	0 out of 5	N/A	\$0
Distribution Main	4162	P-4473	EG	Sanctuary Dr.	8	Ductile Iron	10	19	0 out of 5	N/A	\$0
Distribution Main	4500	P-4467	EG	Sanctuary Dr.	8	Ductile Iron	5	19	0 out of 5	N/A	\$0
Distribution Main	4501	P-4467	EG	Sanctuary Dr.	8	Ductile Iron	527	19	0 out of 5	N/A	\$0
Distribution Main	5235	P-4469	EG	Sanctuary Dr.	8	Ductile Iron	20	19	0 out of 5	N/A	\$0
Distribution Main	6154	P-4469	EG	Sanctuary Dr.	8	Ductile Iron	290	19	0 out of 5	N/A	\$0
Distribution Main	6156	P-4472	EG	Sanctuary Dr.	8	Ductile Iron	149	19	0 out of 5	N/A	\$0
Distribution Main	6157	P-4472	EG	Sanctuary Dr.	8	Ductile Iron	51	19	0 out of 5	N/A	\$0
Distribution Main	6337	P-4467	EG	Sanctuary Dr.	8	Ductile Iron	5	19	0 out of 5	N/A	\$0
Distribution Main	10232	P-4472	EG	Sanctuary Dr.	8	Ductile Iron	129	19	0 out of 5	N/A	\$0
Distribution Main	11292	P-4469	EG	Sanctuary Dr.	8	Ductile Iron	4	19	0 out of 5	N/A	\$0
Distribution Main	6301	P-4442	EG	Sarah'S Trace	8	PVC	26	30	0.43 out of 5	\$442	11,514
Distribution Main	6302	P-4442	EG	Sarah'S Trace	8	PVC	557	30	0.43 out of 5	\$442	246,156

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9479	P-4948	EG	School Ln	1	Copper	151	UNK	1.99 out of 5	\$442	66,731
Distribution Main	9480	P-4948	EG	School Ln	1	Copper	30	UNK	1.99 out of 5	\$442	13,433
Transmission Main	896	P-4669	EG	Second St.	12	Ductile Iron	499	23	0.14 out of 5	N/A	\$0
Transmission Main	6640	P-4663	EG	Second St.	12	Ductile Iron	752	23	0.14 out of 5	N/A	\$0
Distribution Main	8319	P-4812	EG	Secret Lane	8	Ductile Iron	350	14	0 out of 5	N/A	\$0
Transmission Main	5818	P-4020	EG	Sheep Farm Dr	12	PVC	716	32	0.43 out of 5	\$442	316,657
Transmission Main	5819	P-4020	EG	Sheep Farm Dr	12	PVC	772	32	0.43 out of 5	\$442	341,202
Transmission Main	6370	P-4020	EG	Sheep Farm Dr	12	PVC	13	32	0.43 out of 5	\$442	5,963
Transmission Main	5817	P-40001	EG	Sheep Farm Dr.	12	PVC	15	32	0.43 out of 5	\$442	6,537
Distribution Main	5825	P-4021	EG	Sheep Farm Dr.	8	PVC	389	32	0.43 out of 5	\$442	171,853
Transmission Main	6358	P-40001	EG	Sheep Farm Dr.	12	PVC	145	32	0.43 out of 5	\$442	64,110
Transmission Main	6359	P-40001	EG	Sheep Farm Dr.	12	PVC	19	32	0.43 out of 5	\$442	8,538
Distribution Main	6371	P-4021	EG	Sheep Farm Dr.	8	PVC	7	32	0.43 out of 5	\$442	3,199
Transmission Main	1611	P-4814	EG	Shippeetown Rd	12	Ductile Iron	480	15	0 out of 5	N/A	\$0
Transmission Main	1612	P-4814	EG	Shippeetown Rd	12	Ductile Iron	60	15	0 out of 5	N/A	\$0
Transmission Main	3129	P-4996	EG	Shippeetown Rd	12	Ductile Iron	29	14	0 out of 5	N/A	\$0
Transmission Main	4099	P-4996	EG	Shippeetown Rd	12	Ductile Iron	7	14	0 out of 5	N/A	\$0
Transmission Main	8310	P-4814	EG	Shippeetown Rd	12	Ductile Iron	14	14	0 out of 5	N/A	\$0
Transmission Main	8311	P-4814	EG	Shippeetown Rd	12	Ductile Iron	14	15	0 out of 5	N/A	\$0
Transmission Main	8320	P-4741	EG	Shippeetown Rd	12	Ductile Iron	515	14	0 out of 5	N/A	\$0
Transmission Main	8321	P-4741	EG	Shippeetown Rd	12	Ductile Iron	46	14	0 out of 5	N/A	\$0
Distribution Main	8322	P-4998	EG	Shippeetown Rd	8	Ductile Iron	24	14	0 out of 5	N/A	\$0
Transmission Main	10979	P-4997	EG	Shippeetown Rd	12	Ductile Iron	27	14	0 out of 5	N/A	\$0
Transmission Main	11461	P-4741	EG	Shippeetown Rd	12	Ductile Iron	27	14	0 out of 5	N/A	\$0
Transmission Main	11462	P-4741	EG	Shippeetown Rd	12	Ductile Iron	169	14	0 out of 5	N/A	\$0
Transmission Main	504	P-4183	EG	Shippeetown Rd.	16	Ductile Iron	54	24	0.14 out of 5	N/A	\$0
Transmission Main	509	P-4183	EG	Shippeetown Rd.	16	Ductile Iron	996	24	0.14 out of 5	N/A	\$0
Transmission Main	1614	P-4814	EG	Shippeetown Rd.	12	Ductile Iron	647	24	0.14 out of 5	N/A	\$0
Transmission Main	2001	P-4183	EG	Shippeetown Rd.	16	Ductile Iron	443	24	0.14 out of 5	N/A	\$0
Transmission Main	168	P-4177	EG	Signal Ridge Way	20	Ductile Iron	96	36	0.14 out of 5	\$442	42,617
Transmission Main	169	P-4177	EG	Signal Ridge Way	20	Ductile Iron	529	36	0.14 out of 5	\$442	233,666
Transmission Main	963	P-4177	EG	Signal Ridge Way	20	Ductile Iron	18	36	0.14 out of 5	\$442	7,928
Distribution Main	964	P-4880	EG	Signal Ridge Way	8	Ductile Iron	443	30	0.14 out of 5	\$442	195,905
Transmission Main	971	P-4176	EG	Signal Ridge Way	12	Asbestos Cement	504	39	1 out of 5	\$442	222,881
Transmission Main	972	P-4176	EG	Signal Ridge Way	12	Asbestos Cement	48	39	1 out of 5	\$442	21,103
Transmission Main	973	P-4173	EG	Signal Ridge Way	12	Asbestos Cement	311	39	1 out of 5	\$442	137,350
Transmission Main	2024	P-4178	EG	Signal Ridge Way	12	Asbestos Cement	388	39	1 out of 5	\$442	171,631
Transmission Main	2027	P-4880	EG	Signal Ridge Way	12	Ductile Iron	20	39	0.14 out of 5	\$442	9,060
Transmission Main	2032	P-4174	EG	Signal Ridge Way	12	Asbestos Cement	58	39	1 out of 5	\$442	25,777
Transmission Main	2033	P-4179	EG	Signal Ridge Way	20	Ductile Iron	765	36	0.14 out of 5	\$442	338,168
Transmission Main	2035	P-4174	EG	Signal Ridge Way	12	Asbestos Cement	45	39	1 out of 5	\$442	19,752
Transmission Main	2036	P-4174	EG	Signal Ridge Way	12	Asbestos Cement	618	39	1 out of 5	\$442	272,950
Transmission Main	2039	P-4173	EG	Signal Ridge Way	12	Asbestos Cement	10	39	1 out of 5	\$442	4,610
Transmission Main	2040	P-4179	EG	Signal Ridge Way	20	Ductile Iron	761	36	0.14 out of 5	\$442	336,389

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	2041	P-4179	EG	Signal Ridge Way	20	Ductile Iron	35	36	0.14 out of 5	\$442	15,663
Transmission Main	2042	P-4176	EG	Signal Ridge Way	12	Asbestos Cement	34	39	1 out of 5	\$442	14,991
Transmission Main	2043	P-4179	EG	Signal Ridge Way	20	Ductile Iron	34	36	0.14 out of 5	\$442	15,130
Transmission Main	2044	P-4179	EG	Signal Ridge Way	20	Ductile Iron	12	36	0.14 out of 5	\$442	5,105
Transmission Main	9440	P-4179	EG	Signal Ridge Way	20	Ductile Iron	390	36	0.14 out of 5	\$442	172,247
Distribution Main	460	P-4985	EG	Silo Lane	8	Asbestos Cement	22	35	1 out of 5	\$442	9,511
Distribution Main	6379	P-4985	EG	Silo Lane	8	Asbestos Cement	130	35	1 out of 5	\$442	57,372
Distribution Main	10207		EG	Silo Lane	8	Asbestos Cement	238	35	1 out of 5	\$442	105,309
Distribution Main	1815		EG	Silverwood Dr.	6	Asbestos Cement	66	51	1.85 out of 5	\$442	29,061
Distribution Main	3849	P-4298	EG	Silverwood Dr.	6	Asbestos Cement	198	51	1.85 out of 5	\$442	87,683
Distribution Main	5610	P-4394	EG	Silverwood Dr.	6	Asbestos Cement	260	51	1.85 out of 5	\$442	114,965
Distribution Main	5611	P-4297	EG	Silverwood Dr.	6	Asbestos Cement	222	51	1.85 out of 5	\$442	98,110
Distribution Main	6799	P-4298	EG	Silverwood Dr.	6	Asbestos Cement	94	51	1.85 out of 5	\$442	41,535
Distribution Main	10234	P-4297	EG	Silverwood Dr.	6	Asbestos Cement	44	51	1.85 out of 5	\$442	19,241
Distribution Main	662	P-4668	EG	Sixth Ave.	6	Cast Iron	12	129	2.57 out of 5	\$442	5,475
Distribution Main	663	P-40038	EG	Sixth Ave.	6	Cast Iron	236	129	2.57 out of 5	\$442	104,390
Distribution Main	907	P-4207	EG	Sixth Ave.	10	Ductile Iron	3	23	0.14 out of 5	N/A	\$0
Distribution Main	4267	P-4668	EG	Sixth Ave.	6	Cast Iron	11	129	2.57 out of 5	\$442	4,819
Distribution Main	4268	P-4668	EG	Sixth Ave.	6	Cast Iron	219	129	2.57 out of 5	\$442	96,926
Distribution Main	6203	P-4667	EG	Sixth Ave.	6	Cast Iron	218	129	2.57 out of 5	\$442	96,398
Distribution Main	6204	P-4943	EG	Sixth Ave.	6	Cast Iron	464	129	2.57 out of 5	\$442	204,912
Distribution Main	6205	P-4943	EG	Sixth Ave.	6	Cast Iron	14	129	2.57 out of 5	\$442	6,121
Distribution Main	6249	P-4207	EG	Sixth Ave.	10	Ductile Iron	4	23	0.14 out of 5	N/A	\$0
Distribution Main	6262	P-4207	EG	Sixth Ave.	10	Ductile Iron	6	23	0.14 out of 5	N/A	\$0
Distribution Main	6263	P-4207	EG	Sixth Ave.	10	Ductile Iron	22	23	0.14 out of 5	N/A	\$0
Distribution Main	6636	P-4207	EG	Sixth Ave.	10	Ductile Iron	9	23	0.14 out of 5	N/A	\$0
Transmission Main	6637	P-4670	EG	Sixth Ave.	12	Ductile Iron	212	23	0.14 out of 5	N/A	\$0
Transmission Main	10249	P-4668	EG	Sixth Ave.	12	Ductile Iron	13	23	0.14 out of 5	N/A	\$0
Distribution Main	9223	P-40014	EG	Sleepy Hollow Rd	8	Ductile Iron	603	8	0 out of 5	N/A	\$0
Distribution Main	9224	P-4198	EG	Sleepy Hollow Rd	8	Ductile Iron	376	8	0 out of 5	N/A	\$0
Distribution Main	9225	P-4198	EG	Sleepy Hollow Rd	8	Ductile Iron	38	8	0 out of 5	N/A	\$0
Distribution Main	10967	P-40013	EG	Sleepy Hollow Rd	8	Ductile Iron	324	8	0 out of 5	N/A	\$0
Distribution Main	9125	P-4837	EG	So County Tr	6	Ductile Iron	3	UNK	0.71 out of 5	\$442	1,218
Transmission Main	462	P-4830	EG	So County Tr.	12	Asbestos Cement	14	56	1.14 out of 5	\$442	6,051
Transmission Main	1813	P-4743	EG	So County Tr.	12	Asbestos Cement	80	55	1.14 out of 5	\$442	35,142
Transmission Main	3458	P-4830	EG	So County Tr.	12	Asbestos Cement	499	56	1.14 out of 5	\$442	220,634
Transmission Main	3459	P-4830	EG	So County Tr.	12	Asbestos Cement	87	56	1.14 out of 5	\$442	38,329
Transmission Main	5476	P-4115	EG	So County Tr.	12	Asbestos Cement	660	55	1.14 out of 5	\$442	291,728
Transmission Main	5477	P-4115	EG	So County Tr.	12	Asbestos Cement	148	55	1.14 out of 5	\$442	65,335
Transmission Main	5885	P-4743	EG	So County Tr.	12	Asbestos Cement	8	56	1.14 out of 5	\$442	3,737
Transmission Main	5886	P-4743	EG	So County Tr.	12	Asbestos Cement	334	55	1.14 out of 5	\$442	147,567
Transmission Main	5887	P-4743	EG	So County Tr.	12	Asbestos Cement	844	55	1.14 out of 5	\$442	373,127
Transmission Main	5889	P-4115	EG	So County Tr.	12	Asbestos Cement	799	55	1.14 out of 5	\$442	353,081
Transmission Main	5890	P-4115	EG	So County Tr.	12	Asbestos Cement	19	55	1.14 out of 5	\$442	8,317

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	5891	P-4115	EG	So County Tr.	12	Asbestos Cement	337	55	1.14 out of 5	\$442	149,041
Transmission Main	5952	P-4863	EG	So County Tr.	12	Asbestos Cement	693	56	1.14 out of 5	\$442	306,132
Transmission Main	6032	P-4182	EG	So County Tr.	12	Asbestos Cement	11	56	1.14 out of 5	\$442	5,071
Transmission Main	6033	P-4182	EG	So County Tr.	12	Asbestos Cement	573	56	1.14 out of 5	\$442	253,149
Transmission Main	6034	P-4182	EG	So County Tr.	12	Asbestos Cement	742	56	1.14 out of 5	\$442	327,765
Transmission Main	6035	P-4115	EG	So County Tr.	12	Asbestos Cement	204	55	1.14 out of 5	\$442	90,172
Transmission Main	6036	P-4115	EG	So County Tr.	12	Asbestos Cement	467	55	1.14 out of 5	\$442	206,532
Transmission Main	6038	P-4115	EG	So County Tr.	12	Asbestos Cement	25	55	1.14 out of 5	\$442	10,964
Transmission Main	6045	P-4182	EG	So County Tr.	12	Asbestos Cement	509	56	1.14 out of 5	\$442	224,829
Transmission Main	6046	P-4182	EG	So County Tr.	12	Asbestos Cement	398	56	1.14 out of 5	\$442	175,893
Transmission Main	6047	P-4784	EG	So County Tr.	12	Asbestos Cement	417	56	1.14 out of 5	\$442	184,139
Transmission Main	6048	P-4784	EG	So County Tr.	12	Asbestos Cement	408	56	1.14 out of 5	\$442	180,158
Transmission Main	6049	P-4883	EG	So County Tr.	12	Asbestos Cement	508	56	1.14 out of 5	\$442	224,588
Transmission Main	6050	P-4883	EG	So County Tr.	12	Asbestos Cement	495	56	1.14 out of 5	\$442	218,878
Transmission Main	6051	P-4863	EG	So County Tr.	12	Asbestos Cement	483	56	1.14 out of 5	\$442	213,526
Transmission Main	6701	P-4115	EG	So County Tr.	12	Asbestos Cement	15	55	1.14 out of 5	\$442	6,563
Transmission Main	6702	P-4115	EG	So County Tr.	12	Asbestos Cement	776	55	1.14 out of 5	\$442	343,050
Transmission Main	6703	P-4115	EG	So County Tr.	12	Asbestos Cement	1,151	55	1.14 out of 5	\$442	508,720
Transmission Main	9707		EG	So County Tr.	12	Ductile Iron	13	12	0 out of 5	N/A	\$0
Distribution Main	9708		EG	So County Tr.	8	Ductile Iron	12	7	0 out of 5	N/A	\$0
Transmission Main	11316	P-4115	EG	So County Tr.	12	Asbestos Cement	191	55	1.14 out of 5	\$442	84,385
Transmission Main	11321	P-4863	EG	So County Tr.	12	Asbestos Cement	191	56	1.14 out of 5	\$442	84,574
Transmission Main	11323	P-4784	EG	So County Tr.	12	Asbestos Cement	75	56	1.14 out of 5	\$442	33,293
Transmission Main	11819	P-4115	EG	So County Tr.	12	Asbestos Cement	608	55	1.14 out of 5	\$442	268,806
Transmission Main	12087	P-4784	EG	So County Tr.	12	Asbestos Cement	80	56	1.14 out of 5	\$442	35,390
Transmission Main	12088	P-4863	EG	So County Tr.	12	Asbestos Cement	73	56	1.14 out of 5	\$442	32,367
Distribution Main	2910	P-4370	EG	So. Pierce Rd.	8	Ductile Iron	224	36	0.14 out of 5	\$442	98,855
Distribution Main	3655	P-4360	EG	So. Pierce Rd.	8	Ductile Iron	242	36	0.14 out of 5	\$442	106,803
Distribution Main	3838	P-4399	EG	So. Pierce Rd.	8	Ductile Iron	6	36	0.14 out of 5	\$442	2,601
Distribution Main	3839	P-4399	EG	So. Pierce Rd.	8	Ductile Iron	722	36	0.14 out of 5	\$442	319,202
Distribution Main	5597	P-4399	EG	So. Pierce Rd.	8	Ductile Iron	257	36	0.14 out of 5	\$442	113,733
Distribution Main	5598	P-4399	EG	So. Pierce Rd.	8	Ductile Iron	678	36	0.14 out of 5	\$442	299,861
Distribution Main	6137	P-4360	EG	So. Pierce Rd.	8	Ductile Iron	10	36	0.14 out of 5	\$442	4,501
Distribution Main	6478	P-4359	EG	So. Pierce Rd.	8	Ductile Iron	233	36	0.14 out of 5	\$442	102,916
Distribution Main	6479	P-4409	EG	So. Pierce Rd.	8	Ductile Iron	147	36	0.14 out of 5	\$442	64,858
Distribution Main	6480	P-4409	EG	So. Pierce Rd.	8	Ductile Iron	329	36	0.14 out of 5	\$442	145,323
Distribution Main	10242	P-4323	EG	So. Pierce Rd.	8	Ductile Iron	45	36	0.14 out of 5	\$442	20,054
Distribution Main	4248	P-4956	EG	Somerset St.	2	Copper	313	81	2.57 out of 5	\$442	138,537
Distribution Main	6644	P-4952	EG	Somerset St.	1.5	Copper	247	81	2.57 out of 5	\$442	109,365
Distribution Main	9009	P-4951	EG	Somerset St.	6	Ductile Iron	39	17	0.71 out of 5	N/A	\$0
Distribution Main	5830	P-4016	EG	Sonnet Dr.	8	PVC	481	32	0.43 out of 5	\$442	212,420
Distribution Main	5831	P-4016	EG	Sonnet Dr.	8	PVC	132	32	0.43 out of 5	\$442	58,317
Distribution Main	9349		EG	South County Tr	6	Ductile Iron	2	8	0.71 out of 5	N/A	\$0
Distribution Main	9831		EG	South County Tr	8	Ductile Iron	6	11	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9832		EG	South County Tr	8	Ductile Iron	6	11	0 out of 5	N/A	\$0
Distribution Main	9982		EG	South County Tr	4	Ductile Iron	1	6	1.42 out of 5	N/A	\$0
Transmission Main	1809	P-40012	EG	South County Tr.	12	Asbestos Cement	91	56	1.14 out of 5	\$442	40,079
Transmission Main	1810	P-40012	EG	South County Tr.	12	Asbestos Cement	484	56	1.14 out of 5	\$442	214,034
Transmission Main	1811	P-4743	EG	South County Tr.	12	Asbestos Cement	15	56	1.14 out of 5	\$442	6,684
Transmission Main	1816	P-4209	EG	South County Tr.	12	Asbestos Cement	1,075	56	1.14 out of 5	\$442	474,966
Transmission Main	1817	P-4209	EG	South County Tr.	12	Asbestos Cement	371	56	1.14 out of 5	\$442	163,763
Distribution Main	4924	P-4209	EG	South County Tr.	10	HDPE	536	2	0.28 out of 5	N/A	\$0
Transmission Main	5509	P-4186	EG	South County Tr.	12	Asbestos Cement	200	56	1.14 out of 5	\$442	88,293
Transmission Main	5510	P-4186	EG	South County Tr.	12	Asbestos Cement	376	56	1.14 out of 5	\$442	166,324
Transmission Main	5511	P-4210	EG	South County Tr.	12	Asbestos Cement	164	56	1.14 out of 5	\$442	72,425
Transmission Main	5512	P-4210	EG	South County Tr.	12	Asbestos Cement	65	56	1.14 out of 5	\$442	28,648
Transmission Main	5513	P-40008	EG	South County Tr.	12	Asbestos Cement	16	56	1.14 out of 5	\$442	6,945
Transmission Main	5514	P-40008	EG	South County Tr.	12	Asbestos Cement	773	56	1.14 out of 5	\$442	341,612
Transmission Main	5516	P-4209	EG	South County Tr.	12	Asbestos Cement	337	56	1.14 out of 5	\$442	148,810
Transmission Main	5517	P-4209	EG	South County Tr.	12	Asbestos Cement	275	56	1.14 out of 5	\$442	121,676
Transmission Main	5871	P-40012	EG	South County Tr.	12	Asbestos Cement	416	56	1.14 out of 5	\$442	183,717
Transmission Main	5872	P-40012	EG	South County Tr.	12	Asbestos Cement	569	56	1.14 out of 5	\$442	251,320
Transmission Main	6387	P-40009	EG	South County Tr.	12	Asbestos Cement	48	56	1.14 out of 5	\$442	21,287
Transmission Main	6704	P-4837	EG	South County Tr.	12	Asbestos Cement	520	56	1.14 out of 5	\$442	229,704
Transmission Main	6705	P-4208	EG	South County Tr.	12	Ductile Iron	1,067	21	0.14 out of 5	N/A	\$0
Transmission Main	6706		EG	South County Tr.	12	Asbestos Cement	1	56	1.14 out of 5	\$442	338
Transmission Main	6707	P-4837	EG	South County Tr.	12	Asbestos Cement	137	56	1.14 out of 5	\$442	60,769
Transmission Main	6708	P-4837	EG	South County Tr.	12	Asbestos Cement	117	56	1.14 out of 5	\$442	51,914
Transmission Main	9380	P-4837	EG	South County Tr.	12	Asbestos Cement	167	56	1.14 out of 5	\$442	73,876
Transmission Main	9381	P-4837	EG	South County Tr.	12	Asbestos Cement	105	56	1.14 out of 5	\$442	46,569
Transmission Main	9384	P-40017	EG	South County Tr.	12	Ductile Iron	30	21	0.14 out of 5	N/A	\$0
Transmission Main	9441	P-0012	EG	South County Tr.	12	Asbestos Cement	53	56	1.14 out of 5	\$442	23,315
Transmission Main	10603	P-4209	EG	South County Tr.	12	Ductile Iron	74	2	0 out of 5	N/A	\$0
Transmission Main	10604	P-4209	EG	South County Tr.	12	Ductile Iron	29	2	0 out of 5	N/A	\$0
Transmission Main	11304	P-4186	EG	South County Tr.	12	Asbestos Cement	163	56	1.14 out of 5	\$442	72,161
Transmission Main	11305	P-4210	EG	South County Tr.	12	Asbestos Cement	17	56	1.14 out of 5	\$442	7,543
Transmission Main	11306	P-40008	EG	South County Tr.	12	Asbestos Cement	4	56	1.14 out of 5	\$442	1,798
Transmission Main	11307	P-40008	EG	South County Tr.	12	Asbestos Cement	12	56	1.14 out of 5	\$442	5,358
Transmission Main	11308	P-40008	EG	South County Tr.	12	Asbestos Cement	14	56	1.14 out of 5	\$442	6,223
Transmission Main	11348	P-4208	EG	South County Tr.	12	Ductile Iron	50	21	0.14 out of 5	N/A	\$0
Transmission Main	11349	P-4837	EG	South County Tr.	12	Asbestos Cement	113	56	1.14 out of 5	\$442	49,851
Transmission Main	11820	P-4209	EG	South County Tr.	12	Asbestos Cement	456	56	1.14 out of 5	\$442	201,466
Transmission Main	11821	P-4209	EG	South County Tr.	12	Asbestos Cement	15	56	1.14 out of 5	\$442	6,712
Transmission Main	12073	P-4209	EG	South County Tr.	12	Asbestos Cement	194	56	1.14 out of 5	\$442	85,937
Transmission Main	12083	P-4186	EG	South County Tr.	12	Asbestos Cement	187	56	1.14 out of 5	\$442	82,582
Transmission Main	12086	P-40012	EG	South County Tr.	12	Asbestos Cement	302	56	1.14 out of 5	\$442	133,621
Distribution Main	9346	P-4115	EG	South County Trail	8	Ductile Iron	4	10	0 out of 5	N/A	\$0
Distribution Main	9983		EG	South County Trail	6	Ductile Iron	3	6	0.71 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9984		EG	South County Trail	6	Ductile Iron	6	6	0.71 out of 5	N/A	\$0
Transmission Main	10086		EG	South County Trail	12	Ductile Iron	72	24	0.14 out of 5	N/A	\$0
Transmission Main	6393	P-40026	EG	South Pierce Rd.	20	Asbestos Cement	33	55	1.14 out of 5	\$442	14,607
Transmission Main	6463	P-4230	EG	South Pierce Rd.	20	Asbestos Cement	1,395	55	1.14 out of 5	\$442	616,805
Distribution Main	6000	P-4025	EG	Sparrow Ln.	8	Ductile Iron	371	26	0.14 out of 5	\$442	163,854
Distribution Main	6001	P-4025	EG	Sparrow Ln.	8	Ductile Iron	355	26	0.14 out of 5	\$442	156,887
Distribution Main	9478		EG	Spring St		Unknown	20	UNK	0 out of 5	N/A	\$0
Distribution Main	305	P-4925	EG	Spring St.	6	Cast Iron	337	133	2.57 out of 5	\$442	148,750
Transmission Main	905	P-4957	EG	Spring St.	12	Cast Iron	9	133	1.86 out of 5	\$442	4,198
Distribution Main	909	P-4546	EG	Spring St.	8	Ductile Iron	10	17	0 out of 5	N/A	\$0
Distribution Main	1902	P-4575	EG	Spring St.	6	Cast Iron	74	133	2.57 out of 5	\$442	32,699
Distribution Main	1903	P-4556	EG	Spring St.	6	Cast Iron	168	133	2.57 out of 5	\$442	74,421
Distribution Main	1904	P-4556	EG	Spring St.	6	Cast Iron	14	133	2.57 out of 5	\$442	6,328
Distribution Main	1905	P-4547	EG	Spring St.	6	Cast Iron	81	133	2.57 out of 5	\$442	36,000
Distribution Main	1906	P-4546	EG	Spring St.	6	Cast Iron	388	133	2.57 out of 5	\$442	171,637
Distribution Main	1907	P-4546	EG	Spring St.	6	Cast Iron	294	133	2.57 out of 5	\$442	130,050
Distribution Main	3666	P-4573	EG	Spring St.	6	Cast Iron	145	133	2.57 out of 5	\$442	63,962
Distribution Main	4378	P-4920	EG	Spring St.	6	Cast Iron	19	133	2.57 out of 5	\$442	8,218
Distribution Main	6218	P-4605	EG	Spring St.	6	Cast Iron	350	133	2.57 out of 5	\$442	154,581
Transmission Main	6219	P-4957	EG	Spring St.	12	Cast Iron	41	133	1.86 out of 5	\$442	17,976
Distribution Main	6222	P-4556	EG	Spring St.	6	Cast Iron	28	133	2.57 out of 5	\$442	12,430
Transmission Main	6223	P-4582	EG	Spring St.	12	Ductile Iron	14	23	0.14 out of 5	N/A	\$0
Transmission Main	6224	P-4582	EG	Spring St.	12	Ductile Iron	6	23	0.14 out of 5	N/A	\$0
Distribution Main	6269	P-4605	EG	Spring St.	6	Cast Iron	12	133	2.57 out of 5	\$442	5,474
Distribution Main	6270	P-4605	EG	Spring St.	6	Cast Iron	41	133	2.57 out of 5	\$442	18,278
Distribution Main	6740	P-4602	EG	Spring St.	6	Cast Iron	293	133	2.57 out of 5	\$442	129,584
Distribution Main	6741	P-4574	EG	Spring St.	6	Cast Iron	116	133	2.57 out of 5	\$442	51,234
Distribution Main	6742	P-4574	EG	Spring St.	6	Cast Iron	277	133	2.57 out of 5	\$442	122,239
Transmission Main	6743	P-4582	EG	Spring St.	12	Ductile Iron	83	23	0.14 out of 5	N/A	\$0
Distribution Main	9019	P-4546	EG	Spring St.	6	Ductile Iron	4	17	0.71 out of 5	N/A	\$0
Distribution Main	9020	P-4547	EG	Spring St.	6	Ductile Iron	4	17	0.71 out of 5	N/A	\$0
Transmission Main	9310	P-4573	EG	Spring St.	12	Cast Iron	6	133	1.86 out of 5	\$442	2,680
Transmission Main	10984	P-4582	EG	Spring St.	12	Ductile Iron	3	23	0.14 out of 5	N/A	\$0
Distribution Main	10991	P-4547	EG	Spring St.	8	Ductile Iron	10	17	0 out of 5	N/A	\$0
Distribution Main	11327	P-4605	EG	Spring St.	6	Cast Iron	41	133	2.57 out of 5	\$442	18,014
Distribution Main	370	P-4223	EG	Spring Valley Dr.	8	Asbestos Cement	751	51	1.14 out of 5	\$442	331,854
Distribution Main	371	P-4223	EG	Spring Valley Dr.	8	Asbestos Cement	13	51	1.14 out of 5	\$442	5,557
Distribution Main	600	P-4222	EG	Spring Valley Dr.	8	Asbestos Cement	479	51	1.14 out of 5	\$442	211,905
Distribution Main	5237	P-4220	EG	Spring Valley Dr.	8	Asbestos Cement	654	51	1.14 out of 5	\$442	289,063
Distribution Main	5238	P-4219	EG	Spring Valley Dr.	8	Asbestos Cement	232	51	1.14 out of 5	\$442	102,526
Distribution Main	5239	P-4219	EG	Spring Valley Dr.	8	Asbestos Cement	187	51	1.14 out of 5	\$442	82,760
Distribution Main	5240	P-4216	EG	Spring Valley Dr.	8	Asbestos Cement	29	51	1.14 out of 5	\$442	12,963
Distribution Main	5241	P-4216	EG	Spring Valley Dr.	8	Asbestos Cement	830	51	1.14 out of 5	\$442	366,783
Distribution Main	5242	P-4215	EG	Spring Valley Dr.	8	Asbestos Cement	401	51	1.14 out of 5	\$442	177,190

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5243	P-4213	EG	Spring Valley Dr.	8	Asbestos Cement	527	51	1.14 out of 5	\$442	233,044
Distribution Main	3874	P-4045	EG	Squirrel Lane	8	Ductile Iron	38	14	0 out of 5	N/A	\$0
Distribution Main	5310	P-4818	EG	Squirrel Lane	8	Ductile Iron	257	14	0 out of 5	N/A	\$0
Distribution Main	5311	P-4817	EG	Squirrel Lane	8	Ductile Iron	517	14	0 out of 5	N/A	\$0
Distribution Main	5312	P-4817	EG	Squirrel Lane	8	Ductile Iron	80	14	0 out of 5	N/A	\$0
Distribution Main	857	P-4043	EG	Squirrel Ln.	8	Asbestos Cement	616	47	1.14 out of 5	\$442	272,139
Distribution Main	6775	P-4045	EG	Squirrel Ln.	8	Asbestos Cement	12	47	1.14 out of 5	\$442	5,479
Distribution Main	6776	P-4045	EG	Squirrel Ln.	8	Asbestos Cement	121	47	1.14 out of 5	\$442	53,678
Distribution Main	3462	P-4124	EG	Stoneridge Dr.	8	Asbestos Cement	453	44	1.14 out of 5	\$442	200,353
Distribution Main	6012	P-4125	EG	Stoneridge Dr.	8	Asbestos Cement	492	46	1.14 out of 5	\$442	217,438
Distribution Main	6013	P-4125	EG	Stoneridge Dr.	8	Asbestos Cement	934	46	1.14 out of 5	\$442	412,711
Transmission Main	6015	P-4126	EG	Stoneridge Dr.	20	Ductile Iron	58	36	0.14 out of 5	\$442	25,767
Transmission Main	6016	P-4126	EG	Stoneridge Dr.	20	Ductile Iron	502	36	0.14 out of 5	\$442	221,780
Distribution Main	6019	P-4120	EG	Stoneridge Dr.	8	Asbestos Cement	769	46	1.14 out of 5	\$442	339,876
Distribution Main	6020	P-4120	EG	Stoneridge Dr.	8	Asbestos Cement	518	46	1.14 out of 5	\$442	229,153
Distribution Main	6021	P-4125	EG	Stoneridge Dr.	8	Asbestos Cement	61	44	1.14 out of 5	\$442	26,773
Distribution Main	6343	P-4119	EG	Stoneridge Dr.	8	Asbestos Cement	446	46	1.14 out of 5	\$442	196,946
Distribution Main	6344	P-4119	EG	Stoneridge Dr.	8	Asbestos Cement	34	46	1.14 out of 5	\$442	15,089
Distribution Main	6576	P-4120	EG	Stoneridge Dr.	8	Asbestos Cement	22	46	1.14 out of 5	\$442	9,700
Distribution Main	6577	P-4120	EG	Stoneridge Dr.	8	Asbestos Cement	208	46	1.14 out of 5	\$442	92,141
Distribution Main	11835	P-4125	EG	Stoneridge Dr.	8	Asbestos Cement	455	46	1.14 out of 5	\$442	201,276
Distribution Main	6027	P-4218	EG	Sunset Dr.	8	Asbestos Cement	1,107	51	1.14 out of 5	\$442	489,190
Distribution Main	3923	P-4264	EG	Sycamore Dr.	8	Asbestos Cement	236	51	1.14 out of 5	\$442	104,266
Distribution Main	3932	P-4265	EG	Sycamore Dr.	8	Asbestos Cement	196	51	1.14 out of 5	\$442	86,520
Distribution Main	4896	P-4255	EG	Sycamore Dr.	8	Asbestos Cement	475	51	1.14 out of 5	\$442	210,120
Distribution Main	6790	P-4265	EG	Sycamore Dr.	8	Asbestos Cement	215	51	1.14 out of 5	\$442	94,982
Distribution Main	6791	P-4253	EG	Sycamore Dr.	8	Asbestos Cement	334	51	1.14 out of 5	\$442	147,619
Distribution Main	6792	P-4253	EG	Sycamore Dr.	8	Asbestos Cement	78	51	1.14 out of 5	\$442	34,498
Distribution Main	3216	P-4513	EG	Sylvan Dr.	6	Asbestos Cement	13	69	2 out of 5	\$442	5,527
Distribution Main	3217	P-4513	EG	Sylvan Dr.	6	Asbestos Cement	194	69	2 out of 5	\$442	85,775
Distribution Main	5423	P-4510	EG	Sylvan Dr.	8	Asbestos Cement	343	70	1.29 out of 5	\$442	151,476
Distribution Main	5618	P-4506	EG	Sylvan Dr.	8	Asbestos Cement	249	70	1.29 out of 5	\$442	109,996
Distribution Main	6348	P-4511	EG	Sylvan Dr.	8	Asbestos Cement	48	70	1.29 out of 5	\$442	21,090
Distribution Main	6349	P-4511	EG	Sylvan Dr.	8	Asbestos Cement	587	70	1.29 out of 5	\$442	259,417
Distribution Main	6561	P-4505	EG	Sylvan Dr.	8	Asbestos Cement	287	70	1.29 out of 5	\$442	126,982
Distribution Main	9097	P-4506	EG	Sylvan Dr.	8	Asbestos Cement	19	70	1.29 out of 5	\$442	8,490
Distribution Main	5953	P-4478	EG	Tall Pine Dr.	8	Asbestos Cement	126	47	1.14 out of 5	\$442	55,677
Distribution Main	5954	P-4478	EG	Tall Pine Dr.	8	Asbestos Cement	467	47	1.14 out of 5	\$442	206,447
Distribution Main	5608	P-4333	EG	Tamarack Dr.	8	Asbestos Cement	593	50	1.14 out of 5	\$442	261,940
Distribution Main	5609	P-4333	EG	Tamarack Dr.	8	Asbestos Cement	539	50	1.14 out of 5	\$442	238,215
Distribution Main	6039	P-4332	EG	Tamarack Dr.	8	Asbestos Cement	504	50	1.14 out of 5	\$442	222,976
Distribution Main	6040	P-4332	EG	Tamarack Dr.	8	Asbestos Cement	57	50	1.14 out of 5	\$442	25,316
Distribution Main	6041	P-4325	EG	Tamarack Dr.	8	Asbestos Cement	81	50	1.14 out of 5	\$442	35,641
Distribution Main	6042	P-4325	EG	Tamarack Dr.	8	Asbestos Cement	391	50	1.14 out of 5	\$442	172,989

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3850		EG	Tanglewood Dr.	8	Unknown	20	UNK	0 out of 5	N/A	\$0
Distribution Main	4888	P-4315	EG	Tanglewood Dr.	8	Asbestos Cement	670	60	1.14 out of 5	\$442	296,105
Distribution Main	5605	P-4308	EG	Tanglewood Dr.	8	Asbestos Cement	374	60	1.14 out of 5	\$442	165,176
Distribution Main	6408	P-4302	EG	Tanglewood Dr.	8	Asbestos Cement	901	60	1.14 out of 5	\$442	398,322
Distribution Main	6795	P-4319	EG	Tanglewood Dr.	8	Asbestos Cement	39	60	1.14 out of 5	\$442	17,290
Distribution Main	6796	P-4319	EG	Tanglewood Dr.	8	Asbestos Cement	112	50	1.14 out of 5	\$442	49,711
Distribution Main	6802	P-435	EG	Tanglewood Dr.	8	Asbestos Cement	53	60	1.14 out of 5	\$442	23,644
Distribution Main	6803	P-435	EG	Tanglewood Dr.	8	Asbestos Cement	36	60	1.14 out of 5	\$442	15,973
Distribution Main	6805	P-4313	EG	Tanglewood Dr.	8	Asbestos Cement	390	60	1.14 out of 5	\$442	172,426
Distribution Main	6806	P-4320	EG	Tanglewood Dr.	8	Asbestos Cement	232	60	1.14 out of 5	\$442	102,635
Distribution Main	6807	P-4307	EG	Tanglewood Dr.	8	Asbestos Cement	314	60	1.14 out of 5	\$442	138,726
Distribution Main	6808	P-4307	EG	Tanglewood Dr.	8	Asbestos Cement	90	60	1.14 out of 5	\$442	39,711
Distribution Main	6493	P-4406	EG	Taylor Cir.	6	Asbestos Cement	244	51	1.85 out of 5	\$442	107,663
Distribution Main	8604	P-40024	EG	Taylor Cir.	6	Ductile Iron	2	20	0.71 out of 5	N/A	\$0
Distribution Main	8605	P-40024	EG	Taylor Cir.	6	Ductile Iron	34	20	0.71 out of 5	N/A	\$0
Distribution Main	11341	P-4406	EG	Taylor Cir.	6	Asbestos Cement	141	51	1.85 out of 5	\$442	62,152
Distribution Main	3930	P-4254	EG	Teakwood Court	6	Asbestos Cement	347	51	1.85 out of 5	\$442	153,539
Distribution Main	3931	P-4254	EG	Teakwood Court	6	Asbestos Cement	64	51	1.85 out of 5	\$442	28,400
Distribution Main	6797	P-4296	EG	Terrace Dr.	6	Asbestos Cement	820	51	1.85 out of 5	\$442	362,596
Distribution Main	6798	P-4296	EG	Terrace Dr.	6	Asbestos Cement	16	51	1.85 out of 5	\$442	6,957
Distribution Main	11812	P-4296	EG	Terrace Dr.	6	Asbestos Cement	398	51	1.85 out of 5	\$442	175,976
Distribution Main	4266	P-40039	EG	Third St	6	Unknown	151	69	1.14 out of 5	\$442	66,803
Distribution Main	5208	P-4665	EG	Third St.	6	Asbestos Cement	187	69	2 out of 5	\$442	82,856
Distribution Main	3873	P-4825	EG	Tillinghast Rd	8	Ductile Iron	38	14	0 out of 5	N/A	\$0
Transmission Main	3300	P-40007	EG	Tillinghast Rd.	12	Ductile Iron	83	22	0.14 out of 5	N/A	\$0
Transmission Main	4367	P-4821	EG	Tillinghast Rd.	12	Ductile Iron	504	22	0.14 out of 5	N/A	\$0
Transmission Main	4368	P-4717	EG	Tillinghast Rd.	12	Ductile Iron	646	22	0.14 out of 5	N/A	\$0
Transmission Main	4369	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	371	22	0.14 out of 5	N/A	\$0
Transmission Main	4370	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	49	26	0.14 out of 5	\$442	21,831
Transmission Main	4371	P-4821	EG	Tillinghast Rd.	12	Ductile Iron	84	22	0.14 out of 5	N/A	\$0
Transmission Main	4372	P-4821	EG	Tillinghast Rd.	12	Ductile Iron	591	22	0.14 out of 5	N/A	\$0
Transmission Main	4377	P-4822	EG	Tillinghast Rd.	20	Ductile Iron	776	26	0.14 out of 5	\$442	342,834
Transmission Main	4797	P-4076	EG	Tillinghast Rd.	20	Ductile Iron	637	36	0.14 out of 5	\$442	281,578
Transmission Main	4798	P-4076	EG	Tillinghast Rd.	20	Ductile Iron	496	36	0.14 out of 5	\$442	219,019
Transmission Main	4799	P-4717	EG	Tillinghast Rd.	12	Ductile Iron	111	22	0.14 out of 5	N/A	\$0
Transmission Main	4800	P-4078	EG	Tillinghast Rd.	20	Ductile Iron	1,368	36	0.14 out of 5	\$442	604,489
Transmission Main	4801	P-4078	EG	Tillinghast Rd.	20	Ductile Iron	564	36	0.14 out of 5	\$442	249,466
Transmission Main	4802	P-4078	EG	Tillinghast Rd.	20	Ductile Iron	476	36	0.14 out of 5	\$442	210,487
Transmission Main	4803	P-4078	EG	Tillinghast Rd.	20	Ductile Iron	996	36	0.14 out of 5	\$442	440,307
Transmission Main	4858	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	319	26	0.14 out of 5	\$442	141,056
Transmission Main	4859	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	564	26	0.14 out of 5	\$442	249,439
Transmission Main	4860	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	467	26	0.14 out of 5	\$442	206,506
Transmission Main	5285	P-4071	EG	Tillinghast Rd.	12	Ductile Iron	819	26	0.14 out of 5	\$442	362,027
Transmission Main	5286	P-4071	EG	Tillinghast Rd.	12	Ductile Iron	30	19	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	5287	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	324	26	0.14 out of 5	\$442	143,405
Transmission Main	5288	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	1,064	26	0.14 out of 5	\$442	470,278
Transmission Main	5289	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	74	26	0.14 out of 5	\$442	32,783
Transmission Main	5792	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	145	26	0.14 out of 5	\$442	64,291
Transmission Main	5803	P-4077	EG	Tillinghast Rd.	20	Ductile Iron	422	36	0.14 out of 5	\$442	186,592
Transmission Main	5804	P-4077	EG	Tillinghast Rd.	20	Ductile Iron	436	36	0.14 out of 5	\$442	192,653
Transmission Main	6294	P-4078	EG	Tillinghast Rd.	20	Ductile Iron	23	36	0.14 out of 5	\$442	10,197
Transmission Main	9064	P-4821	EG	Tillinghast Rd.	12	Ductile Iron	458	22	0.14 out of 5	N/A	\$0
Transmission Main	9065	P-4076	EG	Tillinghast Rd.	20	Ductile Iron	143	36	0.14 out of 5	\$442	63,127
Transmission Main	9066	P-4076	EG	Tillinghast Rd.	20	Ductile Iron	346	36	0.14 out of 5	\$442	152,886
Transmission Main	10269	P-4717	EG	Tillinghast Rd.	12	Ductile Iron	10	22	0.14 out of 5	N/A	\$0
Transmission Main	11251	P-4070	EG	Tillinghast Rd.	12	Ductile Iron	19	22	0.14 out of 5	N/A	\$0
Transmission Main	11252	P-4821	EG	Tillinghast Rd.	12	Ductile Iron	30	22	0.14 out of 5	N/A	\$0
Transmission Main	11265	P-4078	EG	Tillinghast Rd.	20	Ductile Iron	10	36	0.14 out of 5	\$442	4,527
Transmission Main	11294	P-4071	EG	Tillinghast Rd.	12	Ductile Iron	24	19	0 out of 5	N/A	\$0
Transmission Main	11836	P-4078	EG	Tillinghast Rd.	20	Ductile Iron	15	36	0.14 out of 5	\$442	6,572
Distribution Main	5307	P-4820	EG	Tina Ct	8	Ductile Iron	207	14	0 out of 5	N/A	\$0
Distribution Main	5308	P-4820	EG	Tina Ct	8	Ductile Iron	177	14	0 out of 5	N/A	\$0
Distribution Main	5309	P-4819	EG	Tina Ct	8	Ductile Iron	129	14	0 out of 5	N/A	\$0
Distribution Main	10267	P-4820	EG	Tina Ct	8	Ductile Iron	122	14	0 out of 5	N/A	\$0
Distribution Main	10268	P-4820	EG	Tina Ct	8	Ductile Iron	11	14	0 out of 5	N/A	\$0
Distribution Main	5603	P-4311	EG	Tory Ln.	6	Asbestos Cement	500	60	2.57 out of 5	\$442	220,957
Distribution Main	5604	P-4311	EG	Tory Ln.	6	Asbestos Cement	16	60	1.85 out of 5	\$442	7,237
Distribution Main	3851	P-4314	EG	Trappers Ln.	6	Asbestos Cement	12	60	1.85 out of 5	\$442	5,209
Distribution Main	3852	P-4314	EG	Trappers Ln.	6	Asbestos Cement	390	60	1.85 out of 5	\$442	172,599
Distribution Main	6123	P-4328	EG	Tucker St.	6	Asbestos Cement	509	57	1.85 out of 5	\$442	224,870
Distribution Main	6466	P-4328	EG	Tucker St.	6	Asbestos Cement	3	57	1.85 out of 5	\$442	1,454
Distribution Main	4163	P-4493	EG	Twin Pond Easement	8	Ductile Iron	6	19	0 out of 5	N/A	\$0
Distribution Main	6151	P-4475	EG	Twin Pond Easement	8	Ductile Iron	539	19	0 out of 5	N/A	\$0
Distribution Main	5000	P-4492	EG	Twin Pond Rd.	6	Asbestos Cement	7	54	1.85 out of 5	\$442	3,059
Distribution Main	5955	P-4492	EG	Twin Pond Rd.	6	Asbestos Cement	421	54	1.85 out of 5	\$442	186,263
Distribution Main	5956	P-4492	EG	Twin Pond Rd.	6	Asbestos Cement	159	54	1.85 out of 5	\$442	70,318
Distribution Main	888	P-4658	EG	Union St.	8	Ductile Iron	217	17	0 out of 5	N/A	\$0
Distribution Main	4249	P-4934	EG	Union St.	8	Ductile Iron	75	17	0 out of 5	N/A	\$0
Distribution Main	6687	P-4933	EG	Union St.	8	Ductile Iron	143	17	0 out of 5	N/A	\$0
Distribution Main	6731	P-4954	EG	Union St.	8	Ductile Iron	24	17	0 out of 5	N/A	\$0
Distribution Main	6750	P-4658	EG	Union St.	8	Ductile Iron	20	17	0 out of 5	N/A	\$0
Distribution Main	4262	P-4401	EG	Upland Ave.	8	Ductile Iron	598	12	0 out of 5	N/A	\$0
Distribution Main	5430		EG	Upland Ave.	6	Asbestos Cement	6	51	1.85 out of 5	\$442	2,544
Distribution Main	5682	P-4400	EG	Upland Ave.	6	Asbestos Cement	153	51	1.85 out of 5	\$442	67,682
Distribution Main	5683	P-4400	EG	Upland Ave.	6	Asbestos Cement	54	51	1.85 out of 5	\$442	23,946
Distribution Main	6250	P-4400	EG	Upland Ave.	6	Asbestos Cement	11	51	1.85 out of 5	\$442	4,889
Distribution Main	9231	P-4197	EG	Valley Rd	8	Ductile Iron	27	8	0 out of 5	N/A	\$0
Distribution Main	9232	P-4197	EG	Valley Rd	8	Ductile Iron	965	8	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11559	P-4189	EG	Valley Rd	8	Ductile Iron	188	8	0 out of 5	N/A	\$0
Distribution Main	6562	P-4507	EG	Verndale Dr.	6	Asbestos Cement	207	71	2 out of 5	\$442	91,713
Distribution Main	6563	P-4507	EG	Verndale Dr.	6	Asbestos Cement	829	71	2 out of 5	\$442	366,433
Distribution Main	11343	P-4507	EG	Verndale Dr.	6	Asbestos Cement	8	71	2 out of 5	\$442	3,714
Distribution Main	9473	P-40033	EG	Victory St	1	Copper	313	50	2.28 out of 5	\$442	138,141
Distribution Main	4041		EG	Victory St.	6	Asbestos Cement	14	50	1.85 out of 5	\$442	6,175
Distribution Main	4148	P-4347	EG	Victory St.	6	Asbestos Cement	250	50	1.85 out of 5	\$442	110,343
Distribution Main	4425	P-4595	EG	Vine St.	8	Ductile Iron	259	17	0 out of 5	N/A	\$0
Distribution Main	4252	P-4805	EG	Vine Street	6	Ductile Iron	176	17	0.71 out of 5	N/A	\$0
Distribution Main	9032	P-4805	EG	Vine Street	8	Ductile Iron	17	17	0 out of 5	N/A	\$0
Distribution Main	9904	P-4805	EG	Vine Street	6	Ductile Iron	95	17	0.71 out of 5	N/A	\$0
Distribution Main	6465	P-4408	EG	Violet Ct.	6	Asbestos Cement	92	51	1.85 out of 5	\$442	40,657
Distribution Main	6266	P-4971	EG	Virginia Av	1	Unknown	235	UNK	1.42 out of 5	\$442	103,767
Distribution Main	6725	P-4530	EG	Virginia Ave.	6	Asbestos Cement	734	69	2 out of 5	\$442	324,544
Distribution Main	6726	P-4530	EG	Virginia Ave.	6	Asbestos Cement	41	69	2 out of 5	\$442	17,950
Distribution Main	3927	P-4262	EG	Walnut Dr.	6	Asbestos Cement	169	51	1.85 out of 5	\$442	74,651
Distribution Main	3928	P-4262	EG	Walnut Dr.	6	Asbestos Cement	238	51	1.85 out of 5	\$442	105,382
Distribution Main	5599	P-4261	EG	Walnut Dr.	6	Asbestos Cement	697	51	1.85 out of 5	\$442	308,098
Distribution Main	2513	P-4417	EG	Wanton Shippee Rd.	6	Asbestos Cement	576	64	2 out of 5	\$442	254,569
Distribution Main	2514	P-4417	EG	Wanton Shippee Rd.	6	Asbestos Cement	334	64	2 out of 5	\$442	147,515
Distribution Main	2030	P-4175	EG	Watch Hill	8	Asbestos Cement	60	36	1 out of 5	\$442	26,622
Distribution Main	2031	P-4175	EG	Watch Hill	8	Asbestos Cement	721	36	1 out of 5	\$442	318,742
Distribution Main	2034	P-4170	EG	Watch Hill	8	Asbestos Cement	66	36	1 out of 5	\$442	29,287
Distribution Main	11840	P-4175	EG	Watch Hill	8	Asbestos Cement	687	36	1 out of 5	\$442	303,552
Distribution Main	11841	P-4175	EG	Watch Hill	8	Asbestos Cement	582	36	1 out of 5	\$442	257,154
Distribution Main	11842	P-4175	EG	Watch Hill	8	Asbestos Cement	568	36	1 out of 5	\$442	251,042
Distribution Main	11843	P-4175	EG	Watch Hill	8	Asbestos Cement	688	36	1 out of 5	\$442	304,055
Distribution Main	12181		EG	Watch Hill	8	Asbestos Cement	836	36	1 out of 5	\$442	369,731
Distribution Main	10327	P-4632	EG	Water St	8	Ductile Iron	493	4	0 out of 5	N/A	\$0
Distribution Main	10328	P-4903	EG	Water St	6	Ductile Iron	4	4	0.71 out of 5	N/A	\$0
Distribution Main	12131	P-4632	EG	Water St	8	Ductile Iron	18	4	0 out of 5	N/A	\$0
Distribution Main	5404	P-4655	EG	Water St.	6	Ductile Iron	268	4	0.71 out of 5	N/A	\$0
Distribution Main	6749	P-4655	EG	Water St.	6	Ductile Iron	907	32	0.85 out of 5	\$442	401,025
Distribution Main	10326	P-4903	EG	Water St.	6	Ductile Iron	28	4	0.71 out of 5	N/A	\$0
Distribution Main	910	P-4962	EG	West St.	8	Ductile Iron	18	17	0 out of 5	N/A	\$0
Distribution Main	911	P-4554	EG	West St.	6	Cast Iron	18	133	2.57 out of 5	\$442	8,175
Distribution Main	912	P-4554	EG	West St.	6	Cast Iron	466	133	2.57 out of 5	\$442	206,007
Distribution Main	3855	P-4960	EG	West St.	8	Ductile Iron	25	17	0 out of 5	N/A	\$0
Distribution Main	5687	P-4552	EG	West St.	6	Cast Iron	300	133	2.57 out of 5	\$442	132,725
Distribution Main	6215	P-4555	EG	West St.	6	Cast Iron	6	133	2.57 out of 5	\$442	2,489
Distribution Main	6216	P-4555	EG	West St.	6	Cast Iron	357	133	2.57 out of 5	\$442	157,954
Distribution Main	6728	P-4959	EG	West St.	8	Ductile Iron	15	17	0 out of 5	N/A	\$0
Distribution Main	9017	P-4964	EG	West St.	6	Ductile Iron	4	17	0.71 out of 5	N/A	\$0
Distribution Main	9018	P-4963	EG	West St.	6	Ductile Iron	5	17	0.71 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9021	P-4959	EG	West St.	6	Ductile Iron	3	17	0.71 out of 5	N/A	\$0
Distribution Main	9022	P-4961	EG	West St.	6	Ductile Iron	3	17	0.71 out of 5	N/A	\$0
Distribution Main	10903	P-4964	EG	West St.	8	Ductile Iron	18	17	0 out of 5	N/A	\$0
Transmission Main	3819	P-4165	EG	Westfield Dr	16	Ductile Iron	178	28	0.14 out of 5	\$442	78,872
Transmission Main	4930	P-4165	EG	Westfield Dr	16	Ductile Iron	347	28	0.14 out of 5	\$442	153,256
Transmission Main	10091	P-4165	EG	Westfield Dr	16	Ductile Iron	109	28	0.14 out of 5	\$442	48,292
Transmission Main	1682	P-4166	EG	Westfield Dr.	16	Ductile Iron	60	24	0.14 out of 5	N/A	\$0
Transmission Main	2018	P-4166	EG	Westfield Dr.	16	Ductile Iron	13	24	0.14 out of 5	N/A	\$0
Transmission Main	2019	P-4166	EG	Westfield Dr.	16	Ductile Iron	239	26	0.14 out of 5	\$442	105,451
Transmission Main	2020	P-4166	EG	Westfield Dr.	16	Ductile Iron	596	26	0.14 out of 5	\$442	263,380
Transmission Main	2021	P-4166	EG	Westfield Dr.	16	Ductile Iron	283	26	0.14 out of 5	\$442	125,162
Transmission Main	2022	P-4166	EG	Westfield Dr.	16	Ductile Iron	343	26	0.14 out of 5	\$442	151,765
Transmission Main	2023	P-4166	EG	Westfield Dr.	16	Ductile Iron	58	26	0.14 out of 5	\$442	25,705
Distribution Main	3820	P-4152	EG	Westfield Dr.	8	Ductile Iron	780	28	0.14 out of 5	\$442	344,626
Transmission Main	3833	P-4166	EG	Westfield Dr.	16	Ductile Iron	72	26	0.14 out of 5	\$442	31,959
Transmission Main	3834	P-4166	EG	Westfield Dr.	16	Ductile Iron	426	26	0.14 out of 5	\$442	188,291
Transmission Main	4931	P-4153	EG	Westfield Dr.	16	Ductile Iron	390	28	0.14 out of 5	\$442	172,526
Transmission Main	5781	P-40041	EG	Westfield Dr.	16	Ductile Iron	14	28	0.14 out of 5	\$442	5,987
Transmission Main	5790	P-4153	EG	Westfield Dr.	16	Ductile Iron	265	28	0.14 out of 5	\$442	117,018
Transmission Main	5791	P-4153	EG	Westfield Dr.	16	Ductile Iron	56	28	0.14 out of 5	\$442	24,916
Transmission Main	5892	P-4153	EG	Westfield Dr.	16	Ductile Iron	498	28	0.14 out of 5	\$442	220,297
Transmission Main	5893	P-4153	EG	Westfield Dr.	16	Ductile Iron	102	28	0.14 out of 5	\$442	44,936
Distribution Main	5897	P-4150	EG	Westfield Dr.	8	Ductile Iron	287	28	0.14 out of 5	\$442	127,055
Transmission Main	11236	P-4166	EG	Westfield Dr.	16	Ductile Iron	4	26	0.14 out of 5	\$442	1,834
Transmission Main	11317	P-4153	EG	Westfield Dr.	16	Ductile Iron	2	28	0.14 out of 5	\$442	745
Transmission Main	3324	P-4231	EG	Westwood Dr.	20	Asbestos Cement	1,693	55	1.14 out of 5	\$442	748,113
Distribution Main	4021	P-4416	EG	Westwood Dr.	6	Asbestos Cement	37	50	1.85 out of 5	\$442	16,152
Distribution Main	4022	P-4416	EG	Westwood Dr.	6	Asbestos Cement	1,085	50	1.85 out of 5	\$442	479,491
Distribution Main	9228	P-4192	EG	Wildwood Tr	8	Ductile Iron	921	8	0 out of 5	N/A	\$0
Distribution Main	9319	P-40015	EG	Wildwood Tr	8	Ductile Iron	12	8	0 out of 5	N/A	\$0
Distribution Main	11558	P-40015	EG	Wildwood Tr	8	Ductile Iron	182	8	0 out of 5	N/A	\$0
Distribution Main	3824	P-4163	EG	William Corr Way	8	Ductile Iron	487	26	0.14 out of 5	\$442	215,147
Distribution Main	3825	P-4163	EG	William Corr Way	8	Ductile Iron	95	26	0.14 out of 5	\$442	42,032
Distribution Main	6146	P-4169	EG	Winchester Drive	8	Asbestos Cement	418	41	1.14 out of 5	\$442	184,841
Distribution Main	6147	P-4169	EG	Winchester Drive	8	Asbestos Cement	136	41	1.14 out of 5	\$442	60,198
Distribution Main	6148	P-4169	EG	Winchester Drive	8	Asbestos Cement	22	41	1.14 out of 5	\$442	9,653
Distribution Main	9173	P-4905	EG	Wine St	8	Ductile Iron	228	8	0 out of 5	N/A	\$0
Distribution Main	4030	P-4383	EG	Winthrop Road	6	Asbestos Cement	421	51	1.85 out of 5	\$442	186,137
Distribution Main	4031	P-4383	EG	Winthrop Road	6	Asbestos Cement	609	51	1.85 out of 5	\$442	269,166
Distribution Main	3835	P-4012	EG	Wood Duck Ct.	8	Ductile Iron	14	27	0.14 out of 5	\$442	6,279
Distribution Main	3836	P-4012	EG	Wood Duck Ct.	8	Ductile Iron	386	27	0.14 out of 5	\$442	170,730
Distribution Main	5828	P-4017	EG	Woodbridge Dr.	8	PVC	681	41	0.57 out of 5	\$442	300,975
Distribution Main	5829	P-4017	EG	Woodbridge Dr.	8	PVC	814	41	0.57 out of 5	\$442	359,708
Distribution Main	5832	P-4017	EG	Woodbridge Dr.	8	PVC	602	41	0.57 out of 5	\$442	265,981

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6364	P-4015	EG	Woodbridge Dr.	8	PVC	360	41	0.57 out of 5	\$442	158,980
Distribution Main	6365	P-4015	EG	Woodbridge Dr.	8	PVC	46	41	0.57 out of 5	\$442	20,212
Distribution Main	6368	P-4014	EG	Woodbridge Dr.	8	PVC	918	41	0.57 out of 5	\$442	405,757
Distribution Main	6369	P-4014	EG	Woodbridge Dr.	8	PVC	23	41	0.57 out of 5	\$442	10,342
Distribution Main	11832	P-4014	EG	Woodbridge Dr.	8	PVC	408	41	0.57 out of 5	\$442	180,354
Distribution Main	6410	P-4413	EG	Woodland Rd.	6	Asbestos Cement	937	50	1.85 out of 5	\$442	414,360
Transmission Main	9382	P-40018	NK	Quaker Ln	12	Ductile Iron	686	7	0 out of 5	N/A	\$0
Transmission Main	9383	P-40018	NK	Quaker Ln	12	Ductile Iron	38	7	0 out of 5	N/A	\$0
Distribution Main	9385		NK	Quaker Ln	8	Ductile Iron	45	7	0 out of 5	N/A	\$0
Transmission Main	10460		NK	Quaker Ln	12	Ductile Iron	562	7	0 out of 5	N/A	\$0
Transmission Main	11577	P-40018	NK	Quaker Ln	12	Ductile Iron	377	7	0 out of 5	N/A	\$0
Distribution Main	2654	P-6002	SCIT	Blossom Ln	8	Asbestos Cement	86	46	1.14 out of 5	\$442	38,073
Distribution Main	2655	P-6002	SCIT	Blossom Ln	8	Asbestos Cement	91	46	1.14 out of 5	\$442	40,153
Distribution Main	9991	P-6001	SCIT	Blossom Ln	8	Asbestos Cement	368	46	1.14 out of 5	\$442	162,598
Distribution Main	9992	P-6001	SCIT	Blossom Ln	8	Asbestos Cement	60	46	1.14 out of 5	\$442	26,645
Distribution Main	9812	P-6085	SCIT	Brown St	8	Ductile Iron	176	7	0 out of 5	N/A	\$0
Transmission Main	9542		SCIT	Clinton Ave	12	Ductile Iron	54	15	0 out of 5	N/A	\$0
Transmission Main	9543	P-6086	SCIT	Clinton Ave	12	Ductile Iron	19	15	0 out of 5	N/A	\$0
Transmission Main	9544		SCIT	Clinton Ave	12	Ductile Iron	27	15	0 out of 5	N/A	\$0
Transmission Main	1283	P-6086	SCIT	Clinton Ave.	16	Asbestos Cement	387	47	1.14 out of 5	\$442	170,922
Transmission Main	1284	P-6086	SCIT	Clinton Ave.	16	Asbestos Cement	436	47	1.14 out of 5	\$442	192,931
Transmission Main	1865		SCIT	Clinton Ave.	30	Ductile Iron	95	15	0 out of 5	N/A	\$0
Transmission Main	8202	P-6059	SCIT	Clinton Ave.	24	Ductile Iron	172	15	0 out of 5	N/A	\$0
Transmission Main	8203	P-6059	SCIT	Clinton Ave.	24	Ductile Iron	545	15	0 out of 5	N/A	\$0
Transmission Main	8211	P-6086	SCIT	Clinton Ave.	24	Ductile Iron	13	15	0 out of 5	N/A	\$0
Transmission Main	8212	P-6086	SCIT	Clinton Ave.	24	Ductile Iron	128	15	0 out of 5	N/A	\$0
Transmission Main	8254	P-6059	SCIT	Clinton Ave.	16	Asbestos Cement	334	47	1.14 out of 5	\$442	147,601
Transmission Main	8255	P-6059	SCIT	Clinton Ave.	16	Asbestos Cement	22	47	1.14 out of 5	\$442	9,513
Transmission Main	9541	P-6086	SCIT	Clinton Ave.	24	Ductile Iron	74	15	0 out of 5	N/A	\$0
Transmission Main	9545	P-6059	SCIT	Clinton Ave.	24	Ductile Iron	7	15	0 out of 5	N/A	\$0
Transmission Main	9546		SCIT	Clinton Ave.	24	Ductile Iron	8	15	0 out of 5	N/A	\$0
Transmission Main	9547	P-6086	SCIT	Clinton Ave.	24	Ductile Iron	25	15	0 out of 5	N/A	\$0
Transmission Main	10395		SCIT	Clinton Ave.	16	Ductile Iron	4	15	0 out of 5	N/A	\$0
Transmission Main	10396		SCIT	Clinton Ave.	20	Ductile Iron	2	15	0 out of 5	N/A	\$0
Transmission Main	10993	P-6059	SCIT	Clinton Ave.	24	Ductile Iron	5	15	0 out of 5	N/A	\$0
Transmission Main	11113	P-6086	SCIT	Clinton Ave.	16	Asbestos Cement	108	47	1.14 out of 5	\$442	47,781
Transmission Main	11148		SCIT	Clinton Ave.	30	Ductile Iron	8	15	0 out of 5	N/A	\$0
Transmission Main	11449	P-6059	SCIT	Clinton Ave.	24	Ductile Iron	15	15	0 out of 5	N/A	\$0
Transmission Main	11586	P-6059	SCIT	Clinton Ave.	16	Asbestos Cement	16	47	1.14 out of 5	\$442	7,099
Transmission Main	12067	P-6086	SCIT	Clinton Ave.	16	Asbestos Cement	2	47	1.14 out of 5	\$442	939
Transmission Main	12165	P-6086	SCIT	Clinton Ave.	24	Ductile Iron	50	15	0 out of 5	N/A	\$0
Transmission Main	93	P-8508	SCIT	Colvin St.	20	Ductile Iron	51	15	0 out of 5	N/A	\$0
Transmission Main	8247	P-8508	SCIT	Colvin St.	24	Ductile Iron	370	15	0 out of 5	N/A	\$0
Transmission Main	8248	P-8508	SCIT	Colvin St.	24	Ductile Iron	131	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	8251	P-6091	SCIT	Colvin St.	24	Ductile Iron	465	15	0 out of 5	N/A	\$0
Transmission Main	8252	P-6091	SCIT	Colvin St.	24	Ductile Iron	676	15	0 out of 5	N/A	\$0
Transmission Main	8735	P-6091	SCIT	Colvin St.	24	Ductile Iron	343	15	0 out of 5	N/A	\$0
Transmission Main	10393	P-6061	SCIT	Colvin St.	24	Ductile Iron	20	15	0 out of 5	N/A	\$0
Transmission Main	10394	P-6061	SCIT	Colvin St.	24	Ductile Iron	21	15	0 out of 5	N/A	\$0
Transmission Main	11454	P-8508	SCIT	Colvin St.	24	Ductile Iron	57	15	0 out of 5	N/A	\$0
Distribution Main	9722	P-6032	SCIT	Country Ln	8	Ductile Iron	242	7	0 out of 5	N/A	\$0
Distribution Main	11593	P-6031	SCIT	Country Ln	8	Ductile Iron	56	7	0 out of 5	N/A	\$0
Transmission Main	1273	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	269	28	0.14 out of 5	\$442	118,949
Transmission Main	1274	P-6023	SCIT	Cranberry Dr.	16	Ductile Iron	531	28	0.14 out of 5	\$442	234,782
Transmission Main	1275	P-6023	SCIT	Cranberry Dr.	16	Ductile Iron	328	28	0.14 out of 5	\$442	144,786
Transmission Main	1277	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	5	28	0.14 out of 5	\$442	2,138
Transmission Main	1278	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	361	28	0.14 out of 5	\$442	159,489
Transmission Main	1279	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	125	28	0.14 out of 5	\$442	55,374
Transmission Main	2565	P-6023	SCIT	Cranberry Dr.	16	Ductile Iron	46	28	0.14 out of 5	\$442	20,499
Transmission Main	2566	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	3	28	0.14 out of 5	\$442	1,376
Transmission Main	2567	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	115	28	0.14 out of 5	\$442	50,951
Transmission Main	2568		SCIT	Cranberry Dr.	16	Ductile Iron	18	28	0.14 out of 5	\$442	7,913
Transmission Main	2569	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	339	28	0.14 out of 5	\$442	150,005
Transmission Main	2572	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	7	28	0.14 out of 5	\$442	3,109
Transmission Main	2573		SCIT	Cranberry Dr.	16	Ductile Iron	28	28	0.14 out of 5	\$442	12,317
Transmission Main	8708	P-6025	SCIT	Cranberry Dr.	16	Ductile Iron	5	28	0.14 out of 5	\$442	2,158
Transmission Main	8711	P-6025	SCIT	Cranberry Dr.	16	Ductile Iron	90	28	0.14 out of 5	\$442	39,616
Transmission Main	8712	P-6025	SCIT	Cranberry Dr.	16	Ductile Iron	243	28	0.14 out of 5	\$442	107,563
Distribution Main	10599	P-6023	SCIT	Cranberry Dr.	8	Ductile Iron	41	28	0.14 out of 5	\$442	18,050
Transmission Main	11907	P-6023	SCIT	Cranberry Dr.	16	Ductile Iron	24	28	0.14 out of 5	\$442	10,562
Transmission Main	11908	P-6027	SCIT	Cranberry Dr.	16	Ductile Iron	48	28	0.14 out of 5	\$442	21,273
Distribution Main	1282	P-6050	SCIT	Doray Dr.	8	Asbestos Cement	257	61	1.29 out of 5	\$442	113,595
Distribution Main	2665	P-6051	SCIT	Doray Dr.	8	Asbestos Cement	299	61	1.29 out of 5	\$442	132,206
Distribution Main	7535	P-6130	SCIT	Eagle Dr	8	Ductile Iron	21	28	0.14 out of 5	\$442	9,188
Distribution Main	7536	P-6132	SCIT	Eagle Dr	8	Ductile Iron	27	28	0.14 out of 5	\$442	12,038
Distribution Main	7753	P-6130	SCIT	Eagle Dr	8	Ductile Iron	10	28	0.14 out of 5	\$442	4,373
Distribution Main	7754	P-6130	SCIT	Eagle Dr	8	Ductile Iron	4	28	0.14 out of 5	\$442	1,716
Distribution Main	9723	P-6030	SCIT	Garden Ln	8	Ductile Iron	458	7	0 out of 5	N/A	\$0
Distribution Main	9724	P-6030	SCIT	Garden Ln	8	Ductile Iron	3	7	0 out of 5	N/A	\$0
Distribution Main	9810	P-6084	SCIT	Goddard St	8	Ductile Iron	231	7	0 out of 5	N/A	\$0
Distribution Main	9811	P-6121	SCIT	Goddard St	8	Ductile Iron	36	7	0 out of 5	N/A	\$0
Distribution Main	11611	P-6121	SCIT	Goddard St	8	Ductile Iron	19	7	0 out of 5	N/A	\$0
Distribution Main	9809	P-6084	SCIT	Goddard St.	8	Ductile Iron	13	15	0 out of 5	N/A	\$0
Distribution Main	617	P-6009	SCIT	Harrington Ave.	6	PVC	149	33	1.14 out of 5	\$442	65,926
Distribution Main	618	P-6008	SCIT	Harrington Ave.	6	Cast Iron	156	83	2.43 out of 5	\$442	68,926
Distribution Main	619	P-6008	SCIT	Harrington Ave.	6	Cast Iron	389	83	2.43 out of 5	\$442	171,966
Distribution Main	10083	P-6009	SCIT	Harrington Ave.	8	Ductile Iron	35	15	0 out of 5	N/A	\$0
Distribution Main	11080	P-6009	SCIT	Harrington Ave.	6	PVC	5	33	1.14 out of 5	\$442	2,308

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11903	P-6008	SCIT	Harrington Ave.	6	Cast Iron	261	83	2.43 out of 5	\$442	115,240
Distribution Main	2659	P-6007	SCIT	High St.	6	PVC	494	33	1.14 out of 5	\$442	218,257
Distribution Main	2660	P-6007	SCIT	High St.	6	PVC	335	33	1.14 out of 5	\$442	148,282
Distribution Main	87		SCIT	Hill St	8	Ductile Iron	23	15	0 out of 5	N/A	\$0
Transmission Main	10600	P-6028	SCIT	Hope Av	16	Ductile Iron	640	2	0 out of 5	N/A	\$0
Transmission Main	10601	P-5119	SCIT	Hope Av	16	Ductile Iron	3	2	0 out of 5	N/A	\$0
Transmission Main	10602	P-5119	SCIT	Hope Av	16	Ductile Iron	12	2	0 out of 5	N/A	\$0
Transmission Main	10959	P-6035	SCIT	Hope Av	16	Ductile Iron	196	2	0 out of 5	N/A	\$0
Transmission Main	10960	P-6022	SCIT	Hope Av	16	Ductile Iron	205	2	0 out of 5	N/A	\$0
Transmission Main	9813	P-6134	SCIT	Hope Ave	12	Ductile Iron	10	7	0 out of 5	N/A	\$0
Transmission Main	9814	P-6134	SCIT	Hope Ave	12	Ductile Iron	52	7	0 out of 5	N/A	\$0
Distribution Main	1430	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	169	52	1.14 out of 5	\$442	74,791
Distribution Main	1431	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	634	52	1.14 out of 5	\$442	280,245
Distribution Main	1432	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	26	52	1.14 out of 5	\$442	11,545
Transmission Main	8219	P-6087	SCIT	Hope Ave.	24	Ductile Iron	539	15	0 out of 5	N/A	\$0
Transmission Main	8220	P-6087	SCIT	Hope Ave.	24	Ductile Iron	28	15	0 out of 5	N/A	\$0
Transmission Main	8221	P-6021	SCIT	Hope Ave.	24	Ductile Iron	698	15	0 out of 5	N/A	\$0
Distribution Main	8256	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	92	52	1.14 out of 5	\$442	40,490
Distribution Main	8269	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	130	52	1.14 out of 5	\$442	57,468
Distribution Main	8270	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	173	52	1.14 out of 5	\$442	76,267
Distribution Main	8271	P-6087	SCIT	Hope Ave.	8	Asbestos Cement	711	52	1.14 out of 5	\$442	314,478
Distribution Main	8733	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	15	52	1.14 out of 5	\$442	6,730
Transmission Main	9815	P-6133	SCIT	Hope Ave.	16	Asbestos Cement	15	63	1.29 out of 5	\$442	6,843
Transmission Main	9816	P-6021	SCIT	Hope Ave.	16	Asbestos Cement	7	63	1.29 out of 5	\$442	3,032
Distribution Main	9913	P-6021	SCIT	Hope Ave.	8	Ductile Iron	13	7	0 out of 5	N/A	\$0
Transmission Main	9914	P-6133	SCIT	Hope Ave.	16	Ductile Iron	2	7	0 out of 5	N/A	\$0
Transmission Main	9915	P-6133	SCIT	Hope Ave.	16	Ductile Iron	3	7	0 out of 5	N/A	\$0
Transmission Main	10397	P-6087	SCIT	Hope Ave.	24	Ductile Iron	100	15	0 out of 5	N/A	\$0
Transmission Main	10398	P-6087	SCIT	Hope Ave.	24	Ductile Iron	298	15	0 out of 5	N/A	\$0
Transmission Main	10597	P-6133	SCIT	Hope Ave.	16	Ductile Iron	3	7	0 out of 5	N/A	\$0
Transmission Main	10961	P-6022	SCIT	Hope Ave.	16	Ductile Iron	3	7	0 out of 5	N/A	\$0
Distribution Main	11457	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	9	52	1.14 out of 5	\$442	3,850
Transmission Main	11612	P-6021	SCIT	Hope Ave.	16	Asbestos Cement	3	63	1.29 out of 5	\$442	1,148
Distribution Main	12206	P-6021	SCIT	Hope Ave.	8	Asbestos Cement	169	52	1.14 out of 5	\$442	74,735
Transmission Main	154	P-6016	SCIT	Hope Furnace Rd.	12	Ductile Iron	36	28	0.14 out of 5	\$442	15,719
Transmission Main	155	P-6016	SCIT	Hope Furnace Rd.	12	Ductile Iron	320	28	0.14 out of 5	\$442	141,499
Distribution Main	156	P-6125	SCIT	Hope Furnace Rd.	8	Ductile Iron	16	28	0.14 out of 5	\$442	7,025
Distribution Main	157	P-6123	SCIT	Hope Furnace Rd.	8	Ductile Iron	26	28	0.14 out of 5	\$442	11,569
Transmission Main	158	P-6122	SCIT	Hope Furnace Rd.	12	Ductile Iron	280	28	0.14 out of 5	\$442	123,618
Transmission Main	159	P-6122	SCIT	Hope Furnace Rd.	12	Ductile Iron	185	28	0.14 out of 5	\$442	81,978
Transmission Main	786	P-6124	SCIT	Hope Furnace Rd.	12	Ductile Iron	369	28	0.14 out of 5	\$442	162,944
Transmission Main	787	P-6124	SCIT	Hope Furnace Rd.	12	Ductile Iron	205	28	0.14 out of 5	\$442	90,807
Transmission Main	1102	P-6016	SCIT	Hope Furnace Rd.	12	Ductile Iron	114	28	0.14 out of 5	\$442	50,279
Transmission Main	1103	P-6016	SCIT	Hope Furnace Rd.	12	Ductile Iron	128	28	0.14 out of 5	\$442	56,741

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	6162	P-6018	SCIT	Hope Furnace Rd.	12	Ductile Iron	175	28	0.14 out of 5	\$442	77,446
Transmission Main	6163	P-6018	SCIT	Hope Furnace Rd.	12	Ductile Iron	544	28	0.14 out of 5	\$442	240,337
Transmission Main	6164	P-6020	SCIT	Hope Furnace Rd.	12	Ductile Iron	281	28	0.14 out of 5	\$442	124,266
Transmission Main	6165	P-6020	SCIT	Hope Furnace Rd.	12	Ductile Iron	176	28	0.14 out of 5	\$442	77,948
Distribution Main	6166	P-6126	SCIT	Hope Furnace Rd.	8	Ductile Iron	10	28	0.14 out of 5	\$442	4,597
Transmission Main	7703	P-6018	SCIT	Hope Furnace Rd.	12	Ductile Iron	7	28	0.14 out of 5	\$442	2,972
Distribution Main	7750	P-6126	SCIT	Hope Furnace Rd.	8	Ductile Iron	9	28	0.14 out of 5	\$442	3,972
Transmission Main	7751	P-6120	SCIT	Hope Furnace Rd.	12	Ductile Iron	6	28	0.14 out of 5	\$442	2,860
Distribution Main	10429	P-6122	SCIT	Hope Furnace Rd.	8	Asbestos Cement	26	28	1 out of 5	\$442	11,568
Transmission Main	11905	P-6018	SCIT	Hope Furnace Rd.	12	Ductile Iron	341	28	0.14 out of 5	\$442	150,558
Transmission Main	88	P-7891	SCIT	Hope Furnace Road	24	Ductile Iron	45	15	0 out of 5	N/A	\$0
Transmission Main	89	P-7891	SCIT	Hope Furnace Road	24	Ductile Iron	6	15	0 out of 5	N/A	\$0
Transmission Main	6167	P-6129	SCIT	Howard Ave.	12	Ductile Iron	45	28	0.14 out of 5	\$442	19,812
Transmission Main	6168	P-6129	SCIT	Howard Ave.	12	Ductile Iron	302	28	0.14 out of 5	\$442	133,662
Distribution Main	7530		SCIT	Howard Ave.	8	Unknown	5	UNK	0 out of 5	N/A	\$0
Transmission Main	7533	P-6131	SCIT	Howard Ave.	12	Ductile Iron	38	28	0.14 out of 5	\$442	16,755
Transmission Main	7534	P-6131	SCIT	Howard Ave.	12	Ductile Iron	42	28	0.14 out of 5	\$442	18,557
Transmission Main	7537	P-6127	SCIT	Howard Ave.	12	Ductile Iron	421	28	0.14 out of 5	\$442	186,180
Transmission Main	7538	P-6127	SCIT	Howard Ave.	12	Ductile Iron	78	28	0.14 out of 5	\$442	34,379
Transmission Main	7539	P-6127	SCIT	Howard Ave.	12	Ductile Iron	482	28	0.14 out of 5	\$442	212,962
Transmission Main	7696	P-6127	SCIT	Howard Ave.	12	Ductile Iron	435	28	0.14 out of 5	\$442	192,354
Transmission Main	7697	P-6127	SCIT	Howard Ave.	12	Ductile Iron	31	28	0.14 out of 5	\$442	13,803
Transmission Main	7698	P-6019	SCIT	Howard Ave.	12	Ductile Iron	213	28	0.14 out of 5	\$442	94,261
Transmission Main	7699	P-6129	SCIT	Howard Ave.	12	Ductile Iron	291	28	0.14 out of 5	\$442	128,764
Transmission Main	7700	P-6107	SCIT	Howard Ave.	12	Ductile Iron	512	28	0.14 out of 5	\$442	226,353
Transmission Main	7701	P-6107	SCIT	Howard Ave.	12	Ductile Iron	84	28	0.14 out of 5	\$442	37,333
Transmission Main	7702		SCIT	Howard Ave.	12	Ductile Iron	42	28	0.14 out of 5	\$442	18,623
Transmission Main	11400	P-6127	SCIT	Howard Ave.	12	Ductile Iron	4	28	0.14 out of 5	\$442	1,943
Transmission Main	11401	P-6019	SCIT	Howard Ave.	12	Ductile Iron	29	28	0.14 out of 5	\$442	12,921
Transmission Main	11906	P-6127	SCIT	Howard Ave.	12	Ductile Iron	51	28	0.14 out of 5	\$442	22,721
Distribution Main	90	P-6013	SCIT	Howard Lane	8	Ductile Iron	114	15	0 out of 5	N/A	\$0
Distribution Main	614	P-6081	SCIT	Ives St.	6	Cast Iron	215	80	2.28 out of 5	\$442	95,076
Distribution Main	615	P-6081	SCIT	Ives St.	6	Cast Iron	29	80	2.28 out of 5	\$442	12,671
Distribution Main	2650	P-6082	SCIT	Ives St. Easement	4	Cast Iron	21	80	3 out of 5	\$442	9,441
Distribution Main	2651	P-6082	SCIT	Ives St. Easement	4	Cast Iron	176	80	3 out of 5	\$442	77,877
Distribution Main	10569		SCIT	Jackson Flat Rd	8	Ductile Iron	720	2	0 out of 5	N/A	\$0
Distribution Main	82	P-6061	SCIT	Jackson Flat Rd.	8	Ductile Iron	12	15	0 out of 5	N/A	\$0
Distribution Main	92		SCIT	Jackson Flat Rd.	8	Ductile Iron	69	15	0 out of 5	N/A	\$0
Distribution Main	480	P-6052	SCIT	Jackson Flat Rd.	8	Ductile Iron	329	20	0 out of 5	N/A	\$0
Distribution Main	8209	P-6053	SCIT	Jackson Flat Rd.	8	Ductile Iron	318	20	0 out of 5	N/A	\$0
Distribution Main	8210	P-6053	SCIT	Jackson Flat Rd.	8	Ductile Iron	19	15	0 out of 5	N/A	\$0
Distribution Main	8734	P-6118	SCIT	Jackson Flat Rd.	6	Ductile Iron	367	29	0.85 out of 5	\$442	162,374
Transmission Main	8736	P-6041	SCIT	Jackson Flat Rd.	24	Ductile Iron	130	15	0 out of 5	N/A	\$0
Distribution Main	9616	P-6116	SCIT	Jackson Flat Rd.	8	Asbestos Cement	57	UNK	0.85 out of 5	\$442	25,240

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11904	P-6053	SCIT	Jackson Flat Rd.	8	Ductile Iron	50	20	0 out of 5	N/A	\$0
Distribution Main	84	P-6093	SCIT	Jackson Flat Road	8	Ductile Iron	24	15	0 out of 5	N/A	\$0
Distribution Main	8213	P-6093	SCIT	Jackson Flat Road	6	Ductile Iron	9	15	0.71 out of 5	N/A	\$0
Transmission Main	726	P-6026	SCIT	Kerri Ct.	16	Ductile Iron	12	28	0.14 out of 5	\$442	5,199
Transmission Main	8709	P-6026	SCIT	Kerri Ct.	16	Ductile Iron	382	28	0.14 out of 5	\$442	168,906
Transmission Main	8710	P-6026	SCIT	Kerri Ct.	16	Ductile Iron	221	28	0.14 out of 5	\$442	97,801
Distribution Main	85	P-6082	SCIT	Main St. (Sci)	8	Ductile Iron	20	15	0 out of 5	N/A	\$0
Distribution Main	8217	P-6014	SCIT	Main St. (Sci)	8	Ductile Iron	377	15	0 out of 5	N/A	\$0
Distribution Main	8218	P-6014	SCIT	Main St. (Sci)	8	Ductile Iron	270	15	0 out of 5	N/A	\$0
Distribution Main	8266	P-6010	SCIT	Main St. (Sci)	8	Ductile Iron	333	15	0 out of 5	N/A	\$0
Distribution Main	8267	P-6010	SCIT	Main St. (Sci)	8	Ductile Iron	191	52	0.29 out of 5	\$442	84,525
Distribution Main	9585	P-6141	SCIT	Main St. (Sci)	8	Ductile Iron	117	30	0.14 out of 5	\$442	51,601
Distribution Main	9586	P-6141	SCIT	Main St. (Sci)	8	Ductile Iron	24	15	0 out of 5	N/A	\$0
Distribution Main	11110	P-6010	SCIT	Main St. (Sci)	8	Ductile Iron	10	15	0 out of 5	N/A	\$0
Distribution Main	11111	P-6010	SCIT	Main St. (Sci)	8	Ductile Iron	229	15	0 out of 5	N/A	\$0
Distribution Main	11112	P-6010	SCIT	Main St. (Sci)	8	Ductile Iron	23	15	0 out of 5	N/A	\$0
Distribution Main	11451	P-6014	SCIT	Main St. (Sci)	8	Ductile Iron	244	15	0 out of 5	N/A	\$0
Distribution Main	12151	P-6014	SCIT	Main St. (Sci)	8	Ductile Iron	9	15	0 out of 5	N/A	\$0
Distribution Main	9720	P-6029	SCIT	Meadow Rd	8	Ductile Iron	187	7	0 out of 5	N/A	\$0
Distribution Main	9721	P-6034	SCIT	Meadow Rd	8	Ductile Iron	62	7	0 out of 5	N/A	\$0
Distribution Main	10598	P-6029	SCIT	Meadow Rd	8	Ductile Iron	25	7	0 out of 5	N/A	\$0
Distribution Main	11591	P-6034	SCIT	Meadow Rd	8	Ductile Iron	175	7	0 out of 5	N/A	\$0
Distribution Main	11592	P-6034	SCIT	Meadow Rd	8	Ductile Iron	58	7	0 out of 5	N/A	\$0
Distribution Main	86	P-6013	SCIT	Mill St	8	Ductile Iron	34	15	0 out of 5	N/A	\$0
Distribution Main	616	SCIT	SCIT	Mill St.	6	Cast Iron	46	132	2.57 out of 5	\$442	20,481
Distribution Main	1238	P-6013	SCIT	Mill St.	6	Cast Iron	410	132	2.57 out of 5	\$442	181,263
Distribution Main	1239	P-6013	SCIT	Mill St.	6	Cast Iron	371	132	2.57 out of 5	\$442	164,133
Distribution Main	8043	P-6013	SCIT	Mill St.	6	Cast Iron	128	132	2.57 out of 5	\$442	56,726
Distribution Main	11902	P-6013	SCIT	Mill St.	6	Cast Iron	14	132	2.57 out of 5	\$442	6,090
Distribution Main	12065	P-6013	SCIT	Mill St.	6	Cast Iron	20	132	2.57 out of 5	\$442	8,755
Distribution Main	91	P-6080	SCIT	North Rd.	8	Ductile Iron	45	15	0 out of 5	N/A	\$0
Distribution Main	623	P-6080	SCIT	North Rd.	6	Cast Iron	124	80	2.28 out of 5	\$442	54,908
Distribution Main	1190	P-6012	SCIT	North Rd.	6	PVC	6	33	1.14 out of 5	\$442	2,785
Distribution Main	1191	P-6006	SCIT	North Rd.	6	PVC	287	33	1.14 out of 5	\$442	126,823
Distribution Main	1192	P-6006	SCIT	North Rd.	6	PVC	95	33	1.14 out of 5	\$442	42,009
Distribution Main	1193	P-6004	SCIT	North Rd.	6	PVC	9	33	1.14 out of 5	\$442	3,871
Distribution Main	1194	P-6078	SCIT	North Rd.	8	Asbestos Cement	558	46	1.14 out of 5	\$442	246,749
Distribution Main	1195	P-6078	SCIT	North Rd.	8	Asbestos Cement	202	46	1.14 out of 5	\$442	89,302
Distribution Main	1196	P-6003	SCIT	North Rd.	8	Asbestos Cement	14	47	1.14 out of 5	\$442	6,116
Distribution Main	1240	P-6080	SCIT	North Rd.	6	Cast Iron	85	80	2.28 out of 5	\$442	37,472
Distribution Main	2658	P-6012	SCIT	North Rd.	6	PVC	376	33	1.14 out of 5	\$442	166,326
Distribution Main	2661	P-6006	SCIT	North Rd.	6	PVC	279	33	1.14 out of 5	\$442	123,483
Distribution Main	2662	P-6006	SCIT	North Rd.	6	PVC	85	33	1.14 out of 5	\$442	37,490
Distribution Main	2663	P-6004	SCIT	North Rd.	6	PVC	301	33	1.14 out of 5	\$442	133,172

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2664	P-6004	SCIT	North Rd.	6	PVC	182	33	1.14 out of 5	\$442	80,385
Distribution Main	2652	P-6000	SCIT	Orchard Dr.	8	Asbestos Cement	755	46	1.14 out of 5	\$442	333,590
Distribution Main	2653	P-6000	SCIT	Orchard Dr.	8	Asbestos Cement	287	46	1.14 out of 5	\$442	127,046
Distribution Main	2656	P-6000	SCIT	Orchard Dr.	8	Asbestos Cement	747	46	1.14 out of 5	\$442	330,262
Distribution Main	2657	P-6000	SCIT	Orchard Dr.	8	Asbestos Cement	27	46	1.14 out of 5	\$442	12,126
Transmission Main	1276	P-6024	SCIT	Pasture View Ln.	16	Ductile Iron	1	28	0.14 out of 5	\$442	361
Transmission Main	2570	P-6024	SCIT	Pasture View Ln.	16	Ductile Iron	135	28	0.14 out of 5	\$442	59,732
Transmission Main	2571	P-6024	SCIT	Pasture View Ln.	16	Ductile Iron	344	28	0.14 out of 5	\$442	151,969
Transmission Main	8707	P-6024	SCIT	Pasture View Ln.	16	Ductile Iron	6	28	0.14 out of 5	\$442	2,507
Distribution Main	71	P-6049	SCIT	Patnode Ave	6	Ductile Iron	225	26	0.85 out of 5	\$442	99,543
Distribution Main	9655	P-6049	SCIT	Patnode Ave.	6	Asbestos Cement	298	63	2 out of 5	\$442	131,500
Distribution Main	622	P-6120	SCIT	Reservation Dr.	6	Asbestos Cement	502	55	1.85 out of 5	\$442	221,768
Distribution Main	7752		SCIT	Talbut Rd.	8	Ductile Iron	24	28	0.14 out of 5	\$442	10,512
Distribution Main	7755	P-6128	SCIT	Talbut Rd.	8	Ductile Iron	24	28	0.14 out of 5	\$442	10,450
Distribution Main	620	P-6079	SCIT	White Ln.	6	PVC	4	31	1.14 out of 5	\$442	1,557
Distribution Main	621	P-6079	SCIT	White Ln.	6	PVC	553	31	1.14 out of 5	\$442	244,286
Distribution Main	3219	P-2265	WAR	Abigail St	6	Asbestos Cement	115	66	2 out of 5	\$442	50,653
Distribution Main	5547	P-2254	WAR	Abigail St	8	Ductile Iron	23	19	0 out of 5	N/A	\$0
Distribution Main	6887	P-2265	WAR	Abigail St	6	Asbestos Cement	20	66	2 out of 5	\$442	8,712
Distribution Main	6888	P-2265	WAR	Abigail St	6	Asbestos Cement	453	66	2 out of 5	\$442	200,179
Distribution Main	10366	P-2954	WAR	Abigail St	6	Ductile Iron	13	19	0.71 out of 5	N/A	\$0
Distribution Main	9863	P-2565	WAR	Adelaide Ave	8	Ductile Iron	266	7	0 out of 5	N/A	\$0
Distribution Main	9876	P-2567	WAR	Adelaide Ave	8	Ductile Iron	310	7	0 out of 5	N/A	\$0
Distribution Main	9877	P-2567	WAR	Adelaide Ave	8	Ductile Iron	641	7	0 out of 5	N/A	\$0
Distribution Main	11619	P-2567	WAR	Adelaide Ave	8	Ductile Iron	84	7	0 out of 5	N/A	\$0
Distribution Main	7233	P-2161	WAR	Alanna Ct	8	Ductile Iron	468	29	0.14 out of 5	\$442	207,064
Distribution Main	6515	P-2434	WAR	Alger Av	8	Cast Iron	36	129	1.86 out of 5	\$442	15,942
Distribution Main	6850	P-2434	WAR	Alger Av	8	Cast Iron	242	129	1.86 out of 5	\$442	107,117
Distribution Main	10543		WAR	Alger Av	8	Ductile Iron	64	2	0 out of 5	N/A	\$0
Distribution Main	10544	P-2435	WAR	Alger Av	8	Ductile Iron	367	2	0 out of 5	N/A	\$0
Distribution Main	10545	P-2435	WAR	Alger Av	8	Ductile Iron	365	2	0 out of 5	N/A	\$0
Distribution Main	7234	P-2162	WAR	Alicia Ct	8	Ductile Iron	396	29	0.14 out of 5	\$442	174,994
Distribution Main	9279	P-2877	WAR	Alvin St	8	Ductile Iron	23	11	0 out of 5	N/A	\$0
Distribution Main	9716	P-2878	WAR	Alvin St	2	Copper	8	11	1.99 out of 5	N/A	\$0
Distribution Main	9717	P-2878	WAR	Alvin St	2	Copper	4	11	1.99 out of 5	N/A	\$0
Distribution Main	9464	P-2879	WAR	Alvin Street	1.5	Copper	362	82	2.57 out of 5	\$442	159,842
Distribution Main	6988	P-2512	WAR	Andover Dr	6	Asbestos Cement	467	57	1.85 out of 5	\$442	206,397
Distribution Main	7303	P-2740	WAR	Ann Nolst Ct.	8	Ductile Iron	300	22	0.14 out of 5	N/A	\$0
Distribution Main	7304	P-2740	WAR	Ann Nolst Ct.	8	Ductile Iron	153	22	0.14 out of 5	N/A	\$0
Distribution Main	7310	P-2741	WAR	Ann Nolst Ct.	8	Ductile Iron	24	22	0.14 out of 5	N/A	\$0
Distribution Main	7313	P-2740	WAR	Ann Nolst Ct.	8	Ductile Iron	48	22	0.14 out of 5	N/A	\$0
Distribution Main	7314	P-2740	WAR	Ann Nolst Ct.	8	Ductile Iron	139	22	0.14 out of 5	N/A	\$0
Transmission Main	9204	P-2412	WAR	Arnold Ave	12	Ductile Iron	7	8	0 out of 5	N/A	\$0
Transmission Main	10401	P-2412	WAR	Arnold Ave	12	Ductile Iron	3	8	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	10402	P-2412	WAR	Arnold Ave	12	Ductile Iron	271	8	0 out of 5	N/A	\$0
Distribution Main	5204	P-2600	WAR	Arnolds Neck Dr.	8	Asbestos Cement	593	73	1.29 out of 5	\$442	261,995
Distribution Main	5205	P-2600	WAR	Arnolds Neck Dr.	8	Asbestos Cement	55	73	1.29 out of 5	\$442	24,367
Distribution Main	5225	P-2599	WAR	Arnolds Neck Dr.	8	Asbestos Cement	353	73	1.29 out of 5	\$442	155,955
Distribution Main	5565	P-2423	WAR	Arnolds Neck Dr.	8	Ductile Iron	446	26	0.14 out of 5	\$442	196,965
Distribution Main	5566	P-2423	WAR	Arnolds Neck Dr.	8	Ductile Iron	275	26	0.14 out of 5	\$442	121,681
Distribution Main	5638	P-2601	WAR	Arnolds Neck Dr.	8	Asbestos Cement	640	73	1.29 out of 5	\$442	282,859
Distribution Main	5639	P-2601	WAR	Arnolds Neck Dr.	8	Asbestos Cement	599	73	1.29 out of 5	\$442	264,587
Distribution Main	6439	P-2606	WAR	Arnolds Neck Dr.	8	Asbestos Cement	194	73	1.29 out of 5	\$442	85,740
Distribution Main	6441	P-2605	WAR	Arnolds Neck Dr.	8	Asbestos Cement	352	73	1.29 out of 5	\$442	155,803
Distribution Main	6442	P-2605	WAR	Arnolds Neck Dr.	8	Asbestos Cement	383	73	1.29 out of 5	\$442	169,447
Distribution Main	7052	P-2601	WAR	Arnolds Neck Dr.	8	Asbestos Cement	7	73	1.29 out of 5	\$442	3,088
Distribution Main	10947	P-2423	WAR	Arnolds Neck Dr.	8	Ductile Iron	606	26	0.14 out of 5	\$442	267,753
Distribution Main	11926	P-2600	WAR	Arnolds Neck Dr.	8	Asbestos Cement	218	73	1.29 out of 5	\$442	96,135
Distribution Main	11927	P-2601	WAR	Arnolds Neck Dr.	8	Asbestos Cement	14	73	1.29 out of 5	\$442	6,307
Distribution Main	11928	P-2605	WAR	Arnolds Neck Dr.	8	Asbestos Cement	23	73	1.29 out of 5	\$442	10,301
Distribution Main	11931	P-2423	WAR	Arnolds Neck Dr.	8	Ductile Iron	43	26	0.14 out of 5	\$442	18,932
Distribution Main	4462	P-2121	WAR	Arrowhead Way	8	PVC	58	31	0.43 out of 5	\$442	25,446
Distribution Main	4463	P-2121	WAR	Arrowhead Way	8	PVC	586	31	0.43 out of 5	\$442	259,116
Distribution Main	6426	P-2708	WAR	Ashmont St.	6	Asbestos Cement	158	62	2 out of 5	\$442	69,863
Distribution Main	6430	P-2457	WAR	Ashmont St.	6	Asbestos Cement	144	62	2 out of 5	\$442	63,630
Distribution Main	7092	P-2457	WAR	Ashmont St.	6	Asbestos Cement	6	62	2 out of 5	\$442	2,518
Distribution Main	7361	P-2707	WAR	Ashmont St.	8	Ductile Iron	243	23	0.14 out of 5	N/A	\$0
Distribution Main	10951	P-2708	WAR	Ashmont St.	8	Ductile Iron	40	23	0.14 out of 5	N/A	\$0
Distribution Main	6851	P-2415	WAR	Azalea Ct.	6	Asbestos Cement	14	65	2 out of 5	\$442	6,089
Distribution Main	6852	P-2415	WAR	Azalea Ct.	6	Asbestos Cement	404	65	2 out of 5	\$442	178,379
Distribution Main	10736	P-2550	WAR	Baker St	8	Ductile Iron	390	1	0 out of 5	N/A	\$0
Distribution Main	10737	P-2552	WAR	Baker St	8	Ductile Iron	22	1	0 out of 5	N/A	\$0
Distribution Main	11715	P-2552	WAR	Baker St	8	Ductile Iron	437	1	0 out of 5	N/A	\$0
Distribution Main	11918	P-2550	WAR	Baker St	8	Ductile Iron	71	1	0 out of 5	N/A	\$0
Transmission Main	10720		WAR	Bald Hill Av	16	Ductile Iron	264	1	0 out of 5	N/A	\$0
Distribution Main	9651		WAR	Bald Hill Rd	10	Ductile Iron	13	26	0.14 out of 5	\$442	5,900
Transmission Main	10699		WAR	Bald Hill Rd	42	Asbestos Cement	4,774	UNK	0.85 out of 5	\$442	2,110,113
Transmission Main	1359	P-2231	WAR	Bald Hill Rd.	24	Asbestos Cement	309	35	1 out of 5	\$442	136,730
Transmission Main	2682	P-2231	WAR	Bald Hill Rd.	24	Asbestos Cement	710	35	1 out of 5	\$442	314,007
Transmission Main	2683	P-2231	WAR	Bald Hill Rd.	24	Asbestos Cement	532	35	1 out of 5	\$442	235,073
Transmission Main	5355	P-2667	WAR	Bald Hill Rd.	24	Asbestos Cement	698	35	1 out of 5	\$442	308,731
Transmission Main	5356	P-2667	WAR	Bald Hill Rd.	24	Asbestos Cement	796	35	1 out of 5	\$442	351,693
Transmission Main	7443	P-2896	WAR	Bald Hill Rd.	24	Asbestos Cement	70	35	1 out of 5	\$442	30,905
Transmission Main	7764	P-2667	WAR	Bald Hill Rd.	24	Asbestos Cement	475	35	1 out of 5	\$442	210,160
Transmission Main	7765	P-2667	WAR	Bald Hill Rd.	24	Asbestos Cement	689	35	1 out of 5	\$442	304,515
Transmission Main	9493	P-2667	WAR	Bald Hill Rd.	24	Asbestos Cement	534	35	1 out of 5	\$442	235,857
Transmission Main	9494	P-2667	WAR	Bald Hill Rd.	24	Asbestos Cement	29	35	1 out of 5	\$442	12,647
Transmission Main	11183	P-2231	WAR	Bald Hill Rd.	24	Asbestos Cement	448	35	1 out of 5	\$442	197,996

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11582	P-2667	WAR	Bald Hill Rd.	24	Asbestos Cement	463	35	1 out of 5	\$442	204,513
Transmission Main	11922	P-2667	WAR	Bald Hill Rd.	24	Asbestos Cement	47	35	1 out of 5	\$442	20,773
Transmission Main	11924	P-2231	WAR	Bald Hill Rd.	24	Asbestos Cement	204	35	1 out of 5	\$442	90,252
Transmission Main	4394		WAR	Bald Hill Rd. Ps	24	Asbestos Cement	110	35	1 out of 5	\$442	48,827
Transmission Main	4395		WAR	Bald Hill Rd. Ps	24	Asbestos Cement	11	35	1 out of 5	\$442	5,015
Transmission Main	4396		WAR	Bald Hill Rd. Ps	24	Asbestos Cement	99	35	1 out of 5	\$442	43,870
Distribution Main	3413	P-2864	WAR	Bald Hill Road	6	PVC	10	39	1.14 out of 5	\$442	4,595
Distribution Main	5480	P-2864	WAR	Bald Hill Road	6	PVC	73	39	1.14 out of 5	\$442	32,293
Distribution Main	5482	P-2863	WAR	Bald Hill Road	8	PVC	117	39	0.43 out of 5	\$442	51,751
Distribution Main	7470	P-2863	WAR	Bald Hill Road	6	PVC	158	39	1.14 out of 5	\$442	70,028
Distribution Main	7471	P-2863	WAR	Bald Hill Road	6	PVC	205	39	1.14 out of 5	\$442	90,562
Distribution Main	7472	P-2865	WAR	Bald Hill Road	6	PVC	111	39	1.14 out of 5	\$442	49,250
Distribution Main	7473	P-2864	WAR	Bald Hill Road	6	PVC	30	39	1.14 out of 5	\$442	13,470
Distribution Main	4883		WAR	Baldwin Rd.	6	Asbestos Cement	160	59	1.85 out of 5	\$442	70,500
Distribution Main	4884	P-2011	WAR	Baldwin Rd.	6	Asbestos Cement	489	59	1.85 out of 5	\$442	215,959
Distribution Main	4885	P-2011	WAR	Baldwin Rd.	6	Asbestos Cement	69	59	1.85 out of 5	\$442	30,511
Distribution Main	5439	P-2012	WAR	Baldwin Rd.	6	Asbestos Cement	3	59	1.85 out of 5	\$442	1,493
Distribution Main	5440	P-2012	WAR	Baldwin Rd.	6	Asbestos Cement	174	59	1.85 out of 5	\$442	77,112
Distribution Main	6111	P-2013	WAR	Baldwin Rd.	6	Asbestos Cement	560	59	1.85 out of 5	\$442	247,658
Distribution Main	6945	P-2009	WAR	Baldwin Rd.	6	Asbestos Cement	490	59	1.85 out of 5	\$442	216,778
Distribution Main	6962	P-2017	WAR	Baldwin Rd.	6	Asbestos Cement	142	59	1.85 out of 5	\$442	62,834
Distribution Main	6963	P-2017	WAR	Baldwin Rd.	6	Asbestos Cement	393	59	1.85 out of 5	\$442	173,597
Distribution Main	7008	P-2523	WAR	Bangor St.	6	Asbestos Cement	474	69	2 out of 5	\$442	209,379
Distribution Main	7009	P-2523	WAR	Bangor St.	6	Asbestos Cement	5	69	2 out of 5	\$442	2,189
Distribution Main	5494	P-2587	WAR	Bay View Ave.	10	Cast Iron	21	91	1.72 out of 5	\$442	9,223
Distribution Main	5495	P-2587	WAR	Bay View Ave.	10	Cast Iron	1,154	91	1.72 out of 5	\$442	510,057
Distribution Main	5496	P-2661	WAR	Bay View Ave.	6	Asbestos Cement	6	54	1.85 out of 5	\$442	2,618
Transmission Main	6827	P-2588	WAR	Bay View Ave.	12	Cast Iron	7	91	1.72 out of 5	\$442	2,922
Transmission Main	6839	P-2588	WAR	Bay View Ave.	12	Cast Iron	6	91	1.72 out of 5	\$442	2,567
Transmission Main	6849	P-2592	WAR	Bay View Ave.	12	Cast Iron	660	91	1.72 out of 5	\$442	291,547
Distribution Main	6899	P-2587	WAR	Bay View Ave.	10	Ductile Iron	5	20	0 out of 5	N/A	\$0
Transmission Main	6900	P-2587	WAR	Bay View Ave.	12	Cast Iron	18	91	1.72 out of 5	\$442	7,928
Transmission Main	6906	P-2590	WAR	Bay View Ave.	12	Cast Iron	67	91	1.72 out of 5	\$442	29,573
Transmission Main	6907	P-2590	WAR	Bay View Ave.	12	Cast Iron	506	91	1.72 out of 5	\$442	223,782
Transmission Main	6913	P-2588	WAR	Bay View Ave.	12	Cast Iron	184	91	1.72 out of 5	\$442	81,455
Distribution Main	6930	P-2661	WAR	Bay View Ave.	6	Asbestos Cement	516	54	1.85 out of 5	\$442	228,123
Distribution Main	9591	P-2587	WAR	Bay View Ave.	10	Ductile Iron	13	20	0 out of 5	N/A	\$0
Distribution Main	9592	P-2587	WAR	Bay View Ave.	10	Ductile Iron	18	20	0 out of 5	N/A	\$0
Distribution Main	9593	P-2661	WAR	Bay View Ave.	6	Asbestos Cement	4	54	1.85 out of 5	\$442	1,653
Distribution Main	9594	P-2661	WAR	Bay View Ave.	6	Asbestos Cement	40	54	1.85 out of 5	\$442	17,601
Distribution Main	7111	P-2351	WAR	Bay Vista Pl.	2	Copper	359	55	2.28 out of 5	\$442	158,612
Distribution Main	876	P-2426	WAR	Beacon Hill Drive	8	Asbestos Cement	223	44	1.85 out of 5	\$442	98,731
Distribution Main	877	P-2426	WAR	Beacon Hill Drive	8	Asbestos Cement	173	44	1.14 out of 5	\$442	76,331
Distribution Main	10562	P-2797	WAR	Becker St	8	Ductile Iron	37	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10563	P-2797	WAR	Becker St	8	Ductile Iron	481	2	0 out of 5	N/A	\$0
Distribution Main	8638	P-2921	WAR	Benefit St.	1.5	Copper	202	87	2.57 out of 5	\$442	89,293
Distribution Main	8639	P-2921	WAR	Benefit St.	1.5	Copper	534	87	2.57 out of 5	\$442	236,149
Distribution Main	6889	P-2952	WAR	Benjamin St	8	Asbestos Cement	19	68	1.29 out of 5	\$442	8,508
Distribution Main	6908	P-2269	WAR	Benjamin St	6	Asbestos Cement	155	68	2 out of 5	\$442	68,469
Distribution Main	6909	P-2269	WAR	Benjamin St	6	Asbestos Cement	554	68	2 out of 5	\$442	244,989
Distribution Main	6831	P-2591	WAR	Berkeley Rd.	6	Cast Iron	208	91	2.43 out of 5	\$442	92,062
Distribution Main	6898	P-2591	WAR	Berkeley Rd.	6	Cast Iron	2	91	2.43 out of 5	\$442	915
Distribution Main	6922	P-2591	WAR	Berkeley Rd.	6	Cast Iron	331	91	2.43 out of 5	\$442	146,368
Distribution Main	6923	P-2591	WAR	Berkeley Rd.	6	Cast Iron	41	91	2.43 out of 5	\$442	18,323
Distribution Main	6832	P-2589	WAR	Beverly Rd.	6	Cast Iron	283	80	2.28 out of 5	\$442	124,979
Distribution Main	6924	P-2589	WAR	Beverly Rd.	6	Cast Iron	7	80	2.28 out of 5	\$442	3,027
Transmission Main	9164	P-4898	WAR	Bicknell Ave	12	Ductile Iron	29	8	0 out of 5	N/A	\$0
Distribution Main	9303	P-4898	WAR	Bicknell Ave	8	Ductile Iron	6	8	0 out of 5	N/A	\$0
Transmission Main	11550	P-4898	WAR	Bicknell Ave	12	Ductile Iron	4	8	0 out of 5	N/A	\$0
Distribution Main	4477	P-2075	WAR	Birkshire Dr.	8	Asbestos Cement	782	55	1.14 out of 5	\$442	345,622
Distribution Main	4478	P-2075	WAR	Birkshire Dr.	8	Asbestos Cement	72	55	1.14 out of 5	\$442	31,728
Distribution Main	4482	P-2069	WAR	Birkshire Dr.	8	Asbestos Cement	312	55	1.14 out of 5	\$442	137,906
Distribution Main	4483	P-2069	WAR	Birkshire Dr.	8	Asbestos Cement	177	55	1.14 out of 5	\$442	78,161
Distribution Main	6533	P-2075	WAR	Birkshire Dr.	8	Asbestos Cement	4	55	1.14 out of 5	\$442	1,678
Distribution Main	6309	P-2730	WAR	Bishop Rd.	6	Asbestos Cement	280	50	1.85 out of 5	\$442	123,685
Distribution Main	6593	P-2059	WAR	Bishop Rd.	6	Ductile Iron	244	18	0.71 out of 5	N/A	\$0
Distribution Main	9140	P-2403	WAR	Blackmore St	8	Ductile Iron	194	8	0 out of 5	N/A	\$0
Distribution Main	9141	P-2403	WAR	Blackmore St	8	Ductile Iron	309	8	0 out of 5	N/A	\$0
Distribution Main	9147	P-2403	WAR	Blackmore St	8	Ductile Iron	60	8	0 out of 5	N/A	\$0
Distribution Main	10734	P-2546	WAR	Blade St	6	Ductile Iron	456	1	0.71 out of 5	N/A	\$0
Distribution Main	10735	P-2857	WAR	Blade St	6	Ductile Iron	661	1	0.71 out of 5	N/A	\$0
Distribution Main	11917	P-2857	WAR	Blade St	6	Ductile Iron	217	1	0.71 out of 5	N/A	\$0
Distribution Main	4864	P-2250	WAR	Blair Dr	8	Asbestos Cement	355	49	1.14 out of 5	\$442	156,785
Distribution Main	7291	P-2113	WAR	Blossom Ct	8	PVC	297	32	0.43 out of 5	\$442	131,236
Distribution Main	5227	P-2502	WAR	Blue Hill Dr	6	Asbestos Cement	209	65	2 out of 5	\$442	92,557
Distribution Main	5228	P-2502	WAR	Blue Hill Dr	6	Asbestos Cement	39	65	2 out of 5	\$442	17,045
Distribution Main	5446	P-2497	WAR	Blue Hill Dr	6	Asbestos Cement	214	65	2 out of 5	\$442	94,639
Distribution Main	5447	P-2497	WAR	Blue Hill Dr	6	Asbestos Cement	47	65	2 out of 5	\$442	20,969
Distribution Main	5449	P-2501	WAR	Blue Hill Dr	6	Asbestos Cement	250	65	2 out of 5	\$442	110,396
Distribution Main	6984	P-2496	WAR	Blue Hill Dr	6	Asbestos Cement	290	65	2 out of 5	\$442	128,260
Distribution Main	9102	P-2816	WAR	Blue Hill Dr	8	Ductile Iron	48	14	0 out of 5	N/A	\$0
Distribution Main	9270	P-2909	WAR	Blue Hill Dr	8	Ductile Iron	26	11	0 out of 5	N/A	\$0
Distribution Main	9932	P-2816	WAR	Blue Hill Dr	8	Ductile Iron	56	14	0 out of 5	N/A	\$0
Distribution Main	6673	P-2141	WAR	Blue Ridge Rd	8	Ductile Iron	414	29	0.14 out of 5	\$442	182,790
Distribution Main	6674	P-2141	WAR	Blue Ridge Rd	8	Ductile Iron	74	29	0.14 out of 5	\$442	32,659
Distribution Main	6675	P-2146	WAR	Blue Ridge Rd	8	Ductile Iron	59	29	0.14 out of 5	\$442	26,174
Distribution Main	6676	P-2146	WAR	Blue Ridge Rd	8	Ductile Iron	348	29	0.14 out of 5	\$442	153,659
Distribution Main	6677	P-2156	WAR	Blue Ridge Rd	8	Ductile Iron	337	29	0.14 out of 5	\$442	148,952

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6678	P-2157	WAR	Blue Ridge Rd	8	Ductile Iron	119	29	0.14 out of 5	\$442	52,536
Distribution Main	7228	P-2156	WAR	Blue Ridge Rd	8	Ductile Iron	57	29	0.14 out of 5	\$442	25,277
Distribution Main	7229	P-2156	WAR	Blue Ridge Rd	8	Ductile Iron	22	29	0.14 out of 5	\$442	9,838
Distribution Main	4464	P-2927	WAR	Bokar St	6	Ductile Iron	6	18	0.71 out of 5	N/A	\$0
Distribution Main	4465	P-2927	WAR	Bokar St	6	Ductile Iron	294	18	0.71 out of 5	N/A	\$0
Distribution Main	8630	P-2462	WAR	Bokar St	8	Ductile Iron	31	18	0 out of 5	N/A	\$0
Distribution Main	8631	P-2462	WAR	Bokar St	8	Ductile Iron	201	18	0 out of 5	N/A	\$0
Distribution Main	8632	P-2468	WAR	Bokar St	8	Ductile Iron	250	18	0 out of 5	N/A	\$0
Distribution Main	8634	P-2927	WAR	Bokar St	6	Ductile Iron	71	18	0.71 out of 5	N/A	\$0
Distribution Main	8635	P-2471	WAR	Bokar St	8	Ductile Iron	115	18	0 out of 5	N/A	\$0
Distribution Main	8636	P-2927	WAR	Bokar St	6	Ductile Iron	50	18	0.71 out of 5	N/A	\$0
Distribution Main	10203	P-2468	WAR	Bokar St	8	Ductile Iron	3	18	0 out of 5	N/A	\$0
Distribution Main	10369	P-2927	WAR	Bokar St	6	Ductile Iron	9	18	0.71 out of 5	N/A	\$0
Distribution Main	759	P-2051	WAR	Boulder View Dr.	8	Asbestos Cement	43	42	1.14 out of 5	\$442	19,198
Distribution Main	760	P-2051	WAR	Boulder View Dr.	8	Asbestos Cement	208	42	1.14 out of 5	\$442	92,078
Distribution Main	5696	P-2034	WAR	Boulder View Dr.	8	Asbestos Cement	297	42	1.14 out of 5	\$442	131,327
Distribution Main	5697	P-2033	WAR	Boulder View Dr.	8	PVC	10	31	0.43 out of 5	\$442	4,527
Distribution Main	7061	P-2034	WAR	Boulder View Dr.	8	Asbestos Cement	20	42	1.14 out of 5	\$442	8,843
Distribution Main	7235	P-2715	WAR	Boulder View Dr.	8	PVC	786	31	0.43 out of 5	\$442	347,467
Distribution Main	9266		WAR	Bragger St	2	HDPE	35	11	1.71 out of 5	N/A	\$0
Distribution Main	3401	P-278	WAR	Brayton Ave.	8	Ductile Iron	605	18	0 out of 5	N/A	\$0
Distribution Main	3402	P-278	WAR	Brayton Ave.	8	Ductile Iron	132	18	0 out of 5	N/A	\$0
Distribution Main	4388	P-278	WAR	Brayton Ave.	8	Ductile Iron	117	18	0 out of 5	N/A	\$0
Distribution Main	9281	P-2880	WAR	Breana Ln	8	Ductile Iron	18	11	0 out of 5	N/A	\$0
Distribution Main	9293	P-2880	WAR	Breana Ln	8	Ductile Iron	2	11	0 out of 5	N/A	\$0
Distribution Main	5483	P-2525	WAR	Breana Ln.	6	Ductile Iron	354	31	0.85 out of 5	\$442	156,524
Distribution Main	5484	P-2525	WAR	Breana Ln.	6	Ductile Iron	141	31	0.85 out of 5	\$442	62,403
Distribution Main	7384	P-2541	WAR	Brian Dr.	8	Asbestos Cement	554	55	1.14 out of 5	\$442	244,759
Distribution Main	6070	P-2096	WAR	Brianwood Ct	6	Ductile Iron	219	27	0.85 out of 5	\$442	96,608
Distribution Main	6071	P-2096	WAR	Brianwood Ct	6	Ductile Iron	25	27	0.85 out of 5	\$442	11,042
Distribution Main	3323	P-2663	WAR	Briarbrook Dr.	8	Ductile Iron	548	34	0.14 out of 5	\$442	242,419
Distribution Main	6298	P-2665	WAR	Briarbrook Dr.	8	Ductile Iron	311	34	0.14 out of 5	\$442	137,632
Distribution Main	10769	P-2639	WAR	Bridal Av	8	Ductile Iron	585	0	0 out of 5	N/A	\$0
Distribution Main	10896	P-2640	WAR	Bridal Av	8	Ductile Iron	228	0	0 out of 5	N/A	\$0
Distribution Main	10897	P-2640	WAR	Bridal Av	8	Ductile Iron	173	0	0 out of 5	N/A	\$0
Distribution Main	12156	P-2639	WAR	Bridal Av	8	Ductile Iron	31	0	0 out of 5	N/A	\$0
Distribution Main	12167	P-2639	WAR	Bridal Av	8	Ductile Iron	21	0	0 out of 5	N/A	\$0
Distribution Main	4517	P-2945	WAR	Brier Court	2	Copper	245	79	2.43 out of 5	\$442	108,176
Distribution Main	6082	P-2108	WAR	Brightwater Dr.	8	PVC	65	32	0.43 out of 5	\$442	28,943
Distribution Main	6083	P-2108	WAR	Brightwater Dr.	8	PVC	655	32	0.43 out of 5	\$442	289,702
Distribution Main	8290	P-2813	WAR	Broadbent St	8	Ductile Iron	86	13	0 out of 5	N/A	\$0
Distribution Main	8291	P-2813	WAR	Broadbent St	8	Ductile Iron	155	13	0 out of 5	N/A	\$0
Distribution Main	2840	P-2207	WAR	Brookline Dr.	8	PVC	45	31	0.43 out of 5	\$442	19,765
Distribution Main	2841	P-2207	WAR	Brookline Dr.	8	PVC	45	31	0.43 out of 5	\$442	19,758

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3304	P-2186	WAR	Brookline Dr.	8	PVC	406	31	0.43 out of 5	\$442	179,663
Distribution Main	5456	P-2208	WAR	Brookline Dr.	8	PVC	93	31	0.43 out of 5	\$442	41,005
Distribution Main	6653	P-2207	WAR	Brookline Dr.	8	PVC	527	31	0.43 out of 5	\$442	233,044
Distribution Main	6654	P-2208	WAR	Brookline Dr.	8	PVC	79	31	0.43 out of 5	\$442	34,929
Distribution Main	6655	P-2208	WAR	Brookline Dr.	8	PVC	403	31	0.43 out of 5	\$442	178,106
Distribution Main	6656	P-2205	WAR	Brookline Dr.	8	PVC	243	31	0.43 out of 5	\$442	107,615
Distribution Main	10494		WAR	Brookside Dr	8	Ductile Iron	5	20	0 out of 5	N/A	\$0
Distribution Main	7334	P-2344	WAR	Bruce Ln.	6	Asbestos Cement	203	73	2 out of 5	\$442	89,582
Distribution Main	7335	P-2344	WAR	Bruce Ln.	6	Asbestos Cement	371	73	2 out of 5	\$442	164,202
Distribution Main	10738	P-2551	WAR	Burton St	8	Ductile Iron	302	1	0 out of 5	N/A	\$0
Distribution Main	2239	P-2644	WAR	Cactus St.	8	Asbestos Cement	17	63	1.29 out of 5	\$442	7,316
Distribution Main	4427	P-2642	WAR	Cactus St.	8	Asbestos Cement	160	63	1.29 out of 5	\$442	70,614
Distribution Main	4428	P-2642	WAR	Cactus St.	8	Asbestos Cement	70	63	1.29 out of 5	\$442	31,160
Distribution Main	4429	P-2641	WAR	Cactus St.	8	Asbestos Cement	419	63	1.29 out of 5	\$442	185,071
Distribution Main	4431	P-2644	WAR	Cactus St.	8	Asbestos Cement	61	63	1.29 out of 5	\$442	26,926
Distribution Main	6423	P-2475	WAR	Calhoun Ave.	6	Ductile Iron	239	25	0.85 out of 5	N/A	\$0
Distribution Main	7251	P-2477	WAR	Calhoun Ave.	6	Ductile Iron	142	25	0.85 out of 5	N/A	\$0
Distribution Main	7252	P-2477	WAR	Calhoun Ave.	6	Ductile Iron	45	25	0.85 out of 5	N/A	\$0
Distribution Main	2839	P-2936	WAR	Candle Hill Court	1.5	Copper	318	63	2.43 out of 5	\$442	140,687
Distribution Main	5452	P-2500	WAR	Cardinal St.	6	Asbestos Cement	11	65	2 out of 5	\$442	4,726
Distribution Main	6990	P-2500	WAR	Cardinal St.	6	Asbestos Cement	31	65	2 out of 5	\$442	13,616
Distribution Main	6991	P-2500	WAR	Cardinal St.	6	Asbestos Cement	363	65	2 out of 5	\$442	160,276
Distribution Main	7024	P-2026	WAR	Carriage Hill Dr.	8	Asbestos Cement	7	39	1 out of 5	\$442	3,096
Distribution Main	7048	P-2026	WAR	Carriage Hill Dr.	8	Asbestos Cement	21	39	1 out of 5	\$442	9,424
Distribution Main	7057	P-2026	WAR	Carriage Hill Dr.	6	Asbestos Cement	126	39	1.71 out of 5	\$442	55,714
Distribution Main	7058	P-2026	WAR	Carriage Hill Dr.	6	Asbestos Cement	199	39	1.71 out of 5	\$442	87,749
Distribution Main	3407	P-2695	WAR	Carrs Ln.	6	Ductile Iron	270	28	0.85 out of 5	\$442	119,219
Distribution Main	3412		WAR	Carrs Ln.	6	Ductile Iron	79	28	0.85 out of 5	\$442	34,775
Distribution Main	7478	P-2695	WAR	Carrs Ln.	6	Ductile Iron	34	28	0.85 out of 5	\$442	15,191
Distribution Main	7479		WAR	Carrs Ln.	6	Ductile Iron	6	28	0.85 out of 5	\$442	2,809
Distribution Main	7480	P-2695	WAR	Carrs Ln.	8	Ductile Iron	18	28	0.14 out of 5	\$442	7,741
Distribution Main	7481	P-2695	WAR	Carrs Ln.	8	Ductile Iron	220	28	0.14 out of 5	\$442	97,109
Distribution Main	8637	P-2695	WAR	Carrs Ln.	6	Ductile Iron	11	28	0.85 out of 5	\$442	4,950
Distribution Main	9276	P-2884	WAR	Carson Ave	8	Ductile Iron	13	11	0 out of 5	N/A	\$0
Distribution Main	9277	P-2884	WAR	Carson Ave	8	Ductile Iron	2	11	0 out of 5	N/A	\$0
Distribution Main	9291	P-2886	WAR	Carson Ave	6	Ductile Iron	3	11	0.71 out of 5	N/A	\$0
Distribution Main	5485	P-2490	WAR	Carson Ave.	6	Asbestos Cement	4	47	1.85 out of 5	\$442	1,825
Distribution Main	5486	P-2490	WAR	Carson Ave.	6	Asbestos Cement	370	47	1.85 out of 5	\$442	163,668
Distribution Main	7084	P-2491	WAR	Carson Ave.	6	Asbestos Cement	156	47	1.85 out of 5	\$442	69,018
Distribution Main	7358	P-2943	WAR	Carvin Court	2	Copper	181	79	2.43 out of 5	\$442	79,976
Distribution Main	2515	P-2218	WAR	Castle Rocks Rd.	8	Ductile Iron	463	21	0.14 out of 5	N/A	\$0
Distribution Main	2516	P-2222	WAR	Castle Rocks Rd.	8	Ductile Iron	219	21	0.14 out of 5	N/A	\$0
Distribution Main	2517	P-2222	WAR	Castle Rocks Rd.	8	Ductile Iron	34	21	0.14 out of 5	N/A	\$0
Distribution Main	2518	P-2219	WAR	Castle Rocks Rd.	8	Ductile Iron	54	21	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4595	P-2223	WAR	Castle Rocks Rd.	8	Ductile Iron	309	21	0.14 out of 5	N/A	\$0
Distribution Main	4596	P-2223	WAR	Castle Rocks Rd.	8	Ductile Iron	5	21	0.14 out of 5	N/A	\$0
Distribution Main	4597	P-2219	WAR	Castle Rocks Rd.	8	Ductile Iron	80	21	0.14 out of 5	N/A	\$0
Distribution Main	4598	P-2219	WAR	Castle Rocks Rd.	8	Ductile Iron	152	21	0.14 out of 5	N/A	\$0
Distribution Main	4599	P-2219	WAR	Castle Rocks Rd.	8	Ductile Iron	439	21	0.14 out of 5	N/A	\$0
Distribution Main	5969	P-2223	WAR	Castle Rocks Rd.	8	Ductile Iron	199	21	0.14 out of 5	N/A	\$0
Distribution Main	5970	P-2222	WAR	Castle Rocks Rd.	8	Ductile Iron	254	21	0.14 out of 5	N/A	\$0
Distribution Main	5971	P-2221	WAR	Castle Rocks Rd.	8	Ductile Iron	24	21	0.14 out of 5	N/A	\$0
Distribution Main	5972	P-2221	WAR	Castle Rocks Rd.	8	Ductile Iron	445	21	0.14 out of 5	N/A	\$0
Distribution Main	5973	P-2219	WAR	Castle Rocks Rd.	8	Ductile Iron	226	21	0.14 out of 5	N/A	\$0
Distribution Main	5974	P-2222	WAR	Castle Rocks Rd.	8	Ductile Iron	428	21	0.14 out of 5	N/A	\$0
Distribution Main	5975	P-2222	WAR	Castle Rocks Rd.	8	Ductile Iron	167	21	0.14 out of 5	N/A	\$0
Distribution Main	5976	P-2218	WAR	Castle Rocks Rd.	8	Ductile Iron	7	21	0.14 out of 5	N/A	\$0
Distribution Main	10182	P-2222	WAR	Castle Rocks Rd.	8	Ductile Iron	90	21	0.14 out of 5	N/A	\$0
Distribution Main	10350	P-2222	WAR	Castle Rocks Rd.	8	Ductile Iron	191	21	0.14 out of 5	N/A	\$0
Distribution Main	11322	P-2221	WAR	Castle Rocks Rd.	8	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Distribution Main	11967	P-2222	WAR	Castle Rocks Rd.	8	Ductile Iron	78	21	0.14 out of 5	N/A	\$0
Distribution Main	5448	P-2498	WAR	Caverly St.	6	Asbestos Cement	401	64	2 out of 5	\$442	177,065
Distribution Main	6992	P-2498	WAR	Caverly St.	6	Asbestos Cement	12	64	2 out of 5	\$442	5,327
Distribution Main	11302	P-2498	WAR	Caverly St.	6	Asbestos Cement	9	64	2 out of 5	\$442	3,838
Distribution Main	6815	P-2594	WAR	Cedar St.	6	Asbestos Cement	1,067	53	1.85 out of 5	\$442	471,554
Distribution Main	6816	P-2595	WAR	Cedar St.	6	Cast Iron	17	83	2.43 out of 5	\$442	7,722
Distribution Main	6855	P-2695	WAR	Cedar St.	6	Cast Iron	685	83	2.43 out of 5	\$442	302,878
Distribution Main	6856	P-2695	WAR	Cedar St.	6	Cast Iron	856	83	2.43 out of 5	\$442	378,414
Distribution Main	6876	P-2594	WAR	Cedar St.	6	Asbestos Cement	16	53	1.85 out of 5	\$442	6,924
Distribution Main	6877	P-2597	WAR	Cedar St.	8	Ductile Iron	21	22	0.14 out of 5	N/A	\$0
Distribution Main	9595	P-2594	WAR	Cedar St.	6	Ductile Iron	26	22	0.85 out of 5	N/A	\$0
Distribution Main	9269	P-2906	WAR	Centennial St	8	Ductile Iron	28	11	0 out of 5	N/A	\$0
Distribution Main	9289	P-2907	WAR	Centennial St	6	Ductile Iron	3	11	0.71 out of 5	N/A	\$0
Distribution Main	5703	P-2486	WAR	Centennial St.	6	Asbestos Cement	240	77	2 out of 5	\$442	106,276
Distribution Main	7033	P-2484	WAR	Centennial St.	6	Asbestos Cement	184	77	2 out of 5	\$442	81,149
Transmission Main	1741	P-2420	WAR	Centerville Rd.	12	Ductile Iron	203	UNK	0 out of 5	N/A	\$0
Transmission Main	1742	P-2420	WAR	Centerville Rd.	12	Ductile Iron	71	UNK	0 out of 5	N/A	\$0
Transmission Main	11142	P-2420	WAR	Centerville Rd.	12	Ductile Iron	9	UNK	0 out of 5	N/A	\$0
Distribution Main	9696		WAR	Centerville Rd	10	Ductile Iron	20	14	0 out of 5	N/A	\$0
Transmission Main	10756	P-2420	WAR	Centerville Rd	12	Ductile Iron	62	2	0 out of 5	N/A	\$0
Transmission Main	10757	P-2420	WAR	Centerville Rd	12	Ductile Iron	18	2	0 out of 5	N/A	\$0
Transmission Main	1740	P-2685	WAR	Centerville Rd.	12	Cast Iron	293	91	1.72 out of 5	\$442	129,502
Transmission Main	2579	P-2427	WAR	Centerville Rd.	12	Asbestos Cement	874	61	1.29 out of 5	\$442	386,500
Distribution Main	3594	P-2749	WAR	Centerville Rd.	8	Cast Iron	9	87	1.72 out of 5	\$442	3,985
Distribution Main	3595	P-2722	WAR	Centerville Rd.	8	Cast Iron	216	87	1.72 out of 5	\$442	95,418
Distribution Main	3596	P-2722	WAR	Centerville Rd.	8	Cast Iron	46	87	1.72 out of 5	\$442	20,432
Distribution Main	4057	P-2427	WAR	Centerville Rd.	8	Asbestos Cement	248	61	1.29 out of 5	\$442	109,435
Transmission Main	4380	P-2485	WAR	Centerville Rd.	12	Cast Iron	262	91	1.72 out of 5	\$442	115,877

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	4381	P-2485	WAR	Centerville Rd.	12	Cast Iron	25	91	1.72 out of 5	\$442	11,201
Transmission Main	4880	P-2784	WAR	Centerville Rd.	12	Asbestos Cement	862	61	1.29 out of 5	\$442	380,977
Transmission Main	4881	P-2784	WAR	Centerville Rd.	12	Asbestos Cement	456	61	1.29 out of 5	\$442	201,666
Transmission Main	4886	P-2020	WAR	Centerville Rd.	12	Asbestos Cement	264	61	1.29 out of 5	\$442	116,805
Transmission Main	4887	P-2020	WAR	Centerville Rd.	12	Asbestos Cement	512	61	1.29 out of 5	\$442	226,200
Distribution Main	5220	P-2768	WAR	Centerville Rd.	8	Cast Iron	346	87	1.72 out of 5	\$442	152,717
Distribution Main	5221	P-2024	WAR	Centerville Rd.	8	Asbestos Cement	177	65	1.29 out of 5	\$442	78,176
Distribution Main	5222	P-2024	WAR	Centerville Rd.	8	Asbestos Cement	401	65	1.29 out of 5	\$442	177,171
Distribution Main	5223	P-2768	WAR	Centerville Rd.	8	Cast Iron	15	87	1.72 out of 5	\$442	6,631
Transmission Main	5433	P-2018	WAR	Centerville Rd.	12	Asbestos Cement	359	61	1.29 out of 5	\$442	158,686
Transmission Main	5435	P-2004	WAR	Centerville Rd.	12	Asbestos Cement	49	61	1.29 out of 5	\$442	21,588
Transmission Main	5436	P-2004	WAR	Centerville Rd.	12	Asbestos Cement	399	61	1.29 out of 5	\$442	176,554
Transmission Main	5437	P-2020	WAR	Centerville Rd.	12	Asbestos Cement	112	61	1.29 out of 5	\$442	49,584
Transmission Main	5438	P-2020	WAR	Centerville Rd.	12	Asbestos Cement	9	61	1.29 out of 5	\$442	3,850
Transmission Main	5444	P-2021	WAR	Centerville Rd.	12	Asbestos Cement	74	61	1.29 out of 5	\$442	32,587
Transmission Main	5445	P-2021	WAR	Centerville Rd.	12	Asbestos Cement	168	61	1.29 out of 5	\$442	74,282
Transmission Main	6093	P-2023	WAR	Centerville Rd.	12	Asbestos Cement	656	61	1.29 out of 5	\$442	290,042
Transmission Main	6110		WAR	Centerville Rd.	12	Asbestos Cement	4	61	1.29 out of 5	\$442	1,690
Transmission Main	6159	P-2024	WAR	Centerville Rd.	12	Asbestos Cement	998	61	1.29 out of 5	\$442	441,209
Transmission Main	6160	P-2024	WAR	Centerville Rd.	12	Asbestos Cement	18	61	1.29 out of 5	\$442	7,783
Transmission Main	6946	P-2021	WAR	Centerville Rd.	12	Asbestos Cement	16	61	1.29 out of 5	\$442	7,114
Transmission Main	6975	P-2004	WAR	Centerville Rd.	12	Asbestos Cement	253	61	1.29 out of 5	\$442	111,797
Transmission Main	6976	P-2004	WAR	Centerville Rd.	12	Asbestos Cement	205	61	1.29 out of 5	\$442	90,501
Distribution Main	6998	P-2749	WAR	Centerville Rd.	8	Cast Iron	135	87	1.72 out of 5	\$442	59,672
Distribution Main	7042	P-2024	WAR	Centerville Rd.	8	Asbestos Cement	16	65	1.29 out of 5	\$442	6,923
Distribution Main	7043	P-2768	WAR	Centerville Rd.	8	Cast Iron	2	87	1.72 out of 5	\$442	953
Distribution Main	7044	P-2768	WAR	Centerville Rd.	8	Cast Iron	7	87	1.72 out of 5	\$442	2,903
Distribution Main	7045	P-2721	WAR	Centerville Rd.	8	Cast Iron	462	87	1.72 out of 5	\$442	204,368
Transmission Main	7086	P-2024	WAR	Centerville Rd.	12	Asbestos Cement	105	65	1.29 out of 5	\$442	46,322
Transmission Main	7207	P-2000	WAR	Centerville Rd.	12	Asbestos Cement	381	61	1.29 out of 5	\$442	168,183
Transmission Main	7208	P-2000	WAR	Centerville Rd.	12	Asbestos Cement	553	61	1.29 out of 5	\$442	244,570
Distribution Main	10358	P-2427	WAR	Centerville Rd.	8	Asbestos Cement	121	61	1.29 out of 5	\$442	53,393
Transmission Main	10359	P-2427	WAR	Centerville Rd.	12	Asbestos Cement	19	61	1.29 out of 5	\$442	8,208
Transmission Main	10360	P-2427	WAR	Centerville Rd.	12	Asbestos Cement	40	61	1.29 out of 5	\$442	17,837
Distribution Main	10711	P-2024	WAR	Centerville Rd.	8	Asbestos Cement	427	65	1.29 out of 5	\$442	188,885
Distribution Main	10712	P-2024	WAR	Centerville Rd.	8	Ductile Iron	8	1	0 out of 5	N/A	\$0
Transmission Main	10949	P-2024	WAR	Centerville Rd.	12	Asbestos Cement	58	65	1.29 out of 5	\$442	25,800
Distribution Main	10995	P-2024	WAR	Centerville Rd.	8	Ductile Iron	4	1	0 out of 5	N/A	\$0
Transmission Main	11272	P-2020	WAR	Centerville Rd.	12	Asbestos Cement	71	61	1.29 out of 5	\$442	31,505
Transmission Main	11324	P-2023	WAR	Centerville Rd.	12	Asbestos Cement	8	61	1.29 out of 5	\$442	3,691
Transmission Main	11362	P-2000	WAR	Centerville Rd.	12	Asbestos Cement	234	61	1.29 out of 5	\$442	103,408
Transmission Main	11654	P-2427	WAR	Centerville Rd.	12	Asbestos Cement	14	61	1.29 out of 5	\$442	6,100
Distribution Main	11936	P-2024	WAR	Centerville Rd.	8	Asbestos Cement	168	65	1.29 out of 5	\$442	74,209
Distribution Main	4577	P-2397	WAR	Chace St.	8	Ductile Iron	10	32	0.14 out of 5	\$442	4,283

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6879	P-2396	WAR	Chace St.	8	Ductile Iron	265	32	0.14 out of 5	\$442	117,290
Distribution Main	6883	P-2397	WAR	Chace St.	8	Ductile Iron	215	32	0.14 out of 5	\$442	94,983
Distribution Main	7011	P-2517	WAR	Chapel St.	6	Asbestos Cement	454	69	2 out of 5	\$442	200,535
Distribution Main	6853	P-2440	WAR	Chepiwonxet Way	8	Ductile Iron	255	35	0.14 out of 5	\$442	112,632
Distribution Main	6854	P-2440	WAR	Chepiwonxet Way	8	Ductile Iron	328	35	0.14 out of 5	\$442	145,192
Distribution Main	5471	P-2393	WAR	Chevy Ct.	2	Copper	238	64	2.43 out of 5	\$442	105,256
Distribution Main	7356	P-2393	WAR	Chevy Ct.	2	Copper	53	64	2.43 out of 5	\$442	23,586
Distribution Main	10559	P-2303	WAR	Cindy Ln	8	Ductile Iron	463	2	0 out of 5	N/A	\$0
Distribution Main	10560	P-2303	WAR	Cindy Ln	8	Ductile Iron	471	2	0 out of 5	N/A	\$0
Distribution Main	10561	P-2304	WAR	Cindy Ln	8	Ductile Iron	57	2	0 out of 5	N/A	\$0
Distribution Main	11674	P-2304	WAR	Cindy Ln	8	Ductile Iron	277	2	0 out of 5	N/A	\$0
Distribution Main	6443	P-2479	WAR	Clyde Ave.	6	Asbestos Cement	7	52	1.85 out of 5	\$442	3,309
Distribution Main	7089	P-2479	WAR	Clyde Ave.	6	Asbestos Cement	395	52	1.85 out of 5	\$442	174,681
Distribution Main	1232	P-2202	WAR	Cobble Hill Rd.	8	Asbestos Cement	155	59	1.14 out of 5	\$442	68,406
Distribution Main	3620	P-2147	WAR	Cobble Hill Rd.	8	Asbestos Cement	60	59	1.14 out of 5	\$442	26,710
Distribution Main	3622	P-2145	WAR	Cobble Hill Rd.	8	Asbestos Cement	46	59	1.14 out of 5	\$442	20,553
Distribution Main	3623	P-2145	WAR	Cobble Hill Rd.	8	Asbestos Cement	541	59	1.14 out of 5	\$442	239,240
Distribution Main	5472	P-2151	WAR	Cobble Hill Rd.	8	Asbestos Cement	199	59	1.14 out of 5	\$442	87,824
Distribution Main	5750	P-2145	WAR	Cobble Hill Rd.	8	Asbestos Cement	402	59	1.14 out of 5	\$442	177,830
Distribution Main	11946	P-2145	WAR	Cobble Hill Rd.	8	Asbestos Cement	49	59	1.14 out of 5	\$442	21,612
Distribution Main	3625	P-2201	WAR	Cobble Hill Road	8	Asbestos Cement	125	59	1.14 out of 5	\$442	55,402
Distribution Main	3626	P-2201	WAR	Cobble Hill Road	8	Asbestos Cement	153	59	1.14 out of 5	\$442	67,775
Distribution Main	5777	P-2178	WAR	Cobble Hill Road	8	Asbestos Cement	711	59	1.14 out of 5	\$442	314,284
Distribution Main	1732	P-2543	WAR	College Hill Rd.	8	PVC	28	34	0.43 out of 5	\$442	12,558
Distribution Main	1733	P-2543	WAR	College Hill Rd.	8	PVC	210	34	0.43 out of 5	\$442	93,006
Distribution Main	7380	P-2859	WAR	College Hill Rd.	8	PVC	123	34	0.43 out of 5	\$442	54,411
Distribution Main	5575	P-2915	WAR	College St	4	Cast Iron	405	109	3.29 out of 5	\$442	179,004
Distribution Main	5576	P-2915	WAR	College St	4	Cast Iron	13	109	3.29 out of 5	\$442	5,587
Distribution Main	7379	P-2861	WAR	College View Ct	4	Ductile Iron	302	30	1.57 out of 5	\$442	133,275
Distribution Main	9211	P-2860	WAR	College View Ct	6	Ductile Iron	5	30	0.85 out of 5	\$442	2,229
Distribution Main	9212	P-2860	WAR	College View Ct	6	Ductile Iron	7	30	0.85 out of 5	\$442	3,078
Distribution Main	4548	P-2914	WAR	Colonial Ave.	8	Ductile Iron	22	18	0 out of 5	N/A	\$0
Distribution Main	4549	P-2615	WAR	Colonial Ave.	8	Ductile Iron	14	18	0 out of 5	N/A	\$0
Distribution Main	4552	P-2615	WAR	Colonial Ave.	8	Ductile Iron	195	18	0 out of 5	N/A	\$0
Distribution Main	5568	P-2914	WAR	Colonial Ave.	8	Ductile Iron	174	18	0 out of 5	N/A	\$0
Distribution Main	5569	P-2914	WAR	Colonial Ave.	8	Ductile Iron	252	18	0 out of 5	N/A	\$0
Distribution Main	5015		WAR	Commonwealth Av	8	Ductile Iron	541	UNK	0 out of 5	N/A	\$0
Distribution Main	10556	P-2299	WAR	Commonwealth Av	8	Ductile Iron	54	2	0 out of 5	N/A	\$0
Distribution Main	10570		WAR	Commonwealth Av	8	Ductile Iron	659	2	0 out of 5	N/A	\$0
Distribution Main	10571		WAR	Commonwealth Av	8	Ductile Iron	318	2	0 out of 5	N/A	\$0
Transmission Main	10578	P-2296	WAR	Commonwealth Av	16	Ductile Iron	93	2	0 out of 5	N/A	\$0
Transmission Main	10714	P-2296	WAR	Commonwealth Av	16	Ductile Iron	752	1	0 out of 5	N/A	\$0
Transmission Main	10715	P-2296	WAR	Commonwealth Av	16	Ductile Iron	922	1	0 out of 5	N/A	\$0
Transmission Main	10716	P-2542	WAR	Commonwealth Av	16	Ductile Iron	655	1	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	10717	P-2542	WAR	Commonwealth Av	16	Ductile Iron	649	1	0 out of 5	N/A	\$0
Distribution Main	10992	P-2301	WAR	Commonwealth Av	8	Ductile Iron	33	2	0 out of 5	N/A	\$0
Distribution Main	11676		WAR	Commonwealth Av	8	Ductile Iron	185	2	0 out of 5	N/A	\$0
Transmission Main	11708	P-2538	WAR	Commonwealth Av	16	Ductile Iron	249	1	0 out of 5	N/A	\$0
Transmission Main	11916	P-2542	WAR	Commonwealth Av	16	Ductile Iron	121	1	0 out of 5	N/A	\$0
Transmission Main	11921	P-2542	WAR	Commonwealth Av	16	Ductile Iron	407	1	0 out of 5	N/A	\$0
Transmission Main	11923	P-2296	WAR	Commonwealth Av	16	Ductile Iron	152	1	0 out of 5	N/A	\$0
Transmission Main	12143	P-2542	WAR	Commonwealth Av	16	Ductile Iron	131	1	0 out of 5	N/A	\$0
Transmission Main	12215	P-2296	WAR	Commonwealth Av	16	Ductile Iron	81	1	0 out of 5	N/A	\$0
Distribution Main	6100	P-2299	WAR	Commonwealth Ave.	8	Asbestos Cement	33	60	1.14 out of 5	\$442	14,449
Distribution Main	6101	P-2299	WAR	Commonwealth Ave.	8	Asbestos Cement	5	60	1.14 out of 5	\$442	2,258
Distribution Main	6103	P-2314	WAR	Commonwealth Ave.	8	Ductile Iron	409	24	0.14 out of 5	N/A	\$0
Distribution Main	6158	P-2308	WAR	Commonwealth Ave.	8	Asbestos Cement	305	60	1.14 out of 5	\$442	134,915
Distribution Main	6949	P-2299	WAR	Commonwealth Ave.	8	Asbestos Cement	528	60	1.14 out of 5	\$442	233,493
Distribution Main	6950	P-2299	WAR	Commonwealth Ave.	8	Asbestos Cement	497	60	1.14 out of 5	\$442	219,884
Distribution Main	6952	P-2313	WAR	Commonwealth Ave.	8	Ductile Iron	554	24	0.14 out of 5	N/A	\$0
Distribution Main	6953	P-2313	WAR	Commonwealth Ave.	8	Ductile Iron	20	24	0.14 out of 5	N/A	\$0
Distribution Main	10530	P-2308	WAR	Commonwealth Ave.	8	Asbestos Cement	258	60	1.14 out of 5	\$442	113,977
Distribution Main	10531	P-2308	WAR	Commonwealth Ave.	8	Asbestos Cement	7	60	1.14 out of 5	\$442	3,197
Distribution Main	11932	P-2313	WAR	Commonwealth Ave.	8	Ductile Iron	27	24	0.14 out of 5	N/A	\$0
Distribution Main	6075	P-2152	WAR	Contour Rd.	8	PVC	292	31	0.43 out of 5	\$442	129,137
Distribution Main	7324	P-2153	WAR	Contour Rd.	8	PVC	493	31	0.43 out of 5	\$442	217,946
Distribution Main	7325	P-2153	WAR	Contour Rd.	8	PVC	4	31	0.43 out of 5	\$442	1,880
Distribution Main	6847	P-2747	WAR	Corey Ave.	6	Cast Iron	309	132	2.57 out of 5	\$442	136,362
Distribution Main	6848	P-2747	WAR	Corey Ave.	6	Cast Iron	86	132	2.57 out of 5	\$442	37,884
Distribution Main	6892	P-2748	WAR	Corey Ave.	8	Ductile Iron	123	23	0.14 out of 5	N/A	\$0
Distribution Main	6925	P-2747	WAR	Corey Ave.	6	Cast Iron	13	132	2.57 out of 5	\$442	5,849
Distribution Main	7114	P-2331	WAR	Country Ln.	6	Asbestos Cement	874	71	2 out of 5	\$442	386,297
Distribution Main	9608	P-2331	WAR	Country Ln.	8	Ductile Iron	65	22	0.14 out of 5	N/A	\$0
Distribution Main	9609	P-2331	WAR	Country Ln.	6	Ductile Iron	5	22	0.85 out of 5	N/A	\$0
Distribution Main	9610	P-2331	WAR	Country Ln.	6	Ductile Iron	7	22	0.85 out of 5	N/A	\$0
Distribution Main	10553	P-2322	WAR	Country View Dr	8	Ductile Iron	74	2	0 out of 5	N/A	\$0
Distribution Main	10554	P-2322	WAR	Country View Dr	8	Ductile Iron	536	2	0 out of 5	N/A	\$0
Distribution Main	10555		WAR	Country View Dr	6	Ductile Iron	11	2	0.71 out of 5	N/A	\$0
Distribution Main	11673	P-2322	WAR	Country View Dr	8	Ductile Iron	73	2	0 out of 5	N/A	\$0
Distribution Main	12135	P-2322	WAR	Country View Dr	8	Ductile Iron	52	2	0 out of 5	N/A	\$0
Distribution Main	871	P-2333	WAR	Country View Dr.	8	Asbestos Cement	367	51	1.14 out of 5	\$442	162,147
Distribution Main	878	P-2339	WAR	Country View Dr.	8	Asbestos Cement	269	51	1.14 out of 5	\$442	118,814
Distribution Main	879	P-2339	WAR	Country View Dr.	8	Asbestos Cement	518	51	1.14 out of 5	\$442	229,051
Distribution Main	4293	P-2311	WAR	Country View Dr.	8	Asbestos Cement	812	51	1.14 out of 5	\$442	359,006
Distribution Main	4294	P-2311	WAR	Country View Dr.	8	Asbestos Cement	167	51	1.14 out of 5	\$442	73,762
Distribution Main	10483	P-2322	WAR	Country View Dr.	8	Asbestos Cement	546	51	1.14 out of 5	\$442	241,246
Distribution Main	10551	P-2333	WAR	Country View Dr.	8	Asbestos Cement	41	51	1.14 out of 5	\$442	18,035
Distribution Main	10552	P-2333	WAR	Country View Dr.	8	Asbestos Cement	7	51	1.14 out of 5	\$442	2,912

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	3312	P-2330	WAR	Coweset Rd	12	Ductile Iron	43	22	0.14 out of 5	N/A	\$0
Transmission Main	3313	P-2335	WAR	Coweset Rd	12	Ductile Iron	9	22	0.14 out of 5	N/A	\$0
Transmission Main	3618	P-2134	WAR	Coweset Rd	12	Ductile Iron	33	22	0.14 out of 5	N/A	\$0
Transmission Main	5740	P-2134	WAR	Coweset Rd	12	Ductile Iron	181	22	0.14 out of 5	N/A	\$0
Transmission Main	11210	P-2330	WAR	Coweset Rd	12	Ductile Iron	11	22	0.14 out of 5	N/A	\$0
Transmission Main	11211	P-2335	WAR	Coweset Rd	12	Ductile Iron	6	22	0.14 out of 5	N/A	\$0
Transmission Main	11212	P-2335	WAR	Coweset Rd	12	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Transmission Main	5082	P-2182	WAR	Cowesett Ave.	12	Asbestos Cement	259	53	1.14 out of 5	\$442	114,506
Transmission Main	5357	P-2180	WAR	Cowesett Ave.	12	Asbestos Cement	186	53	1.14 out of 5	\$442	82,405
Transmission Main	5358	P-2180	WAR	Cowesett Ave.	12	Asbestos Cement	10	53	1.14 out of 5	\$442	4,434
Transmission Main	8002	P-2180	WAR	Cowesett Ave.	12	Asbestos Cement	193	53	1.14 out of 5	\$442	85,398
Distribution Main	6074	P-2111	WAR	Cowesett Green Rd.	8	PVC	3	33	0.43 out of 5	\$442	1,293
Distribution Main	6076	P-2109	WAR	Cowesett Green Rd.	8	PVC	304	33	0.43 out of 5	\$442	134,409
Distribution Main	6079	P-2114	WAR	Cowesett Green Rd.	8	PVC	267	33	0.43 out of 5	\$442	117,976
Distribution Main	6080	P-2114	WAR	Cowesett Green Rd.	8	PVC	4	33	0.43 out of 5	\$442	1,594
Distribution Main	6084	P-2112	WAR	Cowesett Green Rd.	8	PVC	585	33	0.43 out of 5	\$442	258,595
Distribution Main	7316	P-2111	WAR	Cowesett Green Rd.	8	PVC	409	33	0.43 out of 5	\$442	180,705
Distribution Main	7326	P-2115	WAR	Cowesett Green Rd.	8	PVC	108	33	0.43 out of 5	\$442	47,881
Distribution Main	7327	P-2115	WAR	Cowesett Green Rd.	8	PVC	627	33	0.43 out of 5	\$442	277,212
Distribution Main	1599		WAR	Cowesett Rd.	10	Unknown	33	UNK	0 out of 5	N/A	\$0
Transmission Main	2222	P-2180	WAR	Cowesett Rd.	12	Asbestos Cement	40	53	1.14 out of 5	\$442	17,759
Transmission Main	2223	P-2180	WAR	Cowesett Rd.	12	Asbestos Cement	415	53	1.14 out of 5	\$442	183,481
Transmission Main	2842	P-2079	WAR	Cowesett Rd.	12	Ductile Iron	268	31	0.14 out of 5	\$442	118,260
Distribution Main	3325	P-2135	WAR	Cowesett Rd.	8	Ductile Iron	41	22	0.14 out of 5	N/A	\$0
Distribution Main	4234	P-2136	WAR	Cowesett Rd.	8	Ductile Iron	41	22	0.14 out of 5	N/A	\$0
Transmission Main	4235	P-2134	WAR	Cowesett Rd.	12	Ductile Iron	5	31	0.14 out of 5	\$442	2,345
Transmission Main	4236	P-2077	WAR	Cowesett Rd.	12	Ductile Iron	49	21	0.14 out of 5	N/A	\$0
Transmission Main	4237	P-2077	WAR	Cowesett Rd.	12	Ductile Iron	111	21	0.14 out of 5	N/A	\$0
Transmission Main	4467	P-2357	WAR	Cowesett Rd.	12	Ductile Iron	42	21	0.14 out of 5	N/A	\$0
Transmission Main	4469	P-2738	WAR	Cowesett Rd.	12	Asbestos Cement	140	53	1.14 out of 5	\$442	61,926
Transmission Main	4470	P-2738	WAR	Cowesett Rd.	12	Asbestos Cement	224	53	1.14 out of 5	\$442	99,032
Transmission Main	4471	P-2737	WAR	Cowesett Rd.	12	Asbestos Cement	310	53	1.14 out of 5	\$442	137,081
Transmission Main	4472	P-2082	WAR	Cowesett Rd.	12	Ductile Iron	310	21	0.14 out of 5	N/A	\$0
Transmission Main	4473	P-2082	WAR	Cowesett Rd.	12	Ductile Iron	300	21	0.14 out of 5	N/A	\$0
Transmission Main	4474	P-2083	WAR	Cowesett Rd.	12	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Transmission Main	4476	P-2076	WAR	Cowesett Rd.	12	Ductile Iron	219	21	0.14 out of 5	N/A	\$0
Transmission Main	5028	P-2081	WAR	Cowesett Rd.	12	Ductile Iron	315	21	0.14 out of 5	N/A	\$0
Transmission Main	5029	P-2081	WAR	Cowesett Rd.	12	Ductile Iron	150	21	0.14 out of 5	N/A	\$0
Transmission Main	5030	P-2092	WAR	Cowesett Rd.	12	Ductile Iron	304	21	0.14 out of 5	N/A	\$0
Transmission Main	5031	P-2092	WAR	Cowesett Rd.	12	Ductile Iron	51	21	0.14 out of 5	N/A	\$0
Transmission Main	5466	P-2095	WAR	Cowesett Rd.	12	Asbestos Cement	951	53	1.14 out of 5	\$442	420,393
Transmission Main	5577	P-2456	WAR	Cowesett Rd.	12	Ductile Iron	11	21	0.14 out of 5	N/A	\$0
Transmission Main	5578	P-2335	WAR	Cowesett Rd.	12	Ductile Iron	440	21	0.14 out of 5	N/A	\$0
Transmission Main	5579	P-2335	WAR	Cowesett Rd.	12	Ductile Iron	441	22	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	5580	P-2336	WAR	Cowesett Rd.	12	Ductile Iron	7	21	0.14 out of 5	N/A	\$0
Transmission Main	5743	P-2077	WAR	Cowesett Rd.	12	Ductile Iron	3	21	0.14 out of 5	N/A	\$0
Transmission Main	6307	P-2082	WAR	Cowesett Rd.	12	Ductile Iron	158	21	0.14 out of 5	N/A	\$0
Transmission Main	6414	P-2355	WAR	Cowesett Rd.	12	Ductile Iron	22	21	0.14 out of 5	N/A	\$0
Transmission Main	6415	P-2355	WAR	Cowesett Rd.	12	Ductile Iron	386	21	0.14 out of 5	N/A	\$0
Transmission Main	6419	P-2336	WAR	Cowesett Rd.	12	Ductile Iron	116	21	0.14 out of 5	N/A	\$0
Transmission Main	6420	P-2336	WAR	Cowesett Rd.	12	Ductile Iron	29	21	0.14 out of 5	N/A	\$0
Transmission Main	6424	P-2356	WAR	Cowesett Rd.	12	Ductile Iron	337	21	0.14 out of 5	N/A	\$0
Transmission Main	6425	P-2452	WAR	Cowesett Rd.	12	Ductile Iron	120	21	0.14 out of 5	N/A	\$0
Transmission Main	6440	P-2335	WAR	Cowesett Rd.	12	Ductile Iron	11	21	0.14 out of 5	N/A	\$0
Transmission Main	6519	P-2357	WAR	Cowesett Rd.	12	Ductile Iron	467	21	0.14 out of 5	N/A	\$0
Transmission Main	6529	P-2076	WAR	Cowesett Rd.	12	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Transmission Main	6609	P-2083	WAR	Cowesett Rd.	12	Ductile Iron	128	21	0.14 out of 5	N/A	\$0
Transmission Main	6610	P-2092	WAR	Cowesett Rd.	12	Ductile Iron	7	21	0.14 out of 5	N/A	\$0
Transmission Main	6664	P-2082	WAR	Cowesett Rd.	12	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Transmission Main	6665	P-2076	WAR	Cowesett Rd.	12	Ductile Iron	7	21	0.14 out of 5	N/A	\$0
Transmission Main	6666	P-2076	WAR	Cowesett Rd.	12	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Transmission Main	6680	P-2138	WAR	Cowesett Rd.	12	Asbestos Cement	98	53	1.14 out of 5	\$442	43,394
Transmission Main	6683	P-2177	WAR	Cowesett Rd.	12	Asbestos Cement	107	53	1.14 out of 5	\$442	47,506
Transmission Main	6684	P-2177	WAR	Cowesett Rd.	12	Asbestos Cement	379	53	1.14 out of 5	\$442	167,566
Transmission Main	6685	P-2180	WAR	Cowesett Rd.	12	Asbestos Cement	904	53	1.14 out of 5	\$442	399,667
Transmission Main	7255	P-2335	WAR	Cowesett Rd.	12	Ductile Iron	7	21	0.14 out of 5	N/A	\$0
Transmission Main	7256	P-2357	WAR	Cowesett Rd.	12	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Transmission Main	7257	P-2357	WAR	Cowesett Rd.	12	Ductile Iron	81	21	0.14 out of 5	N/A	\$0
Transmission Main	7271	P-2959	WAR	Cowesett Rd.	12	Asbestos Cement	969	53	1.14 out of 5	\$442	428,372
Transmission Main	7322	P-2095	WAR	Cowesett Rd.	12	Asbestos Cement	52	53	1.14 out of 5	\$442	22,952
Transmission Main	7448	P-2105	WAR	Cowesett Rd.	12	Asbestos Cement	100	53	1.14 out of 5	\$442	44,303
Transmission Main	7449	P-2105	WAR	Cowesett Rd.	12	Asbestos Cement	154	53	1.14 out of 5	\$442	68,245
Transmission Main	7499	P-2138	WAR	Cowesett Rd.	12	Asbestos Cement	1,360	53	1.14 out of 5	\$442	601,020
Transmission Main	7500	P-2138	WAR	Cowesett Rd.	12	Asbestos Cement	249	53	1.14 out of 5	\$442	110,036
Distribution Main	7501		WAR	Cowesett Rd.	8	Unknown	27	UNK	0 out of 5	N/A	\$0
Distribution Main	7502		WAR	Cowesett Rd.	8	Unknown	5	UNK	0 out of 5	N/A	\$0
Transmission Main	10919	P-2959	WAR	Cowesett Rd.	12	Asbestos Cement	41	53	1.14 out of 5	\$442	18,247
Transmission Main	10920	P-2166	WAR	Cowesett Rd.	12	Asbestos Cement	68	53	1.14 out of 5	\$442	29,881
Transmission Main	11282	P-2081	WAR	Cowesett Rd.	12	Ductile Iron	59	21	0.14 out of 5	N/A	\$0
Transmission Main	11371	P-2095	WAR	Cowesett Rd.	12	Asbestos Cement	6	53	1.14 out of 5	\$442	2,649
Transmission Main	11937	P-2081	WAR	Cowesett Rd.	12	Ductile Iron	94	21	0.14 out of 5	N/A	\$0
Transmission Main	11962	P-2092	WAR	Cowesett Rd.	12	Ductile Iron	94	21	0.14 out of 5	N/A	\$0
Distribution Main	4543	P-2623	WAR	Coyle St.	4	Cast Iron	225	109	3.29 out of 5	\$442	99,586
Distribution Main	5556	P-2621	WAR	Coyle St.	4	Cast Iron	242	109	3.29 out of 5	\$442	106,914
Distribution Main	10567	P-2307	WAR	Craig Rd	8	Ductile Iron	250	2	0 out of 5	N/A	\$0
Distribution Main	10933	P-2897	WAR	Craig Rd	8	Ductile Iron	293	2	0 out of 5	N/A	\$0
Distribution Main	10934	P-2897	WAR	Craig Rd	8	Ductile Iron	47	2	0 out of 5	N/A	\$0
Distribution Main	10935	P-2899	WAR	Craig Rd	8	Ductile Iron	235	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2241	P-1311	WAR	Creamer Ave.	8	Ductile Iron	165	20	0 out of 5	N/A	\$0
Distribution Main	2242	P-1311	WAR	Creamer Ave.	8	Ductile Iron	130	20	0 out of 5	N/A	\$0
Distribution Main	4116	P-1310	WAR	Creamer Ave.	8	Ductile Iron	322	20	0 out of 5	N/A	\$0
Distribution Main	7354	P-2390	WAR	Creston Way	6	Asbestos Cement	493	80	2 out of 5	\$442	217,796
Distribution Main	4519	P-2942	WAR	Crestwood Rd.	8	Asbestos Cement	322	80	1.29 out of 5	\$442	142,158
Distribution Main	6087	P-2383	WAR	Crestwood Rd.	6	Asbestos Cement	375	80	2 out of 5	\$442	165,683
Distribution Main	6089	P-2944	WAR	Crestwood Rd.	6	Asbestos Cement	373	80	2 out of 5	\$442	165,036
Distribution Main	6090	P-2381	WAR	Crestwood Rd.	6	Asbestos Cement	13	80	2 out of 5	\$442	5,729
Distribution Main	6668	P-2387	WAR	Crestwood Rd.	6	Asbestos Cement	5	80	2 out of 5	\$442	1,992
Distribution Main	6669	P-2387	WAR	Crestwood Rd.	6	Asbestos Cement	845	80	2 out of 5	\$442	373,506
Distribution Main	7125	P-2381	WAR	Crestwood Rd.	6	Asbestos Cement	740	80	2 out of 5	\$442	326,976
Distribution Main	7126	P-2381	WAR	Crestwood Rd.	6	Asbestos Cement	5	80	2 out of 5	\$442	2,319
Distribution Main	7127	P-2942	WAR	Crestwood Rd.	8	Asbestos Cement	11	80	1.29 out of 5	\$442	4,738
Distribution Main	7177	P-2383	WAR	Crestwood Rd.	6	Asbestos Cement	8	80	2 out of 5	\$442	3,340
Distribution Main	7346	P-2386	WAR	Crestwood Rd.	8	Asbestos Cement	194	80	1.29 out of 5	\$442	85,764
Distribution Main	7347	P-2385	WAR	Crestwood Rd.	8	Asbestos Cement	1	80	1.29 out of 5	\$442	484
Distribution Main	7348	P-2385	WAR	Crestwood Rd.	8	Asbestos Cement	331	80	1.29 out of 5	\$442	146,460
Distribution Main	7351	P-2384	WAR	Crestwood Rd.	8	Asbestos Cement	83	80	1.29 out of 5	\$442	36,799
Distribution Main	11939	P-2381	WAR	Crestwood Rd.	6	Asbestos Cement	41	80	2 out of 5	\$442	17,942
Distribution Main	1165	P-2643	WAR	Crocus St.	6	Asbestos Cement	652	63	2 out of 5	\$442	288,114
Distribution Main	6417	P-2470	WAR	Cumberland Rd.	8	Ductile Iron	579	18	0 out of 5	N/A	\$0
Distribution Main	6418	P-2470	WAR	Cumberland Rd.	8	Ductile Iron	599	18	0 out of 5	N/A	\$0
Distribution Main	8633	P-2469	WAR	Cumberland Rd.	8	Ductile Iron	176	18	0 out of 5	N/A	\$0
Distribution Main	11334	P-2470	WAR	Cumberland Rd.	8	Ductile Iron	13	18	0 out of 5	N/A	\$0
Distribution Main	5499	P-2583	WAR	D'Agnillo Dr.	8	Asbestos Cement	89	42	1.14 out of 5	\$442	39,397
Distribution Main	5500	P-2583	WAR	D'Agnillo Dr.	8	Asbestos Cement	867	42	1.14 out of 5	\$442	383,307
Distribution Main	6833	P-2583	WAR	D'Agnillo Dr.	8	Asbestos Cement	181	42	1.14 out of 5	\$442	79,792
Distribution Main	6834	P-2583	WAR	D'Agnillo Dr.	8	Asbestos Cement	690	42	1.14 out of 5	\$442	304,844
Distribution Main	6928	P-2583	WAR	D'Agnillo Dr.	8	Asbestos Cement	17	42	1.14 out of 5	\$442	7,647
Distribution Main	7185	P-2091	WAR	Darling St.	8	Ductile Iron	29	18	0 out of 5	N/A	\$0
Distribution Main	7186	P-2091	WAR	Darling St.	8	Ductile Iron	712	18	0 out of 5	N/A	\$0
Distribution Main	7241		WAR	Darling St.	8	Ductile Iron	91	18	0 out of 5	N/A	\$0
Distribution Main	5396	P-2433	WAR	Dawn Ln.	8	Asbestos Cement	313	48	1.14 out of 5	\$442	138,340
Distribution Main	5397	P-2433	WAR	Dawn Ln.	8	Asbestos Cement	153	48	1.14 out of 5	\$442	67,521
Distribution Main	5989	P-2388	WAR	Dexterdale Dr.	8	Asbestos Cement	7	80	1.29 out of 5	\$442	3,261
Distribution Main	6671	P-2388	WAR	Dexterdale Dr.	8	Asbestos Cement	162	80	1.29 out of 5	\$442	71,619
Distribution Main	7352	P-2389	WAR	Dexterdale Dr.	8	Asbestos Cement	12	80	1.29 out of 5	\$442	5,476
Distribution Main	7353	P-2389	WAR	Dexterdale Dr.	8	Asbestos Cement	909	80	1.29 out of 5	\$442	401,826
Distribution Main	365	P-2043	WAR	Diamond Hill Rd.	8	Ductile Iron	268	19	0 out of 5	N/A	\$0
Distribution Main	366	P-2043	WAR	Diamond Hill Rd.	8	Ductile Iron	55	19	0 out of 5	N/A	\$0
Distribution Main	369	P-2027	WAR	Diamond Hill Rd.	8	Ductile Iron	390	19	0 out of 5	N/A	\$0
Distribution Main	5213	P-2025	WAR	Diamond Hill Rd.	8	Ductile Iron	108	19	0 out of 5	N/A	\$0
Distribution Main	5692	P-2725	WAR	Diamond Hill Rd.	8	Ductile Iron	480	19	0 out of 5	N/A	\$0
Distribution Main	5985	P-2084	WAR	Diamond Hill Rd.	8	Ductile Iron	11	19	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6596	P-2087	WAR	Diamond Hill Rd.	8	Ductile Iron	542	19	0 out of 5	N/A	\$0
Distribution Main	6597	P-2087	WAR	Diamond Hill Rd.	8	Ductile Iron	613	19	0 out of 5	N/A	\$0
Distribution Main	6603	P-2054	WAR	Diamond Hill Rd.	8	Ductile Iron	5	19	0 out of 5	N/A	\$0
Distribution Main	6604	P-2054	WAR	Diamond Hill Rd.	8	Ductile Iron	97	19	0 out of 5	N/A	\$0
Distribution Main	6605	P-2053	WAR	Diamond Hill Rd.	8	Ductile Iron	423	19	0 out of 5	N/A	\$0
Distribution Main	6606	P-2086	WAR	Diamond Hill Rd.	8	Ductile Iron	12	19	0 out of 5	N/A	\$0
Distribution Main	6607	P-2086	WAR	Diamond Hill Rd.	8	Ductile Iron	143	19	0 out of 5	N/A	\$0
Distribution Main	6611	P-2084	WAR	Diamond Hill Rd.	8	Ductile Iron	301	19	0 out of 5	N/A	\$0
Distribution Main	7022	P-2025	WAR	Diamond Hill Rd.	8	Ductile Iron	460	19	0 out of 5	N/A	\$0
Distribution Main	7023	P-2027	WAR	Diamond Hill Rd.	8	Ductile Iron	8	19	0 out of 5	N/A	\$0
Distribution Main	7025	P-2919	WAR	Diamond Hill Rd.	8	Ductile Iron	37	19	0 out of 5	N/A	\$0
Distribution Main	7026	P-2919	WAR	Diamond Hill Rd.	8	Ductile Iron	530	19	0 out of 5	N/A	\$0
Distribution Main	7028	P-2724	WAR	Diamond Hill Rd.	8	Ductile Iron	137	19	0 out of 5	N/A	\$0
Distribution Main	7029	P-2724	WAR	Diamond Hill Rd.	8	Ductile Iron	6	19	0 out of 5	N/A	\$0
Distribution Main	7056	P-2025	WAR	Diamond Hill Rd.	8	Ductile Iron	8	19	0 out of 5	N/A	\$0
Distribution Main	7097	P-2053	WAR	Diamond Hill Rd.	8	Ductile Iron	162	19	0 out of 5	N/A	\$0
Distribution Main	7184	P-2044	WAR	Diamond Hill Rd.	8	Ductile Iron	20	19	0 out of 5	N/A	\$0
Transmission Main	9154	P-4888	WAR	Division St	12	Ductile Iron	7	8	0 out of 5	N/A	\$0
Distribution Main	9156	P-4564	WAR	Division St	8	Ductile Iron	3	8	0 out of 5	N/A	\$0
Distribution Main	9157	P-4897	WAR	Division St	8	Ductile Iron	15	8	0 out of 5	N/A	\$0
Transmission Main	9158	P-4566	WAR	Division St	12	Ductile Iron	27	8	0 out of 5	N/A	\$0
Transmission Main	9159	P-4566	WAR	Division St	12	Ductile Iron	232	8	0 out of 5	N/A	\$0
Distribution Main	9190	P-4895	WAR	Division St	8	Ductile Iron	6	8	0 out of 5	N/A	\$0
Distribution Main	9191	P-4895	WAR	Division St	6	Ductile Iron	6	8	0.71 out of 5	N/A	\$0
Distribution Main	9306	P-4887	WAR	Division St	8	Ductile Iron	1	8	0 out of 5	N/A	\$0
Distribution Main	9307	P-4888	WAR	Division St	8	Ductile Iron	2	8	0 out of 5	N/A	\$0
Transmission Main	10852	P-4897	WAR	Division St	12	Ductile Iron	7	8	0 out of 5	N/A	\$0
Transmission Main	10853	P-4565	WAR	Division St	12	Ductile Iron	215	8	0 out of 5	N/A	\$0
Transmission Main	10954	P-4887	WAR	Division St	12	Ductile Iron	6	8	0 out of 5	N/A	\$0
Transmission Main	11549	P-4565	WAR	Division St	12	Ductile Iron	13	8	0 out of 5	N/A	\$0
Distribution Main	4852	P-4899	WAR	Divison Street	6	Cast Iron	315	UNK	1.85 out of 5	\$442	139,183
Distribution Main	4853	P-4899	WAR	Divison Street	6	Cast Iron	11	UNK	1.85 out of 5	\$442	4,852
Distribution Main	5037	P-4899	WAR	Divison Street	6	Cast Iron	14	UNK	1.85 out of 5	\$442	6,249
Distribution Main	9871	P-2568	WAR	Dongay Ave	8	Ductile Iron	244	7	0 out of 5	N/A	\$0
Distribution Main	4882	P-2016	WAR	Douglas Rd.	6	Asbestos Cement	498	59	1.85 out of 5	\$442	220,323
Distribution Main	5434	P-2008	WAR	Douglas Rd.	6	Asbestos Cement	835	59	1.85 out of 5	\$442	369,093
Distribution Main	6108	P-2014	WAR	Douglas Rd.	6	Asbestos Cement	380	59	1.85 out of 5	\$442	168,024
Distribution Main	6109	P-2014	WAR	Douglas Rd.	6	Asbestos Cement	726	59	1.85 out of 5	\$442	320,731
Distribution Main	6961	P-2015	WAR	Douglas Rd.	6	Asbestos Cement	213	59	1.85 out of 5	\$442	94,328
Distribution Main	6973	P-2014	WAR	Douglas Rd.	6	Asbestos Cement	25	59	1.85 out of 5	\$442	10,962
Distribution Main	6974	P-2014	WAR	Douglas Rd.	6	Asbestos Cement	256	59	1.85 out of 5	\$442	113,309
Distribution Main	11915	P-2014	WAR	Douglas Rd.	6	Asbestos Cement	39	59	1.85 out of 5	\$442	17,199
Distribution Main	875	P-2332	WAR	Downing Ln.	8	Ductile Iron	517	47	0.29 out of 5	\$442	228,548
Distribution Main	5218	P-2036	WAR	Drum Rock Ave	8	Cast Iron	517	87	1.72 out of 5	\$442	228,598

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5219	P-2036	WAR	Drum Rock Ave	8	Cast Iron	291	87	1.72 out of 5	\$442	128,532
Distribution Main	8323	P-2036	WAR	Drum Rock Ave	6	Asbestos Cement	279	52	1.85 out of 5	\$442	123,299
Distribution Main	9490	P-2036	WAR	Drum Rock Ave	8	Cast Iron	152	87	1.72 out of 5	\$442	67,103
Distribution Main	9491	P-2036	WAR	Drum Rock Ave	8	Cast Iron	431	87	1.72 out of 5	\$442	190,324
Distribution Main	9142	P-2406	WAR	Duane St	8	Ductile Iron	163	8	0 out of 5	N/A	\$0
Distribution Main	9143	P-2406	WAR	Duane St	8	Ductile Iron	339	8	0 out of 5	N/A	\$0
Distribution Main	9148	P-2408	WAR	Duane St	8	Ductile Iron	52	8	0 out of 5	N/A	\$0
Distribution Main	9149	P-2408	WAR	Duane St	8	Ductile Iron	401	8	0 out of 5	N/A	\$0
Distribution Main	9161	P-2408	WAR	Duane St	8	Ductile Iron	47	8	0 out of 5	N/A	\$0
Distribution Main	12159	P-2408	WAR	Duane St	8	Ductile Iron	25	8	0 out of 5	N/A	\$0
Distribution Main	5215		WAR	Duchess St.	8	Ductile Iron	119	18	0 out of 5	N/A	\$0
Distribution Main	7030	P-2038	WAR	Duchess St.	8	Ductile Iron	601	18	0 out of 5	N/A	\$0
Distribution Main	7031	P-2038	WAR	Duchess St.	8	Ductile Iron	235	18	0 out of 5	N/A	\$0
Distribution Main	9163	P-4616	WAR	Duke St	8	Ductile Iron	38	8	0 out of 5	N/A	\$0
Distribution Main	5441	P-2007	WAR	Dunmore Rd.	8	Asbestos Cement	257	59	1.14 out of 5	\$442	113,578
Distribution Main	7298	P-2741	WAR	Easement	8	Ductile Iron	7	22	0.14 out of 5	N/A	\$0
Distribution Main	7323	P-2741	WAR	Easement	8	Ductile Iron	382	22	0.14 out of 5	N/A	\$0
Distribution Main	9042		WAR	Easement	4	Ductile Iron	6	11	1.42 out of 5	N/A	\$0
Distribution Main	9044	P-2548	WAR	Easement	6	Ductile Iron	119	16	0.71 out of 5	N/A	\$0
Distribution Main	9045	P-2548	WAR	Easement	6	Ductile Iron	166	16	0.71 out of 5	N/A	\$0
Distribution Main	11372	P-2741	WAR	Easement	8	Ductile Iron	8	22	0.14 out of 5	N/A	\$0
Transmission Main	10700		WAR	East Av	42	Asbestos Cement	1,010	UNK	0.85 out of 5	\$442	446,581
Transmission Main	10718		WAR	East Av	16	Ductile Iron	478	1	0 out of 5	N/A	\$0
Transmission Main	10719		WAR	East Av	16	Ductile Iron	189	1	0 out of 5	N/A	\$0
Transmission Main	10721		WAR	East Av	16	Ductile Iron	52	1	0 out of 5	N/A	\$0
Transmission Main	10722		WAR	East Av	16	Ductile Iron	215	1	0 out of 5	N/A	\$0
Transmission Main	11709		WAR	East Av	16	Ductile Iron	94	1	0 out of 5	N/A	\$0
Transmission Main	11710		WAR	East Av	16	Ductile Iron	137	1	0 out of 5	N/A	\$0
Transmission Main	11711		WAR	East Av	16	Ductile Iron	47	1	0 out of 5	N/A	\$0
Transmission Main	11914		WAR	East Av	16	Ductile Iron	112	1	0 out of 5	N/A	\$0
Transmission Main	12195		WAR	East Av	16	Ductile Iron	27	1	0 out of 5	N/A	\$0
Transmission Main	12196		WAR	East Av	16	Ductile Iron	12	1	0 out of 5	N/A	\$0
Transmission Main	10058	P-2850	WAR	East Ave	16	Ductile Iron	219	6	0 out of 5	N/A	\$0
Distribution Main	2835	P-2133	WAR	Edmond Cir.	6	Asbestos Cement	101	65	2 out of 5	\$442	44,751
Distribution Main	5753	P-2133	WAR	Edmond Cir.	6	Asbestos Cement	32	65	2 out of 5	\$442	14,090
Distribution Main	5778	P-2132	WAR	Edmond Cir.	6	Asbestos Cement	18	65	2 out of 5	\$442	7,863
Distribution Main	2833	P-2129	WAR	Edmond Dr.	8	Asbestos Cement	39	65	1.29 out of 5	\$442	17,425
Distribution Main	2834	P-2129	WAR	Edmond Dr.	8	Asbestos Cement	111	65	1.29 out of 5	\$442	48,885
Distribution Main	4225	P-2130	WAR	Edmond Dr.	8	Asbestos Cement	112	65	1.29 out of 5	\$442	49,605
Distribution Main	4226	P-2130	WAR	Edmond Dr.	8	Asbestos Cement	154	65	1.29 out of 5	\$442	67,886
Distribution Main	4238	P-2732	WAR	Edmond Dr.	8	Asbestos Cement	392	65	1.29 out of 5	\$442	173,155
Distribution Main	4867	P-2130	WAR	Edmond Dr.	8	Asbestos Cement	290	65	1.29 out of 5	\$442	128,296
Distribution Main	5744	P-2128	WAR	Edmond Dr.	8	Asbestos Cement	4	65	1.29 out of 5	\$442	1,952
Distribution Main	5758	P-2128	WAR	Edmond Dr.	8	Asbestos Cement	633	65	1.29 out of 5	\$442	279,736

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10542	P-2443	WAR	Elisha St	8	Ductile Iron	256	2	0 out of 5	N/A	\$0
Distribution Main	11672	P-2443	WAR	Elisha St	8	Ductile Iron	210	2	0 out of 5	N/A	\$0
Distribution Main	865	P-2648	WAR	Elmer Ave.	8	Ductile Iron	30	24	0.14 out of 5	N/A	\$0
Distribution Main	1153	P-2648	WAR	Elmer Ave.	8	Ductile Iron	139	24	0.14 out of 5	N/A	\$0
Distribution Main	1154	P-2648	WAR	Elmer Ave.	8	Ductile Iron	276	24	0.14 out of 5	N/A	\$0
Distribution Main	3590	P-2279	WAR	Emily Ln.	8	Ductile Iron	25	2	0 out of 5	N/A	\$0
Distribution Main	6996	P-2279	WAR	Emily Ln.	8	Ductile Iron	160	25	0.14 out of 5	N/A	\$0
Distribution Main	6997	P-2279	WAR	Emily Ln.	8	Ductile Iron	125	25	0.14 out of 5	N/A	\$0
Distribution Main	2528	P-2575	WAR	Fairmount Dr.	6	Asbestos Cement	9	69	2 out of 5	\$442	3,879
Distribution Main	2529		WAR	Fairmount Dr.	6	Unknown	41	69	1.14 out of 5	\$442	18,192
Transmission Main	2530	P-2575	WAR	Fairmount Dr.	20	Asbestos Cement	7	69	1.29 out of 5	\$442	3,023
Distribution Main	4529	P-2575	WAR	Fairmount Dr.	6	Asbestos Cement	293	69	2 out of 5	\$442	129,367
Distribution Main	4530	P-2575	WAR	Fairmount Dr.	6	Asbestos Cement	482	69	2 out of 5	\$442	213,234
Transmission Main	6286	P-2649	WAR	Fairmount Dr.	20	Asbestos Cement	261	55	1.14 out of 5	\$442	115,464
Transmission Main	6287	P-2649	WAR	Fairmount Dr.	20	Asbestos Cement	436	55	1.14 out of 5	\$442	192,583
Distribution Main	3137	P-2282	WAR	Fishs Lane	8	Asbestos Cement	638	52	1.14 out of 5	\$442	281,788
Distribution Main	8278	P-2287	WAR	Flagg Ave.	8	Ductile Iron	597	13	0 out of 5	N/A	\$0
Distribution Main	8295	P-2815	WAR	Flagg Ave.	8	Ductile Iron	179	13	0 out of 5	N/A	\$0
Distribution Main	5431		WAR	Forbes St	6	Ductile Iron	6	26	0.85 out of 5	\$442	2,589
Distribution Main	10574		WAR	Forbes St	8	Ductile Iron	95	2	0 out of 5	N/A	\$0
Distribution Main	5902	P-2326	WAR	Forbes St.	6	Asbestos Cement	110	46	1.85 out of 5	\$442	48,758
Distribution Main	6956	P-2326	WAR	Forbes St.	6	Asbestos Cement	152	46	1.85 out of 5	\$442	67,055
Distribution Main	6957	P-2326	WAR	Forbes St.	6	Asbestos Cement	18	46	1.85 out of 5	\$442	8,113
Distribution Main	11319	P-2326	WAR	Forbes St.	6	Asbestos Cement	23	46	1.85 out of 5	\$442	10,030
Distribution Main	11356	P-2326	WAR	Forbes St.	6	Asbestos Cement	2	46	1.85 out of 5	\$442	785
Distribution Main	8279	P-2814	WAR	Founder Ave.	8	Ductile Iron	281	13	0 out of 5	N/A	\$0
Distribution Main	8285	P-2292	WAR	Founder Ave.	8	Ductile Iron	481	13	0 out of 5	N/A	\$0
Distribution Main	8286	P-2292	WAR	Founder Ave.	8	Ductile Iron	184	13	0 out of 5	N/A	\$0
Distribution Main	5018	P-2363	WAR	Fred Humlak Wy.	6	PVC	688	37	1.14 out of 5	\$442	304,140
Distribution Main	5019	P-2363	WAR	Fred Humlak Wy.	6	PVC	16	37	1.14 out of 5	\$442	7,112
Distribution Main	5987	P-2362	WAR	Fred Humlak Wy.	6	PVC	22	37	1.14 out of 5	\$442	9,589
Distribution Main	6523	P-2465	WAR	Friar Tuck Rd.	8	Ductile Iron	291	18	0 out of 5	N/A	\$0
Distribution Main	6941	P-2450	WAR	Garnet St.	8	Ductile Iron	18	27	0.14 out of 5	\$442	7,795
Distribution Main	6942	P-2450	WAR	Garnet St.	8	Ductile Iron	305	27	0.14 out of 5	\$442	134,685
Distribution Main	10536	P-2450	WAR	Garnet St.	8	Ductile Iron	61	2	0 out of 5	N/A	\$0
Distribution Main	870	P-2300	WAR	Gauvin Dr.	8	Asbestos Cement	53	52	1.14 out of 5	\$442	23,566
Distribution Main	872	P-2281	WAR	Gauvin Dr.	8	Asbestos Cement	397	52	1.14 out of 5	\$442	175,426
Distribution Main	880	P-2306	WAR	Gauvin Dr.	8	Asbestos Cement	195	52	1.14 out of 5	\$442	86,221
Distribution Main	1081	P-2281	WAR	Gauvin Dr.	8	Asbestos Cement	305	52	1.14 out of 5	\$442	134,987
Distribution Main	4292	P-2300	WAR	Gauvin Dr.	8	Asbestos Cement	315	52	1.14 out of 5	\$442	139,344
Distribution Main	9930	P-2285	WAR	Gauvin Dr.	8	Asbestos Cement	181	52	1.14 out of 5	\$442	79,968
Distribution Main	9931	P-2285	WAR	Gauvin Dr.	8	Asbestos Cement	166	52	1.14 out of 5	\$442	73,567
Distribution Main	11094	P-2281	WAR	Gauvin Dr.	8	Asbestos Cement	4	52	1.14 out of 5	\$442	1,574
Distribution Main	6982	P-2816	WAR	Gentian Ave.	8	Ductile Iron	145	14	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2240	P-1493	WAR	Gerald St.	8	Ductile Iron	130	20	0 out of 5	N/A	\$0
Distribution Main	2246	P-1493	WAR	Gerald St.	8	Ductile Iron	95	20	0 out of 5	N/A	\$0
Distribution Main	4426	P-1986	WAR	Gerald St.	8	Ductile Iron	169	20	0 out of 5	N/A	\$0
Distribution Main	4430	P-1987	WAR	Gerald St.	1.25	Copper	105	UNK	1.99 out of 5	\$442	46,606
Distribution Main	9669	P-1608	WAR	Gerald St.	8	Ductile Iron	45	20	0 out of 5	N/A	\$0
Distribution Main	3591	P-2428	WAR	Gilbane St.	8	Asbestos Cement	6	52	1.14 out of 5	\$442	2,555
Distribution Main	3601	P-2276	WAR	Gilbane St.	8	Asbestos Cement	5	52	1.14 out of 5	\$442	2,308
Distribution Main	5487	P-2428	WAR	Gilbane St.	8	Asbestos Cement	19	52	1.14 out of 5	\$442	8,417
Distribution Main	5488	P-2428	WAR	Gilbane St.	8	Asbestos Cement	619	52	1.14 out of 5	\$442	273,637
Distribution Main	6999	P-2276	WAR	Gilbane St.	8	Asbestos Cement	629	52	1.14 out of 5	\$442	278,079
Distribution Main	11941	P-2428	WAR	Gilbane St.	8	Asbestos Cement	467	52	1.14 out of 5	\$442	206,594
Distribution Main	8276	P-2288	WAR	Gilbert St.	8	Ductile Iron	359	13	0 out of 5	N/A	\$0
Distribution Main	8277	P-2288	WAR	Gilbert St.	8	Ductile Iron	548	13	0 out of 5	N/A	\$0
Distribution Main	8287	P-2293	WAR	Gilbert St.	8	Ductile Iron	336	13	0 out of 5	N/A	\$0
Distribution Main	8288	P-2293	WAR	Gilbert St.	8	Ductile Iron	328	13	0 out of 5	N/A	\$0
Distribution Main	8289	P-2291	WAR	Gilbert St.	8	Ductile Iron	242	13	0 out of 5	N/A	\$0
Distribution Main	9934	P-2286	WAR	Gilbert St.	8	Ductile Iron	106	13	0 out of 5	N/A	\$0
Distribution Main	9935	P-2290	WAR	Gilbert St.	8	Ductile Iron	148	13	0 out of 5	N/A	\$0
Distribution Main	9936	P-2286	WAR	Gilbert St.	8	Ductile Iron	136	13	0 out of 5	N/A	\$0
Distribution Main	9937	P-2288	WAR	Gilbert St.	8	Ductile Iron	32	13	0 out of 5	N/A	\$0
Distribution Main	10576	P-2293	WAR	Gilbert St.	8	Ductile Iron	30	13	0 out of 5	N/A	\$0
Distribution Main	11458	P-2293	WAR	Gilbert St.	8	Ductile Iron	4	13	0 out of 5	N/A	\$0
Distribution Main	11625	P-2291	WAR	Gilbert St.	8	Ductile Iron	6	13	0 out of 5	N/A	\$0
Distribution Main	4862	P-2252	WAR	Gilbert Stuart Dr	8	Asbestos Cement	29	46	1.14 out of 5	\$442	12,855
Distribution Main	4863	P-2252	WAR	Gilbert Stuart Dr	8	Asbestos Cement	884	46	1.14 out of 5	\$442	390,828
Distribution Main	6933	P-2252	WAR	Gilbert Stuart Dr	8	Asbestos Cement	25	46	1.14 out of 5	\$442	11,171
Distribution Main	11952	P-2252	WAR	Gilbert Stuart Dr	8	Asbestos Cement	210	46	1.14 out of 5	\$442	92,762
Distribution Main	4865	P-2247	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	620	53	1.14 out of 5	\$442	274,252
Distribution Main	4866	P-2247	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	35	53	1.14 out of 5	\$442	15,330
Distribution Main	5552	P-2245	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	24	53	1.14 out of 5	\$442	10,567
Distribution Main	6812	P-2248	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	307	49	1.14 out of 5	\$442	135,716
Distribution Main	6884	P-2245	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	13	53	1.14 out of 5	\$442	5,533
Distribution Main	6903	P-2248	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	303	53	1.14 out of 5	\$442	133,925
Distribution Main	6904	P-2245	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	268	53	1.14 out of 5	\$442	118,311
Distribution Main	6905	P-2245	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	837	53	1.14 out of 5	\$442	369,749
Distribution Main	6935	P-2233	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	643	53	1.14 out of 5	\$442	284,151
Distribution Main	6936	P-2233	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	290	53	1.14 out of 5	\$442	127,996
Distribution Main	6939	P-2254	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	951	53	1.14 out of 5	\$442	420,384
Distribution Main	6940	P-2254	WAR	Gilbert Stuart Dr.	8	Asbestos Cement	633	53	1.14 out of 5	\$442	279,989
Distribution Main	6608	P-2085	WAR	Ginger St.	8	Ductile Iron	438	18	0 out of 5	N/A	\$0
Distribution Main	6524	P-2476	WAR	Glass St.	6	Ductile Iron	231	25	0.85 out of 5	N/A	\$0
Distribution Main	10568	P-2900	WAR	Globe St	8	Ductile Iron	172	2	0 out of 5	N/A	\$0
Distribution Main	6508	P-2416	WAR	Goodwin St.	1.5	Copper	387	89	2.57 out of 5	\$442	171,246
Distribution Main	6512	P-2416	WAR	Goodwin St.	6	Cast Iron	13	89	2.43 out of 5	\$442	5,710

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6859	P-2416	WAR	Goodwin St.	6	Cast Iron	402	89	2.43 out of 5	\$442	177,707
Distribution Main	6860	P-2416	WAR	Goodwin St.	6	Cast Iron	2	89	2.43 out of 5	\$442	1,091
Distribution Main	9282	P-2883	WAR	Gorton Holden Ter	8	Ductile Iron	22	11	0 out of 5	N/A	\$0
Distribution Main	7006	P-2528	WAR	Gorton Holden Ter.	6	Asbestos Cement	184	41	1.85 out of 5	\$442	81,503
Distribution Main	7007	P-2528	WAR	Gorton Holden Ter.	6	Asbestos Cement	320	41	1.85 out of 5	\$442	141,482
Distribution Main	5501	P-2654	WAR	Governors Dr.	6	Ductile Iron	8	19	0.71 out of 5	N/A	\$0
Distribution Main	5502	P-2654	WAR	Governors Dr.	6	Ductile Iron	25	19	0.71 out of 5	N/A	\$0
Distribution Main	5541	P-2654	WAR	Governors Dr.	8	Ductile Iron	709	19	0 out of 5	N/A	\$0
Distribution Main	5542	P-2654	WAR	Governors Dr.	8	Ductile Iron	145	19	0 out of 5	N/A	\$0
Distribution Main	5543	P-2267	WAR	Governors Dr.	8	Ductile Iron	3	19	0 out of 5	N/A	\$0
Distribution Main	5545	P-2267	WAR	Governors Dr.	8	Ductile Iron	21	19	0 out of 5	N/A	\$0
Distribution Main	5546	P-2267	WAR	Governors Dr.	8	Ductile Iron	351	19	0 out of 5	N/A	\$0
Distribution Main	5548	P-2263	WAR	Governors Dr.	8	Ductile Iron	271	19	0 out of 5	N/A	\$0
Distribution Main	5549	P-2263	WAR	Governors Dr.	8	Ductile Iron	430	19	0 out of 5	N/A	\$0
Distribution Main	10564	P-2897	WAR	Granite St	8	Ductile Iron	11	2	0 out of 5	N/A	\$0
Distribution Main	10565	P-2897	WAR	Granite St	8	Ductile Iron	110	2	0 out of 5	N/A	\$0
Distribution Main	10936		WAR	Granite St	8	Ductile Iron	128	2	0 out of 5	N/A	\$0
Distribution Main	11675	P-2897	WAR	Granite St	8	Ductile Iron	41	2	0 out of 5	N/A	\$0
Distribution Main	9271	P-2910	WAR	Great Oak Dr	8	Ductile Iron	28	21	0.14 out of 5	N/A	\$0
Distribution Main	7066	P-2488	WAR	Great Oak Dr.	8	Ductile Iron	206	21	0.14 out of 5	N/A	\$0
Distribution Main	7067	P-2488	WAR	Great Oak Dr.	8	Ductile Iron	111	21	0.14 out of 5	N/A	\$0
Distribution Main	6299	P-2664	WAR	Green Hill Way	8	Ductile Iron	72	34	0.14 out of 5	\$442	31,970
Distribution Main	6300	P-2664	WAR	Green Hill Way	8	Ductile Iron	301	34	0.14 out of 5	\$442	132,924
Distribution Main	6081	P-2116	WAR	Green Meadow Dr	8	PVC	171	33	0.43 out of 5	\$442	75,517
Distribution Main	3903	P-2890	WAR	Greenbush Road	8	Ductile Iron	185	14	0 out of 5	N/A	\$0
Distribution Main	3904	P-2890	WAR	Greenbush Road	8	Ductile Iron	3	14	0 out of 5	N/A	\$0
Distribution Main	3905	P-2890	WAR	Greenbush Road	8	Ductile Iron	15	14	0 out of 5	N/A	\$0
Distribution Main	3906	P-2889	WAR	Greenbush Road	8	PVC	46	31	0.43 out of 5	\$442	20,119
Transmission Main	10753	P-2902	WAR	Greenwich Av	12	Ductile Iron	17	2	0 out of 5	N/A	\$0
Transmission Main	10763	P-2633	WAR	Greenwich Av	12	Ductile Iron	331	2	0 out of 5	N/A	\$0
Transmission Main	10764	P-2633	WAR	Greenwich Av	12	Ductile Iron	263	2	0 out of 5	N/A	\$0
Transmission Main	9262	P-2634	WAR	Greenwich Ave	12	Ductile Iron	411	11	0 out of 5	N/A	\$0
Transmission Main	9263	P-2634	WAR	Greenwich Ave	12	Ductile Iron	166	11	0 out of 5	N/A	\$0
Transmission Main	9264	P-2902	WAR	Greenwich Ave	12	Ductile Iron	17	11	0 out of 5	N/A	\$0
Transmission Main	9267	P-2634	WAR	Greenwich Ave	12	Ductile Iron	57	11	0 out of 5	N/A	\$0
Transmission Main	9268	P-2634	WAR	Greenwich Ave	12	Ductile Iron	498	11	0 out of 5	N/A	\$0
Transmission Main	9272	P-2489	WAR	Greenwich Ave	12	Ductile Iron	161	11	0 out of 5	N/A	\$0
Transmission Main	9273	P-2527	WAR	Greenwich Ave	12	Ductile Iron	213	11	0 out of 5	N/A	\$0
Transmission Main	9283	P-2758	WAR	Greenwich Ave	12	Ductile Iron	295	11	0 out of 5	N/A	\$0
Distribution Main	9284	P-2531	WAR	Greenwich Ave	8	Ductile Iron	326	11	0 out of 5	N/A	\$0
Transmission Main	9296	P-2634	WAR	Greenwich Ave	12	Ductile Iron	50	11	0 out of 5	N/A	\$0
Transmission Main	9297	P-2634	WAR	Greenwich Ave	12	Ductile Iron	217	11	0 out of 5	N/A	\$0
Distribution Main	9725	P-2868	WAR	Greenwich Ave	6	Ductile Iron	5	11	0.71 out of 5	N/A	\$0
Transmission Main	10937	P-20011	WAR	Greenwich Ave	12	Ductile Iron	304	11	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	10938	P-2487	WAR	Greenwich Ave	12	Ductile Iron	111	11	0 out of 5	N/A	\$0
Transmission Main	10939	P-2487	WAR	Greenwich Ave	12	Ductile Iron	334	11	0 out of 5	N/A	\$0
Transmission Main	10941	P-2903	WAR	Greenwich Ave	12	Ductile Iron	151	11	0 out of 5	N/A	\$0
Transmission Main	10942	P-2903	WAR	Greenwich Ave	12	Ductile Iron	216	11	0 out of 5	N/A	\$0
Transmission Main	11564	P-2634	WAR	Greenwich Ave	12	Ductile Iron	126	11	0 out of 5	N/A	\$0
Transmission Main	11566	P-2876	WAR	Greenwich Ave	12	Ductile Iron	231	11	0 out of 5	N/A	\$0
Transmission Main	11567	P-2521	WAR	Greenwich Ave	12	Ductile Iron	269	11	0 out of 5	N/A	\$0
Transmission Main	11568	P-2526	WAR	Greenwich Ave	12	Ductile Iron	277	11	0 out of 5	N/A	\$0
Transmission Main	11569	P-2527	WAR	Greenwich Ave	12	Ductile Iron	162	11	0 out of 5	N/A	\$0
Transmission Main	11570	P-2527	WAR	Greenwich Ave	12	Ductile Iron	8	11	0 out of 5	N/A	\$0
Transmission Main	11571	P-2872	WAR	Greenwich Ave	12	Ductile Iron	33	11	0 out of 5	N/A	\$0
Distribution Main	11572	P-2537	WAR	Greenwich Ave	8	Ductile Iron	323	11	0 out of 5	N/A	\$0
Distribution Main	11573	P-2872	WAR	Greenwich Ave	8	Ductile Iron	125	11	0 out of 5	N/A	\$0
Distribution Main	11574	P-2529	WAR	Greenwich Ave	8	Ductile Iron	124	11	0 out of 5	N/A	\$0
Transmission Main	12148	P-2487	WAR	Greenwich Ave	12	Ductile Iron	25	11	0 out of 5	N/A	\$0
Transmission Main	12149	P-2903	WAR	Greenwich Ave	12	Ductile Iron	33	11	0 out of 5	N/A	\$0
Transmission Main	12152	P-2526	WAR	Greenwich Ave	12	Ductile Iron	11	11	0 out of 5	N/A	\$0
Transmission Main	10752	P-2420	WAR	Greenwich Ave.	12	Ductile Iron	8	UNK	0 out of 5	N/A	\$0
Transmission Main	10011		WAR	Greenwich Blvd	12	Ductile Iron	57	11	0 out of 5	N/A	\$0
Transmission Main	10012		WAR	Greenwich Blvd	12	Ductile Iron	24	11	0 out of 5	N/A	\$0
Distribution Main	9295		WAR	Greenwood Commons	8	Ductile Iron	7	11	0 out of 5	N/A	\$0
Transmission Main	9151	P-2411	WAR	Hall St.	12	Ductile Iron	37	8	0 out of 5	N/A	\$0
Transmission Main	9152	P-2411	WAR	Hall St.	12	Ductile Iron	365	8	0 out of 5	N/A	\$0
Transmission Main	9205	P-4889	WAR	Hall St.	12	Ductile Iron	6	8	0 out of 5	N/A	\$0
Distribution Main	6077	P-2110	WAR	Hallmark Dr	8	PVC	409	32	0.43 out of 5	\$442	180,923
Distribution Main	6078	P-2110	WAR	Hallmark Dr	8	PVC	294	32	0.43 out of 5	\$442	130,095
Distribution Main	10248		WAR	Harbour Ln	1	Copper	95	2	1.99 out of 5	N/A	\$0
Distribution Main	6947	P-2022	WAR	Hardig Rd.	8	Asbestos Cement	105	47	1.14 out of 5	\$442	46,396
Distribution Main	6948	P-2022	WAR	Hardig Rd.	8	Asbestos Cement	6	47	1.14 out of 5	\$442	2,537
Transmission Main	10509	P-2104	WAR	Hardig Rd.	12	Ductile Iron	56	22	0.14 out of 5	N/A	\$0
Transmission Main	10510	P-2104	WAR	Hardig Rd.	12	Ductile Iron	11	22	0.14 out of 5	N/A	\$0
Transmission Main	10511	P-2104	WAR	Hardig Rd.	12	Ductile Iron	194	22	0.14 out of 5	N/A	\$0
Transmission Main	10513		WAR	Hardig Rd.	12	Ductile Iron	14	22	0.14 out of 5	N/A	\$0
Transmission Main	11668	P-2104	WAR	Hardig Rd.	12	Ductile Iron	10	22	0.14 out of 5	N/A	\$0
Distribution Main	5203	P-2927	WAR	Harrop Ave.	6	Cast Iron	19	86	2.43 out of 5	\$442	8,467
Distribution Main	5224	P-2597	WAR	Harrop Ave.	6	Cast Iron	7	86	2.43 out of 5	\$442	2,912
Distribution Main	5701	P-2597	WAR	Harrop Ave.	6	Cast Iron	627	86	2.43 out of 5	\$442	277,249
Distribution Main	5702	P-2597	WAR	Harrop Ave.	6	Cast Iron	21	86	2.43 out of 5	\$442	9,222
Distribution Main	7040	P-2424	WAR	Harrop Ave.	8	Asbestos Cement	641	73	1.29 out of 5	\$442	283,528
Distribution Main	7041	P-2424	WAR	Harrop Ave.	8	Asbestos Cement	46	73	1.29 out of 5	\$442	20,480
Distribution Main	2836	P-2272	WAR	Hedgerow Dr.	6	Asbestos Cement	172	54	1.85 out of 5	\$442	75,903
Distribution Main	2837	P-2197	WAR	Hedgerow Dr.	8	Asbestos Cement	171	54	1.14 out of 5	\$442	75,505
Distribution Main	3630	P-2211	WAR	Hedgerow Dr.	8	Asbestos Cement	223	54	1.14 out of 5	\$442	98,649
Distribution Main	3631	P-2210	WAR	Hedgerow Dr.	8	Asbestos Cement	112	54	1.14 out of 5	\$442	49,535

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3632	P-2191	WAR	Hedgerow Dr.	8	Asbestos Cement	172	54	1.14 out of 5	\$442	75,951
Distribution Main	3633	P-2191	WAR	Hedgerow Dr.	8	Asbestos Cement	51	54	1.14 out of 5	\$442	22,441
Distribution Main	4874	P-2271	WAR	Hedgerow Dr.	8	Asbestos Cement	398	54	1.14 out of 5	\$442	176,110
Distribution Main	4875	P-2212	WAR	Hedgerow Dr.	2	Copper	148	54	2.28 out of 5	\$442	65,574
Distribution Main	5775	P-2270	WAR	Hedgerow Dr.	8	Asbestos Cement	117	54	1.14 out of 5	\$442	51,845
Distribution Main	5776	P-2270	WAR	Hedgerow Dr.	8	Asbestos Cement	425	54	1.14 out of 5	\$442	187,993
Distribution Main	10537	P-2445	WAR	Herbert St	8	Ductile Iron	502	2	0 out of 5	N/A	\$0
Distribution Main	10538	P-2446	WAR	Herbert St	8	Ductile Iron	124	2	0 out of 5	N/A	\$0
Distribution Main	10952	P-2447	WAR	Herbert St	8	Ductile Iron	31	2	0 out of 5	N/A	\$0
Distribution Main	10953	P-2447	WAR	Herbert St	8	Ductile Iron	179	2	0 out of 5	N/A	\$0
Distribution Main	11669	P-2446	WAR	Herbert St	8	Ductile Iron	67	2	0 out of 5	N/A	\$0
Distribution Main	11670	P-2446	WAR	Herbert St	8	Ductile Iron	25	2	0 out of 5	N/A	\$0
Distribution Main	3221	P-2240	WAR	Heritage Dr.	8	Asbestos Cement	15	53	1.14 out of 5	\$442	6,514
Distribution Main	5538	P-2232	WAR	Heritage Dr.	8	Asbestos Cement	7	55	1.14 out of 5	\$442	3,089
Distribution Main	6303	P-2235	WAR	Heritage Dr.	8	Asbestos Cement	312	53	1.14 out of 5	\$442	137,765
Distribution Main	6885	P-2232	WAR	Heritage Dr.	8	Asbestos Cement	118	55	1.14 out of 5	\$442	52,124
Distribution Main	6886	P-2232	WAR	Heritage Dr.	8	Asbestos Cement	496	55	1.14 out of 5	\$442	219,229
Distribution Main	6896	P-2240	WAR	Heritage Dr.	8	Asbestos Cement	299	53	1.14 out of 5	\$442	131,941
Distribution Main	6897	P-2240	WAR	Heritage Dr.	8	Asbestos Cement	761	53	1.14 out of 5	\$442	336,507
Distribution Main	6937	P-2243	WAR	Heritage Dr.	8	Asbestos Cement	256	53	1.14 out of 5	\$442	113,309
Distribution Main	6938	P-2243	WAR	Heritage Dr.	8	Asbestos Cement	564	53	1.14 out of 5	\$442	249,467
Distribution Main	6825	P-2400	WAR	Hesper Dr.	8	Ductile Iron	11	32	0.14 out of 5	\$442	4,996
Distribution Main	6826	P-2400	WAR	Hesper Dr.	8	Ductile Iron	525	32	0.14 out of 5	\$442	231,903
Distribution Main	6427	P-2453	WAR	Hibiscus Ln.	8	Ductile Iron	5	23	0.14 out of 5	N/A	\$0
Distribution Main	7243	P-2455	WAR	Hibiscus Ln.	8	Ductile Iron	239	23	0.14 out of 5	N/A	\$0
Distribution Main	7244	P-2455	WAR	Hibiscus Ln.	8	Ductile Iron	214	23	0.14 out of 5	N/A	\$0
Distribution Main	7253	P-2453	WAR	Hibiscus Ln.	8	Ductile Iron	252	23	0.14 out of 5	N/A	\$0
Distribution Main	7254	P-2453	WAR	Hibiscus Ln.	8	Ductile Iron	82	23	0.14 out of 5	N/A	\$0
Distribution Main	11963	P-2455	WAR	Hibiscus Ln.	8	Ductile Iron	121	23	0.14 out of 5	N/A	\$0
Distribution Main	7112	P-2346	WAR	Highland Ave.	8	Asbestos Cement	579	66	1.29 out of 5	\$442	255,793
Distribution Main	7113	P-2346	WAR	Highland Ave.	8	Asbestos Cement	425	66	1.29 out of 5	\$442	187,939
Distribution Main	7116	P-2342	WAR	Highland Ave.	8	Cast Iron	37	83	1.72 out of 5	\$442	16,134
Distribution Main	7117	P-2342	WAR	Highland Ave.	8	Cast Iron	644	83	1.72 out of 5	\$442	284,545
Distribution Main	7337	P-2345	WAR	Highland Ave.	8	Cast Iron	104	83	1.72 out of 5	\$442	46,170
Distribution Main	7338	P-2345	WAR	Highland Ave.	8	Cast Iron	748	83	1.72 out of 5	\$442	330,753
Distribution Main	9604	P-2342	WAR	Highland Ave.	8	Ductile Iron	31	22	0.14 out of 5	N/A	\$0
Distribution Main	11947	P-2345	WAR	Highland Ave.	8	Cast Iron	300	83	1.72 out of 5	\$442	132,518
Distribution Main	6868	P-2414	WAR	Highpoint Dr.	6	Asbestos Cement	627	65	2 out of 5	\$442	277,105
Distribution Main	6869	P-2414	WAR	Highpoint Dr.	6	Asbestos Cement	59	65	2 out of 5	\$442	25,900
Distribution Main	10572		WAR	Hilary St	8	Ductile Iron	125	2	0 out of 5	N/A	\$0
Distribution Main	10573	P-2324	WAR	Hilary St	8	Ductile Iron	225	2	0 out of 5	N/A	\$0
Distribution Main	10566	P-2898	WAR	Hilburt St	8	Ductile Iron	139	2	0 out of 5	N/A	\$0
Distribution Main	2524	P-2578	WAR	Hill Top Dr.	6	Asbestos Cement	6	71	2 out of 5	\$442	2,583
Distribution Main	2525	P-2578	WAR	Hill Top Dr.	6	Asbestos Cement	490	71	2 out of 5	\$442	216,523

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4585	P-2574	WAR	Hill Top Dr.	6	Asbestos Cement	325	71	2 out of 5	\$442	143,523
Distribution Main	5032	P-2576	WAR	Hill Top Dr.	6	Asbestos Cement	2	71	2 out of 5	\$442	729
Distribution Main	5033	P-2576	WAR	Hill Top Dr.	6	Asbestos Cement	695	71	2.71 out of 5	\$442	307,202
Transmission Main	5034	P-2650	WAR	Hill Top Dr.	20	Asbestos Cement	320	55	1.14 out of 5	\$442	141,262
Distribution Main	5042	P-2578	WAR	Hill Top Dr.	6	Asbestos Cement	341	71	2 out of 5	\$442	150,515
Distribution Main	11257	P-2574	WAR	Hill Top Dr.	6	Asbestos Cement	5	71	2 out of 5	\$442	2,375
Distribution Main	5694	P-2031	WAR	Hollow Ct.	6	Asbestos Cement	348	42	1.85 out of 5	\$442	153,795
Distribution Main	4495	P-2262	WAR	Indian Hill Rd.	6	Ductile Iron	35	19	0.71 out of 5	N/A	\$0
Distribution Main	4496	P-2262	WAR	Indian Hill Rd.	6	Ductile Iron	319	19	0.71 out of 5	N/A	\$0
Distribution Main	11970	P-2262	WAR	Indian Hill Rd.	6	Ductile Iron	224	19	0.71 out of 5	N/A	\$0
Distribution Main	367	P-2040	WAR	Irene St.	8	Ductile Iron	163	18	0 out of 5	N/A	\$0
Distribution Main	5214	P-2041	WAR	Irene St.	8	Ductile Iron	82	18	0 out of 5	N/A	\$0
Distribution Main	5699	P-2040	WAR	Irene St.	8	Ductile Iron	265	18	0 out of 5	N/A	\$0
Distribution Main	7065	P-2505	WAR	Irondale St.	6	Asbestos Cement	508	65	2 out of 5	\$442	224,444
Distribution Main	7004	P-2535	WAR	Ironwood Ct.	1	Copper	209	62	2.43 out of 5	\$442	92,338
Distribution Main	7106	P-2348	WAR	Island View Dr.	8	Asbestos Cement	204	44	1.14 out of 5	\$442	90,048
Distribution Main	7107	P-2348	WAR	Island View Dr.	8	Asbestos Cement	8	44	1.14 out of 5	\$442	3,335
Distribution Main	7336	P-2349	WAR	Island View Dr.	8	Asbestos Cement	359	44	1.14 out of 5	\$442	158,685
Distribution Main	7340	P-2348	WAR	Island View Dr.	8	Asbestos Cement	8	44	1.14 out of 5	\$442	3,649
Distribution Main	9872	P-2570	WAR	Jambray Ave	8	Ductile Iron	292	7	0 out of 5	N/A	\$0
Distribution Main	9873	P-2570	WAR	Jambray Ave	8	Ductile Iron	93	7	0 out of 5	N/A	\$0
Distribution Main	9880	P-2573	WAR	Jambray Ave	8	Ductile Iron	869	7	0 out of 5	N/A	\$0
Distribution Main	9881	P-2573	WAR	Jambray Ave	8	Ductile Iron	308	7	0 out of 5	N/A	\$0
Distribution Main	11620	P-2573	WAR	Jambray Ave	8	Ductile Iron	70	7	0 out of 5	N/A	\$0
Distribution Main	4461	P-2093	WAR	Jerry St.	6	Ductile Iron	7	25	0.85 out of 5	N/A	\$0
Distribution Main	6068	P-2093	WAR	Jerry St.	6	Ductile Iron	85	25	0.85 out of 5	N/A	\$0
Distribution Main	6069	P-2093	WAR	Jerry St.	6	Ductile Iron	218	25	0.85 out of 5	N/A	\$0
Distribution Main	6502	P-2438	WAR	John Wickes Ave.	6	Ductile Iron	3	31	0.85 out of 5	\$442	1,232
Distribution Main	6503	P-2438	WAR	John Wickes Ave.	6	Ductile Iron	648	31	0.85 out of 5	\$442	286,375
Distribution Main	10549	P-2438	WAR	John Wickes Ave.	6	Ductile Iron	15	2	0.71 out of 5	N/A	\$0
Distribution Main	10550	P-2438	WAR	John Wickes Ave.	6	Ductile Iron	16	2	0.71 out of 5	N/A	\$0
Distribution Main	6875	P-2259	WAR	Joseph Ct	8	PVC	525	33	0.43 out of 5	\$442	231,919
Distribution Main	10208	P-2259	WAR	Joseph Ct	8	PVC	601	33	0.43 out of 5	\$442	265,501
Distribution Main	10209	P-2259	WAR	Joseph Ct	8	PVC	635	33	0.43 out of 5	\$442	280,758
Distribution Main	11954	P-2259	WAR	Joseph Ct	8	PVC	433	33	0.43 out of 5	\$442	191,533
Distribution Main	6088	P-2394	WAR	Joyce Glen	1	Copper	188	63	2.43 out of 5	\$442	83,166
Distribution Main	6612	P-2045	WAR	Judge St.	8	Asbestos Cement	24	58	1.14 out of 5	\$442	10,635
Distribution Main	7359	P-2045	WAR	Judge St.	6	Asbestos Cement	234	58	1.85 out of 5	\$442	103,525
Distribution Main	6672	P-2144	WAR	Katelyn Ct.	8	Ductile Iron	400	29	0.14 out of 5	\$442	176,842
Distribution Main	7383	P-2539	WAR	Kearsage Dr.	8	Asbestos Cement	304	56	1.14 out of 5	\$442	134,365
Distribution Main	11379	P-2539	WAR	Kearsage Dr.	8	Asbestos Cement	129	56	1.14 out of 5	\$442	57,135
Distribution Main	9146	P-2409	WAR	Ladd St	8	Ductile Iron	240	8	0 out of 5	N/A	\$0
Distribution Main	9189	P-2404	WAR	Ladd St	8	Ductile Iron	241	8	0 out of 5	N/A	\$0
Distribution Main	10850	P-2457	WAR	Ladd St	8	Ductile Iron	238	8	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4538	P-2409	WAR	Ladd St.	4	Cast Iron	42	129	3.29 out of 5	\$442	18,766
Distribution Main	5759	P-2174	WAR	Ladderlook Road	8	Asbestos Cement	987	59	1.14 out of 5	\$442	436,473
Distribution Main	5760	P-2174	WAR	Ladderlook Road	8	Asbestos Cement	9	59	1.14 out of 5	\$442	3,830
Distribution Main	9280	P-2881	WAR	Lancaster Ave	8	Ductile Iron	19	11	0 out of 5	N/A	\$0
Distribution Main	9292	P-2881	WAR	Lancaster Ave	6	Ductile Iron	2	11	0.71 out of 5	N/A	\$0
Distribution Main	7010	P-2518	WAR	Lancaster Ave.	6	Asbestos Cement	265	69	2 out of 5	\$442	117,041
Distribution Main	7012	P-2882	WAR	Lancaster Ave.	6	Asbestos Cement	232	69	2 out of 5	\$442	102,384
Distribution Main	7014	P-2508	WAR	Lancaster Ave.	6	Asbestos Cement	123	69	2 out of 5	\$442	54,341
Distribution Main	7015	P-2508	WAR	Lancaster Ave.	6	Asbestos Cement	476	69	2 out of 5	\$442	210,460
Distribution Main	7016	P-2506	WAR	Lancaster Ave.	6	Asbestos Cement	242	69	2 out of 5	\$442	106,976
Distribution Main	7076	P-2524	WAR	Lancaster Ave.	6	Asbestos Cement	138	69	2 out of 5	\$442	60,829
Distribution Main	7077	P-2524	WAR	Lancaster Ave.	6	Asbestos Cement	114	69	2 out of 5	\$442	50,254
Distribution Main	4870	P-2163	WAR	Landmark Rd.	8	Asbestos Cement	1,105	63	1.29 out of 5	\$442	488,623
Distribution Main	7176	P-2712	WAR	Lantern Ln.	6	Asbestos Cement	560	73	2 out of 5	\$442	247,655
Distribution Main	4379	P-2028	WAR	Larchmont Rd.	6	Asbestos Cement	559	57	1.85 out of 5	\$442	247,211
Distribution Main	5691	P-2028	WAR	Larchmont Rd.	8	Asbestos Cement	6	57	1.14 out of 5	\$442	2,712
Distribution Main	5698		WAR	Larchmont Rd.	6	Asbestos Cement	15	57	1.85 out of 5	\$442	6,608
Distribution Main	5981	P-2049	WAR	Larchmont Rd.	6	Asbestos Cement	251	57	1.85 out of 5	\$442	110,811
Distribution Main	7046	P-2028	WAR	Larchmont Rd.	6	Asbestos Cement	26	57	1.85 out of 5	\$442	11,702
Distribution Main	7047	P-2028	WAR	Larchmont Rd.	6	Asbestos Cement	682	57	2.57 out of 5	\$442	301,452
Distribution Main	7062	P-2028	WAR	Larchmont Rd.	8	Asbestos Cement	4	57	1.14 out of 5	\$442	1,637
Distribution Main	7064		WAR	Larchmont Rd.	6	Asbestos Cement	79	57	1.85 out of 5	\$442	34,975
Distribution Main	7369	P-2046	WAR	Larchmont Rd.	6	Asbestos Cement	192	57	1.85 out of 5	\$442	84,781
Distribution Main	7370	P-2046	WAR	Larchmont Rd.	6	Asbestos Cement	421	57	1.85 out of 5	\$442	186,011
Transmission Main	10195		WAR	Larchwood Dr	12	PVC	4	32	0.43 out of 5	\$442	1,851
Transmission Main	10196		WAR	Larchwood Dr	12	PVC	38	32	0.43 out of 5	\$442	16,791
Transmission Main	6066	P-2120	WAR	Larchwood Dr.	12	PVC	194	32	0.43 out of 5	\$442	85,749
Transmission Main	6067	P-2120	WAR	Larchwood Dr.	12	PVC	507	32	0.43 out of 5	\$442	223,927
Transmission Main	7319	P-2122	WAR	Larchwood Dr.	12	PVC	336	32	0.43 out of 5	\$442	148,702
Transmission Main	10187	P-2120	WAR	Larchwood Dr.	12	PVC	21	32	0.43 out of 5	\$442	9,388
Transmission Main	10188	P-2120	WAR	Larchwood Dr.	12	PVC	315	32	0.43 out of 5	\$442	139,082
Transmission Main	10189	P-2122	WAR	Larchwood Dr.	12	PVC	14	32	0.43 out of 5	\$442	6,035
Transmission Main	10190	P-2122	WAR	Larchwood Dr.	12	PVC	410	32	0.43 out of 5	\$442	181,090
Transmission Main	10191	P-2126	WAR	Larchwood Dr.	12	PVC	417	32	0.43 out of 5	\$442	184,409
Transmission Main	10192	P-2126	WAR	Larchwood Dr.	12	PVC	257	32	0.43 out of 5	\$442	113,482
Transmission Main	10193	P-2126	WAR	Larchwood Dr.	12	PVC	137	32	0.43 out of 5	\$442	60,644
Transmission Main	10194	P-2126	WAR	Larchwood Dr.	12	PVC	576	32	0.43 out of 5	\$442	254,544
Transmission Main	10197	P-2120	WAR	Larchwood Dr.	12	PVC	160	32	0.43 out of 5	\$442	70,606
Transmission Main	10198	P-2126	WAR	Larchwood Dr.	12	PVC	7	32	0.43 out of 5	\$442	3,187
Transmission Main	10199	P-2126	WAR	Larchwood Dr.	12	PVC	216	32	0.43 out of 5	\$442	95,356
Transmission Main	10915	P-2119	WAR	Larchwood Dr.	12	PVC	363	32	0.43 out of 5	\$442	160,634
Transmission Main	10916	P-2124	WAR	Larchwood Dr.	12	PVC	187	32	0.43 out of 5	\$442	82,600
Transmission Main	11643	P-2126	WAR	Larchwood Dr.	12	PVC	201	32	0.43 out of 5	\$442	89,020
Transmission Main	12214	P-2122	WAR	Larchwood Dr.	12	PVC	136	32	0.43 out of 5	\$442	60,130

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4295	P-2312	WAR	Ledgemont Dr.	8	Asbestos Cement	646	52	1.14 out of 5	\$442	285,392
Distribution Main	6094	P-2316	WAR	Leon Whipple Rd.	8	Ductile Iron	4	24	0.14 out of 5	N/A	\$0
Distribution Main	6095	P-2316	WAR	Leon Whipple Rd.	8	Ductile Iron	194	24	0.14 out of 5	N/A	\$0
Distribution Main	6104	P-2316	WAR	Leon Whipple Rd.	8	Ductile Iron	11	24	0.14 out of 5	N/A	\$0
Distribution Main	6106	P-2316	WAR	Leon Whipple Rd.	8	Ductile Iron	472	24	0.14 out of 5	N/A	\$0
Distribution Main	6107	P-2316	WAR	Leon Whipple Rd.	8	Ductile Iron	8	24	0.14 out of 5	N/A	\$0
Distribution Main	6951	P-2315	WAR	Leon Whipple Rd.	8	Ductile Iron	355	24	0.14 out of 5	N/A	\$0
Distribution Main	9874	P-2569	WAR	Levesque St	8	Ductile Iron	44	7	0 out of 5	N/A	\$0
Distribution Main	9875	P-2569	WAR	Levesque St	8	Ductile Iron	301	7	0 out of 5	N/A	\$0
Distribution Main	9878	P-2571	WAR	Levesque St	8	Ductile Iron	386	7	0 out of 5	N/A	\$0
Distribution Main	9879	P-2571	WAR	Levesque St	8	Ductile Iron	470	7	0 out of 5	N/A	\$0
Distribution Main	9917	P-2571	WAR	Levesque St	8	Ductile Iron	126	7	0 out of 5	N/A	\$0
Distribution Main	6657	P-2206	WAR	Lisa Marie Cir.	8	PVC	532	31	0.43 out of 5	\$442	235,315
Distribution Main	6658	P-2206	WAR	Lisa Marie Cir.	8	PVC	7	31	0.43 out of 5	\$442	3,180
Distribution Main	7355	P-2941	WAR	Little Lane	1	Copper	207	70	2.43 out of 5	\$442	91,413
Distribution Main	9325	P-2652	WAR	Love Ln	8	Ductile Iron	49	22	0.14 out of 5	N/A	\$0
Distribution Main	9326	P-2658	WAR	Love Ln	8	Ductile Iron	26	22	0.14 out of 5	N/A	\$0
Distribution Main	10210	P-2652	WAR	Love Ln	8	Ductile Iron	6	22	0.14 out of 5	N/A	\$0
Transmission Main	3311	P-2330	WAR	Love Ln.	12	Ductile Iron	15	22	0.14 out of 5	N/A	\$0
Transmission Main	4231	P-2273	WAR	Love Ln.	12	Ductile Iron	151	22	0.14 out of 5	N/A	\$0
Transmission Main	4232	P-2273	WAR	Love Ln.	12	Ductile Iron	338	22	0.14 out of 5	N/A	\$0
Transmission Main	4527	P-2657	WAR	Love Ln.	12	Asbestos Cement	25	62	1.29 out of 5	\$442	10,898
Transmission Main	4528	P-2657	WAR	Love Ln.	12	Asbestos Cement	19	62	1.29 out of 5	\$442	8,471
Transmission Main	4584	P-2574	WAR	Love Ln.	20	Asbestos Cement	15	55	1.14 out of 5	\$442	6,688
Transmission Main	5553	P-2657	WAR	Love Ln.	12	Asbestos Cement	913	62	1.29 out of 5	\$442	403,459
Transmission Main	5554	P-2657	WAR	Love Ln.	12	Asbestos Cement	1,369	62	1.29 out of 5	\$442	605,062
Transmission Main	5736	P-2330	WAR	Love Ln.	16	Ductile Iron	300	22	0.14 out of 5	N/A	\$0
Transmission Main	5737	P-2330	WAR	Love Ln.	16	Ductile Iron	224	22	0.14 out of 5	N/A	\$0
Transmission Main	5738	P-2139	WAR	Love Ln.	12	Ductile Iron	574	22	0.14 out of 5	N/A	\$0
Transmission Main	5739	P-2139	WAR	Love Ln.	12	Ductile Iron	299	22	0.14 out of 5	N/A	\$0
Transmission Main	5741	P-2338	WAR	Love Ln.	16	Ductile Iron	351	22	0.14 out of 5	N/A	\$0
Transmission Main	5742	P-2338	WAR	Love Ln.	16	Ductile Iron	152	22	0.14 out of 5	N/A	\$0
Transmission Main	5745	P-2164	WAR	Love Ln.	12	Ductile Iron	503	22	0.14 out of 5	N/A	\$0
Transmission Main	5746	P-2164	WAR	Love Ln.	12	Ductile Iron	120	22	0.14 out of 5	N/A	\$0
Transmission Main	5748	P-2377	WAR	Love Ln.	16	Ductile Iron	157	22	0.14 out of 5	N/A	\$0
Transmission Main	5749	P-2377	WAR	Love Ln.	16	Ductile Iron	844	22	0.14 out of 5	N/A	\$0
Transmission Main	5766	P-2165	WAR	Love Ln.	12	Ductile Iron	478	22	0.14 out of 5	N/A	\$0
Transmission Main	5767	P-2165	WAR	Love Ln.	12	Ductile Iron	521	22	0.14 out of 5	N/A	\$0
Transmission Main	5773	P-2596	WAR	Love Ln.	16	Ductile Iron	262	22	0.14 out of 5	N/A	\$0
Transmission Main	5774	P-2596	WAR	Love Ln.	16	Ductile Iron	1,389	22	0.14 out of 5	N/A	\$0
Transmission Main	6828	P-2273	WAR	Love Ln.	12	Ductile Iron	68	22	0.14 out of 5	N/A	\$0
Transmission Main	6837	P-2659	WAR	Love Ln.	12	Ductile Iron	63	22	0.14 out of 5	N/A	\$0
Transmission Main	6890	P-2832	WAR	Love Ln.	16	Ductile Iron	254	22	0.14 out of 5	N/A	\$0
Transmission Main	6891	P-2832	WAR	Love Ln.	16	Ductile Iron	241	22	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	6914	P-2829	WAR	Love Ln.	20	Asbestos Cement	698	55	1.14 out of 5	\$442	308,300
Transmission Main	6917	P-2828	WAR	Love Ln.	20	Asbestos Cement	149	55	1.14 out of 5	\$442	65,637
Transmission Main	6918	P-2828	WAR	Love Ln.	20	Asbestos Cement	438	55	1.14 out of 5	\$442	193,394
Transmission Main	6919	P-2659	WAR	Love Ln.	12	Asbestos Cement	75	62	1.29 out of 5	\$442	33,205
Transmission Main	6920	P-2830	WAR	Love Ln.	20	Asbestos Cement	215	55	1.14 out of 5	\$442	94,842
Transmission Main	9486	P-2651	WAR	Love Ln.	20	Asbestos Cement	126	55	1.14 out of 5	\$442	55,763
Transmission Main	9487	P-2659	WAR	Love Ln.	20	Asbestos Cement	70	55	1.14 out of 5	\$442	30,816
Transmission Main	9589	P-2831	WAR	Love Ln.	12	Asbestos Cement	127	62	1.29 out of 5	\$442	56,231
Transmission Main	9590	P-2651	WAR	Love Ln.	20	Asbestos Cement	99	55	1.14 out of 5	\$442	43,596
Transmission Main	9599	P-2164	WAR	Love Ln.	12	Ductile Iron	262	22	0.14 out of 5	N/A	\$0
Transmission Main	9600	P-2164	WAR	Love Ln.	12	Ductile Iron	223	22	0.14 out of 5	N/A	\$0
Transmission Main	9601	P-2596	WAR	Love Ln.	16	Ductile Iron	1,269	22	0.14 out of 5	N/A	\$0
Transmission Main	9605	P-2139	WAR	Love Ln.	12	Ductile Iron	254	22	0.14 out of 5	N/A	\$0
Transmission Main	9606	P-2139	WAR	Love Ln.	12	Ductile Iron	52	22	0.14 out of 5	N/A	\$0
Transmission Main	9607	P-2343	WAR	Love Ln.	16	Ductile Iron	226	22	0.14 out of 5	N/A	\$0
Transmission Main	9611	P-2659	WAR	Love Ln.	20	Ductile Iron	6	22	0.14 out of 5	N/A	\$0
Transmission Main	11950	P-2273	WAR	Love Ln.	12	Ductile Iron	73	22	0.14 out of 5	N/A	\$0
Transmission Main	11964	P-2164	WAR	Love Ln.	12	Ductile Iron	461	22	0.14 out of 5	N/A	\$0
Transmission Main	11965	P-2164	WAR	Love Ln.	12	Ductile Iron	555	22	0.14 out of 5	N/A	\$0
Transmission Main	11966	P-2164	WAR	Love Ln.	12	Ductile Iron	473	22	0.14 out of 5	N/A	\$0
Transmission Main	12209	P-2164	WAR	Love Ln.	12	Ductile Iron	78	22	0.14 out of 5	N/A	\$0
Transmission Main	12210	P-2139	WAR	Love Ln.	12	Ductile Iron	152	22	0.14 out of 5	N/A	\$0
Distribution Main	9265	P-2904	WAR	Luther Ave	6	Ductile Iron	41	11	0.71 out of 5	N/A	\$0
Distribution Main	9465	P-2905	WAR	Luther Ave	1	Copper	240	UNK	1.99 out of 5	\$442	106,094
Distribution Main	11565		WAR	Luther Ave	6	Ductile Iron	1	11	0.71 out of 5	N/A	\$0
Distribution Main	7321	P-2127	WAR	Macara Cir.	8	PVC	345	31	0.43 out of 5	\$442	152,563
Distribution Main	1212	P-2744	WAR	Major Potter Rd.	8	Ductile Iron	768	19	0 out of 5	N/A	\$0
Distribution Main	1738		WAR	Major Potter Rd.	8	PVC	3	31	0.43 out of 5	\$442	1,323
Distribution Main	1739		WAR	Major Potter Rd.	8	PVC	16	31	0.43 out of 5	\$442	7,126
Transmission Main	2519	P-2103	WAR	Major Potter Rd.	12	Ductile Iron	261	22	0.14 out of 5	N/A	\$0
Transmission Main	2520	P-2224	WAR	Major Potter Rd.	12	Ductile Iron	128	22	0.14 out of 5	N/A	\$0
Transmission Main	2521	P-2224	WAR	Major Potter Rd.	12	Ductile Iron	88	22	0.14 out of 5	N/A	\$0
Transmission Main	2522	P-2224	WAR	Major Potter Rd.	12	Ductile Iron	77	22	0.14 out of 5	N/A	\$0
Distribution Main	3309	P-2258	WAR	Major Potter Rd.	8	Asbestos Cement	642	44	1.14 out of 5	\$442	283,721
Distribution Main	3624	P-2261	WAR	Major Potter Rd.	8	Asbestos Cement	500	44	1.14 out of 5	\$442	220,888
Distribution Main	4239	P-2185	WAR	Major Potter Rd.	8	PVC	293	33	0.43 out of 5	\$442	129,533
Distribution Main	4240	P-2185	WAR	Major Potter Rd.	8	PVC	252	33	0.43 out of 5	\$442	111,484
Transmission Main	4695		WAR	Major Potter Rd.	12	Unknown	9	UNK	0 out of 5	N/A	\$0
Distribution Main	4873	P-2260	WAR	Major Potter Rd.	8	Asbestos Cement	264	44	1.14 out of 5	\$442	116,827
Transmission Main	4913	P-2743	WAR	Major Potter Rd.	12	Asbestos Cement	355	42	1.14 out of 5	\$442	157,063
Transmission Main	4914	P-2743	WAR	Major Potter Rd.	12	Asbestos Cement	11	42	1.14 out of 5	\$442	4,688
Transmission Main	5903	P-2224	WAR	Major Potter Rd.	12	Ductile Iron	262	22	0.14 out of 5	N/A	\$0
Distribution Main	6383	P-2745	WAR	Major Potter Rd.	8	Ductile Iron	4	19	0 out of 5	N/A	\$0
Transmission Main	6650	P-2225	WAR	Major Potter Rd.	12	PVC	413	22	0.43 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6651	P-2184	WAR	Major Potter Rd.	8	PVC	136	33	0.43 out of 5	\$442	60,110
Distribution Main	6652	P-2184	WAR	Major Potter Rd.	8	PVC	450	33	0.43 out of 5	\$442	198,939
Distribution Main	6735	P-2744	WAR	Major Potter Rd.	8	Ductile Iron	17	19	0 out of 5	N/A	\$0
Distribution Main	6871	P-2257	WAR	Major Potter Rd.	8	PVC	313	33	0.43 out of 5	\$442	138,510
Distribution Main	6872	P-2257	WAR	Major Potter Rd.	8	PVC	84	33	0.43 out of 5	\$442	37,002
Distribution Main	6873	P-2256	WAR	Major Potter Rd.	8	PVC	24	33	0.43 out of 5	\$442	10,720
Distribution Main	6874	P-2256	WAR	Major Potter Rd.	8	PVC	177	33	0.43 out of 5	\$442	78,436
Transmission Main	7179	P-2103	WAR	Major Potter Rd.	12	Ductile Iron	3	22	0.14 out of 5	N/A	\$0
Distribution Main	7181	P-2103	WAR	Major Potter Rd.	8	Ductile Iron	3	22	0.14 out of 5	N/A	\$0
Transmission Main	7182	P-2118	WAR	Major Potter Rd.	12	PVC	215	31	0.43 out of 5	\$442	95,238
Distribution Main	7281	P-2645	WAR	Major Potter Rd.	8	PVC	544	36	0.43 out of 5	\$442	240,378
Distribution Main	7282	P-2645	WAR	Major Potter Rd.	8	PVC	515	36	0.43 out of 5	\$442	227,421
Distribution Main	7287	P-2745	WAR	Major Potter Rd.	8	Ductile Iron	11	19	0 out of 5	N/A	\$0
Transmission Main	7292	P-2646	WAR	Major Potter Rd.	12	Asbestos Cement	128	42	1.14 out of 5	\$442	56,503
Transmission Main	9298	P-2746	WAR	Major Potter Rd.	12	PVC	314	36	0.43 out of 5	\$442	138,687
Transmission Main	9299	P-2646	WAR	Major Potter Rd.	12	PVC	578	36	0.43 out of 5	\$442	255,385
Transmission Main	9300	P-2646	WAR	Major Potter Rd.	12	PVC	274	36	0.43 out of 5	\$442	121,231
Distribution Main	9596	P-2261	WAR	Major Potter Rd.	8	Ductile Iron	12	22	0.14 out of 5	N/A	\$0
Distribution Main	9597	P-2261	WAR	Major Potter Rd.	8	Ductile Iron	33	22	0.14 out of 5	N/A	\$0
Distribution Main	11106	P-2744	WAR	Major Potter Rd.	8	Ductile Iron	17	19	0 out of 5	N/A	\$0
Distribution Main	11955	P-2645	WAR	Major Potter Rd.	8	PVC	137	36	0.43 out of 5	\$442	60,378
Distribution Main	11956	P-2645	WAR	Major Potter Rd.	8	PVC	362	36	0.43 out of 5	\$442	160,002
Distribution Main	11957	P-2645	WAR	Major Potter Rd.	8	PVC	484	36	0.43 out of 5	\$442	214,060
Distribution Main	11958	P-2645	WAR	Major Potter Rd.	8	PVC	426	36	0.43 out of 5	\$442	188,289
Distribution Main	11959	P-2645	WAR	Major Potter Rd.	8	PVC	497	36	0.43 out of 5	\$442	219,829
Distribution Main	11960	P-2645	WAR	Major Potter Rd.	8	PVC	473	36	0.43 out of 5	\$442	208,944
Distribution Main	11961	P-2645	WAR	Major Potter Rd.	8	PVC	55	36	0.43 out of 5	\$442	24,479
Transmission Main	12221	P-2646	WAR	Major Potter Rd.	12	Asbestos Cement	10	42	1.14 out of 5	\$442	4,431
Distribution Main	10541	P-2950	WAR	Manton St	8	Ductile Iron	165	2	0 out of 5	N/A	\$0
Distribution Main	5711	P-2088	WAR	Mark Allen Dr.	8	Ductile Iron	417	18	0 out of 5	N/A	\$0
Distribution Main	5712	P-2088	WAR	Mark Allen Dr.	8	Ductile Iron	44	18	0 out of 5	N/A	\$0
Distribution Main	6598	P-2088	WAR	Mark Allen Dr.	8	Ductile Iron	289	18	0 out of 5	N/A	\$0
Distribution Main	6599	P-2088	WAR	Mark Allen Dr.	8	Ductile Iron	129	18	0 out of 5	N/A	\$0
Transmission Main	9160	P-4614	WAR	Marlborough St	12	Ductile Iron	12	8	0 out of 5	N/A	\$0
Distribution Main	6679	P-2175	WAR	Martingale Dr.	8	Asbestos Cement	582	39	1 out of 5	\$442	257,252
Distribution Main	7232	P-2176	WAR	Martingale Dr.	8	Asbestos Cement	588	39	1 out of 5	\$442	260,117
Distribution Main	5492		WAR	Masthead Dr	6	Ductile Iron	11	52	1 out of 5	\$442	4,899
Distribution Main	5022	P-2362	WAR	Masthead Dr.	6	Asbestos Cement	506	52	1.85 out of 5	\$442	223,439
Distribution Main	5988	P-2362	WAR	Masthead Dr.	6	Asbestos Cement	2	52	1.85 out of 5	\$442	1,034
Distribution Main	11281	P-2362	WAR	Masthead Dr.	6	Asbestos Cement	37	52	1.85 out of 5	\$442	16,440
Distribution Main	5211	P-2483	WAR	Matteson Ave.	8	Cast Iron	259	86	1.72 out of 5	\$442	114,421
Distribution Main	7049	P-2924	WAR	Matteson Ave.	1.5	Cast Iron	157	86	3.14 out of 5	\$442	69,397
Distribution Main	7053	P-2483	WAR	Matteson Ave.	8	Cast Iron	9	86	1.72 out of 5	\$442	3,954
Distribution Main	11290	P-2483	WAR	Matteson Ave.	8	Cast Iron	4	86	1.72 out of 5	\$442	1,562

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4550	P-2418	WAR	Meadow St	4	Cast Iron	484	91	3.14 out of 5	\$442	213,711
Distribution Main	4551	P-2418	WAR	Meadow St	4	Cast Iron	15	91	3.14 out of 5	\$442	6,508
Distribution Main	5555	P-2418	WAR	Meadow St	4	Cast Iron	17	91	3.14 out of 5	\$442	7,515
Distribution Main	4868	P-2143	WAR	Meeting House Dr.	8	Ductile Iron	44	22	0.14 out of 5	N/A	\$0
Distribution Main	5747	P-2143	WAR	Meeting House Dr.	8	Asbestos Cement	275	63	1.29 out of 5	\$442	121,752
Distribution Main	7320	P-2125	WAR	Michelle Cir.	8	PVC	286	31	0.43 out of 5	\$442	126,376
Distribution Main	5450	P-2495	WAR	Montgomery St.	6	Asbestos Cement	864	67	2 out of 5	\$442	381,902
Distribution Main	5451	P-2495	WAR	Montgomery St.	6	Asbestos Cement	6	67	2 out of 5	\$442	2,713
Distribution Main	7017	P-2507	WAR	Montgomery St.	6	Asbestos Cement	254	67	2 out of 5	\$442	112,440
Distribution Main	9495	P-2917	WAR	Music Ln	6	Ductile Iron	19	18	0.71 out of 5	N/A	\$0
Distribution Main	9144	P-2956	WAR	N Marlborough St	8	Ductile Iron	163	8	0 out of 5	N/A	\$0
Distribution Main	9145	P-2956	WAR	N Marlborough St	8	Ductile Iron	246	8	0 out of 5	N/A	\$0
Distribution Main	9150	P-2410	WAR	N Marlborough St	8	Ductile Iron	399	8	0 out of 5	N/A	\$0
Distribution Main	9155	P-2410	WAR	N Marlborough St	8	Ductile Iron	44	8	0 out of 5	N/A	\$0
Distribution Main	10851	P-4896	WAR	N Marlborough St	8	Ductile Iron	9	8	0 out of 5	N/A	\$0
Distribution Main	4479	P-2065	WAR	Nanci Karen Dr.	8	Asbestos Cement	346	42	1.14 out of 5	\$442	152,731
Distribution Main	4480	P-2065	WAR	Nanci Karen Dr.	8	Asbestos Cement	146	42	1.14 out of 5	\$442	64,678
Distribution Main	5259	P-2064	WAR	Nanci Karen Dr.	8	Asbestos Cement	353	42	1.14 out of 5	\$442	156,189
Distribution Main	5262	P-2067	WAR	Nanci Karen Dr.	8	Asbestos Cement	234	42	1.14 out of 5	\$442	103,465
Distribution Main	5263	P-2067	WAR	Nanci Karen Dr.	8	Asbestos Cement	2	42	1.14 out of 5	\$442	1,002
Distribution Main	7364	P-2066	WAR	Nanci Karen Dr.	8	Asbestos Cement	56	42	1.14 out of 5	\$442	24,811
Distribution Main	7365	P-2066	WAR	Nanci Karen Dr.	8	Asbestos Cement	456	42	1.14 out of 5	\$442	201,730
Distribution Main	11373	P-2066	WAR	Nanci Karen Dr.	8	Asbestos Cement	41	42	1.14 out of 5	\$442	18,193
Distribution Main	5768	P-2168	WAR	Nancy Allen Dr.	8	Asbestos Cement	242	58	1.14 out of 5	\$442	106,998
Distribution Main	9598	P-2168	WAR	Nancy Allen Dr.	8	Ductile Iron	56	22	0.14 out of 5	N/A	\$0
Distribution Main	6102	P-2321	WAR	Natalie Ln.	8	Ductile Iron	168	24	0.14 out of 5	N/A	\$0
Distribution Main	6932	P-2242	WAR	Nathaniel Green Dr.	6	Asbestos Cement	695	55	1.85 out of 5	\$442	307,349
Distribution Main	10534	P-2451	WAR	Neptune St	8	Ductile Iron	120	2	0 out of 5	N/A	\$0
Distribution Main	10535	P-2451	WAR	Neptune St	8	Ductile Iron	83	2	0 out of 5	N/A	\$0
Distribution Main	5393	P-2430	WAR	New England Way	8	Asbestos Cement	88	52	1.14 out of 5	\$442	38,984
Distribution Main	5394	P-2430	WAR	New England Way	8	Asbestos Cement	248	52	1.14 out of 5	\$442	109,658
Distribution Main	5489	P-2429	WAR	New England Way	8	Asbestos Cement	432	52	1.14 out of 5	\$442	191,155
Distribution Main	6096	P-2320	WAR	Nicolas Ln.	8	Ductile Iron	53	24	0.14 out of 5	N/A	\$0
Distribution Main	6097	P-2320	WAR	Nicolas Ln.	8	Ductile Iron	231	24	0.14 out of 5	N/A	\$0
Distribution Main	6098	P-2318	WAR	Nicolas Ln.	8	Ductile Iron	4	24	0.14 out of 5	N/A	\$0
Distribution Main	6099	P-2318	WAR	Nicolas Ln.	8	Ductile Iron	228	24	0.14 out of 5	N/A	\$0
Distribution Main	6105	P-2317	WAR	Nicolas Ln.	8	Ductile Iron	389	24	0.14 out of 5	N/A	\$0
Distribution Main	4233	P-2154	WAR	North Winnisquam Dr.	8	PVC	163	31	0.43 out of 5	\$442	71,855
Distribution Main	5473		WAR	North Winnisquam Dr.	8	PVC	47	31	0.43 out of 5	\$442	20,767
Distribution Main	6985	P-2513	WAR	Northbridge Ave.	8	Asbestos Cement	588	57	1.14 out of 5	\$442	260,018
Distribution Main	6986	P-2514	WAR	Northbridge Ave.	8	Asbestos Cement	55	57	1.14 out of 5	\$442	24,521
Distribution Main	6987	P-2514	WAR	Northbridge Ave.	8	Asbestos Cement	817	57	1.14 out of 5	\$442	361,155
Distribution Main	10546	P-2437	WAR	Oak Grove Av	8	Ductile Iron	299	2	0 out of 5	N/A	\$0
Distribution Main	10547	P-2437	WAR	Oak Grove Av	8	Ductile Iron	44	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10710		WAR	Oak Grove Av	6	Ductile Iron	9	2	0.71 out of 5	N/A	\$0
Distribution Main	11354	P-2437	WAR	Oak Grove Av	8	Ductile Iron	9	2	0 out of 5	N/A	\$0
Distribution Main	6863	P-2439	WAR	Oak Grove St.	8	Ductile Iron	230	35	0.14 out of 5	\$442	101,556
Distribution Main	11353	P-2439	WAR	Oak Grove St.	8	Ductile Iron	174	35	0.14 out of 5	\$442	76,861
Distribution Main	4541	P-2627	WAR	Oak St.	4	Cast Iron	195	109	3.29 out of 5	\$442	86,190
Distribution Main	4542	P-2627	WAR	Oak St.	4	Cast Iron	10	109	3.29 out of 5	\$442	4,499
Distribution Main	5562	P-2627	WAR	Oak St.	4	Cast Iron	14	109	3.29 out of 5	\$442	6,226
Distribution Main	5573	P-2629	WAR	Oak St.	8	Ductile Iron	178	29	0.14 out of 5	\$442	78,807
Distribution Main	5574	P-2629	WAR	Oak St.	8	Ductile Iron	43	29	0.14 out of 5	\$442	18,898
Distribution Main	7039	P-2629	WAR	Oak St.	8	Ductile Iron	15	29	0.14 out of 5	\$442	6,477
Distribution Main	11256	P-2627	WAR	Oak St.	4	Cast Iron	9	109	3.29 out of 5	\$442	3,818
Distribution Main	6600	P-2731	WAR	Oberlin Dr.	8	Ductile Iron	265	18	0 out of 5	N/A	\$0
Distribution Main	6602	P-2732	WAR	Oberlin Dr.	8	Ductile Iron	539	18	0 out of 5	N/A	\$0
Distribution Main	7187	P-2089	WAR	Oberlin Dr.	8	Ductile Iron	453	18	0 out of 5	N/A	\$0
Distribution Main	7054	P-2920	WAR	Octave Street	8	Ductile Iron	59	19	0 out of 5	N/A	\$0
Distribution Main	9864	P-2564	WAR	Odonnell Ave	8	Ductile Iron	356	7	0 out of 5	N/A	\$0
Distribution Main	9865	P-2564	WAR	Odonnell Ave	8	Ductile Iron	19	7	0 out of 5	N/A	\$0
Distribution Main	9870	P-2867	WAR	Odonnell Ave	8	Ductile Iron	117	7	0 out of 5	N/A	\$0
Distribution Main	10415	P-2563	WAR	Odonnell Ave	8	Ductile Iron	41	7	0 out of 5	N/A	\$0
Distribution Main	12117	P-2866	WAR	Odonnell Ave	8	Ductile Iron	64	7	0 out of 5	N/A	\$0
Distribution Main	9287	P-2869	WAR	Old East Ave	8	Ductile Iron	23	11	0 out of 5	N/A	\$0
Distribution Main	9288	P-2869	WAR	Old East Ave	8	Ductile Iron	7	11	0 out of 5	N/A	\$0
Distribution Main	7001	P-2536	WAR	Old East Ave.	6	Asbestos Cement	11	62	2 out of 5	\$442	5,006
Distribution Main	7005	P-2532	WAR	Old East Ave.	8	Asbestos Cement	227	62	1.29 out of 5	\$442	100,305
Distribution Main	7074	P-2534	WAR	Old East Ave.	8	Asbestos Cement	223	62	1.29 out of 5	\$442	98,476
Distribution Main	7075	P-2534	WAR	Old East Ave.	8	Asbestos Cement	23	62	1.29 out of 5	\$442	10,228
Distribution Main	4876	P-2203	WAR	Old Lyme Dr.	8	Asbestos Cement	428	59	1.14 out of 5	\$442	188,962
Distribution Main	4227	P-2198	WAR	Old Oak Dr.	8	Asbestos Cement	537	52	1.14 out of 5	\$442	237,369
Distribution Main	8996		WAR	Old Quaker Ln	10	Asbestos Cement	139	UNK	0.85 out of 5	\$442	61,238
Distribution Main	8999	P-4707	WAR	Old Quaker Ln	8	Ductile Iron	301	16	0 out of 5	N/A	\$0
Distribution Main	9000		WAR	Old Quaker Ln	4	Ductile Iron	29	16	1.42 out of 5	N/A	\$0
Distribution Main	9002	P-4707	WAR	Old Quaker Ln	8	Ductile Iron	212	16	0 out of 5	N/A	\$0
Distribution Main	11536		WAR	Old Quaker Ln	10	Asbestos Cement	25	UNK	0.85 out of 5	\$442	11,112
Distribution Main	11538	P-4707	WAR	Old Quaker Ln	8	Ductile Iron	16	16	0 out of 5	N/A	\$0
Distribution Main	5226	P-2499	WAR	Ontario Ave.	6	Asbestos Cement	231	64	2 out of 5	\$442	102,141
Distribution Main	3599	P-2720	WAR	Orchard Ave.	8	Ductile Iron	958	1	0 out of 5	N/A	\$0
Distribution Main	3600	P-2720	WAR	Orchard Ave.	8	Ductile Iron	26	1	0 out of 5	N/A	\$0
Distribution Main	10703		WAR	Orchard Ave.	8	Ductile Iron	442	1	0 out of 5	N/A	\$0
Distribution Main	364	P-2042	WAR	Orient St.	8	Ductile Iron	358	18	0 out of 5	N/A	\$0
Distribution Main	368	P-2042	WAR	Orient St.	8	Ductile Iron	229	18	0 out of 5	N/A	\$0
Distribution Main	7027	P-2726	WAR	Osborne St.	8	Asbestos Cement	44	55	1.14 out of 5	\$442	19,358
Distribution Main	7063	P-2726	WAR	Osborne St.	6	Asbestos Cement	158	55	1.85 out of 5	\$442	69,918
Distribution Main	5497	P-2584	WAR	Overhill Rd.	6	Cast Iron	845	133	2.57 out of 5	\$442	373,471
Distribution Main	5498	P-2584	WAR	Overhill Rd.	6	Cast Iron	33	133	2.57 out of 5	\$442	14,662

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6835	P-2584	WAR	Overhill Rd.	6	Cast Iron	10	133	2.57 out of 5	\$442	4,310
Distribution Main	6929	P-2584	WAR	Overhill Rd.	6	Cast Iron	2	133	2.57 out of 5	\$442	799
Distribution Main	11948	P-2584	WAR	Overhill Rd.	6	Cast Iron	433	133	2.57 out of 5	\$442	191,546
Distribution Main	7230	P-2171	WAR	Paddock Dr.	8	Asbestos Cement	52	39	1 out of 5	\$442	23,099
Distribution Main	7231	P-2171	WAR	Paddock Dr.	8	Asbestos Cement	873	39	1 out of 5	\$442	385,986
Distribution Main	11953	P-2171	WAR	Paddock Dr.	8	Asbestos Cement	55	39	1 out of 5	\$442	24,508
Distribution Main	10775	P-2679	WAR	Panto St	8	Ductile Iron	175	0	0 out of 5	N/A	\$0
Distribution Main	10776	P-2637	WAR	Panto St	8	Ductile Iron	352	0	0 out of 5	N/A	\$0
Distribution Main	10777	P-2637	WAR	Panto St	8	Ductile Iron	290	0	0 out of 5	N/A	\$0
Distribution Main	10923	P-2636	WAR	Panto St	8	Ductile Iron	289	0	0 out of 5	N/A	\$0
Distribution Main	7318	P-2123	WAR	Pasco Cir.	8	PVC	626	31	0.43 out of 5	\$442	276,843
Distribution Main	9046	P-2933	WAR	Patrick Way	8	Ductile Iron	293	15	0 out of 5	N/A	\$0
Distribution Main	9047	P-2933	WAR	Patrick Way	8	Ductile Iron	173	15	0 out of 5	N/A	\$0
Distribution Main	7109	P-2334	WAR	Patterson Ave.	6	Asbestos Cement	5	73	2 out of 5	\$442	2,363
Distribution Main	7115	P-2341	WAR	Patterson Ave.	6	Asbestos Cement	344	73	2 out of 5	\$442	152,091
Distribution Main	7328	P-2340	WAR	Patterson Ave.	6	Asbestos Cement	347	73	2 out of 5	\$442	153,209
Distribution Main	7332	P-2334	WAR	Patterson Ave.	6	Asbestos Cement	72	73	2 out of 5	\$442	31,663
Distribution Main	7333	P-2334	WAR	Patterson Ave.	6	Asbestos Cement	451	73	2 out of 5	\$442	199,144
Distribution Main	7345	P-2341	WAR	Patterson Ave.	6	Asbestos Cement	16	73	2 out of 5	\$442	6,874
Distribution Main	5581	P-2607	WAR	Paul Ave.	6	Asbestos Cement	233	73	2 out of 5	\$442	103,007
Distribution Main	6421	P-2608	WAR	Paul Ave.	6	Asbestos Cement	75	73	2 out of 5	\$442	33,099
Distribution Main	6422	P-2608	WAR	Paul Ave.	6	Asbestos Cement	56	73	2 out of 5	\$442	24,727
Distribution Main	9921	P-2608	WAR	Paul Ave.	6	Ductile Iron	121	29	0.85 out of 5	\$442	53,596
Distribution Main	6681	P-2179	WAR	Peaceful Ln.	8	Ductile Iron	291	21	0.14 out of 5	N/A	\$0
Distribution Main	6682	P-2179	WAR	Peaceful Ln.	8	Ductile Iron	76	21	0.14 out of 5	N/A	\$0
Distribution Main	4228	P-2714	WAR	Peacock Rd.	8	Ductile Iron	23	27	0.14 out of 5	\$442	10,229
Distribution Main	4229	P-2714	WAR	Peacock Rd.	8	Ductile Iron	446	27	0.14 out of 5	\$442	197,250
Distribution Main	4230	P-2934	WAR	Peacock Rd.	8	Asbestos Cement	198	47	1.14 out of 5	\$442	87,700
Distribution Main	9489	P-2713	WAR	Peacock Rd.	8	Ductile Iron	184	27	0.14 out of 5	\$442	81,230
Distribution Main	5968	P-2102	WAR	Pender John Ct.	8	Ductile Iron	170	22	0.14 out of 5	N/A	\$0
Distribution Main	5979	P-2102	WAR	Pender John Ct.	8	Ductile Iron	333	22	0.14 out of 5	N/A	\$0
Distribution Main	6964	P-2010	WAR	Pitman Rd.	6	Asbestos Cement	951	59	1.85 out of 5	\$442	420,185
Distribution Main	6965	P-2010	WAR	Pitman Rd.	6	Asbestos Cement	45	59	1.85 out of 5	\$442	19,939
Distribution Main	5453	P-2503	WAR	Plantation St.	6	Asbestos Cement	2	60	1.85 out of 5	\$442	904
Distribution Main	5454	P-2503	WAR	Plantation St.	6	Asbestos Cement	590	60	1.85 out of 5	\$442	260,591
Distribution Main	6983	P-2503	WAR	Plantation St.	6	Asbestos Cement	290	60	1.85 out of 5	\$442	127,979
Distribution Main	5559	P-2620	WAR	Pleasant St.	4	Cast Iron	354	109	3.29 out of 5	\$442	156,300
Distribution Main	5560	P-2911	WAR	Pleasant St.	2	Copper	203	29	2.14 out of 5	\$442	89,716
Distribution Main	5561	P-2630	WAR	Pleasant St.	8	Ductile Iron	420	29	0.14 out of 5	\$442	185,473
Distribution Main	10539	P-2444	WAR	Plymouth St	8	Ductile Iron	336	2	0 out of 5	N/A	\$0
Distribution Main	10540	P-2444	WAR	Plymouth St	8	Ductile Iron	136	2	0 out of 5	N/A	\$0
Distribution Main	11671	P-2444	WAR	Plymouth St	8	Ductile Iron	27	2	0 out of 5	N/A	\$0
Distribution Main	7070	P-2492	WAR	Pond View Dr.	6	Asbestos Cement	302	47	1.85 out of 5	\$442	133,700
Distribution Main	7071	P-2492	WAR	Pond View Dr.	6	Asbestos Cement	163	47	1.85 out of 5	\$442	72,091

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10742	P-2554	WAR	Pontiac St	8	Ductile Iron	528	1	0 out of 5	N/A	\$0
Distribution Main	10743	P-2557	WAR	Pontiac St	8	Ductile Iron	263	1	0 out of 5	N/A	\$0
Distribution Main	11716	P-2554	WAR	Pontiac St	8	Ductile Iron	35	1	0 out of 5	N/A	\$0
Distribution Main	11718	P-2555	WAR	Pontiac St	8	Ductile Iron	306	1	0 out of 5	N/A	\$0
Distribution Main	7245	P-2454	WAR	Poppy Pl.	8	Ductile Iron	211	23	0.14 out of 5	N/A	\$0
Distribution Main	7246	P-2454	WAR	Poppy Pl.	8	Ductile Iron	11	23	0.14 out of 5	N/A	\$0
Transmission Main	9203	P-2376	WAR	Post Rd	16	Ductile Iron	3	8	0 out of 5	N/A	\$0
Distribution Main	9315		WAR	Post Rd	6	Ductile Iron	2	10	0.71 out of 5	N/A	\$0
Distribution Main	9316		WAR	Post Rd	6	Ductile Iron	36	10	0.71 out of 5	N/A	\$0
Distribution Main	9333		WAR	Post Rd	4	Ductile Iron	25	9	1.42 out of 5	N/A	\$0
Transmission Main	9884	P-4269	WAR	Post Rd	12	Unknown	41	UNK	0 out of 5	N/A	\$0
Transmission Main	9886		WAR	Post Rd	12	Unknown	2	UNK	0 out of 5	N/A	\$0
Distribution Main	10754	P-2614	WAR	Post Rd	8	Ductile Iron	410	2	0 out of 5	N/A	\$0
Distribution Main	10755	P-2614	WAR	Post Rd	8	Ductile Iron	360	2	0 out of 5	N/A	\$0
Distribution Main	10758		WAR	Post Rd	8	Ductile Iron	257	2	0 out of 5	N/A	\$0
Distribution Main	10759	P-2912	WAR	Post Rd	8	Ductile Iron	630	2	0 out of 5	N/A	\$0
Distribution Main	10760	P-2912	WAR	Post Rd	8	Ductile Iron	186	2	0 out of 5	N/A	\$0
Distribution Main	10943	P-2619	WAR	Post Rd	8	Ductile Iron	235	2	0 out of 5	N/A	\$0
Distribution Main	10944	P-2619	WAR	Post Rd	8	Ductile Iron	61	2	0 out of 5	N/A	\$0
Distribution Main	10945	P-2618	WAR	Post Rd	8	Ductile Iron	163	2	0 out of 5	N/A	\$0
Distribution Main	10946	P-2617	WAR	Post Rd	8	Ductile Iron	223	2	0 out of 5	N/A	\$0
Transmission Main	11196	P-4269	WAR	Post Rd	12	Unknown	11	UNK	0 out of 5	N/A	\$0
Distribution Main	12191	P-2618	WAR	Post Rd	8	Ductile Iron	86	2	0 out of 5	N/A	\$0
Distribution Main	12199	P-2614	WAR	Post Rd	8	Ductile Iron	206	2	0 out of 5	N/A	\$0
Distribution Main	12217	P-2912	WAR	Post Rd	8	Ductile Iron	64	2	0 out of 5	N/A	\$0
Distribution Main	12225		WAR	Post Rd	8	Ductile Iron	113	2	0 out of 5	N/A	\$0
Distribution Main	12226	P-2619	WAR	Post Rd	8	Ductile Iron	32	2	0 out of 5	N/A	\$0
Distribution Main	12228	P-2619	WAR	Post Rd	8	Ductile Iron	83	2	0 out of 5	N/A	\$0
Transmission Main	2237	P-2353	WAR	Post Rd.	16	Ductile Iron	17	20	0 out of 5	N/A	\$0
Transmission Main	2250	P-2376	WAR	Post Rd.	16	Ductile Iron	369	20	0 out of 5	N/A	\$0
Transmission Main	2251	P-2958	WAR	Post Rd.	16	Ductile Iron	26	20	0 out of 5	N/A	\$0
Transmission Main	2252	P-2958	WAR	Post Rd.	16	Ductile Iron	10	20	0 out of 5	N/A	\$0
Transmission Main	4518	P-2347	WAR	Post Rd.	16	Ductile Iron	15	20	0 out of 5	N/A	\$0
Transmission Main	4540	P-4563	WAR	Post Rd.	16	Ductile Iron	12	20	0 out of 5	N/A	\$0
Transmission Main	4553	P-2704	WAR	Post Rd.	12	Cast Iron	200	91	1.72 out of 5	\$442	88,180
Transmission Main	4581	P-2705	WAR	Post Rd.	12	Cast Iron	133	91	1.72 out of 5	\$442	58,707
Distribution Main	4582	P-2706	WAR	Post Rd.	8	Cast Iron	21	91	1.72 out of 5	\$442	9,287
Distribution Main	4583	P-2703	WAR	Post Rd.	8	Cast Iron	23	129	1.86 out of 5	\$442	10,213
Transmission Main	5016	P-2364	WAR	Post Rd.	16	Ductile Iron	526	20	0 out of 5	N/A	\$0
Transmission Main	5017	P-2364	WAR	Post Rd.	16	Ductile Iron	27	20	0 out of 5	N/A	\$0
Transmission Main	5020	P-2364	WAR	Post Rd.	16	Ductile Iron	450	20	0 out of 5	N/A	\$0
Transmission Main	5021	P-2364	WAR	Post Rd.	16	Ductile Iron	84	20	0 out of 5	N/A	\$0
Transmission Main	5038	P-4891	WAR	Post Rd.	16	Ductile Iron	43	20	0 out of 5	N/A	\$0
Transmission Main	5210	P-2422	WAR	Post Rd.	16	Ductile Iron	16	20	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	5212	P-2482	WAR	Post Rd.	16	Ductile Iron	18	20	0 out of 5	N/A	\$0
Transmission Main	5216	P-2482	WAR	Post Rd.	16	Ductile Iron	148	20	0 out of 5	N/A	\$0
Transmission Main	5455	P-2365	WAR	Post Rd.	16	Ductile Iron	29	20	0 out of 5	N/A	\$0
Distribution Main	5571	P-2610	WAR	Post Rd.	8	Cast Iron	119	120	1.86 out of 5	\$442	52,704
Distribution Main	5572	P-2626	WAR	Post Rd.	2	Copper	246	73	2.43 out of 5	\$442	108,577
Transmission Main	5642	P-2478	WAR	Post Rd.	16	Ductile Iron	15	20	0 out of 5	N/A	\$0
Transmission Main	5700	P-2480	WAR	Post Rd.	16	Ductile Iron	76	20	0 out of 5	N/A	\$0
Transmission Main	6072	P-2458	WAR	Post Rd.	16	Ductile Iron	222	20	0 out of 5	N/A	\$0
Transmission Main	6073	P-2458	WAR	Post Rd.	16	Ductile Iron	457	20	0 out of 5	N/A	\$0
Transmission Main	6284	P-2373	WAR	Post Rd.	16	Ductile Iron	17	20	0 out of 5	N/A	\$0
Transmission Main	6285	P-2375	WAR	Post Rd.	16	Ductile Iron	595	20	0 out of 5	N/A	\$0
Transmission Main	6412		WAR	Post Rd.	12	Unknown	16	UNK	0 out of 5	N/A	\$0
Transmission Main	6413	P-2928	WAR	Post Rd.	16	Ductile Iron	55	20	0 out of 5	N/A	\$0
Transmission Main	6416	P-2458	WAR	Post Rd.	16	Ductile Iron	6	20	0 out of 5	N/A	\$0
Transmission Main	6428	P-2458	WAR	Post Rd.	16	Ductile Iron	24	20	0 out of 5	N/A	\$0
Transmission Main	6431	P-2783	WAR	Post Rd.	16	Ductile Iron	12	20	0 out of 5	N/A	\$0
Transmission Main	6432	P-2474	WAR	Post Rd.	16	Ductile Iron	17	20	0 out of 5	N/A	\$0
Transmission Main	6433	P-2925	WAR	Post Rd.	16	Ductile Iron	57	20	0 out of 5	N/A	\$0
Transmission Main	6434	P-2478	WAR	Post Rd.	16	Ductile Iron	179	20	0 out of 5	N/A	\$0
Transmission Main	6435	P-2478	WAR	Post Rd.	16	Ductile Iron	67	20	0 out of 5	N/A	\$0
Transmission Main	6436	P-2480	WAR	Post Rd.	16	Ductile Iron	21	20	0 out of 5	N/A	\$0
Transmission Main	6437	P-2460	WAR	Post Rd.	16	Ductile Iron	142	20	0 out of 5	N/A	\$0
Transmission Main	6438	P-2460	WAR	Post Rd.	16	Ductile Iron	108	20	0 out of 5	N/A	\$0
Transmission Main	6504	P-2368	WAR	Post Rd.	16	Ductile Iron	31	20	0 out of 5	N/A	\$0
Transmission Main	6505	P-2368	WAR	Post Rd.	16	Ductile Iron	196	20	0 out of 5	N/A	\$0
Transmission Main	6506	P-2449	WAR	Post Rd.	16	Ductile Iron	174	20	0 out of 5	N/A	\$0
Transmission Main	6507	P-2369	WAR	Post Rd.	16	Ductile Iron	129	20	0 out of 5	N/A	\$0
Transmission Main	6509	P-2366	WAR	Post Rd.	16	Ductile Iron	13	20	0 out of 5	N/A	\$0
Transmission Main	6513	P-2365	WAR	Post Rd.	16	Ductile Iron	487	20	0 out of 5	N/A	\$0
Transmission Main	6514	P-2365	WAR	Post Rd.	16	Ductile Iron	13	20	0 out of 5	N/A	\$0
Transmission Main	6518	P-2928	WAR	Post Rd.	16	Ductile Iron	26	20	0 out of 5	N/A	\$0
Transmission Main	6520		WAR	Post Rd.	12	Unknown	5	UNK	0 out of 5	N/A	\$0
Transmission Main	6670	P-2364	WAR	Post Rd.	16	Ductile Iron	26	20	0 out of 5	N/A	\$0
Transmission Main	6772	P-2375	WAR	Post Rd.	16	Ductile Iron	12	20	0 out of 5	N/A	\$0
Distribution Main	6817		WAR	Post Rd.	6	Unknown	29	UNK	0.71 out of 5	\$442	12,934
Distribution Main	6818		WAR	Post Rd.	6	Unknown	4	UNK	0.71 out of 5	\$442	1,624
Transmission Main	6819	P-2372	WAR	Post Rd.	16	Ductile Iron	41	20	0 out of 5	N/A	\$0
Transmission Main	6820	P-2372	WAR	Post Rd.	16	Ductile Iron	20	20	0 out of 5	N/A	\$0
Transmission Main	6821	P-2370	WAR	Post Rd.	16	Ductile Iron	256	20	0 out of 5	N/A	\$0
Transmission Main	6822	P-2370	WAR	Post Rd.	16	Ductile Iron	382	20	0 out of 5	N/A	\$0
Transmission Main	6829	P-2371	WAR	Post Rd.	16	Ductile Iron	7	20	0 out of 5	N/A	\$0
Transmission Main	6830	P-2371	WAR	Post Rd.	16	Ductile Iron	575	20	0 out of 5	N/A	\$0
Transmission Main	6836	P-2370	WAR	Post Rd.	16	Ductile Iron	35	20	0 out of 5	N/A	\$0
Transmission Main	6841	P-2570	WAR	Post Rd.	16	Ductile Iron	34	20	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	6842	P-2372	WAR	Post Rd.	16	Ductile Iron	5	20	0 out of 5	N/A	\$0
Transmission Main	6843	P-2372	WAR	Post Rd.	16	Ductile Iron	207	20	0 out of 5	N/A	\$0
Transmission Main	6844	P-2373	WAR	Post Rd.	16	Ductile Iron	204	20	0 out of 5	N/A	\$0
Transmission Main	6857	P-2692	WAR	Post Rd.	16	Ductile Iron	35	20	0 out of 5	N/A	\$0
Transmission Main	6858	P-2368	WAR	Post Rd.	16	Ductile Iron	6	20	0 out of 5	N/A	\$0
Transmission Main	6861	P-2366	WAR	Post Rd.	16	Ductile Iron	291	20	0 out of 5	N/A	\$0
Transmission Main	6862	P-2366	WAR	Post Rd.	16	Ductile Iron	207	20	0 out of 5	N/A	\$0
Transmission Main	6864	P-2692	WAR	Post Rd.	16	Ductile Iron	567	20	0 out of 5	N/A	\$0
Transmission Main	6870	P-2365	WAR	Post Rd.	16	Ductile Iron	34	20	0 out of 5	N/A	\$0
Transmission Main	6878	P-2371	WAR	Post Rd.	16	Ductile Iron	156	20	0 out of 5	N/A	\$0
Transmission Main	6882	P-2371	WAR	Post Rd.	16	Ductile Iron	32	20	0 out of 5	N/A	\$0
Transmission Main	6902	P-2373	WAR	Post Rd.	16	Ductile Iron	4	20	0 out of 5	N/A	\$0
Transmission Main	6910	P-2371	WAR	Post Rd.	16	Ductile Iron	12	20	0 out of 5	N/A	\$0
Transmission Main	6979	P-2699	WAR	Post Rd.	12	Cast Iron	25	91	1.72 out of 5	\$442	11,118
Distribution Main	6980	P-2610	WAR	Post Rd.	8	Cast Iron	79	120	1.86 out of 5	\$442	35,077
Distribution Main	7032	P-2610	WAR	Post Rd.	8	Cast Iron	36	120	1.86 out of 5	\$442	15,891
Transmission Main	7035	P-2422	WAR	Post Rd.	16	Ductile Iron	315	20	0 out of 5	N/A	\$0
Transmission Main	7036	P-2422	WAR	Post Rd.	16	Ductile Iron	476	20	0 out of 5	N/A	\$0
Transmission Main	7037	P-2422	WAR	Post Rd.	16	Ductile Iron	690	20	0 out of 5	N/A	\$0
Transmission Main	7038	P-2422	WAR	Post Rd.	16	Ductile Iron	197	20	0 out of 5	N/A	\$0
Transmission Main	7051	P-2482	WAR	Post Rd.	16	Ductile Iron	137	20	0 out of 5	N/A	\$0
Transmission Main	7090	P-2783	WAR	Post Rd.	16	Ductile Iron	272	20	0 out of 5	N/A	\$0
Transmission Main	7091	P-2783	WAR	Post Rd.	16	Ductile Iron	149	20	0 out of 5	N/A	\$0
Transmission Main	7096	P-2458	WAR	Post Rd.	16	Ductile Iron	131	20	0 out of 5	N/A	\$0
Transmission Main	7101	P-2347	WAR	Post Rd.	16	Ductile Iron	331	20	0 out of 5	N/A	\$0
Transmission Main	7102	P-2347	WAR	Post Rd.	16	Ductile Iron	201	20	0 out of 5	N/A	\$0
Transmission Main	7103	P-2353	WAR	Post Rd.	16	Ductile Iron	86	20	0 out of 5	N/A	\$0
Transmission Main	7104	P-2353	WAR	Post Rd.	16	Ductile Iron	386	20	0 out of 5	N/A	\$0
Transmission Main	7105	P-2352	WAR	Post Rd.	16	Ductile Iron	135	20	0 out of 5	N/A	\$0
Transmission Main	7183	P-2364	WAR	Post Rd.	16	Ductile Iron	189	20	0 out of 5	N/A	\$0
Transmission Main	7249	P-2474	WAR	Post Rd.	16	Ductile Iron	224	20	0 out of 5	N/A	\$0
Transmission Main	7250	P-2472	WAR	Post Rd.	16	Ductile Iron	21	20	0 out of 5	N/A	\$0
Transmission Main	7290	P-2353	WAR	Post Rd.	16	Ductile Iron	10	20	0 out of 5	N/A	\$0
Transmission Main	7317	P-2458	WAR	Post Rd.	16	Ductile Iron	21	20	0 out of 5	N/A	\$0
Transmission Main	7329	P-2353	WAR	Post Rd.	16	Ductile Iron	9	20	0 out of 5	N/A	\$0
Transmission Main	7331	P-2352	WAR	Post Rd.	16	Ductile Iron	20	20	0 out of 5	N/A	\$0
Distribution Main	10484	P-2702	WAR	Post Rd.	8	Cast Iron	42	129	1.86 out of 5	\$442	18,429
Distribution Main	10485	P-2701	WAR	Post Rd.	8	Cast Iron	253	129	1.86 out of 5	\$442	111,691
Transmission Main	10748	P-2704	WAR	Post Rd.	12	Cast Iron	124	91	1.72 out of 5	\$442	54,608
Distribution Main	10749		WAR	Post Rd.	8	Cast Iron	4	129	1.86 out of 5	\$442	1,909
Transmission Main	10914	P-2373	WAR	Post Rd.	16	Ductile Iron	7	20	0 out of 5	N/A	\$0
Transmission Main	10955	P-2375	WAR	Post Rd.	16	Ductile Iron	6	20	0 out of 5	N/A	\$0
Transmission Main	11313	P-2480	WAR	Post Rd.	16	Ductile Iron	8	20	0 out of 5	N/A	\$0
Transmission Main	11355	P-2371	WAR	Post Rd.	16	Ductile Iron	105	20	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11357	P-2783	WAR	Post Rd.	16	Ductile Iron	25	20	0 out of 5	N/A	\$0
Transmission Main	11359	P-2347	WAR	Post Rd.	16	Ductile Iron	60	20	0 out of 5	N/A	\$0
Distribution Main	11664	P-2702	WAR	Post Rd.	8	Cast Iron	46	129	1.86 out of 5	\$442	20,508
Distribution Main	11933	P-2701	WAR	Post Rd.	8	Cast Iron	56	129	1.86 out of 5	\$442	24,625
Transmission Main	11949	P-2365	WAR	Post Rd.	16	Ductile Iron	386	20	0 out of 5	N/A	\$0
Transmission Main	11968	P-2353	WAR	Post Rd.	16	Ductile Iron	55	20	0 out of 5	N/A	\$0
Transmission Main	11969	P-2422	WAR	Post Rd.	16	Ductile Iron	32	20	0 out of 5	N/A	\$0
Transmission Main	12212	P-2364	WAR	Post Rd.	16	Ductile Iron	3	20	0 out of 5	N/A	\$0
Transmission Main	12236		WAR	Post Rd.	12	Cast Iron	274	91	1.72 out of 5	\$442	121,080
Distribution Main	5558	P-2691	WAR	Prospect St.	8	Ductile Iron	360	29	0.14 out of 5	\$442	159,270
Distribution Main	5563	P-2628	WAR	Prospect St.	8	Ductile Iron	329	29	0.14 out of 5	\$442	145,265
Distribution Main	5564	P-2628	WAR	Prospect St.	8	Ductile Iron	31	29	0.14 out of 5	\$442	13,839
Distribution Main	9344		WAR	Providence St	6	Ductile Iron	24	8	0.71 out of 5	N/A	\$0
Distribution Main	9345		WAR	Providence St	6	Ductile Iron	36	8	0.71 out of 5	N/A	\$0
Distribution Main	9866	P-1762	WAR	Providence St	8	Ductile Iron	13	7	0 out of 5	N/A	\$0
Distribution Main	5026	P-2072	WAR	Quaid Ln.	8	Asbestos Cement	280	54	1.14 out of 5	\$442	123,659
Distribution Main	5027	P-2072	WAR	Quaid Ln.	8	Asbestos Cement	38	54	1.14 out of 5	\$442	16,799
Distribution Main	7239	P-2070	WAR	Quaid Ln.	8	Asbestos Cement	385	54	1.14 out of 5	\$442	170,045
Distribution Main	7240	P-2070	WAR	Quaid Ln.	8	Asbestos Cement	47	54	1.14 out of 5	\$442	20,820
Distribution Main	3538		WAR	Quail Ridge Lane	8	Ductile Iron	3	UNK	0 out of 5	N/A	\$0
Distribution Main	8521	P-2894	WAR	Quaker Lane	6	Ductile Iron	44	20	0.71 out of 5	N/A	\$0
Transmission Main	463	P-4711	WAR	Quaker Ln.	12	Asbestos Cement	12	50	1.14 out of 5	\$442	5,255
Transmission Main	978	P-2196	WAR	Quaker Ln.	20	Asbestos Cement	73	50	1.14 out of 5	\$442	32,050
Transmission Main	979	P-2196	WAR	Quaker Ln.	20	Asbestos Cement	819	50	1.14 out of 5	\$442	361,919
Transmission Main	1873	P-2698	WAR	Quaker Ln.	20	Asbestos Cement	14	50	1.14 out of 5	\$442	6,054
Transmission Main	1874	P-2698	WAR	Quaker Ln.	20	Asbestos Cement	917	50	1.14 out of 5	\$442	405,338
Transmission Main	3417	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	87	39	1 out of 5	\$442	38,569
Transmission Main	3418	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	526	39	1 out of 5	\$442	232,531
Transmission Main	3419	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	671	39	1 out of 5	\$442	296,738
Transmission Main	3420	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	244	39	1 out of 5	\$442	107,875
Transmission Main	3421	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	79	39	1 out of 5	\$442	35,100
Transmission Main	3422	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	257	39	1 out of 5	\$442	113,537
Transmission Main	3423	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	95	39	1 out of 5	\$442	41,893
Transmission Main	3424	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	67	39	1 out of 5	\$442	29,772
Transmission Main	3425	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	214	39	1 out of 5	\$442	94,659
Transmission Main	3426	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	80	39	1 out of 5	\$442	35,519
Transmission Main	3427	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	276	39	1 out of 5	\$442	122,121
Transmission Main	3430	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	72	39	1 out of 5	\$442	32,028
Transmission Main	3431	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	46	39	1 out of 5	\$442	20,448
Transmission Main	3543	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	879	39	1.14 out of 5	\$442	388,374
Transmission Main	3544	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	347	39	1 out of 5	\$442	153,292
Transmission Main	3809	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	10	39	1.14 out of 5	\$442	4,241
Transmission Main	4216	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	675	39	1 out of 5	\$442	298,467
Transmission Main	4217	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	540	39	1 out of 5	\$442	238,707

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	4774	P-2188	WAR	Quaker Ln.	16	Asbestos Cement	13	39	1 out of 5	\$442	5,559
Transmission Main	5075	P-2230	WAR	Quaker Ln.	24	Asbestos Cement	130	39	1 out of 5	\$442	57,408
Transmission Main	5076	P-2230	WAR	Quaker Ln.	24	Asbestos Cement	153	39	1 out of 5	\$442	67,636
Transmission Main	5091	P-2698	WAR	Quaker Ln.	20	Asbestos Cement	24	50	1.14 out of 5	\$442	10,471
Transmission Main	5651	P-4711	WAR	Quaker Ln.	20	Asbestos Cement	9	50	1.14 out of 5	\$442	3,842
Transmission Main	5652	P-4711	WAR	Quaker Ln.	20	Asbestos Cement	896	50	1.14 out of 5	\$442	396,009
Transmission Main	6331	P-4711	WAR	Quaker Ln.	12	Asbestos Cement	16	50	1.14 out of 5	\$442	7,149
Transmission Main	6516	P-4710	WAR	Quaker Ln.	20	Asbestos Cement	17	50	1.14 out of 5	\$442	7,330
Transmission Main	6517	P-4710	WAR	Quaker Ln.	20	Asbestos Cement	373	50	1.14 out of 5	\$442	165,070
Transmission Main	6811	P-4710	WAR	Quaker Ln.	20	Asbestos Cement	880	50	1.14 out of 5	\$442	388,987
Transmission Main	11218	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	168	39	1 out of 5	\$442	74,035
Transmission Main	11248	P-2188	WAR	Quaker Ln.	24	Asbestos Cement	38	39	1 out of 5	\$442	16,716
Transmission Main	11352	P-4710	WAR	Quaker Ln.	20	Asbestos Cement	5	50	1.14 out of 5	\$442	2,223
Transmission Main	12211	P-4710	WAR	Quaker Ln.	20	Asbestos Cement	143	50	1.14 out of 5	\$442	63,046
Distribution Main	7002	P-2533	WAR	Quinlan Ct.	1	Copper	45	62	2.43 out of 5	\$442	19,971
Distribution Main	7003	P-2533	WAR	Quinlan Ct.	1	Copper	166	62	2.43 out of 5	\$442	73,275
Distribution Main	10747	P-2560	WAR	Railroad Row	8	Ductile Iron	683	1	0 out of 5	N/A	\$0
Distribution Main	11719	P-2560	WAR	Railroad Row	8	Ductile Iron	16	1	0 out of 5	N/A	\$0
Distribution Main	2838	P-2940	WAR	Red Chimney Dr.	1.5	Copper	164	63	2.43 out of 5	\$442	72,310
Distribution Main	3310	P-2142	WAR	Red Chimney Dr.	8	Asbestos Cement	113	63	1.29 out of 5	\$442	49,929
Distribution Main	3621	P-2159	WAR	Red Chimney Dr.	8	Asbestos Cement	307	63	1.29 out of 5	\$442	135,771
Distribution Main	3629	P-2167	WAR	Red Chimney Dr.	8	Asbestos Cement	35	63	1.29 out of 5	\$442	15,521
Distribution Main	3634	P-2170	WAR	Red Chimney Dr.	8	Asbestos Cement	142	63	1.29 out of 5	\$442	62,960
Distribution Main	3635	P-2169	WAR	Red Chimney Dr.	8	Asbestos Cement	235	63	1.29 out of 5	\$442	104,088
Distribution Main	3636	P-2160	WAR	Red Chimney Dr.	8	Asbestos Cement	505	63	1.29 out of 5	\$442	223,072
Distribution Main	3637	P-2160	WAR	Red Chimney Dr.	8	Asbestos Cement	163	63	1.29 out of 5	\$442	71,848
Distribution Main	3638	P-2939	WAR	Red Chimney Dr.	8	Asbestos Cement	331	63	1.29 out of 5	\$442	146,418
Distribution Main	4241	P-2155	WAR	Red Chimney Dr.	8	Asbestos Cement	300	63	1.29 out of 5	\$442	132,787
Distribution Main	4869	P-2140	WAR	Red Chimney Dr.	8	Asbestos Cement	55	63	1.29 out of 5	\$442	24,139
Distribution Main	4871	P-2172	WAR	Red Chimney Dr.	8	Asbestos Cement	73	63	1.29 out of 5	\$442	32,110
Distribution Main	4872	P-2172	WAR	Red Chimney Dr.	8	Asbestos Cement	117	63	1.29 out of 5	\$442	51,533
Distribution Main	5754	P-2140	WAR	Red Chimney Dr.	8	Asbestos Cement	264	63	1.29 out of 5	\$442	116,744
Distribution Main	5755	P-2140	WAR	Red Chimney Dr.	8	Asbestos Cement	428	63	1.29 out of 5	\$442	189,054
Distribution Main	5761	P-2169	WAR	Red Chimney Dr.	8	Asbestos Cement	45	63	1.29 out of 5	\$442	19,825
Distribution Main	5763	P-2173	WAR	Red Chimney Dr.	8	Asbestos Cement	417	63	1.29 out of 5	\$442	184,201
Distribution Main	5764	P-2167	WAR	Red Chimney Dr.	8	Asbestos Cement	885	63	1.29 out of 5	\$442	391,000
Distribution Main	5765	P-2167	WAR	Red Chimney Dr.	8	Asbestos Cement	313	63	1.29 out of 5	\$442	138,321
Distribution Main	5771	P-2935	WAR	Red Chimney Dr.	8	Asbestos Cement	165	63	1.29 out of 5	\$442	72,723
Distribution Main	5772	P-2935	WAR	Red Chimney Dr.	8	Asbestos Cement	139	63	1.29 out of 5	\$442	61,239
Distribution Main	9488	P-2167	WAR	Red Chimney Dr.	8	Asbestos Cement	121	63	1.29 out of 5	\$442	53,683
Distribution Main	6444	P-2473	WAR	Reeland Ave.	6	Asbestos Cement	4	54	1.85 out of 5	\$442	1,638
Distribution Main	7247	P-2473	WAR	Reeland Ave.	6	Asbestos Cement	52	54	1.85 out of 5	\$442	23,029
Distribution Main	7248	P-2473	WAR	Reeland Ave.	6	Asbestos Cement	448	54	1.85 out of 5	\$442	198,174
Distribution Main	6954	P-2319	WAR	Remy Cir	8	Ductile Iron	37	24	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6955	P-2319	WAR	Remy Cir	8	Ductile Iron	367	24	0.14 out of 5	N/A	\$0
Distribution Main	6445	P-2459	WAR	Rice St.	6	Asbestos Cement	26	27	1.71 out of 5	\$442	11,549
Distribution Main	6446	P-2459	WAR	Rice St.	6	Asbestos Cement	295	27	1.71 out of 5	\$442	130,212
Distribution Main	7093	P-2459	WAR	Rice St.	6	Asbestos Cement	8	27	1.71 out of 5	\$442	3,415
Distribution Main	10459	P-2459	WAR	Rice St.	6	Ductile Iron	154	27	0.85 out of 5	\$442	68,047
Distribution Main	7242	P-2463	WAR	Rip Van Winkle Cir	8	Ductile Iron	88	18	0 out of 5	N/A	\$0
Distribution Main	6521	P-2466	WAR	Rip Van Winkle Cir.	8	Ductile Iron	771	18	0 out of 5	N/A	\$0
Distribution Main	6522	P-2466	WAR	Rip Van Winkle Cir.	8	Ductile Iron	106	18	0 out of 5	N/A	\$0
Distribution Main	4933		WAR	Riverdale Avenue	6	Unknown	101	UNK	0.71 out of 5	\$442	44,653
Distribution Main	9477	P-2926	WAR	Robin Hill Rd.	2	Unknown	203	UNK	1.42 out of 5	\$442	89,877
Distribution Main	5539	P-2246	WAR	Roelker Dr.	8	Asbestos Cement	299	55	1.14 out of 5	\$442	131,945
Distribution Main	6880	P-2246	WAR	Roelker Dr.	8	Asbestos Cement	7	55	1.14 out of 5	\$442	3,034
Distribution Main	6881	P-2246	WAR	Roelker Dr.	8	Asbestos Cement	243	55	1.14 out of 5	\$442	107,376
Distribution Main	10739	P-2553	WAR	Rossi St	8	Ductile Iron	332	1	0 out of 5	N/A	\$0
Distribution Main	9274	P-2887	WAR	Rutherford Ave	8	Ductile Iron	19	11	0 out of 5	N/A	\$0
Distribution Main	9275	P-2887	WAR	Rutherford Ave	8	Ductile Iron	2	11	0 out of 5	N/A	\$0
Distribution Main	9290	P-2887	WAR	Rutherford Ave	6	Ductile Iron	2	11	0.71 out of 5	N/A	\$0
Distribution Main	7018	P-2493	WAR	Rutherford Ave.	6	Asbestos Cement	68	69	2 out of 5	\$442	29,903
Distribution Main	7019	P-2493	WAR	Rutherford Ave.	6	Asbestos Cement	166	69	2 out of 5	\$442	73,493
Distribution Main	7020	P-2696	WAR	Rutherford Ave.	6	Asbestos Cement	472	69	2 out of 5	\$442	208,496
Distribution Main	7081	P-2493	WAR	Rutherford Ave.	6	Asbestos Cement	63	69	2 out of 5	\$442	27,878
Distribution Main	7083	P-2494	WAR	Rutherford Ave.	6	Asbestos Cement	288	69	2 out of 5	\$442	127,391
Distribution Main	7069	P-2697	WAR	Rutherford Ct.	6	Asbestos Cement	208	69	2 out of 5	\$442	91,999
Distribution Main	5258	P-2728	WAR	Sage Dr.	6	Asbestos Cement	244	50	1.85 out of 5	\$442	107,716
Distribution Main	5260	P-2052	WAR	Sage Dr.	6	Asbestos Cement	9	50	1.85 out of 5	\$442	4,052
Distribution Main	5261	P-2052	WAR	Sage Dr.	6	Asbestos Cement	114	50	1.85 out of 5	\$442	50,186
Distribution Main	6310	P-2727	WAR	Sage Dr.	6	Asbestos Cement	369	50	1.85 out of 5	\$442	163,169
Distribution Main	7236	P-2052	WAR	Sage Dr.	6	Asbestos Cement	311	50	1.85 out of 5	\$442	137,386
Distribution Main	11330	P-2727	WAR	Sage Dr.	6	Asbestos Cement	3	50	1.85 out of 5	\$442	1,343
Distribution Main	6810	P-2581	WAR	Sammartino Cir.	8	Asbestos Cement	2	43	1.14 out of 5	\$442	987
Distribution Main	6921	P-2582	WAR	Sammartino Cir.	8	Asbestos Cement	146	43	1.14 out of 5	\$442	64,583
Distribution Main	6927	P-2581	WAR	Sammartino Cir.	8	Asbestos Cement	499	43	1.14 out of 5	\$442	220,668
Distribution Main	2832	P-2736	WAR	Sandro Cir.	6	Asbestos Cement	162	65	2 out of 5	\$442	71,593
Distribution Main	3619	P-2734	WAR	Sandro Dr.	6	Asbestos Cement	259	65	2 out of 5	\$442	114,641
Distribution Main	5756	P-2735	WAR	Sandro Dr.	6	Asbestos Cement	11	65	2 out of 5	\$442	4,993
Distribution Main	5757	P-2735	WAR	Sandro Dr.	6	Asbestos Cement	556	65	2 out of 5	\$442	245,967
Distribution Main	4600	P-2228	WAR	Sandy Brook Ct.	8	PVC	111	29	0.43 out of 5	\$442	49,103
Distribution Main	5980	P-2048	WAR	Saxony Dr.	6	Asbestos Cement	517	57	1.85 out of 5	\$442	228,664
Distribution Main	5982	P-2056	WAR	Saxony Dr.	6	Asbestos Cement	62	57	1.85 out of 5	\$442	27,572
Distribution Main	7237	P-2056	WAR	Saxony Dr.	6	Asbestos Cement	564	57	1.85 out of 5	\$442	249,289
Distribution Main	7238	P-2056	WAR	Saxony Dr.	6	Asbestos Cement	33	57	1.85 out of 5	\$442	14,490
Distribution Main	7068	P-2510	WAR	Scarsdale St.	6	Asbestos Cement	291	67	2 out of 5	\$442	128,597
Distribution Main	7082	P-2509	WAR	Scarsdale St.	6	Asbestos Cement	412	67	2 out of 5	\$442	182,166
Distribution Main	9938	P-2510	WAR	Scarsdale St.	6	Asbestos Cement	30	67	2 out of 5	\$442	13,087

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11626	P-2510	WAR	Scarsdale St.	6	Asbestos Cement	21	67	2 out of 5	\$442	9,113
Transmission Main	10577		WAR	School Rd	12	Ductile Iron	53	2	0 out of 5	N/A	\$0
Distribution Main	7339	P-2350	WAR	Sea Breeze Ln.	6	Asbestos Cement	176	44	1.85 out of 5	\$442	77,743
Distribution Main	1351	P-120	WAR	Setian Ln.	8	Asbestos Cement	7	43	1.14 out of 5	\$442	3,209
Distribution Main	2328	P-120	WAR	Setian Ln.	8	Asbestos Cement	392	43	1.14 out of 5	\$442	173,436
Distribution Main	2329	P-120	WAR	Setian Ln.	8	Asbestos Cement	93	43	1.14 out of 5	\$442	40,935
Distribution Main	4601	P-2226	WAR	Shadowbrook Dr.	8	PVC	696	29	0.43 out of 5	\$442	307,717
Distribution Main	6661	P-2227	WAR	Shadowbrook Dr.	8	PVC	754	29	0.43 out of 5	\$442	333,189
Distribution Main	10135	P-2226	WAR	Shadowbrook Dr.	8	PVC	40	29	0.43 out of 5	\$442	17,701
Distribution Main	10136	P-2226	WAR	Shadowbrook Dr.	8	PVC	99	29	0.43 out of 5	\$442	43,968
Distribution Main	10137	P-2227	WAR	Shadowbrook Dr.	8	PVC	9	29	0.43 out of 5	\$442	3,963
Distribution Main	10138	P-2227	WAR	Shadowbrook Dr.	8	PVC	607	29	0.43 out of 5	\$442	268,337
Distribution Main	4536	P-2577	WAR	Shady Glen Dr.	6	Asbestos Cement	840	71	2 out of 5	\$442	371,429
Distribution Main	5635	P-2602	WAR	Shattock Ave.	6	Asbestos Cement	322	73	2 out of 5	\$442	142,421
Distribution Main	5636	P-2923	WAR	Shattock Ave.	6	Ductile Iron	220	73	1.14 out of 5	\$442	97,161
Distribution Main	5637	P-2923	WAR	Shattock Ave.	6	Ductile Iron	10	73	1.14 out of 5	\$442	4,357
Distribution Main	5710	P-2923	WAR	Shattock Ave.	6	Ductile Iron	15	73	1.14 out of 5	\$442	6,713
Distribution Main	6447	P-2461	WAR	Shenandoah Rd.	8	Ductile Iron	11	18	0 out of 5	N/A	\$0
Distribution Main	6527	P-2461	WAR	Shenandoah Rd.	8	Ductile Iron	535	18	0 out of 5	N/A	\$0
Distribution Main	6528	P-2461	WAR	Shenandoah Rd.	8	Ductile Iron	140	18	0 out of 5	N/A	\$0
Distribution Main	7094	P-2467	WAR	Shenandoah Rd.	8	Ductile Iron	550	18	0 out of 5	N/A	\$0
Distribution Main	7095	P-2467	WAR	Shenandoah Rd.	8	Ductile Iron	320	18	0 out of 5	N/A	\$0
Distribution Main	10950	P-2461	WAR	Shenandoah Rd.	8	Ductile Iron	5	18	0 out of 5	N/A	\$0
Distribution Main	11929	P-2461	WAR	Shenandoah Rd.	8	Ductile Iron	522	18	0 out of 5	N/A	\$0
Distribution Main	11930	P-2467	WAR	Shenandoah Rd.	8	Ductile Iron	227	18	0 out of 5	N/A	\$0
Distribution Main	4877	P-2938	WAR	Silent Drive	2	Copper	111	52	2.28 out of 5	\$442	48,873
Distribution Main	5904	P-2101	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	270	22	0.14 out of 5	N/A	\$0
Distribution Main	5977	P-2099	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	40	22	0.14 out of 5	N/A	\$0
Distribution Main	5978	P-2099	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	437	22	0.14 out of 5	N/A	\$0
Distribution Main	7180	P-2101	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	6	22	0.14 out of 5	N/A	\$0
Distribution Main	7293	P-2097	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	31	22	0.14 out of 5	N/A	\$0
Distribution Main	7294	P-2097	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	1,649	22	0.14 out of 5	N/A	\$0
Distribution Main	7295	P-2097	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	201	22	0.14 out of 5	N/A	\$0
Distribution Main	7296	P-2097	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	191	22	0.14 out of 5	N/A	\$0
Distribution Main	7297	P-2097	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	328	22	0.14 out of 5	N/A	\$0
Distribution Main	7299	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	97	22	0.14 out of 5	N/A	\$0
Distribution Main	7300	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	4	22	0.14 out of 5	N/A	\$0
Distribution Main	7301	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	363	22	0.14 out of 5	N/A	\$0
Distribution Main	7302	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Distribution Main	7307	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Distribution Main	7308	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	497	22	0.14 out of 5	N/A	\$0
Distribution Main	7311	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	401	22	0.14 out of 5	N/A	\$0
Distribution Main	7312	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	124	22	0.14 out of 5	N/A	\$0
Distribution Main	7315	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	276	22	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10202	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	88	22	0.14 out of 5	N/A	\$0
Distribution Main	10917	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	3	22	0.14 out of 5	N/A	\$0
Distribution Main	10918	P-2100	WAR	Sleepy Hollow Farm Dr.	8	Ductile Iron	147	22	0.14 out of 5	N/A	\$0
Distribution Main	3307	P-2217	WAR	Slient Dr.	8	Asbestos Cement	182	53	1.14 out of 5	\$442	80,441
Distribution Main	4878	P-2937	WAR	Slient Dr.	8	Asbestos Cement	207	53	1.14 out of 5	\$442	91,427
Distribution Main	10778	P-2638	WAR	Sophia Dr	8	Ductile Iron	459	0	0.71 out of 5	N/A	\$0
Distribution Main	10779	P-2638	WAR	Sophia Dr	8	Ductile Iron	530	0	0 out of 5	N/A	\$0
Distribution Main	2526	P-2579	WAR	Spencer Ave.	10	Cast Iron	50	129	1.86 out of 5	\$442	22,225
Distribution Main	2527	P-2579	WAR	Spencer Ave.	10	Cast Iron	470	129	1.86 out of 5	\$442	207,547
Distribution Main	4537	P-2579	WAR	Spencer Ave.	10	Cast Iron	141	129	1.86 out of 5	\$442	62,269
Distribution Main	5041	P-4968	WAR	Spencer Ave.	10	Cast Iron	28	129	1.86 out of 5	\$442	12,528
Distribution Main	6838	P-2593	WAR	Spencer Ave.	6	Cast Iron	350	83	2.43 out of 5	\$442	154,858
Distribution Main	6840	P-2586	WAR	Spencer Ave.	10	Cast Iron	259	129	1.86 out of 5	\$442	114,258
Distribution Main	6901	P-2585	WAR	Spencer Ave.	10	Cast Iron	824	129	1.86 out of 5	\$442	364,347
Distribution Main	6911	P-2593	WAR	Spencer Ave.	6	Cast Iron	19	83	2.43 out of 5	\$442	8,532
Distribution Main	6912	P-2593	WAR	Spencer Ave.	6	Cast Iron	350	83	2.43 out of 5	\$442	154,748
Distribution Main	6915	P-2580	WAR	Spencer Ave.	10	Cast Iron	182	129	1.86 out of 5	\$442	80,232
Distribution Main	6916	P-2580	WAR	Spencer Ave.	10	Cast Iron	406	129	1.86 out of 5	\$442	179,439
Distribution Main	6926	P-2586	WAR	Spencer Ave.	10	Cast Iron	40	129	1.86 out of 5	\$442	17,472
Distribution Main	7305	P-2742	WAR	Spencer Hill Ct.	8	Ductile Iron	57	22	0.14 out of 5	N/A	\$0
Distribution Main	7306	P-2742	WAR	Spencer Hill Ct.	8	Ductile Iron	282	22	0.14 out of 5	N/A	\$0
Distribution Main	7309	P-2741	WAR	Spencer Hill Ct.	8	Ductile Iron	122	22	0.14 out of 5	N/A	\$0
Distribution Main	4475	P-2080	WAR	Spinnaker Ln.	8	Ductile Iron	7	24	0.14 out of 5	N/A	\$0
Distribution Main	6532	P-2080	WAR	Spinnaker Ln.	8	Ductile Iron	416	24	0.14 out of 5	N/A	\$0
Distribution Main	7098	P-2080	WAR	Spinnaker Ln.	8	Ductile Iron	197	24	0.14 out of 5	N/A	\$0
Distribution Main	7099	P-2080	WAR	Spinnaker Ln.	8	Ductile Iron	173	24	0.14 out of 5	N/A	\$0
Distribution Main	4544	P-2624	WAR	Spruce St.	4	Cast Iron	357	109	3.29 out of 5	\$442	157,963
Distribution Main	5570	P-2625	WAR	Spruce St.	6	PVC	356	34	1.14 out of 5	\$442	157,239
Distribution Main	5640	P-2603	WAR	Staples Ave.	6	Asbestos Cement	833	73	2 out of 5	\$442	368,244
Distribution Main	5641	P-2603	WAR	Staples Ave.	6	Asbestos Cement	592	73	2 out of 5	\$442	261,609
Distribution Main	7050	P-2603	WAR	Staples Ave.	6	Asbestos Cement	7	73	2 out of 5	\$442	3,078
Distribution Main	7087	P-2604	WAR	Staples Ave.	6	Asbestos Cement	6	73	2 out of 5	\$442	2,681
Distribution Main	7088	P-2604	WAR	Staples Ave.	6	Asbestos Cement	592	73	2 out of 5	\$442	261,729
Distribution Main	2238	P-2930	WAR	Stiness Dr.	2	Copper	133	83	2.57 out of 5	\$442	58,929
Distribution Main	7110	P-2361	WAR	Stiness Dr.	2	Copper	408	83	2.57 out of 5	\$442	180,453
Distribution Main	7119	P-2358	WAR	Stiness Dr.	6	PVC	418	31	1.14 out of 5	\$442	184,925
Distribution Main	7120	P-2358	WAR	Stiness Dr.	6	PVC	130	31	1.14 out of 5	\$442	57,491
Distribution Main	7341	P-2930	WAR	Stiness Dr.	2	Copper	21	83	2.57 out of 5	\$442	9,242
Distribution Main	7344	P-2358	WAR	Stiness Dr.	6	PVC	10	31	1.14 out of 5	\$442	4,437
Distribution Main	3305	P-2213	WAR	Stubtoe Dr.	8	Asbestos Cement	358	52	1.14 out of 5	\$442	158,363
Distribution Main	3306	P-2214	WAR	Stubtoe Dr.	8	Asbestos Cement	429	52	1.14 out of 5	\$442	189,758
Distribution Main	5762	P-2193	WAR	Stubtoe Dr.	8	Asbestos Cement	522	52	1.14 out of 5	\$442	230,940
Distribution Main	4481	P-2078	WAR	Sturbridge Dr.	8	Asbestos Cement	5	40	1 out of 5	\$442	1,995
Distribution Main	5025	P-2074	WAR	Sturbridge Dr.	8	Asbestos Cement	449	40	1 out of 5	\$442	198,329

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	6530	P-2078	WAR	Sturbridge Dr.	8	Asbestos Cement	558	40	1 out of 5	\$442	246,524
Distribution Main	6531	P-2078	WAR	Sturbridge Dr.	8	Asbestos Cement	300	40	1 out of 5	\$442	132,735
Distribution Main	7367	P-2073	WAR	Sturbridge Dr.	8	Asbestos Cement	412	40	1 out of 5	\$442	182,043
Distribution Main	7368	P-2073	WAR	Sturbridge Dr.	8	Asbestos Cement	157	40	1 out of 5	\$442	69,427
Distribution Main	3899	P-137	WAR	Sturbridge Way	8	Ductile Iron	117	21	0.14 out of 5	N/A	\$0
Distribution Main	3900	P-137	WAR	Sturbridge Way	8	Ductile Iron	357	21	0.14 out of 5	N/A	\$0
Distribution Main	4829	P-137	WAR	Sturbridge Way	8	Ductile Iron	195	21	0.14 out of 5	N/A	\$0
Distribution Main	11762	P-137	WAR	Sturbridge Way	8	Ductile Iron	24	21	0.14 out of 5	N/A	\$0
Distribution Main	10746	P-2853	WAR	Sue St	8	Ductile Iron	223	1	0 out of 5	N/A	\$0
Distribution Main	5984	P-2055	WAR	Superior St.	8	Asbestos Cement	13	57	1.14 out of 5	\$442	5,638
Distribution Main	7360	P-2055	WAR	Superior St.	6	Asbestos Cement	327	57	1.85 out of 5	\$442	144,562
Distribution Main	10204	P-2057	WAR	Superior St.	6	Asbestos Cement	127	57	1.85 out of 5	\$442	55,970
Distribution Main	10205	P-2057	WAR	Superior St.	6	Asbestos Cement	221	57	1.85 out of 5	\$442	97,522
Distribution Main	8292	P-2289	WAR	Sutter Ave.	8	Ductile Iron	493	13	0 out of 5	N/A	\$0
Distribution Main	8293	P-2816	WAR	Sutter Ave.	8	Ductile Iron	142	14	0 out of 5	N/A	\$0
Distribution Main	8294	P-2816	WAR	Sutter Ave.	8	Ductile Iron	33	14	0 out of 5	N/A	\$0
Distribution Main	1434	P-1313	WAR	Sykes St.	4	Ductile Iron	9	20	1.42 out of 5	N/A	\$0
Distribution Main	2243	P-1313	WAR	Sykes St.	8	Ductile Iron	512	20	0 out of 5	N/A	\$0
Distribution Main	8280	P-2283	WAR	Tanner Ave.	8	Ductile Iron	794	13	0 out of 5	N/A	\$0
Distribution Main	8283	P-2817	WAR	Tanner Ave.	8	Ductile Iron	625	13	0 out of 5	N/A	\$0
Distribution Main	8284	P-2817	WAR	Tanner Ave.	8	Ductile Iron	84	13	0 out of 5	N/A	\$0
Distribution Main	9933	P-2284	WAR	Tanner Ave.	8	Ductile Iron	389	13	0 out of 5	N/A	\$0
Distribution Main	5490	P-2709	WAR	Taylor Ln.	8	Ductile Iron	82	16	0 out of 5	N/A	\$0
Distribution Main	5491	P-2709	WAR	Taylor Ln.	8	Ductile Iron	123	16	0 out of 5	N/A	\$0
Distribution Main	6429	P-2709	WAR	Taylor Ln.	8	Ductile Iron	8	16	0 out of 5	N/A	\$0
Transmission Main	6943	P-2187	WAR	Telmore Rd.	12	Asbestos Cement	894	46	1.14 out of 5	\$442	395,092
Transmission Main	6944	P-2187	WAR	Telmore Rd.	12	Asbestos Cement	141	46	1.14 out of 5	\$442	62,370
Distribution Main	9285	P-2870	WAR	Thames Ave	8	Ductile Iron	38	11	0 out of 5	N/A	\$0
Distribution Main	9286	P-2871	WAR	Thames Ave	2	HDPE	31	11	1.71 out of 5	N/A	\$0
Distribution Main	7013	P-2530	WAR	Thames Ave.	2	Copper	563	79	2.43 out of 5	\$442	248,784
Distribution Main	10740	P-2547	WAR	Tillinghast Av	6	Ductile Iron	17	1	0.71 out of 5	N/A	\$0
Distribution Main	10741	P-2547	WAR	Tillinghast Av	6	Ductile Iron	376	1	0.71 out of 5	N/A	\$0
Distribution Main	4384	P-2858	WAR	Tillinghast Ave	8	Ductile Iron	101	16	0 out of 5	N/A	\$0
Distribution Main	4385	P-2858	WAR	Tillinghast Ave	8	Ductile Iron	177	16	0 out of 5	N/A	\$0
Distribution Main	9415	P-2858	WAR	Tillinghast Ave	8	Ductile Iron	12	16	0 out of 5	N/A	\$0
Transmission Main	10698	WAR	WAR	Tillinghast Ave	42	Asbestos Cement	1,036	UNK	0.85 out of 5	\$442	457,926
Distribution Main	10733	P-2856	WAR	Tillinghast Ave	8	Ductile Iron	4	16	0 out of 5	N/A	\$0
Distribution Main	9043	P-2548	WAR	Tillinghast Ave Easement	8	Ductile Iron	15	16	0 out of 5	N/A	\$0
Distribution Main	11540	P-2858	WAR	Tillinghast Ave Easement	8	Ductile Iron	4	16	0 out of 5	N/A	\$0
Distribution Main	2979	P-2548	WAR	Tillinghast Ave.	6	Ductile Iron	519	16	0.71 out of 5	N/A	\$0
Distribution Main	7129	P-2545	WAR	Tillinghast Ave.	6	Ductile Iron	62	24	0.85 out of 5	N/A	\$0
Distribution Main	7130	P-2545	WAR	Tillinghast Ave.	6	Ductile Iron	513	24	0.85 out of 5	N/A	\$0
Distribution Main	10723	P-2545	WAR	Tillinghast Ave.	6	Ductile Iron	25	24	0.85 out of 5	N/A	\$0
Distribution Main	11361	P-2545	WAR	Tillinghast Ave.	6	Ductile Iron	59	24	0.85 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5769	P-2158	WAR	Timberline Rd.	8	Asbestos Cement	846	63	1.29 out of 5	\$442	373,742
Distribution Main	5770	P-2158	WAR	Timberline Rd.	8	Asbestos Cement	427	63	1.29 out of 5	\$442	188,759
Distribution Main	11938	P-2158	WAR	Timberline Rd.	8	Asbestos Cement	574	63	1.29 out of 5	\$442	253,763
Distribution Main	6525	P-2337	WAR	Tivoli Ct.	8	Ductile Iron	138	31	0.14 out of 5	\$442	60,988
Distribution Main	6526	P-2337	WAR	Tivoli Ct.	8	Ductile Iron	482	31	0.14 out of 5	\$442	213,079
Distribution Main	10176		WAR	Toll Gate Rd	4	Copper	34	17	1.99 out of 5	N/A	\$0
Distribution Main	3907		WAR	Tollgate Rd	2	Unknown	9	UNK	1.42 out of 5	\$442	3,911
Distribution Main	3908		WAR	Tollgate Rd	2	Unknown	7	UNK	1.42 out of 5	\$442	3,100
Distribution Main	9103		WAR	Tollgate Rd	2	Unknown	27	UNK	1.42 out of 5	\$442	12,116
Distribution Main	9976		WAR	Tollgate Rd	6	Ductile Iron	25	11	0.71 out of 5	N/A	\$0
Distribution Main	9977		WAR	Tollgate Rd	6	Ductile Iron	1	11	0.71 out of 5	N/A	\$0
Distribution Main	10575		WAR	Tollgate Rd	6	Ductile Iron	9	2	0.71 out of 5	N/A	\$0
Transmission Main	10579	P-2833	WAR	Tollgate Rd	16	Ductile Iron	672	2	0 out of 5	N/A	\$0
Transmission Main	10580	P-2833	WAR	Tollgate Rd	16	Ductile Iron	16	2	0 out of 5	N/A	\$0
Transmission Main	10581	P-2719	WAR	Tollgate Rd	16	Ductile Iron	611	2	0 out of 5	N/A	\$0
Transmission Main	10582	P-2710	WAR	Tollgate Rd	16	Ductile Iron	164	2	0 out of 5	N/A	\$0
Transmission Main	10583	P-2323	WAR	Tollgate Rd	16	Ductile Iron	49	2	0 out of 5	N/A	\$0
Transmission Main	10584	P-2323	WAR	Tollgate Rd	16	Ductile Iron	526	2	0 out of 5	N/A	\$0
Transmission Main	10585	P-2328	WAR	Tollgate Rd	16	Ductile Iron	375	2	0 out of 5	N/A	\$0
Transmission Main	10586	P-2964	WAR	Tollgate Rd	16	Ductile Iron	1,008	2	0 out of 5	N/A	\$0
Transmission Main	10587	P-2964	WAR	Tollgate Rd	16	Ductile Iron	225	2	0 out of 5	N/A	\$0
Transmission Main	10588	P-2278	WAR	Tollgate Rd	16	Ductile Iron	215	2	0 out of 5	N/A	\$0
Transmission Main	10589	P-2717	WAR	Tollgate Rd	16	Ductile Iron	406	2	0 out of 5	N/A	\$0
Transmission Main	10590	P-2717	WAR	Tollgate Rd	16	Ductile Iron	82	2	0 out of 5	N/A	\$0
Transmission Main	10940	P-2278	WAR	Tollgate Rd	16	Ductile Iron	93	2	0 out of 5	N/A	\$0
Transmission Main	11677	P-2833	WAR	Tollgate Rd	16	Ductile Iron	459	2	0 out of 5	N/A	\$0
Transmission Main	11678	P-2310	WAR	Tollgate Rd	16	Ductile Iron	420	2	0 out of 5	N/A	\$0
Transmission Main	11679	P-2833	WAR	Tollgate Rd	16	Ductile Iron	156	2	0 out of 5	N/A	\$0
Transmission Main	11681	P-2327	WAR	Tollgate Rd	16	Ductile Iron	103	2	0 out of 5	N/A	\$0
Transmission Main	11682	P-2328	WAR	Tollgate Rd	16	Ductile Iron	23	2	0 out of 5	N/A	\$0
Transmission Main	11683	P-2717	WAR	Tollgate Rd	16	Ductile Iron	82	2	0 out of 5	N/A	\$0
Transmission Main	12136	P-2323	WAR	Tollgate Rd	16	Ductile Iron	71	2	0 out of 5	N/A	\$0
Transmission Main	12137	P-2323	WAR	Tollgate Rd	16	Ductile Iron	6	2	0 out of 5	N/A	\$0
Transmission Main	12138	P-2323	WAR	Tollgate Rd	16	Ductile Iron	117	2	0 out of 5	N/A	\$0
Transmission Main	12170	P-2710	WAR	Tollgate Rd	16	Ductile Iron	11	2	0 out of 5	N/A	\$0
Distribution Main	866	P-2647	WAR	Tollgate Rd.	10	Cast Iron	95	91	1.72 out of 5	\$442	41,988
Distribution Main	1148	P-2862	WAR	Tollgate Rd.	10	Cast Iron	387	91	1.72 out of 5	\$442	171,092
Distribution Main	1149	P-2862	WAR	Tollgate Rd.	10	Cast Iron	133	91	1.72 out of 5	\$442	58,913
Distribution Main	1152	P-2647	WAR	Tollgate Rd.	10	Cast Iron	73	91	1.72 out of 5	\$442	32,324
Distribution Main	2146	P-2862	WAR	Tollgate Rd.	10	Cast Iron	150	91	1.72 out of 5	\$442	66,301
Distribution Main	3408	P-2862	WAR	Tollgate Rd.	10	Cast Iron	198	91	1.72 out of 5	\$442	87,522
Distribution Main	3409	P-2862	WAR	Tollgate Rd.	10	Cast Iron	504	91	1.72 out of 5	\$442	222,889
Distribution Main	3410	P-2862	WAR	Tollgate Rd.	10	Cast Iron	605	91	1.72 out of 5	\$442	267,259
Distribution Main	3411	P-2862	WAR	Tollgate Rd.	10	Cast Iron	456	91	1.72 out of 5	\$442	201,425

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	3597	P-2776	WAR	Tollgate Rd.	12	Cast Iron	754	91	1.72 out of 5	\$442	333,481
Distribution Main	4796	P-2298	WAR	Tollgate Rd.	10	Cast Iron	220	91	1.72 out of 5	\$442	97,039
Transmission Main	7085	P-2716	WAR	Tollgate Rd.	12	Cast Iron	61	91	1.72 out of 5	\$442	27,119
Distribution Main	7474	P-2298	WAR	Tollgate Rd.	10	Cast Iron	109	91	1.72 out of 5	\$442	48,079
Distribution Main	7476	P-2298	WAR	Tollgate Rd.	10	Cast Iron	1,487	91	1.72 out of 5	\$442	657,117
Distribution Main	7477	P-2298	WAR	Tollgate Rd.	10	Cast Iron	84	91	1.72 out of 5	\$442	36,937
Distribution Main	10978	P-2298	WAR	Tollgate Rd.	10	Cast Iron	4	91	1.72 out of 5	\$442	1,722
Distribution Main	11925	P-2862	WAR	Tollgate Rd.	10	Cast Iron	381	91	1.72 out of 5	\$442	168,392
Distribution Main	4468	P-2733	WAR	Tomahawk Ct.	6	Asbestos Cement	197	69	2 out of 5	\$442	86,983
Distribution Main	6601	P-2733	WAR	Tomahawk Ct.	8	Ductile Iron	48	18	0 out of 5	N/A	\$0
Distribution Main	10370	P-2733	WAR	Tomahawk Ct.	6	Asbestos Cement	6	69	2 out of 5	\$442	2,856
Distribution Main	10371	P-2733	WAR	Tomahawk Ct.	6	Asbestos Cement	237	69	2 out of 5	\$442	104,734
Distribution Main	6659	P-2209	WAR	Turtle Creek Dr.	8	PVC	49	31	0.43 out of 5	\$442	21,438
Distribution Main	6660	P-2209	WAR	Turtle Creek Dr.	8	PVC	324	31	0.43 out of 5	\$442	143,112
Distribution Main	10118		WAR	Vale St	1.25	Copper	39	46	2.28 out of 5	\$442	17,369
Distribution Main	5432	P-2327	WAR	Vale St.	8	Ductile Iron	41	2	0 out of 5	N/A	\$0
Distribution Main	6958	P-2329	WAR	Vale St.	6	Asbestos Cement	182	46	1.85 out of 5	\$442	80,467
Distribution Main	4466	P-2354	WAR	Valentine Cir.	6	Asbestos Cement	9	46	1.85 out of 5	\$442	3,916
Distribution Main	6085	P-2360	WAR	Valentine Cir.	2	Copper	198	46	2.28 out of 5	\$442	87,497
Distribution Main	7100	P-2354	WAR	Valentine Cir.	6	Asbestos Cement	166	46	1.85 out of 5	\$442	73,503
Distribution Main	7108	P-2359	WAR	Valentine Cir.	6	Cast Iron	29	83	2.43 out of 5	\$442	12,635
Distribution Main	7121	P-2929	WAR	Valentine Cir.	2	Copper	16	46	2.28 out of 5	\$442	7,216
Distribution Main	7122	P-2359	WAR	Valentine Cir.	6	Cast Iron	508	83	2.43 out of 5	\$442	224,605
Distribution Main	7123	P-2359	WAR	Valentine Cir.	6	Cast Iron	10	83	2.43 out of 5	\$442	4,204
Distribution Main	7330	P-2360	WAR	Valentine Cir.	6	Asbestos Cement	123	46	1.85 out of 5	\$442	54,565
Distribution Main	7342	P-2929	WAR	Valentine Cir.	2	Copper	10	46	2.28 out of 5	\$442	4,585
Distribution Main	7343	P-2359	WAR	Valentine Cir.	6	Cast Iron	15	83	2.43 out of 5	\$442	6,789
Distribution Main	6893	P-2251	WAR	Valley Brook Dr.	8	Asbestos Cement	7	46	1.14 out of 5	\$442	3,089
Distribution Main	6894	P-2251	WAR	Valley Brook Dr.	8	Asbestos Cement	160	46	1.14 out of 5	\$442	70,652
Distribution Main	6895	P-2249	WAR	Valley Brook Dr.	8	Asbestos Cement	697	46	1.14 out of 5	\$442	308,208
Distribution Main	9278	P-2874	WAR	Vancouver Ave	8	Ductile Iron	17	11	0 out of 5	N/A	\$0
Distribution Main	9294	P-2874	WAR	Vancouver Ave	6	Ductile Iron	2	11	0.71 out of 5	N/A	\$0
Distribution Main	5704	P-2515	WAR	Vancouver Ave.	6	Asbestos Cement	467	69	2 out of 5	\$442	206,345
Distribution Main	5705	P-2511	WAR	Vancouver Ave.	6	Asbestos Cement	428	69	2 out of 5	\$442	189,377
Distribution Main	6989	P-2515	WAR	Vancouver Ave.	6	Asbestos Cement	13	69	2 out of 5	\$442	5,536
Distribution Main	6993	P-2515	WAR	Vancouver Ave.	6	Asbestos Cement	115	69	2 out of 5	\$442	50,969
Distribution Main	6994	P-2515	WAR	Vancouver Ave.	6	Asbestos Cement	149	69	2 out of 5	\$442	65,681
Distribution Main	6995	P-2504	WAR	Vancouver Ave.	6	Asbestos Cement	441	69	2 out of 5	\$442	195,060
Distribution Main	7072	P-2516	WAR	Vancouver Ave.	6	Asbestos Cement	231	69	2 out of 5	\$442	101,937
Distribution Main	7073	P-2516	WAR	Vancouver Ave.	6	Asbestos Cement	125	69	2 out of 5	\$442	55,283
Distribution Main	7078	P-2520	WAR	Vancouver Ave.	6	Asbestos Cement	226	69	2 out of 5	\$442	100,011
Distribution Main	7079	P-2520	WAR	Vancouver Ave.	6	Asbestos Cement	38	69	2 out of 5	\$442	17,015
Distribution Main	7080	P-2519	WAR	Vancouver Ave.	6	Asbestos Cement	256	69	2 out of 5	\$442	113,110
Distribution Main	3220	P-2239	WAR	Varnum Dr.	8	Asbestos Cement	18	55	1.14 out of 5	\$442	8,040

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5550	P-2238	WAR	Varnum Dr.	8	Asbestos Cement	192	55	1.14 out of 5	\$442	84,789
Distribution Main	5551	P-2238	WAR	Varnum Dr.	8	Asbestos Cement	1,475	55	1.14 out of 5	\$442	651,831
Distribution Main	6352	P-2238	WAR	Varnum Dr.	8	Asbestos Cement	12	55	1.14 out of 5	\$442	5,516
Distribution Main	6813	P-2239	WAR	Varnum Dr.	8	Asbestos Cement	626	55	1.14 out of 5	\$442	276,592
Distribution Main	6814	P-2239	WAR	Varnum Dr.	8	Asbestos Cement	927	55	1.14 out of 5	\$442	409,648
Distribution Main	6934	P-2237	WAR	Varnum Dr.	8	Asbestos Cement	506	55	1.14 out of 5	\$442	223,487
Distribution Main	11940	P-2239	WAR	Varnum Dr.	8	Asbestos Cement	60	55	1.14 out of 5	\$442	26,362
Distribution Main	11942	P-2239	WAR	Varnum Dr.	8	Asbestos Cement	153	55	1.14 out of 5	\$442	67,710
Distribution Main	6823	P-2398	WAR	Venus Dr.	8	Ductile Iron	7	32	0.14 out of 5	\$442	3,048
Distribution Main	6824	P-2398	WAR	Venus Dr.	8	Ductile Iron	267	32	0.14 out of 5	\$442	117,860
Distribution Main	6845	P-2399	WAR	Venus Dr.	8	Ductile Iron	107	32	0.14 out of 5	\$442	47,134
Distribution Main	6846	P-2399	WAR	Venus Dr.	8	Ductile Iron	265	32	0.14 out of 5	\$442	117,290
Distribution Main	5779	P-2148	WAR	Verdant Ln.	8	Asbestos Cement	474	47	1.14 out of 5	\$442	209,568
Distribution Main	10761	P-2632	WAR	Veterans Memorial Dr	8	Ductile Iron	524	2	0 out of 5	N/A	\$0
Distribution Main	10762	P-2632	WAR	Veterans Memorial Dr	8	Ductile Iron	249	2	0 out of 5	N/A	\$0
Distribution Main	11934	P-2632	WAR	Veterans Memorial Dr	8	Ductile Iron	366	2	0 out of 5	N/A	\$0
Distribution Main	12168	P-2632	WAR	Veterans Memorial Dr	6	Ductile Iron	36	UNK	0.71 out of 5	\$442	16,069
Distribution Main	12192	P-2632	WAR	Veterans Memorial Dr	8	Ductile Iron	253	2	0 out of 5	N/A	\$0
Distribution Main	12216	P-2632	WAR	Veterans Memorial Dr	8	Ductile Iron	56	2	0 out of 5	N/A	\$0
Distribution Main	12230	P-2632	WAR	Veterans Memorial Dr	8	Ductile Iron	152	2	0 out of 5	N/A	\$0
Distribution Main	9660	P-2931	WAR	Viceroy Rd	8	Ductile Iron	5	14	0 out of 5	N/A	\$0
Distribution Main	9661	P-2931	WAR	Viceroy Rd	8	Ductile Iron	69	14	0 out of 5	N/A	\$0
Distribution Main	5983	P-2062	WAR	Viceroy Rd.	6	Asbestos Cement	438	57	1.85 out of 5	\$442	193,632
Distribution Main	6308	P-2058	WAR	Viceroy Rd.	6	Asbestos Cement	948	57	1.85 out of 5	\$442	419,117
Distribution Main	6594	P-2060	WAR	Viceroy Rd.	6	Asbestos Cement	19	57	1.85 out of 5	\$442	8,523
Distribution Main	6595	P-2060	WAR	Viceroy Rd.	6	Asbestos Cement	198	57	1.85 out of 5	\$442	87,607
Distribution Main	7055	P-2047	WAR	Viceroy Rd.	6	Asbestos Cement	429	57	1.85 out of 5	\$442	189,670
Distribution Main	7362	P-2061	WAR	Viceroy Rd.	6	Asbestos Cement	92	57	1.85 out of 5	\$442	40,712
Distribution Main	7363	P-2061	WAR	Viceroy Rd.	6	Asbestos Cement	6	57	1.85 out of 5	\$442	2,676
Distribution Main	2244	P-1309	WAR	Waite St.	6	Asbestos Cement	339	69	2 out of 5	\$442	149,903
Distribution Main	4117	WAR	WAR	Waite St.	6	Ductile Iron	20	UNK	0.71 out of 5	\$442	8,791
Distribution Main	9862	P-1761	WAR	Wallace Ave	8	Ductile Iron	384	7	0 out of 5	N/A	\$0
Distribution Main	5693	P-2030	WAR	Wampum Dr.	8	Asbestos Cement	326	42	1.14 out of 5	\$442	144,074
Distribution Main	5695	P-2032	WAR	Wampum Dr.	8	Asbestos Cement	31	42	1.14 out of 5	\$442	13,799
Distribution Main	7059	P-2032	WAR	Wampum Dr.	8	Asbestos Cement	200	42	1.14 out of 5	\$442	88,423
Distribution Main	7060	P-2032	WAR	Wampum Dr.	8	Asbestos Cement	23	42	1.14 out of 5	\$442	10,284
Distribution Main	4545	P-2613	WAR	Water St.	8	Ductile Iron	469	18	0 out of 5	N/A	\$0
Distribution Main	4546	P-2613	WAR	Water St.	8	Ductile Iron	257	18	0 out of 5	N/A	\$0
Distribution Main	4547	P-2613	WAR	Water St.	8	Ductile Iron	73	18	0 out of 5	N/A	\$0
Distribution Main	5202	P-2611	WAR	Water St.	8	Ductile Iron	107	18	0 out of 5	N/A	\$0
Distribution Main	5557	P-2613	WAR	Water St.	8	Ductile Iron	44	18	0 out of 5	N/A	\$0
Distribution Main	5567	P-2611	WAR	Water St.	6	Ductile Iron	23	18	0.71 out of 5	N/A	\$0
Distribution Main	7034	P-2611	WAR	Water St.	6	Ductile Iron	20	18	0.71 out of 5	N/A	\$0
Distribution Main	6981	P-2485	WAR	Weber Ave.	6	Asbestos Cement	465	40	1.71 out of 5	\$442	205,481

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5540	P-2266	WAR	Welthian Ct.	6	Asbestos Cement	7	66	2 out of 5	\$442	2,927
Distribution Main	5544	P-2953	WAR	Welthian Ct.	1	Copper	175	66	2.43 out of 5	\$442	77,213
Distribution Main	6931	P-2266	WAR	Welthian Ct.	6	Asbestos Cement	341	66	2 out of 5	\$442	150,896
Distribution Main	10744	P-2558	WAR	West Pontiac St	8	Ductile Iron	100	1	0 out of 5	N/A	\$0
Distribution Main	10745	P-2855	WAR	West Pontiac St	8	Ductile Iron	370	1	0 out of 5	N/A	\$0
Distribution Main	11717	P-2854	WAR	West Pontiac St	8	Ductile Iron	20	1	0 out of 5	N/A	\$0
Distribution Main	11920	P-2854	WAR	West Pontiac St	8	Ductile Iron	17	1	0 out of 5	N/A	\$0
Distribution Main	7118	P-2392	WAR	Westchester Way	6	Asbestos Cement	547	53	1.85 out of 5	\$442	241,685
Distribution Main	7124		WAR	Westchester Way	6	Unknown	382	53	1 out of 5	\$442	168,922
Distribution Main	7349	P-2391	WAR	Westchester Way	6	Asbestos Cement	25	53	1.85 out of 5	\$442	10,894
Distribution Main	7350	P-2391	WAR	Westchester Way	6	Asbestos Cement	230	53	1.85 out of 5	\$442	101,681
Distribution Main	7357	P-2392	WAR	Westchester Way	6	Asbestos Cement	24	53	1.85 out of 5	\$442	10,600
Distribution Main	11360	P-2392	WAR	Westchester Way	6	Asbestos Cement	40	53	1.85 out of 5	\$442	17,742
Distribution Main	5493	P-2947	WAR	Weymouth Ln	8	Ductile Iron	5	17	0 out of 5	N/A	\$0
Distribution Main	6510	P-2947	WAR	Weymouth Ln	8	Ductile Iron	311	17	0 out of 5	N/A	\$0
Distribution Main	6511	P-2947	WAR	Weymouth Ln	8	Ductile Iron	76	17	0 out of 5	N/A	\$0
Distribution Main	4460	P-2738	WAR	Whispering Ln.	6	PVC	385	31	1.14 out of 5	\$442	170,173
Distribution Main	10557	P-2301	WAR	Whitehall Dr	8	Ductile Iron	229	2	0 out of 5	N/A	\$0
Distribution Main	10558	P-2301	WAR	Whitehall Dr	8	Ductile Iron	43	2	0 out of 5	N/A	\$0
Distribution Main	10847	P-2302	WAR	Whitehall Dr	8	Ductile Iron	180	2	0 out of 5	N/A	\$0
Distribution Main	5395	P-2432	WAR	Wilcar St	8	Asbestos Cement	149	48	1.14 out of 5	\$442	65,892
Distribution Main	5398	P-2431	WAR	Wilcar St.	8	Asbestos Cement	354	48	1.14 out of 5	\$442	156,420
Distribution Main	9139	P-2401	WAR	Williams St	8	Ductile Iron	257	8	0 out of 5	N/A	\$0
Distribution Main	10911	P-2955	WAR	Williams St	8	Ductile Iron	59	8	0 out of 5	N/A	\$0
Distribution Main	10912	P-2955	WAR	Williams St	8	Ductile Iron	34	8	0 out of 5	N/A	\$0
Distribution Main	10913	P-2401	WAR	Williams St	8	Ductile Iron	242	8	0 out of 5	N/A	\$0
Distribution Main	6283	P-2955	WAR	Williams St.	4	Cast Iron	36	129	3.29 out of 5	\$442	16,109
Distribution Main	4516	P-2380	WAR	Windemere Way	8	Asbestos Cement	9	80	1.29 out of 5	\$442	3,893
Distribution Main	6086	P-2711	WAR	Windemere Way	8	Asbestos Cement	443	80	1.29 out of 5	\$442	195,727
Distribution Main	6091	P-2710	WAR	Windemere Way	8	Asbestos Cement	196	80	1.29 out of 5	\$442	86,517
Distribution Main	6092	P-2710	WAR	Windemere Way	8	Asbestos Cement	42	80	1.29 out of 5	\$442	18,653
Distribution Main	6534	P-2378	WAR	Windemere Way	8	Asbestos Cement	344	80	1.29 out of 5	\$442	151,849
Distribution Main	7175	P-2380	WAR	Windemere Way	8	Asbestos Cement	634	80	1.29 out of 5	\$442	280,138
Distribution Main	7178	P-2710	WAR	Windemere Way	8	Asbestos Cement	13	80	1.29 out of 5	\$442	5,638
Distribution Main	9602	P-2378	WAR	Windemere Way	8	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Distribution Main	9603	P-2378	WAR	Windemere Way	8	Ductile Iron	28	22	0.14 out of 5	N/A	\$0
Distribution Main	3598	P-2295	WAR	Winman Ct.	8	Ductile Iron	49	25	0.14 out of 5	N/A	\$0
Distribution Main	7000	P-2295	WAR	Winman Ct.	8	Ductile Iron	4	25	0.14 out of 5	N/A	\$0
Distribution Main	7021	P-2295	WAR	Winman Ct.	8	Ductile Iron	493	25	0.14 out of 5	N/A	\$0
Distribution Main	8281	2-229P-2295	WAR	Winman Ct.	8	Ductile Iron	22	25	0.14 out of 5	N/A	\$0
Distribution Main	8282	2-229P-2295	WAR	Winman Ct.	8	Ductile Iron	55	14	0 out of 5	N/A	\$0
Distribution Main	3308	P-2216	WAR	Winnisquam Dr.	8	Asbestos Cement	433	53	1.14 out of 5	\$442	191,244
Distribution Main	3627	P-2199	WAR	Winnisquam Dr.	8	Asbestos Cement	308	53	1.14 out of 5	\$442	136,093
Distribution Main	3628	P-2200	WAR	Winnisquam Dr.	8	Asbestos Cement	123	53	1.14 out of 5	\$442	54,527

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4222	P-2215	WAR	Winnisquam Dr.	8	Asbestos Cement	200	53	1.14 out of 5	\$442	88,400
Distribution Main	4223	P-2215	WAR	Winnisquam Dr.	8	Asbestos Cement	9	53	1.14 out of 5	\$442	4,157
Distribution Main	4224	P-2215	WAR	Winnisquam Dr.	8	Asbestos Cement	34	53	1.14 out of 5	\$442	15,223
Distribution Main	4242	P-2215	WAR	Winnisquam Dr.	8	Asbestos Cement	10	53	1.14 out of 5	\$442	4,408
Distribution Main	5751	P-2194	WAR	Winnisquam Dr.	8	Asbestos Cement	262	53	1.14 out of 5	\$442	115,943
Distribution Main	5752	P-2194	WAR	Winnisquam Dr.	8	Asbestos Cement	54	53	1.14 out of 5	\$442	23,807
Distribution Main	5780	P-2194	WAR	Winnisquam Dr.	8	Asbestos Cement	18	53	1.14 out of 5	\$442	8,026
Distribution Main	6865	P-2417	WAR	Wolverstone Rd.	6	PVC	429	44	1.28 out of 5	\$442	189,658
Distribution Main	6866	P-2417	WAR	Wolverstone Rd.	6	PVC	331	44	1.28 out of 5	\$442	146,476
Distribution Main	6867	P-2417	WAR	Wolverstone Rd.	6	PVC	213	44	1.28 out of 5	\$442	94,289
Distribution Main	4484	P-2071	WAR	Zinnia St.	8	Asbestos Cement	369	42	1.14 out of 5	\$442	163,292
Distribution Main	4485	P-2068	WAR	Zinnia St.	8	Asbestos Cement	383	42	1.14 out of 5	\$442	169,382
Distribution Main	7366	P-2063	WAR	Zinnia St.	8	Asbestos Cement	269	42	1.14 out of 5	\$442	118,790
Distribution Main	7566	P-3009	WG	Bailey Dr.	8	Asbestos Cement	653	48	1.14 out of 5	\$442	288,653
Distribution Main	7567	P-3009	WG	Bailey Dr.	8	Asbestos Cement	560	48	1.14 out of 5	\$442	247,531
Distribution Main	7681	P-3008	WG	Bailey Dr.	8	Asbestos Cement	101	48	1.14 out of 5	\$442	44,444
Distribution Main	7552	P-3043	WG	Brant Tr.	6	Asbestos Cement	11	54	1.85 out of 5	\$442	4,794
Distribution Main	7553	P-3043	WG	Brant Tr.	6	Asbestos Cement	65	54	1.85 out of 5	\$442	28,870
Distribution Main	8088	P-3086	WG	Buck Hollow Rd	8	Ductile Iron	829	UNK	0 out of 5	N/A	\$0
Distribution Main	8089	P-3086	WG	Buck Hollow Rd	8	Ductile Iron	574	UNK	0 out of 5	N/A	\$0
Distribution Main	11427	P-3086	WG	Buck Hollow Rd	8	Ductile Iron	216	UNK	0 out of 5	N/A	\$0
Distribution Main	11428	P-3086	WG	Buck Hollow Rd	8	Ductile Iron	19	UNK	0 out of 5	N/A	\$0
Distribution Main	7136	P-3027	WG	Cambio Ct.	6	Asbestos Cement	375	42	1.85 out of 5	\$442	165,579
Transmission Main	1671	P-3080	WG	Carrs Pond Rd.	20	Ductile Iron	1,081	18	0 out of 5	N/A	\$0
Transmission Main	1672	P-3080	WG	Carrs Pond Rd.	20	Ductile Iron	606	18	0 out of 5	N/A	\$0
Transmission Main	1673	P-3080	WG	Carrs Pond Rd.	20	Ductile Iron	41	18	0 out of 5	N/A	\$0
Transmission Main	1747	P-3080	WG	Carrs Pond Rd.	20	Ductile Iron	274	18	0 out of 5	N/A	\$0
Transmission Main	3686	P-40043	WG	Carrs Pond Rd.	20	Ductile Iron	9	18	0 out of 5	N/A	\$0
Transmission Main	4580	P-40043	WG	Carrs Pond Rd.	16	Ductile Iron	53	18	0 out of 5	N/A	\$0
Transmission Main	4978	P-3054	WG	Carrs Pond Rd.	20	Ductile Iron	44	18	0 out of 5	N/A	\$0
Transmission Main	4979	P-3054	WG	Carrs Pond Rd.	20	Ductile Iron	915	18	0 out of 5	N/A	\$0
Transmission Main	4980	P-3080	WG	Carrs Pond Rd.	20	Ductile Iron	38	18	0 out of 5	N/A	\$0
Transmission Main	4981	P-3080	WG	Carrs Pond Rd.	20	Ductile Iron	668	18	0 out of 5	N/A	\$0
Transmission Main	5713	P-3056	WG	Carrs Pond Rd.	20	Ductile Iron	675	18	0 out of 5	N/A	\$0
Transmission Main	5715	P-3056	WG	Carrs Pond Rd.	20	Ductile Iron	118	18	0 out of 5	N/A	\$0
Transmission Main	5716	P-3056	WG	Carrs Pond Rd.	20	Ductile Iron	908	18	0 out of 5	N/A	\$0
Transmission Main	8880	P-3056	WG	Carrs Pond Rd.	20	Ductile Iron	105	18	0 out of 5	N/A	\$0
Transmission Main	9922	P-3080	WG	Carrs Pond Rd.	20	Ductile Iron	38	18	0 out of 5	N/A	\$0
Transmission Main	9990	P-3080	WG	Carrs Pond Rd.	20	Ductile Iron	25	18	0 out of 5	N/A	\$0
Transmission Main	2974	P-3055	WG	Carrs Pond Rd. Tank	16	Ductile Iron	713	18	0 out of 5	N/A	\$0
Transmission Main	3450	P-3137	WG	Carrs Pond Rd. Tank	12	Ductile Iron	37	18	0 out of 5	N/A	\$0
Transmission Main	4221	WG	WG	Carrs Pond Rd. Tank	12	Ductile Iron	264	18	0 out of 5	N/A	\$0
Transmission Main	5714	P-3055	WG	Carrs Pond Rd. Tank	16	Ductile Iron	32	18	0 out of 5	N/A	\$0
Transmission Main	9910	P-3055	WG	Carrs Pond Rd. Tank	12	Ductile Iron	16	18	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	9911	P-3055	WG	Carrs Pond Rd. Tank	12	Ductile Iron	24	18	0 out of 5	N/A	\$0
Distribution Main	7663	P-3014	WG	Cheyene Tr.	6	Asbestos Cement	515	48	1.85 out of 5	\$442	227,810
Distribution Main	7268	P-3022	WG	Clubhouse Rd.	6	Asbestos Cement	332	48	1.85 out of 5	\$442	146,812
Distribution Main	7639	P-3022	WG	Clubhouse Rd.	6	Asbestos Cement	209	48	1.85 out of 5	\$442	92,571
Distribution Main	7640	P-3022	WG	Clubhouse Rd.	6	Asbestos Cement	482	48	1.85 out of 5	\$442	213,057
Distribution Main	7655	P-3023	WG	Clubhouse Rd.	6	Asbestos Cement	589	48	1.85 out of 5	\$442	260,424
Distribution Main	7656	P-3023	WG	Clubhouse Rd.	6	Asbestos Cement	524	48	1.85 out of 5	\$442	231,784
Distribution Main	7659	P-3020	WG	Clubhouse Rd.	6	Asbestos Cement	23	48	1.85 out of 5	\$442	10,209
Distribution Main	7660	P-3020	WG	Clubhouse Rd.	6	Asbestos Cement	625	48	1.85 out of 5	\$442	276,314
Distribution Main	7679	P-3015	WG	Comanche Trail	8	Asbestos Cement	541	48	1.14 out of 5	\$442	239,253
Distribution Main	8085	P-3087	WG	Deer Run Rd	8	Ductile Iron	1,267	18	0 out of 5	N/A	\$0
Distribution Main	8086	P-3087	WG	Deer Run Rd	8	Ductile Iron	576	UNK	0 out of 5	N/A	\$0
Distribution Main	11426	P-3087	WG	Deer Run Rd	8	Ductile Iron	522	UNK	0 out of 5	N/A	\$0
Distribution Main	11429	P-3087	WG	Deer Run Rd	8	Ductile Iron	28	UNK	0 out of 5	N/A	\$0
Transmission Main	505	P-3135	WG	Division Road	16	Ductile Iron	499	18	0 out of 5	N/A	\$0
Transmission Main	506	P-3135	WG	Division Road	16	Ductile Iron	189	18	0 out of 5	N/A	\$0
Transmission Main	507	P-3101	WG	Division Road	16	Ductile Iron	868	18	0 out of 5	N/A	\$0
Transmission Main	508	P-3101	WG	Division Road	16	Ductile Iron	120	18	0 out of 5	N/A	\$0
Transmission Main	2002	P-3101	WG	Division Road	16	Ductile Iron	183	18	0 out of 5	N/A	\$0
Transmission Main	2003	P-3053	WG	Division Road	16	Ductile Iron	891	18	0 out of 5	N/A	\$0
Transmission Main	2004	P-3059	WG	Division Road	20	Ductile Iron	1,163	18	0 out of 5	N/A	\$0
Transmission Main	2005	P-3059	WG	Division Road	20	Ductile Iron	1,088	18	0 out of 5	N/A	\$0
Transmission Main	2006	P-3057	WG	Division Road	20	Ductile Iron	1,433	18	0 out of 5	N/A	\$0
Transmission Main	2007	P-3057	WG	Division Road	20	Ductile Iron	688	18	0 out of 5	N/A	\$0
Transmission Main	2008	P-3133	WG	Division Road	20	Ductile Iron	70	18	0 out of 5	N/A	\$0
Transmission Main	2009	P-3133	WG	Division Road	20	Ductile Iron	979	18	0 out of 5	N/A	\$0
Transmission Main	2010	P-3133	WG	Division Road	20	Ductile Iron	114	18	0 out of 5	N/A	\$0
Transmission Main	2011	P-3135	WG	Division Road	16	Ductile Iron	600	18	0 out of 5	N/A	\$0
Transmission Main	2012	P-3101	WG	Division Road	16	Ductile Iron	3	18	0 out of 5	N/A	\$0
Transmission Main	2014	P-3135	WG	Division Road	16	Ductile Iron	3	18	0 out of 5	N/A	\$0
Transmission Main	4982	P-3059	WG	Division Road	20	Ductile Iron	810	18	0 out of 5	N/A	\$0
Transmission Main	8879	P-3101	WG	Division Road	16	Ductile Iron	195	18	0 out of 5	N/A	\$0
Transmission Main	8881	P-3057	WG	Division Road	20	Ductile Iron	194	18	0 out of 5	N/A	\$0
Transmission Main	10099	P-3059	WG	Division Road	20	Ductile Iron	97	18	0 out of 5	N/A	\$0
Transmission Main	10101		WG	Division Road	20	Ductile Iron	33	18	0 out of 5	N/A	\$0
Transmission Main	11522	P-3133	WG	Division Road	20	Ductile Iron	4	18	0 out of 5	N/A	\$0
Distribution Main	8090	P-3138	WG	Doe Place	8	Ductile Iron	450	UNK	0 out of 5	N/A	\$0
Distribution Main	7270	P-3004	WG	Easement	8	Asbestos Cement	579	38	1 out of 5	\$442	255,882
Distribution Main	7680	P-3063	WG	Eddy St.	8	Asbestos Cement	225	48	1.14 out of 5	\$442	99,423
Transmission Main	10002	P-3111	WG	Hopkins Hill Rd	12	Ductile Iron	3	7	0 out of 5	N/A	\$0
Distribution Main	10102		WG	Hopkins Hill Rd	8	Ductile Iron	1	13	0 out of 5	N/A	\$0
Distribution Main	10104	P-3142	WG	Hopkins Hill Rd	6	Unknown	96	UNK	0.71 out of 5	\$442	42,634
Transmission Main	492	P-3140	WG	Hopkins Hill Rd.	12	Ductile Iron	885	30	0.14 out of 5	\$442	391,369
Transmission Main	493	P-3140	WG	Hopkins Hill Rd.	12	Ductile Iron	49	30	0.14 out of 5	\$442	21,520

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	494	P-3047	WG	Hopkins Hill Rd.	16	Ductile Iron	540	31	0.14 out of 5	\$442	238,787
Transmission Main	2973	P-3130	WG	Hopkins Hill Rd.	16	Ductile Iron	87	31	0.14 out of 5	\$442	38,577
Transmission Main	4095	P-3131	WG	Hopkins Hill Rd.	12	Ductile Iron	51	UNK	0 out of 5	N/A	\$0
Transmission Main	4220	P-3047	WG	Hopkins Hill Rd.	16	Ductile Iron	319	31	0.14 out of 5	\$442	141,167
Transmission Main	4815	P-3058	WG	Hopkins Hill Rd.	20	Ductile Iron	810	18	0 out of 5	N/A	\$0
Transmission Main	4835	P-3110	WG	Hopkins Hill Rd.	20	Ductile Iron	78	18	0 out of 5	N/A	\$0
Transmission Main	4836	P-3046	WG	Hopkins Hill Rd.	20	Ductile Iron	818	18	0 out of 5	N/A	\$0
Transmission Main	4837	P-3046	WG	Hopkins Hill Rd.	20	Ductile Iron	359	18	0 out of 5	N/A	\$0
Transmission Main	4919	P-3046	WG	Hopkins Hill Rd.	20	Ductile Iron	221	18	0 out of 5	N/A	\$0
Transmission Main	4920	P-3046	WG	Hopkins Hill Rd.	20	Ductile Iron	38	18	0 out of 5	N/A	\$0
Transmission Main	5314	P-3046	WG	Hopkins Hill Rd.	20	Ductile Iron	302	18	0 out of 5	N/A	\$0
Transmission Main	5315	P-3110	WG	Hopkins Hill Rd.	20	Ductile Iron	24	18	0 out of 5	N/A	\$0
Transmission Main	5316	P-3110	WG	Hopkins Hill Rd.	20	Ductile Iron	768	18	0 out of 5	N/A	\$0
Transmission Main	5317	P-3058	WG	Hopkins Hill Rd.	20	Ductile Iron	1,296	18	0 out of 5	N/A	\$0
Transmission Main	5318	P-3129	WG	Hopkins Hill Rd.	20	Ductile Iron	43	18	0 out of 5	N/A	\$0
Transmission Main	10100		WG	Hopkins Hill Rd.	20	Ductile Iron	34	18	0 out of 5	N/A	\$0
Transmission Main	11267	P-3110	WG	Hopkins Hill Rd.	20	Ductile Iron	12	18	0 out of 5	N/A	\$0
Transmission Main	11295	P-3140	WG	Hopkins Hill Rd.	12	Ductile Iron	45	30	0.14 out of 5	\$442	19,843
Transmission Main	12062	P-3140	WG	Hopkins Hill Rd.	12	Ductile Iron	282	30	0.14 out of 5	\$442	124,610
Transmission Main	12080	P-3110	WG	Hopkins Hill Rd.	20	Ductile Iron	15	18	0 out of 5	N/A	\$0
Distribution Main	10222	P-3031	WG	Lake Dr	8	Ductile Iron	16	5	0 out of 5	N/A	\$0
Distribution Main	5232	P-3028	WG	Lake Dr.	8	Asbestos Cement	1,208	48	1.14 out of 5	\$442	533,989
Distribution Main	5233	P-3028	WG	Lake Dr.	8	Asbestos Cement	80	48	1.14 out of 5	\$442	35,256
Distribution Main	7556	P-3026	WG	Lake Dr.	8	Asbestos Cement	21	48	1.14 out of 5	\$442	9,217
Distribution Main	7557	P-3026	WG	Lake Dr.	8	Asbestos Cement	558	48	1.14 out of 5	\$442	246,828
Distribution Main	7560	P-3031	WG	Lake Dr.	8	Asbestos Cement	970	48	1.14 out of 5	\$442	428,574
Distribution Main	7661	P-3028	WG	Lake Dr.	8	Asbestos Cement	39	48	1.14 out of 5	\$442	17,169
Distribution Main	7662	P-3028	WG	Lake Dr.	8	Asbestos Cement	962	48	1.14 out of 5	\$442	425,252
Distribution Main	10123		WG	Lake Dr.	8	Asbestos Cement	26	48	1.14 out of 5	\$442	11,304
Distribution Main	10124		WG	Lake Dr.	8	Asbestos Cement	26	48	1.14 out of 5	\$442	11,335
Distribution Main	11291	P-3028	WG	Lake Dr.	8	Asbestos Cement	9	48	1.14 out of 5	\$442	3,767
Distribution Main	11984	P-3028	WG	Lake Dr.	8	Asbestos Cement	487	48	1.14 out of 5	\$442	215,087
Distribution Main	11985	P-3028	WG	Lake Dr.	8	Asbestos Cement	10	48	1.14 out of 5	\$442	4,635
Distribution Main	7649	P-3025	WG	Mac Cue Point Rd.	8	Asbestos Cement	207	48	1.14 out of 5	\$442	91,472
Distribution Main	5231	P-7452	WG	Melrose Dr.	8	Ductile Iron	787	26	0.14 out of 5	\$442	347,938
Distribution Main	9920		WG	Mishnock Rd	8	Asbestos Cement	22	49	1.14 out of 5	\$442	9,755
Transmission Main	10215	P-3061	WG	Mishnock Rd	16	Ductile Iron	126	5	0 out of 5	N/A	\$0
Transmission Main	10216	P-3060	WG	Mishnock Rd	16	Ductile Iron	760	5	0 out of 5	N/A	\$0
Transmission Main	10217	P-3060	WG	Mishnock Rd	16	Ductile Iron	285	5	0 out of 5	N/A	\$0
Transmission Main	10218		WG	Mishnock Rd	16	Ductile Iron	800	5	0 out of 5	N/A	\$0
Transmission Main	10219		WG	Mishnock Rd	16	Ductile Iron	220	5	0 out of 5	N/A	\$0
Transmission Main	10220	P-3060	WG	Mishnock Rd	12	Ductile Iron	73	5	0 out of 5	N/A	\$0
Transmission Main	10221	P-3033	WG	Mishnock Rd	12	Ductile Iron	73	5	0 out of 5	N/A	\$0
Transmission Main	10223		WG	Mishnock Rd	16	Ductile Iron	408	5	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	10224		WG	Mishnock Rd	16	Ductile Iron	284	5	0 out of 5	N/A	\$0
Transmission Main	10225		WG	Mishnock Rd	16	Ductile Iron	386	5	0 out of 5	N/A	\$0
Transmission Main	10226		WG	Mishnock Rd	16	Ductile Iron	324	5	0 out of 5	N/A	\$0
Transmission Main	10227	P-3036	WG	Mishnock Rd	12	Ductile Iron	5	5	0 out of 5	N/A	\$0
Distribution Main	10228	P-3035	WG	Mishnock Rd	6	Ductile Iron	21	5	0.71 out of 5	N/A	\$0
Transmission Main	10750		WG	Mishnock Rd	16	Ductile Iron	5,310	1	0 out of 5	N/A	\$0
Transmission Main	10751		WG	Mishnock Rd	16	Ductile Iron	1,165	5	0 out of 5	N/A	\$0
Transmission Main	10998	P-3034	WG	Mishnock Rd	12	Ductile Iron	3	5	0 out of 5	N/A	\$0
Transmission Main	11644	P-3060	WG	Mishnock Rd	12	Ductile Iron	14	5	0 out of 5	N/A	\$0
Transmission Main	4921	P-3006	WG	Mishnock Rd.	12	Asbestos Cement	183	49	1.14 out of 5	\$442	80,994
Transmission Main	5353	P-3006	WG	Mishnock Rd.	12	Asbestos Cement	3	49	1.14 out of 5	\$442	1,462
Transmission Main	5923	P-3010	WG	Mishnock Rd.	12	Asbestos Cement	171	49	1.14 out of 5	\$442	75,791
Transmission Main	6628		WG	Mishnock Rd.	12	Asbestos Cement	16	49	1.14 out of 5	\$442	6,982
Transmission Main	7561	P-3010	WG	Mishnock Rd.	12	Asbestos Cement	177	49	1.14 out of 5	\$442	78,274
Transmission Main	7562	P-3010	WG	Mishnock Rd.	12	Asbestos Cement	418	49	1.14 out of 5	\$442	184,613
Transmission Main	7563	P-3034	WG	Mishnock Rd.	12	Asbestos Cement	175	49	1.14 out of 5	\$442	77,487
Transmission Main	7564	P-3011	WG	Mishnock Rd.	12	Asbestos Cement	315	49	1.14 out of 5	\$442	139,390
Transmission Main	7565	P-3011	WG	Mishnock Rd.	12	Asbestos Cement	63	49	1.14 out of 5	\$442	27,627
Transmission Main	7641	P-3036	WG	Mishnock Rd.	12	Asbestos Cement	638	49	1.14 out of 5	\$442	282,039
Transmission Main	7642	P-3036	WG	Mishnock Rd.	12	Asbestos Cement	497	49	1.14 out of 5	\$442	219,651
Transmission Main	7670	P-3010	WG	Mishnock Rd.	12	Asbestos Cement	610	49	1.14 out of 5	\$442	269,800
Transmission Main	7671	P-3011	WG	Mishnock Rd.	12	Asbestos Cement	355	49	1.14 out of 5	\$442	157,018
Transmission Main	7672	P-3011	WG	Mishnock Rd.	12	Asbestos Cement	356	49	1.14 out of 5	\$442	157,285
Transmission Main	7673	P-3034	WG	Mishnock Rd.	12	Asbestos Cement	174	49	1.14 out of 5	\$442	76,746
Transmission Main	7674	P-3034	WG	Mishnock Rd.	12	Asbestos Cement	291	49	1.14 out of 5	\$442	128,668
Transmission Main	7675	P-3033	WG	Mishnock Rd.	12	Asbestos Cement	575	49	1.14 out of 5	\$442	254,312
Transmission Main	7676	P-3060	WG	Mishnock Rd.	12	Asbestos Cement	845	49	1.14 out of 5	\$442	373,575
Transmission Main	7677	P-3060	WG	Mishnock Rd.	12	Asbestos Cement	1,014	49	1.14 out of 5	\$442	448,264
Transmission Main	10420	P-3006	WG	Mishnock Rd.	12	Asbestos Cement	4	49	1.14 out of 5	\$442	1,749
Transmission Main	10421	P-3006	WG	Mishnock Rd.	12	Asbestos Cement	174	49	1.14 out of 5	\$442	76,735
Transmission Main	11388	P-3011	WG	Mishnock Rd.	12	Asbestos Cement	19	49	1.14 out of 5	\$442	8,204
Transmission Main	11656	P-3006	WG	Mishnock Rd.	12	Asbestos Cement	15	49	1.14 out of 5	\$442	6,499
Transmission Main	11983	P-3011	WG	Mishnock Rd.	12	Asbestos Cement	330	49	1.14 out of 5	\$442	145,875
Distribution Main	7266	P-3018	WG	Mohawk Tr.	8	Asbestos Cement	155	48	1.14 out of 5	\$442	68,666
Distribution Main	7267	P-3018	WG	Mohawk Tr.	8	Asbestos Cement	9	48	1.14 out of 5	\$442	3,976
Distribution Main	7568	P-3012	WG	Mohawk Tr.	8	Asbestos Cement	14	48	1.14 out of 5	\$442	6,367
Distribution Main	7569	P-3012	WG	Mohawk Tr.	8	Asbestos Cement	391	48	1.14 out of 5	\$442	172,871
Distribution Main	7667	P-3017	WG	Mohawk Tr.	8	Asbestos Cement	119	48	1.14 out of 5	\$442	52,447
Distribution Main	7668	P-3016	WG	Mohawk Tr.	8	Asbestos Cement	225	48	1.14 out of 5	\$442	99,235
Distribution Main	7669	P-3012	WG	Mohawk Tr.	8	Asbestos Cement	13	48	1.14 out of 5	\$442	5,912
Distribution Main	7678	P-3021	WG	Mohawk Tr.	8	Asbestos Cement	235	48	1.14 out of 5	\$442	103,922
Transmission Main	1995	P-3136	WG	Moosehorn Road	16	Ductile Iron	5	18	0 out of 5	N/A	\$0
Transmission Main	1996	P-3136	WG	Moosehorn Road	16	Ductile Iron	31	18	0 out of 5	N/A	\$0
Transmission Main	2013	P-3136	WG	Moosehorn Road	16	Ductile Iron	3	18	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	10212		WG	Nooseneck Hill Rd	16	Ductile Iron	73	5	0 out of 5	N/A	\$0
Transmission Main	10213		WG	Nooseneck Hill Rd	16	Ductile Iron	825	5	0 out of 5	N/A	\$0
Transmission Main	10214		WG	Nooseneck Hill Rd	16	Ductile Iron	664	5	0 out of 5	N/A	\$0
Transmission Main	10706		WG	Nooseneck Hill Rd	12	HDPE	50	5	0.28 out of 5	N/A	\$0
Distribution Main	10707		WG	Nooseneck Hill Rd	2	Copper	2	5	1.99 out of 5	N/A	\$0
Transmission Main	10708		WG	Nooseneck Hill Rd	16	Ductile Iron	115	5	0 out of 5	N/A	\$0
Transmission Main	10709		WG	Nooseneck Hill Rd	16	Ductile Iron	568	5	0 out of 5	N/A	\$0
Transmission Main	11067		WG	Nooseneck Hill Rd	16	Ductile Iron	14	5	0 out of 5	N/A	\$0
Transmission Main	11068		WG	Nooseneck Hill Rd	16	Ductile Iron	15	5	0 out of 5	N/A	\$0
Transmission Main	11358		WG	Nooseneck Hill Rd	16	Ductile Iron	11	5	0 out of 5	N/A	\$0
Distribution Main	7137	P-3040	WG	Nooseneck Hill Rd.	8	Asbestos Cement	220	54	1.14 out of 5	\$442	97,030
Distribution Main	7138	P-3040	WG	Nooseneck Hill Rd.	8	Asbestos Cement	150	54	1.14 out of 5	\$442	66,453
Distribution Main	7140	P-3042	WG	Nooseneck Hill Rd.	8	Asbestos Cement	167	54	1.14 out of 5	\$442	73,849
Distribution Main	7141	P-3042	WG	Nooseneck Hill Rd.	8	Asbestos Cement	598	54	1.14 out of 5	\$442	264,420
Distribution Main	7142	P-3038	WG	Nooseneck Hill Rd.	8	Asbestos Cement	127	54	1.14 out of 5	\$442	56,341
Distribution Main	7143	P-3038	WG	Nooseneck Hill Rd.	8	Asbestos Cement	790	54	1.14 out of 5	\$442	349,254
Distribution Main	7146	P-3044	WG	Nooseneck Hill Rd.	8	Asbestos Cement	140	54	1.14 out of 5	\$442	62,052
Transmission Main	7543	P-3038	WG	Nooseneck Hill Rd.	12	Asbestos Cement	26	54	1.14 out of 5	\$442	11,285
Distribution Main	9437	P-3044	WG	Nooseneck Hill Rd.	8	Asbestos Cement	299	54	1.14 out of 5	\$442	132,013
Distribution Main	7657	P-3024	WG	Old Hickory Rd.	8	Ductile Iron	809	22	0.14 out of 5	N/A	\$0
Distribution Main	7658	P-3024	WG	Old Hickory Rd.	8	Ductile Iron	894	22	0.14 out of 5	N/A	\$0
Distribution Main	9684	P-3026	WG	Old Hickory Rd.	8	Ductile Iron	52	22	0.14 out of 5	N/A	\$0
Distribution Main	5234	P-7455	WG	Pine Hill Rd.	8	Ductile Iron	23	25	0.14 out of 5	N/A	\$0
Distribution Main	7573	P-7454	WG	Pine Hill Rd.	8	Ductile Iron	114	25	0.14 out of 5	N/A	\$0
Distribution Main	7576	P-7454	WG	Pine Hill Rd.	8	Ductile Iron	3	25	0.14 out of 5	N/A	\$0
Distribution Main	7577	P-7455	WG	Pine Hill Rd.	8	Ductile Iron	128	25	0.14 out of 5	N/A	\$0
Distribution Main	7578	P-7455	WG	Pine Hill Rd.	8	Ductile Iron	31	25	0.14 out of 5	N/A	\$0
Distribution Main	7579	P-7455	WG	Pine Hill Rd.	8	Ductile Iron	4	25	0.14 out of 5	N/A	\$0
Distribution Main	7646		WG	Pine Hill Rd.	8	Ductile Iron	4	25	0.14 out of 5	N/A	\$0
Distribution Main	7650	P-7455	WG	Pine Hill Rd.	8	Ductile Iron	4	25	0.14 out of 5	N/A	\$0
Distribution Main	7558	P-3032	WG	Pine Tree Ln.	8	Asbestos Cement	100	48	1.14 out of 5	\$442	44,223
Distribution Main	7559	P-3032	WG	Pine Tree Ln.	8	Asbestos Cement	853	48	1.14 out of 5	\$442	377,117
Distribution Main	7684	P-3028	WG	Pine Tree Ln.	8	Asbestos Cement	874	48	1.14 out of 5	\$442	386,454
Distribution Main	10229	P-3032	WG	Pine Tree Ln.	8	Ductile Iron	26	5	0 out of 5	N/A	\$0
Distribution Main	7580	P-3000	WG	Pinehill Rd.	8	Ductile Iron	174	24	0.14 out of 5	N/A	\$0
Distribution Main	7682	P-3030	WG	Pond View Ct.	6	Asbestos Cement	671	43	1.85 out of 5	\$442	296,764
Distribution Main	7683	P-3030	WG	Pond View Ct.	6	Asbestos Cement	47	43	1.85 out of 5	\$442	20,611
Distribution Main	7664	P-3035	WG	Ragnell Rd.	6	Asbestos Cement	11	43	1.85 out of 5	\$442	4,784
Distribution Main	7665	P-3035	WG	Ragnell Rd.	6	Asbestos Cement	450	43	1.85 out of 5	\$442	198,978
Distribution Main	10686	P-3035	WG	Ragnell Rd.	2	Copper	137	43	2.28 out of 5	\$442	60,769
Distribution Main	7643	P-3064	WG	Roland Dr.	8	Asbestos Cement	617	48	1.14 out of 5	\$442	272,695
Distribution Main	7644	P-3064	WG	Roland Dr.	8	Asbestos Cement	683	48	1.14 out of 5	\$442	301,936
Distribution Main	11982	P-3064	WG	Roland Dr.	8	Asbestos Cement	322	48	1.14 out of 5	\$442	142,111
Distribution Main	7647	P-3015	WG	Seminole Tr.	8	Asbestos Cement	206	48	1.14 out of 5	\$442	91,124

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7648	P-3015	WG	Seminole Tr.	8	Asbestos Cement	318	48	1.14 out of 5	\$442	140,591
Distribution Main	7666	P-3013	WG	Seminole Tr.	8	Asbestos Cement	340	48	1.14 out of 5	\$442	150,080
Transmission Main	68	P-3051	WG	Technology Park Tank	16	Ductile Iron	265	31	0.14 out of 5	\$442	117,221
Transmission Main	65	P-3132	WG	Technology Way	16	Ductile Iron	653	31	0.14 out of 5	\$442	288,448
Transmission Main	2982	P-3050	WG	Technology Way	16	Ductile Iron	483	31	0.14 out of 5	\$442	213,330
Transmission Main	2983	P-3050	WG	Technology Way	16	Ductile Iron	360	31	0.14 out of 5	\$442	159,280
Transmission Main	7623		WG	Technology Way	12	Unknown	2	UNK	0 out of 5	N/A	\$0
Distribution Main	9131		WG	Technology Way	6	Ductile Iron	54	8	0.71 out of 5	N/A	\$0
Transmission Main	9501	P-3100	WG	Technology Way	16	Ductile Iron	108	31	0.14 out of 5	\$442	47,940
Transmission Main	9502	P-3100	WG	Technology Way	16	Ductile Iron	1,103	31	0.14 out of 5	\$442	487,450
Transmission Main	9896	P-3132	WG	Technology Way	16	Ductile Iron	74	31	0.14 out of 5	\$442	32,843
Transmission Main	9979	P-3100	WG	Technology Way	16	Ductile Iron	76	31	0.14 out of 5	\$442	33,683
Transmission Main	9980	P-3100	WG	Technology Way	16	Ductile Iron	334	31	0.14 out of 5	\$442	147,731
Transmission Main	11013	P-3132	WG	Technology Way	16	Ductile Iron	372	31	0.14 out of 5	\$442	164,225
Transmission Main	11621	P-3065	WG	Technology Way	16	Ductile Iron	23	31	0.14 out of 5	\$442	9,989
Transmission Main	11986	P-3050	WG	Technology Way	16	Ductile Iron	42	31	0.14 out of 5	\$442	18,365
Transmission Main	12213	P-3050	WG	Technology Way	16	Ductile Iron	447	31	0.14 out of 5	\$442	197,625
Distribution Main	3687		WG	Terrace Dr	8	Ductile Iron	7	18	0 out of 5	N/A	\$0
Distribution Main	3688		WG	Terrace Dr	8	Ductile Iron	50	18	0 out of 5	N/A	\$0
Distribution Main	8087	P-3084	WG	Tiffany Ln	8	Ductile Iron	647	UNK	0 out of 5	N/A	\$0
Distribution Main	7144	P-3041	WG	Valerie Dr.	8	Asbestos Cement	436	54	1.14 out of 5	\$442	192,585
Distribution Main	7145	P-3041	WG	Valerie Dr.	8	Asbestos Cement	58	50	1.14 out of 5	\$442	25,556
Distribution Main	7555	P-3039	WG	Valerie Dr.	8	Ductile Iron	6	29	0.14 out of 5	\$442	2,686
Transmission Main	7	P-8424	WG	Welgen - 95 Easement	16	Ductile Iron	245	24	0.14 out of 5	N/A	\$0
Transmission Main	8	P-8424	WG	Welgen - 95 Easement	16	Ductile Iron	49	24	0.14 out of 5	N/A	\$0
Transmission Main	51	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	2,480	24	0.14 out of 5	N/A	\$0
Transmission Main	52	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	531	24	0.14 out of 5	N/A	\$0
Transmission Main	53	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	1,025	24	0.14 out of 5	N/A	\$0
Transmission Main	54	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	108	24	0.14 out of 5	N/A	\$0
Transmission Main	55	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	55	24	0.14 out of 5	N/A	\$0
Transmission Main	56	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	257	24	0.14 out of 5	N/A	\$0
Transmission Main	57	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	153	24	0.14 out of 5	N/A	\$0
Transmission Main	58	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	106	24	0.14 out of 5	N/A	\$0
Transmission Main	59	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	131	24	0.14 out of 5	N/A	\$0
Transmission Main	1631	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	101	24	0.14 out of 5	N/A	\$0
Transmission Main	2189	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	164	24	0.14 out of 5	N/A	\$0
Transmission Main	11161	P-3052	WG	Welgen - 95 Easement	16	Ductile Iron	105	24	0.14 out of 5	N/A	\$0
Distribution Main	3093	P-1830	WW	Aberdeen St	6	Cast Iron	349	97	2.43 out of 5	\$442	154,044
Distribution Main	3504	P-971	WW	Aberdeen St	6	Cast Iron	759	97	2.43 out of 5	\$442	335,479
Distribution Main	3505	P-971	WW	Aberdeen St	6	Cast Iron	46	97	2.43 out of 5	\$442	20,322
Distribution Main	8407	P-1677	WW	Aberdeen St	8	Ductile Iron	353	10	0 out of 5	N/A	\$0
Distribution Main	8408	P-1677	WW	Aberdeen St	8	Ductile Iron	11	10	0 out of 5	N/A	\$0
Distribution Main	8477	P-1831	WW	Aberdeen St	6	Ductile Iron	35	10	0.71 out of 5	N/A	\$0
Transmission Main	8478	P-970	WW	Aberdeen St	12	Ductile Iron	4	10	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	8479	P-970	WW	Aberdeen St	12	Ductile Iron	140	10	0 out of 5	N/A	\$0
Distribution Main	8480	P-1829	WW	Aberdeen St	6	Ductile Iron	7	10	0.71 out of 5	N/A	\$0
Transmission Main	9672	P-1828	WW	Aberdeen St	12	Ductile Iron	5	10	0 out of 5	N/A	\$0
Distribution Main	471		WW	Acorn La	8	Asbestos Cement	9	46	1.14 out of 5	\$442	3,961
Distribution Main	1832	P-52	WW	Acorn La	8	Asbestos Cement	359	46	1.14 out of 5	\$442	158,461
Distribution Main	2179	P-55	WW	Acorn La	8	Asbestos Cement	548	46	1.14 out of 5	\$442	242,043
Distribution Main	2180	P-55	WW	Acorn La	8	Asbestos Cement	505	46	1.14 out of 5	\$442	223,401
Distribution Main	3559	P-53	WW	Acorn La	8	Asbestos Cement	186	46	1.14 out of 5	\$442	82,080
Distribution Main	3560	P-53	WW	Acorn La	8	Asbestos Cement	37	46	1.14 out of 5	\$442	16,424
Distribution Main	4632	P-54	WW	Acorn La	8	Asbestos Cement	208	46	1.14 out of 5	\$442	91,853
Distribution Main	4635	P-54	WW	Acorn La	8	Asbestos Cement	43	46	1.14 out of 5	\$442	19,076
Distribution Main	4641	P-53	WW	Acorn La	8	Asbestos Cement	27	46	1.14 out of 5	\$442	11,951
Distribution Main	11160	P-54	WW	Acorn La	8	Asbestos Cement	20	46	1.14 out of 5	\$442	8,695
Transmission Main	1077	P-1275	WW	Acorn Ln	12	Ductile Iron	627	19	0 out of 5	N/A	\$0
Distribution Main	10147	P-1458	WW	Acorn Ln	8	Ductile Iron	16	22	0.14 out of 5	N/A	\$0
Distribution Main	10148	P-1458	WW	Acorn Ln	8	Ductile Iron	10	22	0.14 out of 5	N/A	\$0
Distribution Main	3674	P-710	WW	Agnes St	6	Cast Iron	7	109	2.57 out of 5	\$442	2,912
Distribution Main	3783	P-710	WW	Agnes St	6	Cast Iron	399	109	2.57 out of 5	\$442	176,154
Distribution Main	3522	P-1909	WW	Agnews Court	6	PVC	148	38	1.14 out of 5	\$442	65,247
Distribution Main	3887		WW	Albion St	6	Asbestos Cement	32	70	2 out of 5	\$442	13,986
Distribution Main	3888	P-539	WW	Albion St	6	Asbestos Cement	419	70	2 out of 5	\$442	185,260
Distribution Main	5128	P-539	WW	Albion St	6	Asbestos Cement	7	70	2 out of 5	\$442	3,178
Distribution Main	3585	P-1733	WW	Alden Dr	8	Ductile Iron	18	15	0 out of 5	N/A	\$0
Distribution Main	8912	P-219	WW	Alden Dr	8	Ductile Iron	236	9	0 out of 5	N/A	\$0
Distribution Main	8913	P-1732	WW	Alden Dr	8	Ductile Iron	445	9	0 out of 5	N/A	\$0
Distribution Main	8914	P-1732	WW	Alden Dr	8	Ductile Iron	13	9	0 out of 5	N/A	\$0
Distribution Main	8950	P-1747	WW	Alden Dr	8	Ductile Iron	131	9	0 out of 5	N/A	\$0
Distribution Main	8952	P-203	WW	Alden Dr	8	Ductile Iron	388	9	0 out of 5	N/A	\$0
Distribution Main	8953	P-1743	WW	Alden Dr	8	Ductile Iron	26	9	0 out of 5	N/A	\$0
Distribution Main	8959	P-199	WW	Alden Dr	8	Ductile Iron	309	9	0 out of 5	N/A	\$0
Distribution Main	9397	P-202	WW	Alden Dr	8	Ductile Iron	136	9	0 out of 5	N/A	\$0
Distribution Main	9400	P-1733	WW	Alden Dr	8	Ductile Iron	22	15	0 out of 5	N/A	\$0
Distribution Main	9401	P-1733	WW	Alden Dr	8	Ductile Iron	5	9	0 out of 5	N/A	\$0
Distribution Main	10929	P-201	WW	Alden Dr	8	Ductile Iron	93	9	0 out of 5	N/A	\$0
Distribution Main	10930	P-201	WW	Alden Dr	8	Ductile Iron	25	9	0 out of 5	N/A	\$0
Distribution Main	10931	P-1747	WW	Alden Dr	8	Ductile Iron	110	9	0 out of 5	N/A	\$0
Distribution Main	11529	P-1743	WW	Alden Dr	8	Ductile Iron	87	9	0 out of 5	N/A	\$0
Distribution Main	9733	P-600	WW	Aldrich St	8	Ductile Iron	10	14	0 out of 5	N/A	\$0
Distribution Main	9762	P-600	WW	Aldrich St	8	Ductile Iron	422	14	0 out of 5	N/A	\$0
Distribution Main	9763	P-600	WW	Aldrich St	8	Ductile Iron	38	8	0 out of 5	N/A	\$0
Distribution Main	9775	P-1962	WW	Aldrich St	8	Ductile Iron	624	8	0 out of 5	N/A	\$0
Distribution Main	11601	P-1962	WW	Aldrich St	8	Ductile Iron	47	8	0 out of 5	N/A	\$0
Distribution Main	945	P-9067	WW	Alex St	1	Copper	209	66	2.43 out of 5	\$442	92,532
Transmission Main	1201	P-837	WW	Alexander Dr	12	Ductile Iron	286	18	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	1205	P-837	WW	Alexander Dr	12	Ductile Iron	4	18	0 out of 5	N/A	\$0
Transmission Main	1550	P-836	WW	Alexander Dr	12	Ductile Iron	391	18	0 out of 5	N/A	\$0
Transmission Main	1551	P-836	WW	Alexander Dr	12	Ductile Iron	87	18	0 out of 5	N/A	\$0
Transmission Main	1781	P-836	WW	Alexander Dr	12	Ductile Iron	4	18	0 out of 5	N/A	\$0
Transmission Main	12047	P-836	WW	Alexander Dr	12	Ductile Iron	169	18	0 out of 5	N/A	\$0
Transmission Main	8402	P-972	WW	Alpine St	12	Ductile Iron	172	10	0 out of 5	N/A	\$0
Transmission Main	8403	P-972	WW	Alpine St	12	Ductile Iron	33	10	0 out of 5	N/A	\$0
Transmission Main	8472	P-974	WW	Alpine St	12	Ductile Iron	210	10	0 out of 5	N/A	\$0
Transmission Main	8474	P-1834	WW	Alpine St	12	Ductile Iron	34	10	0 out of 5	N/A	\$0
Transmission Main	8527	P-1228	WW	Ames St	16	Ductile Iron	149	13	0 out of 5	N/A	\$0
Transmission Main	8528	P-1228	WW	Ames St	16	Ductile Iron	232	13	0 out of 5	N/A	\$0
Transmission Main	8529	P-1924	WW	Ames St	12	Ductile Iron	21	10	0 out of 5	N/A	\$0
Transmission Main	8984	P-1211	WW	Ames St	16	Ductile Iron	74	13	0 out of 5	N/A	\$0
Transmission Main	8985	P-1612	WW	Ames St	12	Ductile Iron	50	9	0 out of 5	N/A	\$0
Transmission Main	11042	P-1228	WW	Ames St	16	Ductile Iron	22	13	0 out of 5	N/A	\$0
Distribution Main	2961	P-1720	WW	Anderson Ave	8	Ductile Iron	9	15	0 out of 5	N/A	\$0
Distribution Main	2963	P-82	WW	Anderson Ave	6	Asbestos Cement	117	78	2 out of 5	\$442	51,792
Distribution Main	2965	P-82	WW	Anderson Ave	8	Ductile Iron	28	15	0 out of 5	N/A	\$0
Distribution Main	6555	P-102	WW	Anderson Ave	6	Asbestos Cement	173	78	2 out of 5	\$442	76,625
Distribution Main	6556	P-102	WW	Anderson Ave	6	Asbestos Cement	48	78	2 out of 5	\$442	21,225
Distribution Main	8158	P-82	WW	Anderson Ave	6	Asbestos Cement	48	78	2 out of 5	\$442	21,090
Distribution Main	9377	P-82	WW	Anderson Ave	6	Ductile Iron	3	15	0.71 out of 5	N/A	\$0
Distribution Main	34	P-693	WW	Andrews Ave	2	Galvanized Iron	844	109	3.57 out of 5	\$442	372,918
Distribution Main	132		WW	Andrews Ave	6	Cast Iron	23	133	2.57 out of 5	\$442	10,383
Distribution Main	346	P-1947	WW	Andrews Ave	6	Cast Iron	322	133	2.57 out of 5	\$442	142,383
Distribution Main	347	P-1947	WW	Andrews Ave	6	Cast Iron	19	133	2.57 out of 5	\$442	8,554
Distribution Main	1608	P-693	WW	Andrews Ave	2	Galvanized Iron	20	109	3.57 out of 5	\$442	8,832
Distribution Main	1609	P-693	WW	Andrews Ave	2	Galvanized Iron	12	109	3.57 out of 5	\$442	5,243
Distribution Main	3258	P-1951	WW	Andrews Ave	6	Cast Iron	235	89	2.43 out of 5	\$442	104,061
Distribution Main	3259	P-1951	WW	Andrews Ave	6	Cast Iron	441	89	2.43 out of 5	\$442	194,928
Distribution Main	3669	P-1951	WW	Andrews Ave	6	Cast Iron	341	89	2.43 out of 5	\$442	150,918
Distribution Main	3786	P-1951	WW	Andrews Ave	6	Cast Iron	283	89	2.43 out of 5	\$442	125,036
Distribution Main	3787	P-715	WW	Andrews Ave	2	Galvanized Iron	267	89	4.14 out of 5	\$442	118,063
Distribution Main	9520	P-691	WW	Andrews Ave	6	Cast Iron	291	133	2.57 out of 5	\$442	128,437
Distribution Main	11745	P-1948	WW	Andrews Ave	6	Cast Iron	133	133	2.57 out of 5	\$442	58,677
Transmission Main	3499	P-837	WW	Andrews Drive	12	Ductile Iron	9	18	0 out of 5	N/A	\$0
Transmission Main	3500	P-837	WW	Andrews Drive	12	Ductile Iron	153	18	0 out of 5	N/A	\$0
Distribution Main	9729	P-936	WW	Angell St	6	Ductile Iron	29	22	0.85 out of 5	N/A	\$0
Distribution Main	10353	P-919	WW	Angell St	8	Ductile Iron	1	22	0.14 out of 5	N/A	\$0
Distribution Main	1792	P-1853	WW	Angell St.	2	Galvanized Iron	237	91	3.43 out of 5	\$442	104,655
Distribution Main	1794	P-937	WW	Angell St.	2	Galvanized Iron	261	91	4.14 out of 5	\$442	115,312
Distribution Main	3487	P-936	WW	Angell St.	6	Asbestos Cement	25	42	2.57 out of 5	\$442	10,887
Distribution Main	3488	P-936	WW	Angell St.	6	Asbestos Cement	411	42	1.85 out of 5	\$442	181,677
Distribution Main	3728	P-936	WW	Angell St.	6	Asbestos Cement	8	42	1.85 out of 5	\$442	3,452

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9656	P-1852	WW	Angell St.	2	Galvanized Iron	159	91	3.43 out of 5	\$442	70,343
Distribution Main	11222	P-936	WW	Angell St.	6	Asbestos Cement	4	42	1.85 out of 5	\$442	1,650
Distribution Main	9905	P-1945	WW	April Ct	8	Ductile Iron	195	13	0 out of 5	N/A	\$0
Distribution Main	9906	P-1945	WW	April Ct	8	Ductile Iron	20	13	0 out of 5	N/A	\$0
Distribution Main	12118	P-1945	WW	April Ct	8	Ductile Iron	7	13	0 out of 5	N/A	\$0
Distribution Main	8176	P-1512	WW	Arcadia Rd	8	Ductile Iron	360	13	0 out of 5	N/A	\$0
Distribution Main	8177	P-1512	WW	Arcadia Rd	8	Ductile Iron	207	13	0 out of 5	N/A	\$0
Distribution Main	9648		WW	Archambault Ave	6	Ductile Iron	5	11	0.71 out of 5	N/A	\$0
Distribution Main	10004		WW	Archambault Ave	2	Copper	195	83	2.57 out of 5	\$442	86,059
Transmission Main	160	P-1624	WW	Archambault Ave.	12	Asbestos Cement	151	78	1.29 out of 5	\$442	66,633
Transmission Main	161	P-1624	WW	Archambault Ave.	12	Asbestos Cement	52	78	1.29 out of 5	\$442	22,944
Distribution Main	323	P-1047	WW	Archambault Ave.	6	Cast Iron	90	132	2.57 out of 5	\$442	39,622
Transmission Main	868	P-726	WW	Archambault Ave.	12	Asbestos Cement	25	78	1.29 out of 5	\$442	10,910
Distribution Main	1068		WW	Archambault Ave.	6	Cast Iron	8	132	2.57 out of 5	\$442	3,384
Distribution Main	1572	P-745	WW	Archambault Ave.	6	Cast Iron	214	79	2.28 out of 5	\$442	94,550
Distribution Main	1877	P-1046	WW	Archambault Ave.	6	Cast Iron	321	132	2.57 out of 5	\$442	141,806
Distribution Main	1878	P-1046	WW	Archambault Ave.	6	Cast Iron	23	132	2.57 out of 5	\$442	10,288
Distribution Main	1881	P-1047	WW	Archambault Ave.	6	Cast Iron	3	132	2.57 out of 5	\$442	1,339
Transmission Main	1883	P-1050	WW	Archambault Ave.	12	Asbestos Cement	224	78	1.29 out of 5	\$442	98,929
Distribution Main	2386	P-745	WW	Archambault Ave.	6	Cast Iron	24	79	2.28 out of 5	\$442	10,730
Distribution Main	2387	P-1977	WW	Archambault Ave.	6	Cast Iron	42	79	2.28 out of 5	\$442	18,535
Distribution Main	2389		WW	Archambault Ave.	6	Cast Iron	118	82	2.43 out of 5	\$442	52,210
Transmission Main	2487	P-1979	WW	Archambault Ave.	12	Asbestos Cement	190	78	1.29 out of 5	\$442	83,894
Transmission Main	2488	P-1979	WW	Archambault Ave.	12	Asbestos Cement	16	78	1.29 out of 5	\$442	7,125
Transmission Main	2491	P-1675	WW	Archambault Ave.	12	Asbestos Cement	330	78	1.29 out of 5	\$442	146,009
Transmission Main	3130	P-1314	WW	Archambault Ave.	12	Asbestos Cement	86	75	1.29 out of 5	\$442	38,129
Transmission Main	3131	P-1049	WW	Archambault Ave.	12	Asbestos Cement	74	75	1.29 out of 5	\$442	32,814
Transmission Main	3244	P-746	WW	Archambault Ave.	12	Asbestos Cement	313	78	1.29 out of 5	\$442	138,300
Transmission Main	3245	P-746	WW	Archambault Ave.	12	Asbestos Cement	41	78	1.29 out of 5	\$442	18,250
Transmission Main	3251	P-1049	WW	Archambault Ave.	12	Asbestos Cement	2	78	1.29 out of 5	\$442	1,003
Transmission Main	3252	P-1049	WW	Archambault Ave.	12	Asbestos Cement	346	78	1.29 out of 5	\$442	153,038
Transmission Main	3773	P-726	WW	Archambault Ave.	12	Asbestos Cement	384	78	1.29 out of 5	\$442	169,879
Distribution Main	3793		WW	Archambault Ave.	6	Cast Iron	23	82	2.43 out of 5	\$442	9,955
Transmission Main	4287	P-1314	WW	Archambault Ave.	12	Asbestos Cement	152	75	1.29 out of 5	\$442	67,392
Transmission Main	4289	P-1338	WW	Archambault Ave.	12	Asbestos Cement	213	75	1.29 out of 5	\$442	94,002
Transmission Main	4290	P-1338	WW	Archambault Ave.	12	Asbestos Cement	127	75	1.29 out of 5	\$442	56,028
Distribution Main	4291		WW	Archambault Ave.	6	Unknown	4	UNK	0.71 out of 5	\$442	1,986
Transmission Main	11043	P-1624	WW	Archambault Ave.	12	Asbestos Cement	14	78	1.29 out of 5	\$442	6,216
Transmission Main	11145	P-1624	WW	Archambault Ave.	12	Asbestos Cement	4	78	1.29 out of 5	\$442	1,802
Transmission Main	11206	P-746	WW	Archambault Ave.	12	Asbestos Cement	142	78	1.29 out of 5	\$442	62,932
Transmission Main	11250	P-1314	WW	Archambault Ave.	12	Asbestos Cement	4	75	1.29 out of 5	\$442	1,766
Transmission Main	11993	P-746	WW	Archambault Ave.	12	Asbestos Cement	39	78	1.29 out of 5	\$442	17,282
Transmission Main	12150	P-746	WW	Archambault Ave.	12	Asbestos Cement	3	78	1.29 out of 5	\$442	1,510
Distribution Main	2435	P-1388	WW	Arrow Ct.	6	Ductile Iron	213	28	0.85 out of 5	\$442	94,224

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2159	P-579	WW	Arthur St.	2	Galvanized Iron	16	84	3.43 out of 5	\$442	6,897
Distribution Main	2392	P-579	WW	Arthur St.	2	Galvanized Iron	538	84	3.43 out of 5	\$442	237,855
Distribution Main	2393	P-579	WW	Arthur St.	2	Galvanized Iron	120	84	3.43 out of 5	\$442	53,095
Distribution Main	3111	P-562	WW	Arthur St.	6	Asbestos Cement	11	79	2 out of 5	\$442	5,047
Distribution Main	3971	P-562	WW	Arthur St.	6	Asbestos Cement	435	79	2 out of 5	\$442	192,478
Distribution Main	3972	P-562	WW	Arthur St.	6	Asbestos Cement	28	79	2 out of 5	\$442	12,529
Distribution Main	3973	P-571	WW	Arthur St.	6	Asbestos Cement	9	79	2 out of 5	\$442	4,143
Distribution Main	4306	P-571	WW	Arthur St.	6	Asbestos Cement	7	79	2 out of 5	\$442	2,931
Distribution Main	4321	P-562	WW	Arthur St.	6	Asbestos Cement	7	79	2 out of 5	\$442	3,204
Distribution Main	4332	P-571	WW	Arthur St.	6	Asbestos Cement	325	79	2 out of 5	\$442	143,694
Distribution Main	5062	P-579	WW	Arthur St.	2	Galvanized Iron	9	84	3.43 out of 5	\$442	4,052
Distribution Main	3890		WW	Ashton St.	6	PVC	21	35	1.14 out of 5	\$442	9,082
Distribution Main	5110	P-543	WW	Ashton St.	6	PVC	265	35	1.14 out of 5	\$442	117,013
Distribution Main	12024	P-543	WW	Ashton St.	6	PVC	26	35	1.14 out of 5	\$442	11,675
Distribution Main	10731	P-225	WW	Aster St	8	Ductile Iron	610	1	0 out of 5	N/A	\$0
Distribution Main	10732	P-226	WW	Aster St	8	Ductile Iron	181	1	0 out of 5	N/A	\$0
Distribution Main	11714	P-226	WW	Aster St	8	Ductile Iron	53	1	0 out of 5	N/A	\$0
Distribution Main	7131		WW	Aster St.	6	Asbestos Cement	3	46	1.85 out of 5	\$442	1,454
Distribution Main	10119	P-433	WW	Atlantic Ave	1	Copper	205	UNK	1.99 out of 5	\$442	90,784
Distribution Main	804	P-433	WW	Atlantic Ave.	6	Asbestos Cement	13	53	1.85 out of 5	\$442	5,699
Distribution Main	805	P-433	WW	Atlantic Ave.	6	Asbestos Cement	535	53	1.85 out of 5	\$442	236,473
Distribution Main	4438	P-434	WW	Atlantic Ave.	6	Asbestos Cement	284	53	1.85 out of 5	\$442	125,632
Distribution Main	4439	P-434	WW	Atlantic Ave.	6	Asbestos Cement	169	53	1.85 out of 5	\$442	74,682
Distribution Main	8406	P-1832	WW	Atwood St	8	Ductile Iron	16	10	0 out of 5	N/A	\$0
Distribution Main	8475	P-1833	WW	Atwood St	6	Ductile Iron	5	10	0.71 out of 5	N/A	\$0
Distribution Main	8476	P-1833	WW	Atwood St	6	Ductile Iron	2	10	0.71 out of 5	N/A	\$0
Distribution Main	9456	P-1840	WW	Atwood St	1	Unknown	8	UNK	1.42 out of 5	\$442	3,529
Distribution Main	9457	P-1840	WW	Atwood St	1	Unknown	244	UNK	1.42 out of 5	\$442	108,061
Distribution Main	3694	P-973	WW	Atwood St.	6	Asbestos Cement	190	42	1.85 out of 5	\$442	84,002
Distribution Main	3695	P-973	WW	Atwood St.	6	Asbestos Cement	487	42	1.85 out of 5	\$442	215,328
Distribution Main	10024	P-1755	WW	Auburn St	8	Ductile Iron	204	6	0 out of 5	N/A	\$0
Distribution Main	10025	P-1755	WW	Auburn St	8	Ductile Iron	20	6	0 out of 5	N/A	\$0
Distribution Main	10812	P-282	WW	Auburn St	8	Ductile Iron	187	6	0 out of 5	N/A	\$0
Distribution Main	3882	P-449	WW	Audrey Dr.	6	Asbestos Cement	304	41	1.85 out of 5	\$442	134,154
Distribution Main	3883	P-449	WW	Audrey Dr.	6	Asbestos Cement	212	41	1.85 out of 5	\$442	93,822
Distribution Main	1146	P-300	WW	Babcock St.	8	Asbestos Cement	257	52	1.14 out of 5	\$442	113,592
Distribution Main	1147	P-296	WW	Babcock St.	8	Asbestos Cement	221	52	1.14 out of 5	\$442	97,813
Distribution Main	1151	P-298	WW	Babcock St.	8	Asbestos Cement	201	52	1.14 out of 5	\$442	88,742
Distribution Main	8706	P-296	WW	Babcock St.	8	Asbestos Cement	86	52	1.14 out of 5	\$442	38,120
Distribution Main	1210	P-681	WW	Baker St.	2	Galvanized Iron	33	119	3.57 out of 5	\$442	14,802
Distribution Main	3772	P-1489	WW	Baker St.	2	Galvanized Iron	434	119	3.57 out of 5	\$442	191,935
Distribution Main	10017	P-275	WW	Ball Ave	8	Ductile Iron	89	6	0 out of 5	N/A	\$0
Distribution Main	10029	P-275	WW	Ball Ave	8	Ductile Iron	196	6	0 out of 5	N/A	\$0
Distribution Main	10030	P-275	WW	Ball Ave	8	Ductile Iron	38	6	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11630	P-275	WW	Ball Ave	8	Ductile Iron	133	6	0 out of 5	N/A	\$0
Distribution Main	11998	P-275	WW	Ball Ave	8	Ductile Iron	53	6	0 out of 5	N/A	\$0
Distribution Main	608	P-1052	WW	Bank St.	6	Cast Iron	23	129	2.57 out of 5	\$442	10,157
Distribution Main	9206	P-1054	WW	Bank St.	8	Ductile Iron	248	8	0 out of 5	N/A	\$0
Distribution Main	11554	P-1981	WW	Bank St.	8	Ductile Iron	92	8	0 out of 5	N/A	\$0
Distribution Main	10055	P-250	WW	Barbers Ct	6	Ductile Iron	15	6	0.71 out of 5	N/A	\$0
Distribution Main	5206	P-250	WW	Barbers Ct.	6	Ductile Iron	300	19	0.71 out of 5	N/A	\$0
Distribution Main	2851	P-732	WW	Barnes St.	8	Cast Iron	100	83	1.72 out of 5	\$442	44,327
Distribution Main	3246	P-744	WW	Barnes St.	8	Cast Iron	268	83	1.72 out of 5	\$442	118,293
Distribution Main	3800	P-734	WW	Barnes St.	8	Cast Iron	14	83	1.72 out of 5	\$442	6,273
Distribution Main	3801	P-734	WW	Barnes St.	8	Cast Iron	144	83	1.72 out of 5	\$442	63,612
Distribution Main	11190	P-732	WW	Barnes St.	8	Cast Iron	79	83	2.43 out of 5	\$442	34,720
Distribution Main	11233	P-734	WW	Barnes St.	8	Cast Iron	1	83	1.72 out of 5	\$442	613
Distribution Main	9764	P-598	WW	Barnold St	8	Ductile Iron	387	8	0 out of 5	N/A	\$0
Distribution Main	9778	P-624	WW	Barnold St	8	Ductile Iron	556	8	0 out of 5	N/A	\$0
Distribution Main	11602	P-624	WW	Barnold St	8	Ductile Iron	109	8	0 out of 5	N/A	\$0
Distribution Main	9734	P-598	WW	Barnold St.	8	Ductile Iron	12	14	0 out of 5	N/A	\$0
Distribution Main	4656	P-504	WW	Bayberry Dr.	6	Asbestos Cement	3	55	1.85 out of 5	\$442	1,515
Distribution Main	4657	P-504	WW	Bayberry Dr.	6	Asbestos Cement	740	55	1.85 out of 5	\$442	327,069
Distribution Main	3775	P-698	WW	Beauchene St.	6	Cast Iron	22	131	2.57 out of 5	\$442	9,868
Distribution Main	3776	P-698	WW	Beauchene St.	6	Cast Iron	205	131	2.57 out of 5	\$442	90,501
Distribution Main	10728	P-229	WW	Begonia St	8	Ductile Iron	369	1	0 out of 5	N/A	\$0
Distribution Main	10729	P-229	WW	Begonia St	8	Ductile Iron	193	1	0 out of 5	N/A	\$0
Distribution Main	10616	P-405	WW	Bel-Air Av	8	Ductile Iron	212	2	0 out of 5	N/A	\$0
Distribution Main	10617	P-405	WW	Bel-Air Av	8	Ductile Iron	268	2	0 out of 5	N/A	\$0
Distribution Main	3975	P-575	WW	Bell St.	6	Asbestos Cement	461	44	1.85 out of 5	\$442	203,546
Distribution Main	4307	P-575	WW	Bell St.	6	Asbestos Cement	11	44	1.85 out of 5	\$442	5,035
Distribution Main	2695	P-8037	WW	Bennett St.	2	Galvanized Iron	300	119	3.57 out of 5	\$442	132,758
Distribution Main	2721	P-9059	WW	Bennett St.	1	Copper	135	67	2.43 out of 5	\$442	59,494
Distribution Main	2724	P-8037	WW	Bennett St.	2	Galvanized Iron	26	119	3.57 out of 5	\$442	11,363
Distribution Main	3127	P-541	WW	Berkeley St.	2	PVC	159	35	1.85 out of 5	\$442	70,440
Distribution Main	3128	P-541	WW	Berkeley St.	2	PVC	133	35	1.85 out of 5	\$442	58,918
Distribution Main	5126	P-541	WW	Berkeley St.	2	PVC	23	35	1.85 out of 5	\$442	10,213
Distribution Main	3484	P-938	WW	Bettez St.	4	Cast Iron	217	134	3.29 out of 5	\$442	96,084
Distribution Main	3485	P-938	WW	Bettez St.	4	Cast Iron	327	134	3.29 out of 5	\$442	144,453
Distribution Main	3730	P-938	WW	Bettez St.	4	Cast Iron	2	134	3.29 out of 5	\$442	880
Distribution Main	11760	P-938	WW	Bettez St.	4	Cast Iron	247	134	3.29 out of 5	\$442	109,274
Distribution Main	1821	P-151	WW	Birchwood Ln	8	Asbestos Cement	396	50	1.14 out of 5	\$442	175,087
Distribution Main	2216	P-150	WW	Birchwood Ln	8	Asbestos Cement	123	50	1.14 out of 5	\$442	54,566
Distribution Main	2212	P-141	WW	Birchwood Ln.	8	Asbestos Cement	365	50	1.14 out of 5	\$442	161,252
Distribution Main	4650	P-148	WW	Birchwood Ln.	8	Asbestos Cement	61	50	1.14 out of 5	\$442	27,002
Distribution Main	4651	P-148	WW	Birchwood Ln.	8	Asbestos Cement	4	50	1.14 out of 5	\$442	1,767
Distribution Main	10658		WW	Bishop St	8	Ductile Iron	197	2	0 out of 5	N/A	\$0
Distribution Main	10659	P-373	WW	Bishop St	8	Ductile Iron	283	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	131	P-1956	WW	Blanchard St	1	Unknown	15	UNK	1.42 out of 5	\$442	6,806
Distribution Main	3774	P-1956	WW	Blanchard St	1	Unknown	84	UNK	1.42 out of 5	\$442	37,000
Distribution Main	174	P-578	WW	Bleach Ave	6	Cast Iron	207	83	2.43 out of 5	\$442	91,648
Distribution Main	3105	P-578	WW	Bleach Ave	8	Ductile Iron	13	14	0 out of 5	N/A	\$0
Distribution Main	3106	P-578	WW	Bleach Ave	8	Ductile Iron	11	14	0 out of 5	N/A	\$0
Distribution Main	9370	P-578	WW	Bleach Ave	6	Ductile Iron	5	14	0.71 out of 5	N/A	\$0
Distribution Main	10015	P-280	WW	Blossom St	8	Ductile Iron	179	6	0 out of 5	N/A	\$0
Distribution Main	10019	P-1754	WW	Blossom St	8	Ductile Iron	135	6	0 out of 5	N/A	\$0
Distribution Main	10020	P-1754	WW	Blossom St	8	Ductile Iron	133	6	0 out of 5	N/A	\$0
Distribution Main	10811	P-283	WW	Blossom St	8	Ductile Iron	406	6	0 out of 5	N/A	\$0
Distribution Main	10813	P-281	WW	Blossom St	8	Ductile Iron	236	6	0 out of 5	N/A	\$0
Distribution Main	10791	P-352	WW	Border St	8	Ductile Iron	407	0	0 out of 5	N/A	\$0
Distribution Main	10792	P-351	WW	Border St	8	Ductile Iron	601	0	0 out of 5	N/A	\$0
Distribution Main	11732	P-347	WW	Border St	8	Ductile Iron	236	0	0 out of 5	N/A	\$0
Distribution Main	11733	P-10068	WW	Border St	8	Ductile Iron	200	0	0 out of 5	N/A	\$0
Distribution Main	12037	P-10068	WW	Border St	8	Ductile Iron	166	0	0 out of 5	N/A	\$0
Distribution Main	12038	P-347	WW	Border St	8	Ductile Iron	210	0	0 out of 5	N/A	\$0
Distribution Main	12041	P-347	WW	Border St	8	Ductile Iron	157	0	0 out of 5	N/A	\$0
Distribution Main	12201	P-347	WW	Border St	8	Ductile Iron	144	0	0 out of 5	N/A	\$0
Distribution Main	3672	P-763	WW	Bouchard St.	6	Asbestos Cement	19	52	1.85 out of 5	\$442	8,377
Distribution Main	3785	P-763	WW	Bouchard St.	6	Asbestos Cement	412	52	1.85 out of 5	\$442	182,202
Distribution Main	4824	P-522	WW	Boucher St.	6	Asbestos Cement	12	51	1.85 out of 5	\$442	5,352
Distribution Main	4825	P-522	WW	Boucher St.	6	Asbestos Cement	348	51	1.85 out of 5	\$442	153,969
Distribution Main	5095	P-523	WW	Boucher St.	6	Asbestos Cement	214	51	1.85 out of 5	\$442	94,401
Distribution Main	10304	P-1765	WW	Bowen Ct	6	Ductile Iron	160	25	0.85 out of 5	N/A	\$0
Transmission Main	7498	P-265	WW	Bowen Ct.	12	Ductile Iron	126	25	0.14 out of 5	N/A	\$0
Distribution Main	3096	P-1660	WW	Bradford Court	6	Asbestos Cement	417	44	1.85 out of 5	\$442	184,252
Distribution Main	3525	P-1661	WW	Bradford Court	6	Asbestos Cement	135	72	2.71 out of 5	\$442	59,540
Distribution Main	8386	P-1660	WW	Bradford Ct	8	Ductile Iron	14	10	0 out of 5	N/A	\$0
Distribution Main	8450	P-1660	WW	Bradford Ct	6	Ductile Iron	5	10	0.71 out of 5	N/A	\$0
Distribution Main	3379	P-1287	WW	Bradley Court	6	Unknown	158	79	1.14 out of 5	\$442	69,618
Distribution Main	9657	P-1880	WW	Bradley Ct	1	PVC	93	28	1.85 out of 5	\$442	41,176
Distribution Main	289	P-1287	WW	Bradley Ct.	6	Cast Iron	177	133	2.57 out of 5	\$442	78,410
Distribution Main	290	P-1287	WW	Bradley Ct.	6	Cast Iron	54	133	2.57 out of 5	\$442	24,026
Distribution Main	4627	P-59	WW	Bramble Lane	8	Asbestos Cement	665	46	1.14 out of 5	\$442	293,764
Distribution Main	4628	P-59	WW	Bramble Lane	8	Asbestos Cement	521	46	1.14 out of 5	\$442	230,260
Transmission Main	464	P-1372	WW	Bratt Ln.	12	Ductile Iron	616	19	0 out of 5	N/A	\$0
Distribution Main	465	P-1372	WW	Bratt Ln.	8	Ductile Iron	12	19	0 out of 5	N/A	\$0
Transmission Main	983	P-1372	WW	Bratt Ln.	12	Ductile Iron	413	19	0 out of 5	N/A	\$0
Distribution Main	1833	P-1376	WW	Bratt Ln.	8	Asbestos Cement	204	44	1.14 out of 5	\$442	90,068
Distribution Main	4642	P-1371	WW	Bratt Ln.	8	Asbestos Cement	846	44	1.14 out of 5	\$442	373,786
Distribution Main	4643	P-1371	WW	Bratt Ln.	8	Asbestos Cement	111	44	1.14 out of 5	\$442	48,933
Transmission Main	9500	P-1372	WW	Bratt Ln.	12	Ductile Iron	217	19	0 out of 5	N/A	\$0
Distribution Main	10164	P-1371	WW	Bratt Ln.	8	Asbestos Cement	1	44	1.14 out of 5	\$442	383

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11060	P-1372	WW	Bratt Ln.	12	Ductile Iron	16	19	0 out of 5	N/A	\$0
Distribution Main	11061	P-1371	WW	Bratt Ln.	8	Asbestos Cement	6	44	1.14 out of 5	\$442	2,820
Distribution Main	12208	P-1371	WW	Bratt Ln.	8	Asbestos Cement	70	44	1.14 out of 5	\$442	30,935
Distribution Main	10053	P-278	WW	Brayton Ave	8	Ductile Iron	47	18	0 out of 5	N/A	\$0
Distribution Main	1606	P-1011	WW	Brayton St.	4	Cast Iron	261	134	3.29 out of 5	\$442	115,429
Distribution Main	1607	P-1011	WW	Brayton St.	4	Cast Iron	462	134	3.29 out of 5	\$442	204,002
Distribution Main	4313	P-548	WW	Brewster Ave.	6	Cast Iron	203	109	2.57 out of 5	\$442	89,811
Distribution Main	3432	P-142	WW	Brichwood Ln.	8	Asbestos Cement	198	50	1.14 out of 5	\$442	87,635
Distribution Main	3433	P-142	WW	Brichwood Ln.	8	Asbestos Cement	280	50	1.14 out of 5	\$442	123,666
Distribution Main	3988	P-643	WW	Bridal Ave.	6	Cast Iron	169	97	2.43 out of 5	\$442	74,489
Distribution Main	3989	P-645	WW	Bridal Ave.	6	Cast Iron	22	97	2.43 out of 5	\$442	9,583
Distribution Main	4006	P-1614	WW	Bridal Ave.	6	Cast Iron	491	97	2.43 out of 5	\$442	216,890
Distribution Main	4007	P-1614	WW	Bridal Ave.	6	Cast Iron	172	97	2.43 out of 5	\$442	76,163
Distribution Main	4326	P-645	WW	Bridal Ave.	6	Cast Iron	96	97	2.43 out of 5	\$442	42,321
Distribution Main	9667	P-1616	WW	Bridal Ave.	6	Cast Iron	71	97	2.43 out of 5	\$442	31,251
Distribution Main	9668	P-1616	WW	Bridal Ave.	6	Cast Iron	37	97	2.43 out of 5	\$442	16,315
Distribution Main	12031		WW	Bridal Ave.	6	Cast Iron	54	UNK	1.85 out of 5	\$442	23,850
Distribution Main	12032	P-643	WW	Bridal Ave.	6	Cast Iron	3	97	2.43 out of 5	\$442	1,391
Distribution Main	12033	P-1616	WW	Bridal Ave.	6	Cast Iron	4	97	2.43 out of 5	\$442	1,781
Distribution Main	431	P-1017	WW	Bridge St.	6	Cast Iron	264	84	2.43 out of 5	\$442	116,873
Distribution Main	438	P-997	WW	Bridge St.	4	Cast Iron	97	84	3.14 out of 5	\$442	42,989
Distribution Main	439	P-1003	WW	Bridge St.	6	Cast Iron	12	84	2.43 out of 5	\$442	5,485
Distribution Main	1601	P-997	WW	Bridge St.	4	Cast Iron	22	84	3.14 out of 5	\$442	9,616
Distribution Main	3328	P-997	WW	Bridge St.	4	Cast Iron	432	84	3.14 out of 5	\$442	190,989
Distribution Main	3329	P-997	WW	Bridge St.	4	Cast Iron	412	84	3.14 out of 5	\$442	181,933
Distribution Main	3336	P-1003	WW	Bridge St.	6	Cast Iron	7	84	2.43 out of 5	\$442	3,125
Distribution Main	3349	P-1017	WW	Bridge St.	6	Cast Iron	24	84	2.43 out of 5	\$442	10,518
Distribution Main	3363	P-1002	WW	Bridge St.	6	Cast Iron	63	84	2.43 out of 5	\$442	27,693
Distribution Main	3364	P-1002	WW	Bridge St.	6	Cast Iron	574	84	2.43 out of 5	\$442	253,809
Distribution Main	4137	P-1192	WW	Brisas Dr.	6	Asbestos Cement	171	49	1.85 out of 5	\$442	75,421
Distribution Main	5160	P-1192	WW	Brisas Dr.	6	Asbestos Cement	19	49	1.85 out of 5	\$442	8,216
Transmission Main	8387	P-1910	WW	Broad St	12	Ductile Iron	6	10	0 out of 5	N/A	\$0
Transmission Main	8388	P-1910	WW	Broad St	12	Ductile Iron	340	10	0 out of 5	N/A	\$0
Transmission Main	8456	P-1910	WW	Broad St	12	Ductile Iron	32	10	0 out of 5	N/A	\$0
Distribution Main	8424	P-1816	WW	Brook St	8	Ductile Iron	19	10	0 out of 5	N/A	\$0
Distribution Main	3196	P-948	WW	Brook St.	6	Ductile Iron	353	27	0.85 out of 5	\$442	156,062
Distribution Main	3495	P-948	WW	Brook St.	6	Ductile Iron	41	27	0.85 out of 5	\$442	18,223
Distribution Main	9455	P-1817	WW	Brook St.	2	Unknown	220	27	1.57 out of 5	\$442	97,289
Distribution Main	8960	P-203	WW	Brookdale Dr	8	Ductile Iron	10	9	0 out of 5	N/A	\$0
Distribution Main	8961	P-203	WW	Brookdale Dr	8	Ductile Iron	3	9	0 out of 5	N/A	\$0
Distribution Main	8966	P-203	WW	Brookdale Dr	6	Ductile Iron	6	9	0.71 out of 5	N/A	\$0
Distribution Main	4389		WW	Brookdale Dr.	6	Asbestos Cement	18	62	2 out of 5	\$442	8,006
Distribution Main	4935	P-203	WW	Brookdale Dr.	6	Asbestos Cement	707	62	2 out of 5	\$442	312,574
Distribution Main	4949	P-203	WW	Brookdale Dr.	8	Asbestos Cement	47	62	1.29 out of 5	\$442	20,948

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	7482	P-203	WW	Brookdale Dr.	8	Asbestos Cement	12	62	1.29 out of 5	\$442	5,200
Distribution Main	9614	P-1793	WW	Brookfield Dr	1	Copper	118	64	2.43 out of 5	\$442	52,116
Distribution Main	1527		WW	Brookfield Dr.	6	Asbestos Cement	9	47	1.85 out of 5	\$442	3,864
Distribution Main	1532	P-1792	WW	Brookfield Dr.	6	Ductile Iron	63	22	0.85 out of 5	N/A	\$0
Distribution Main	3193	P-848	WW	Brookfield Dr.	6	Asbestos Cement	141	47	2 out of 5	\$442	62,150
Distribution Main	3194		WW	Brookfield Dr.	6	Asbestos Cement	143	47	1.85 out of 5	\$442	63,175
Distribution Main	12071	P-1792	WW	Brookfield Dr.	6	Ductile Iron	7	22	0.85 out of 5	N/A	\$0
Distribution Main	134	P-672	WW	Brookside Ave.	8	Cast Iron	35	97	1.72 out of 5	\$442	15,278
Distribution Main	2280	P-702	WW	Brookside Ave.	8	Ductile Iron	136	19	0 out of 5	N/A	\$0
Distribution Main	2281	P-702	WW	Brookside Ave.	8	Ductile Iron	69	19	0 out of 5	N/A	\$0
Distribution Main	2282	P-672	WW	Brookside Ave.	8	Cast Iron	184	97	1.72 out of 5	\$442	81,399
Distribution Main	2887	P-653	WW	Brookside Ave.	8	Cast Iron	37	134	1.86 out of 5	\$442	16,506
Distribution Main	2899	P-655	WW	Brookside Ave.	8	Cast Iron	728	134	1.86 out of 5	\$442	321,916
Distribution Main	2900	P-655	WW	Brookside Ave.	8	Cast Iron	56	134	1.86 out of 5	\$442	24,750
Distribution Main	3768	P-664	WW	Brookside Ave.	10	Cast Iron	189	134	1.86 out of 5	\$442	83,443
Distribution Main	3769	P-664	WW	Brookside Ave.	10	Cast Iron	312	134	1.86 out of 5	\$442	138,095
Distribution Main	3781	P-701	WW	Brookside Ave.	8	Cast Iron	344	97	1.72 out of 5	\$442	152,129
Distribution Main	3782	P-701	WW	Brookside Ave.	8	Cast Iron	12	97	1.72 out of 5	\$442	5,418
Distribution Main	3985	P-655	WW	Brookside Ave.	8	Cast Iron	14	134	1.86 out of 5	\$442	6,059
Distribution Main	3986	P-653	WW	Brookside Ave.	8	Cast Iron	484	134	1.86 out of 5	\$442	214,000
Distribution Main	3987	P-653	WW	Brookside Ave.	8	Cast Iron	224	134	1.86 out of 5	\$442	99,196
Distribution Main	4703		WW	Brown St	6	Unknown	365	UNK	0.71 out of 5	\$442	161,508
Distribution Main	4704		WW	Brown St	6	Unknown	11	UNK	0.71 out of 5	\$442	5,080
Distribution Main	12015		WW	Brown St	6	Unknown	3	UNK	0.71 out of 5	\$442	1,394
Distribution Main	9794	P-637	WW	Bryant Pl	8	Ductile Iron	176	8	0 out of 5	N/A	\$0
Distribution Main	9795	P-637	WW	Bryant Pl	8	Ductile Iron	57	8	0 out of 5	N/A	\$0
Distribution Main	9798	P-637	WW	Bryant Pl	8	Ductile Iron	203	8	0 out of 5	N/A	\$0
Distribution Main	3114	P-521	WW	Buckley Ave.	6	Asbestos Cement	220	65	2 out of 5	\$442	97,084
Distribution Main	5096	P-520	WW	Buckley Ave.	6	Asbestos Cement	248	65	2 out of 5	\$442	109,477
Distribution Main	5097	P-520	WW	Buckley Ave.	6	Asbestos Cement	23	65	2 out of 5	\$442	10,264
Distribution Main	8428	P-898	WW	Buehler Dr	8	Ductile Iron	30	10	0 out of 5	N/A	\$0
Distribution Main	8499	P-898	WW	Buehler Dr	6	Ductile Iron	12	10	0.71 out of 5	N/A	\$0
Distribution Main	481	P-1795	WW	Buehler Dr.	6	Asbestos Cement	181	66	2 out of 5	\$442	80,071
Distribution Main	1007	P-897	WW	Buehler Dr.	6	Asbestos Cement	241	66	2 out of 5	\$442	106,657
Distribution Main	11064	P-1795	WW	Buehler Dr.	6	Asbestos Cement	27	66	2 out of 5	\$442	12,127
Distribution Main	8435	P-1794	WW	Bueller Dr	6	Ductile Iron	17	10	0.71 out of 5	N/A	\$0
Distribution Main	8436	P-1794	WW	Bueller Dr	6	Ductile Iron	2	10	0.71 out of 5	N/A	\$0
Distribution Main	9416	P-1794	WW	Bueller Dr	8	Ductile Iron	4	10	0 out of 5	N/A	\$0
Distribution Main	1408	P-686	WW	Burlingame Rd.	8	PVC	191	38	0.43 out of 5	\$442	84,309
Distribution Main	1409	P-686	WW	Burlingame Rd.	8	PVC	273	38	0.43 out of 5	\$442	120,487
Distribution Main	1553	P-1786	WW	Burlingame Rd.	8	PVC	21	38	0.43 out of 5	\$442	9,299
Distribution Main	3188	P-1786	WW	Burlingame Rd.	8	PVC	688	38	0.43 out of 5	\$442	304,172
Distribution Main	3189	P-1786	WW	Burlingame Rd.	8	PVC	745	38	0.43 out of 5	\$442	329,114
Distribution Main	11128	P-686	WW	Burlingame Rd.	8	PVC	14	38	0.43 out of 5	\$442	6,154

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11204	P-1786	WW	Burlingame Rd.	8	PVC	18	38	0.43 out of 5	\$442	7,946
Distribution Main	12070	P-686	WW	Burlingame Rd.	8	PVC	13	38	0.43 out of 5	\$442	5,749
Distribution Main	10016	P-1759	WW	Burns St	8	Ductile Iron	252	6	0 out of 5	N/A	\$0
Distribution Main	10031	P-1759	WW	Burns St	8	Ductile Iron	124	6	0 out of 5	N/A	\$0
Distribution Main	4693	P-1161	WW	Campbell St.	6	Asbestos Cement	404	67	2 out of 5	\$442	178,749
Distribution Main	4694	P-1161	WW	Campbell St.	6	Asbestos Cement	922	67	2 out of 5	\$442	407,370
Distribution Main	5124	P-1158	WW	Campbell St.	6	Asbestos Cement	16	67	2 out of 5	\$442	6,898
Distribution Main	2149	P-297	WW	Cantara St.	6	Asbestos Cement	313	52	1.85 out of 5	\$442	138,271
Distribution Main	2150	P-297	WW	Cantara St.	6	Asbestos Cement	308	52	1.85 out of 5	\$442	136,144
Distribution Main	2157	P-1487	WW	Capron St.	2	Cast Iron	268	109	3.29 out of 5	\$442	118,457
Distribution Main	4309	P-1486	WW	Capron St.	4	Cast Iron	10	109	3.29 out of 5	\$442	4,244
Distribution Main	4310	P-1486	WW	Capron St.	4	Cast Iron	448	109	3.29 out of 5	\$442	198,009
Distribution Main	1751	P-437	WW	Carder St.	6	PVC	488	33	1.14 out of 5	\$442	215,887
Distribution Main	1752	P-437	WW	Carder St.	6	PVC	8	33	1.14 out of 5	\$442	3,490
Distribution Main	3120	P-515	WW	Carlson Cir.	6	Asbestos Cement	8	69	2 out of 5	\$442	3,371
Distribution Main	3885	P-529	WW	Carlson Cir.	6	Asbestos Cement	160	69	2 out of 5	\$442	70,793
Distribution Main	3886	P-529	WW	Carlson Cir.	6	Asbestos Cement	462	69	2 out of 5	\$442	204,210
Distribution Main	4826	P-515	WW	Carlson Cir.	6	Asbestos Cement	19	69	2 out of 5	\$442	8,305
Distribution Main	4827	P-515	WW	Carlson Cir.	6	Asbestos Cement	278	69	2 out of 5	\$442	122,711
Distribution Main	5098	P-516	WW	Carlson Cir.	6	Asbestos Cement	423	69	2 out of 5	\$442	186,924
Distribution Main	5135	P-529	WW	Carlson Cir.	6	Asbestos Cement	211	69	2 out of 5	\$442	93,322
Distribution Main	10900		WW	Carlson Cir.	6	Asbestos Cement	6	69	2 out of 5	\$442	2,598
Distribution Main	2896	P-549	WW	Carlton Pl.	6	Asbestos Cement	370	65	2 out of 5	\$442	163,334
Distribution Main	8675	P-1775	WW	Carnival Ter	8	Ductile Iron	35	15	0 out of 5	N/A	\$0
Distribution Main	8676	P-1775	WW	Carnival Ter	8	Ductile Iron	560	15	0 out of 5	N/A	\$0
Distribution Main	3564	P-98	WW	Carolyn Dr.	8	Asbestos Cement	325	41	1.14 out of 5	\$442	143,686
Distribution Main	3565	P-98	WW	Carolyn Dr.	8	Asbestos Cement	153	41	1.14 out of 5	\$442	67,518
Distribution Main	4134	P-98	WW	Carolyn Dr.	8	Asbestos Cement	45	41	1.14 out of 5	\$442	19,956
Distribution Main	5161	P-97	WW	Carolyn Dr.	8	Asbestos Cement	383	41	1.14 out of 5	\$442	169,391
Distribution Main	1721	P-1950	WW	Carpenters Court	1	Copper	438	73	2.43 out of 5	\$442	193,773
Distribution Main	8934	P-1	WW	Carriage Rd	8	Ductile Iron	4	9	0 out of 5	N/A	\$0
Distribution Main	8939	P-1	WW	Carriage Rd	6	Ductile Iron	3	9	0.71 out of 5	N/A	\$0
Transmission Main	2072	P-856	WW	Carrie Ann Dr.	12	Ductile Iron	255	29	0.14 out of 5	\$442	112,599
Transmission Main	2074	P-858	WW	Carrie Ann Dr.	12	Ductile Iron	49	29	0.14 out of 5	\$442	21,569
Transmission Main	2101	P-856	WW	Carrie Ann Dr.	12	Ductile Iron	8	29	0.14 out of 5	\$442	3,345
Transmission Main	8052	P-858	WW	Carrie Ann Dr.	12	Ductile Iron	22	29	0.14 out of 5	\$442	9,773
Transmission Main	8053	P-858	WW	Carrie Ann Dr.	12	Ductile Iron	17	29	0.14 out of 5	\$442	7,717
Distribution Main	3435	P-502	WW	Cedar Dr.	6	Asbestos Cement	247	51	1.85 out of 5	\$442	109,369
Distribution Main	3574	P-501	WW	Cedar Dr.	6	Asbestos Cement	724	51	1.85 out of 5	\$442	319,889
Distribution Main	9715	P-1809	WW	Centracchio Ct	6	Ductile Iron	22	27	0.85 out of 5	\$442	9,756
Distribution Main	10996	P-1810	WW	Centracchio Ct	6	Ductile Iron	14	27	0.85 out of 5	\$442	6,260
Distribution Main	1767	P-947	WW	Centracchio St.	6	Ductile Iron	71	27	0.85 out of 5	\$442	31,332
Distribution Main	1768	P-947	WW	Centracchio St.	6	Ductile Iron	69	27	0.85 out of 5	\$442	30,662
Distribution Main	3195	P-947	WW	Centracchio St.	6	Ductile Iron	36	27	0.85 out of 5	\$442	16,127

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3199	P-945	WW	Centracchio St.	6	PVC	15	32	1.14 out of 5	\$442	6,609
Distribution Main	3200	P-945	WW	Centracchio St.	6	PVC	312	32	1.14 out of 5	\$442	137,717
Distribution Main	3519	P-946	WW	Centracchio St.	6	Ductile Iron	203	27	0.85 out of 5	\$442	89,688
Transmission Main	8609	P-999	WW	Central St	12	Ductile Iron	129	12	0 out of 5	N/A	\$0
Transmission Main	8612	P-1004	WW	Central St	12	Ductile Iron	20	12	0 out of 5	N/A	\$0
Distribution Main	8617	P-1876	WW	Central St	8	Ductile Iron	12	12	0 out of 5	N/A	\$0
Transmission Main	8618	P-1876	WW	Central St	12	Ductile Iron	3	12	0 out of 5	N/A	\$0
Transmission Main	8619	P-1876	WW	Central St	12	Ductile Iron	4	12	0 out of 5	N/A	\$0
Transmission Main	8620	P-1874	WW	Central St	12	Ductile Iron	54	12	0 out of 5	N/A	\$0
Transmission Main	8621	P-1341	WW	Central St	12	Ductile Iron	70	12	0 out of 5	N/A	\$0
Distribution Main	429	P-1001	WW	Central St.	8	Cast Iron	342	82	1.72 out of 5	\$442	151,349
Distribution Main	430	P-1001	WW	Central St.	8	Cast Iron	462	82	1.72 out of 5	\$442	204,070
Distribution Main	443	P-1342	WW	Central St.	6	Cast Iron	124	133	2.57 out of 5	\$442	54,617
Distribution Main	9421	P-1342	WW	Central St.	6	Cast Iron	6	133	2.57 out of 5	\$442	2,435
Distribution Main	9529	P-1000	WW	Central St.	8	Cast Iron	133	82	1.72 out of 5	\$442	58,808
Distribution Main	10665	P-1106	WW	Centre St	8	Ductile Iron	438	2	0 out of 5	N/A	\$0
Distribution Main	10666	P-1106	WW	Centre St	8	Ductile Iron	471	2	0 out of 5	N/A	\$0
Distribution Main	4559	P-30	WW	Chamber Road	6	Asbestos Cement	24	51	1.85 out of 5	\$442	10,638
Distribution Main	4967	P-30	WW	Chamber Road	6	Asbestos Cement	247	51	1.85 out of 5	\$442	109,087
Distribution Main	3396	P-10037	WW	Church St.	4	Cast Iron	322	83	3.14 out of 5	\$442	142,286
Distribution Main	3397	P-1081	WW	Church St.	6	Cast Iron	259	83	2.43 out of 5	\$442	114,597
Distribution Main	3398	P-10037	WW	Church St.	4	Cast Iron	265	83	3.14 out of 5	\$442	116,932
Distribution Main	3399		WW	Church St.	6	Cast Iron	6	UNK	1.85 out of 5	\$442	2,686
Distribution Main	4075	P-1080	WW	Church St.	6	Cast Iron	46	83	2.43 out of 5	\$442	20,208
Distribution Main	4076	P-1080	WW	Church St.	6	Cast Iron	129	134	2.57 out of 5	\$442	56,908
Distribution Main	4077	P-1080	WW	Church St.	6	Cast Iron	633	134	2.57 out of 5	\$442	279,910
Distribution Main	4088		WW	Church St.	6	Cast Iron	9	83	2.43 out of 5	\$442	3,767
Distribution Main	4089		WW	Church St.	6	Cast Iron	2	83	2.43 out of 5	\$442	1,027
Distribution Main	4296	P-1103	WW	Church St.	4	Cast Iron	109	83	3.14 out of 5	\$442	48,349
Distribution Main	4784	P-1080	WW	Church St.	6	Cast Iron	175	134	2.57 out of 5	\$442	77,433
Distribution Main	5083	P-1102	WW	Church St.	4	Cast Iron	601	83	3.14 out of 5	\$442	265,790
Distribution Main	5084	P-1095	WW	Church St.	4	Cast Iron	208	83	3.14 out of 5	\$442	92,051
Distribution Main	5085		WW	Church St.	4	Cast Iron	70	134	3.29 out of 5	\$442	30,942
Distribution Main	10675	P-10040	WW	Church St.	4	Cast Iron	16	124	3.29 out of 5	\$442	7,152
Distribution Main	11771	P-1080	WW	Church St.	6	Cast Iron	336	84	2.43 out of 5	\$442	148,719
Distribution Main	10021	P-284	WW	Circle Dr	8	Ductile Iron	30	6	0 out of 5	N/A	\$0
Distribution Main	10022	P-284	WW	Circle Dr	8	Ductile Iron	219	6	0 out of 5	N/A	\$0
Distribution Main	10026	P-1756	WW	Circle Dr	8	Ductile Iron	26	6	0 out of 5	N/A	\$0
Distribution Main	10027	P-1756	WW	Circle Dr	8	Ductile Iron	46	6	0 out of 5	N/A	\$0
Distribution Main	3547	P-109	WW	Claire St.	6	Asbestos Cement	97	55	1.85 out of 5	\$442	43,073
Distribution Main	3548	P-109	WW	Claire St.	6	Asbestos Cement	282	55	1.85 out of 5	\$442	124,770
Distribution Main	4645	P-110	WW	Claire St.	6	Asbestos Cement	267	55	1.85 out of 5	\$442	117,809
Distribution Main	4646	P-109	WW	Claire St.	6	Asbestos Cement	26	55	1.85 out of 5	\$442	11,595
Distribution Main	1528	P-899	WW	Cleveland St.	6	Asbestos Cement	72	71	2 out of 5	\$442	31,783

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	1529	P-899	WW	Cleveland St.	6	Asbestos Cement	133	71	2 out of 5	\$442	58,775
Distribution Main	1533	P-903	WW	Cleveland St.	6	Asbestos Cement	134	71	2 out of 5	\$442	59,435
Distribution Main	1540	P-901	WW	Cleveland St.	6	Asbestos Cement	4	71	2 out of 5	\$442	1,716
Distribution Main	1541	P-901	WW	Cleveland St.	6	Asbestos Cement	321	71	2 out of 5	\$442	141,912
Distribution Main	1542	P-904	WW	Cleveland St.	6	Asbestos Cement	229	71	2 out of 5	\$442	101,064
Distribution Main	3496	P-906	WW	Cleveland St.	6	Asbestos Cement	213	71	2 out of 5	\$442	94,253
Distribution Main	3497	P-899	WW	Cleveland St.	6	Asbestos Cement	583	71	2 out of 5	\$442	257,712
Distribution Main	1514	P-921	WW	Clyde St	6	Cast Iron	215	133	2.57 out of 5	\$442	95,199
Transmission Main	8545	P-831	WW	Clyde St	12	Ductile Iron	38	13	0 out of 5	N/A	\$0
Distribution Main	8546	P-1863	WW	Clyde St	6	Ductile Iron	20	13	0.71 out of 5	N/A	\$0
Distribution Main	8579	P-1863	WW	Clyde St	6	Ductile Iron	15	13	0.71 out of 5	N/A	\$0
Distribution Main	9730	P-1855	WW	Clyde St	6	Ductile Iron	60	22	0.85 out of 5	N/A	\$0
Transmission Main	9826	P-831	WW	Clyde St	12	Ductile Iron	3	7	0 out of 5	N/A	\$0
Transmission Main	9827	P-831	WW	Clyde St	12	Ductile Iron	12	7	0 out of 5	N/A	\$0
Distribution Main	9828	P-820	WW	Clyde St	6	Ductile Iron	19	7	0.71 out of 5	N/A	\$0
Transmission Main	11615	P-1859	WW	Clyde St	12	Ductile Iron	9	7	0 out of 5	N/A	\$0
Transmission Main	2276	P-1859	WW	Clyde St.	12	PVC	363	39	0.43 out of 5	\$442	160,568
Transmission Main	2278	P-1358	WW	Clyde St.	12	PVC	136	39	0.43 out of 5	\$442	60,118
Transmission Main	2279	P-1358	WW	Clyde St.	12	PVC	3	39	0.43 out of 5	\$442	1,538
Distribution Main	2956	P-1861	WW	Clyde St.	6	Cast Iron	102	133	2.57 out of 5	\$442	45,104
Distribution Main	2957	P-912	WW	Clyde St.	6	Cast Iron	609	133	2.57 out of 5	\$442	269,030
Distribution Main	2958	P-912	WW	Clyde St.	6	Cast Iron	118	133	2.57 out of 5	\$442	52,294
Distribution Main	3469	P-1353	WW	Clyde St.	6	Cast Iron	269	133	2.57 out of 5	\$442	118,808
Distribution Main	3482	P-910	WW	Clyde St.	6	Cast Iron	290	134	2.57 out of 5	\$442	128,028
Distribution Main	3483	P-910	WW	Clyde St.	6	Cast Iron	485	134	2.57 out of 5	\$442	214,586
Distribution Main	3507	P-1353	WW	Clyde St.	6	Cast Iron	144	133	2.57 out of 5	\$442	63,649
Distribution Main	3508	P-1354	WW	Clyde St.	6	Cast Iron	116	133	2.57 out of 5	\$442	51,203
Distribution Main	3737	P-1863	WW	Clyde St.	6	Cast Iron	228	133	2.57 out of 5	\$442	100,829
Distribution Main	3738	P-1863	WW	Clyde St.	6	Cast Iron	2	133	2.57 out of 5	\$442	789
Transmission Main	9825	P-831	WW	Clyde St.	12	PVC	347	39	0.43 out of 5	\$442	153,354
Distribution Main	11221	P-910	WW	Clyde St.	6	Cast Iron	16	134	2.57 out of 5	\$442	7,057
Distribution Main	12022	P-912	WW	Clyde St.	6	Cast Iron	386	133	2.57 out of 5	\$442	170,803
Distribution Main	9801	P-622	WW	Coaches Ct	8	Ductile Iron	203	8	0 out of 5	N/A	\$0
Distribution Main	2437	P-11	WW	Cobblestone La.	8	Ductile Iron	202	28	0.14 out of 5	\$442	89,447
Distribution Main	2438	P-11	WW	Cobblestone La.	8	Ductile Iron	44	28	0.14 out of 5	\$442	19,622
Distribution Main	634	P-468	WW	Cochran St.	6	Asbestos Cement	52	64	2 out of 5	\$442	23,030
Distribution Main	635	P-468	WW	Cochran St.	6	Asbestos Cement	222	64	2 out of 5	\$442	98,269
Distribution Main	5150	P-467	WW	Cochran St.	6	Asbestos Cement	480	64	2 out of 5	\$442	212,281
Distribution Main	5151	P-467	WW	Cochran St.	6	Asbestos Cement	38	64	2 out of 5	\$442	16,677
Distribution Main	5152	P-472	WW	Cochran St.	6	Asbestos Cement	724	64	2 out of 5	\$442	320,212
Distribution Main	5153	P-472	WW	Cochran St.	6	Asbestos Cement	606	64	2 out of 5	\$442	267,901
Distribution Main	10680	P-432	WW	Coit Av	8	Ductile Iron	10	2	0 out of 5	N/A	\$0
Distribution Main	10681	P-432	WW	Coit Av	8	Ductile Iron	16	2	0 out of 5	N/A	\$0
Distribution Main	10682		WW	Coit Av	8	Ductile Iron	1	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	633	P-1476	WW	Coit Ave.	6	Asbestos Cement	275	51	1.85 out of 5	\$442	121,466
Distribution Main	636	P-429	WW	Coit Ave.	6	Cast Iron	220	81	2.43 out of 5	\$442	97,382
Distribution Main	637	P-429	WW	Coit Ave.	6	Cast Iron	26	81	2.43 out of 5	\$442	11,556
Distribution Main	638	P-445	WW	Coit Ave.	6	Cast Iron	101	81	2.43 out of 5	\$442	44,847
Distribution Main	639	P-448	WW	Coit Ave.	6	Cast Iron	143	81	2.43 out of 5	\$442	63,152
Distribution Main	640	P-10021	WW	Coit Ave.	8	Asbestos Cement	168	51	1.14 out of 5	\$442	74,232
Distribution Main	803	P-419	WW	Coit Ave.	6	Cast Iron	235	81	2.43 out of 5	\$442	103,916
Distribution Main	1211	P-423	WW	Coit Ave.	6	Cast Iron	206	81	2.43 out of 5	\$442	91,052
Distribution Main	1748	P-431	WW	Coit Ave.	6	Cast Iron	164	81	2.43 out of 5	\$442	72,298
Distribution Main	1749	P-418	WW	Coit Ave.	6	Cast Iron	45	81	2.43 out of 5	\$442	19,757
Distribution Main	3135	P-432	WW	Coit Ave.	6	Cast Iron	867	81	2.43 out of 5	\$442	383,337
Distribution Main	4445	P-422	WW	Coit Ave.	6	Cast Iron	37	81	2.43 out of 5	\$442	16,539
Distribution Main	4446	P-422	WW	Coit Ave.	6	Cast Iron	10	81	2.43 out of 5	\$442	4,264
Distribution Main	4667	P-462	WW	Coit Ave.	8	Asbestos Cement	549	51	1.14 out of 5	\$442	242,849
Distribution Main	4670	P-451	WW	Coit Ave.	6	Cast Iron	269	81	2.43 out of 5	\$442	118,865
Distribution Main	4675	P-445	WW	Coit Ave.	6	Cast Iron	102	81	2.43 out of 5	\$442	45,099
Distribution Main	5143	P-430	WW	Coit Ave.	6	Cast Iron	192	81	2.43 out of 5	\$442	84,915
Distribution Main	5149	P-447	WW	Coit Ave.	6	Cast Iron	213	81	2.43 out of 5	\$442	94,138
Distribution Main	10899	P-1477	WW	Coit Ave.	8	Asbestos Cement	129	51	1.14 out of 5	\$442	56,923
Distribution Main	11260	P-462	WW	Coit Ave.	8	Asbestos Cement	216	51	1.14 out of 5	\$442	95,379
Distribution Main	12072	P-431	WW	Coit Ave.	6	Cast Iron	13	81	2.43 out of 5	\$442	5,683
Distribution Main	4610	P-128	WW	Cold Spring Dr.	8	PVC	226	34	0.43 out of 5	\$442	100,015
Distribution Main	4611	P-130	WW	Cold Spring Dr.	8	PVC	133	34	0.43 out of 5	\$442	58,853
Distribution Main	4612	P-130	WW	Cold Spring Dr.	8	PVC	600	34	0.43 out of 5	\$442	265,225
Distribution Main	12053	P-130	WW	Cold Spring Dr.	8	PVC	401	34	0.43 out of 5	\$442	177,242
Distribution Main	1228	P-597	WW	Colonial Way	8	Ductile Iron	42	14	0 out of 5	N/A	\$0
Distribution Main	1229	P-597	WW	Colonial Way	8	Ductile Iron	6	14	0 out of 5	N/A	\$0
Distribution Main	4008	P-597	WW	Colonial Way	6	Asbestos Cement	789	72	2 out of 5	\$442	348,526
Distribution Main	4336	P-597	WW	Colonial Way	6	Ductile Iron	9	72	1.14 out of 5	\$442	3,768
Distribution Main	4708	P-597	WW	Colonial Way	8	Ductile Iron	32	14	0 out of 5	N/A	\$0
Distribution Main	9373	P-597	WW	Colonial Way	6	Ductile Iron	3	14	0.71 out of 5	N/A	\$0
Distribution Main	9374	P-597	WW	Colonial Way	6	Ductile Iron	4	14	0.71 out of 5	N/A	\$0
Distribution Main	9891	P-597	WW	Colonial Way	6	Ductile Iron	16	14	0.71 out of 5	N/A	\$0
Distribution Main	9466	P-1866	WW	Colvin St	1	Unknown	160	UNK	1.42 out of 5	\$442	70,921
Distribution Main	1503	P-1203	WW	Colvin St.	6	Cast Iron	14	79	2.28 out of 5	\$442	6,070
Distribution Main	3489	P-1201	WW	Colvin St.	4	Cast Iron	208	134	3.29 out of 5	\$442	92,061
Distribution Main	3742	P-1203	WW	Colvin St.	6	Cast Iron	379	79	2.28 out of 5	\$442	167,418
Distribution Main	3743	P-1203	WW	Colvin St.	6	Cast Iron	26	79	2.28 out of 5	\$442	11,502
Distribution Main	11227	P-1203	WW	Colvin St.	6	Cast Iron	3	79	2.28 out of 5	\$442	1,174
Distribution Main	10631	P-394	WW	Concord Av	8	Ductile Iron	65	2	0 out of 5	N/A	\$0
Distribution Main	10632	P-394	WW	Concord Av	8	Ductile Iron	187	2	0 out of 5	N/A	\$0
Distribution Main	10633		WW	Concord Av	8	Ductile Iron	247	2	0 out of 5	N/A	\$0
Distribution Main	469		WW	Cone Dr.	8	Ductile Iron	10	19	0 out of 5	N/A	\$0
Transmission Main	1357	P-1460	WW	Cone Dr.	12	Ductile Iron	312	19	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	2352	P-1642	WW	Cone Dr.	12	Ductile Iron	38	19	0 out of 5	N/A	\$0
Distribution Main	3558	P-57	WW	Cone Dr.	8	Asbestos Cement	159	46	1.14 out of 5	\$442	70,477
Distribution Main	4631	P-1456	WW	Cone Dr.	8	Asbestos Cement	195	46	1.14 out of 5	\$442	86,193
Distribution Main	4633	P-58	WW	Cone Dr.	8	Asbestos Cement	629	46	1.14 out of 5	\$442	278,227
Distribution Main	4634	P-58	WW	Cone Dr.	8	Asbestos Cement	271	46	1.14 out of 5	\$442	119,980
Distribution Main	4636	P-1461	WW	Cone Dr.	8	Asbestos Cement	326	46	1.14 out of 5	\$442	144,199
Distribution Main	10149	P-57	WW	Cone Dr.	8	Asbestos Cement	38	46	1.14 out of 5	\$442	16,817
Distribution Main	12078	P-1461	WW	Cone Dr.	8	Asbestos Cement	43	46	1.14 out of 5	\$442	18,823
Distribution Main	9463	P-1864	WW	Coogan Ct	1	Unknown	235	UNK	1.42 out of 5	\$442	103,736
Distribution Main	1726	P-558	WW	Cottage St.	4	Cast Iron	287	109	3.29 out of 5	\$442	126,645
Distribution Main	1727	P-558	WW	Cottage St.	4	Cast Iron	275	109	3.29 out of 5	\$442	121,469
Distribution Main	2888	P-558	WW	Cottage St.	4	Cast Iron	8	109	3.29 out of 5	\$442	3,450
Distribution Main	1976	P-483	WW	Country Dr.	8	Asbestos Cement	15	63	1.29 out of 5	\$442	6,662
Distribution Main	1980	P-478	WW	Country Dr.	6	Asbestos Cement	15	63	2 out of 5	\$442	6,437
Distribution Main	1990	P-475	WW	Country Dr.	8	Asbestos Cement	25	63	1.29 out of 5	\$442	10,910
Distribution Main	1991	P-475	WW	Country Dr.	8	Asbestos Cement	602	63	1.29 out of 5	\$442	266,153
Distribution Main	3391	P-478	WW	Country Dr.	6	Asbestos Cement	428	63	2 out of 5	\$442	189,263
Distribution Main	3392	P-478	WW	Country Dr.	6	Asbestos Cement	315	63	2 out of 5	\$442	139,362
Distribution Main	3393	P-483	WW	Country Dr.	8	Asbestos Cement	241	63	1.14 out of 5	\$442	106,400
Distribution Main	4213	P-477	WW	Country Dr.	6	Asbestos Cement	244	63	2 out of 5	\$442	107,724
Distribution Main	5071	P-476	WW	Country Dr.	8	Asbestos Cement	412	63	1.29 out of 5	\$442	182,156
Distribution Main	5072	P-476	WW	Country Dr.	8	Asbestos Cement	43	63	1.29 out of 5	\$442	19,153
Distribution Main	9923	P-1786	WW	Countryside Way	8	Ductile Iron	392	10	0 out of 5	N/A	\$0
Distribution Main	9924	P-1786	WW	Countryside Way	8	Ductile Iron	240	10	0 out of 5	N/A	\$0
Distribution Main	1971	P-1058	WW	Coutu Ct.	4	Cast Iron	278	83	3.14 out of 5	\$442	122,961
Distribution Main	3242	P-1058	WW	Coutu Ct.	4	Cast Iron	11	83	3.14 out of 5	\$442	4,793
Distribution Main	644	P-1474	WW	Cowesett Ave.	8	Asbestos Cement	29	79	1.29 out of 5	\$442	12,847
Distribution Main	651	P-511	WW	Cowesett Ave.	8	Asbestos Cement	67	79	1.29 out of 5	\$442	29,640
Distribution Main	652	P-465	WW	Cowesett Ave.	8	Asbestos Cement	32	79	1.29 out of 5	\$442	13,935
Distribution Main	653	P-465	WW	Cowesett Ave.	8	Asbestos Cement	284	79	1.29 out of 5	\$442	125,585
Distribution Main	654	P-464	WW	Cowesett Ave.	8	Asbestos Cement	392	79	1.29 out of 5	\$442	173,146
Distribution Main	1096	P-1079	WW	Cowesett Ave.	6	Cast Iron	502	124	2.57 out of 5	\$442	221,708
Transmission Main	1977	P-490	WW	Cowesett Ave.	12	Asbestos Cement	149	47	1.14 out of 5	\$442	65,807
Transmission Main	1987	P-489	WW	Cowesett Ave.	12	Asbestos Cement	258	47	1.14 out of 5	\$442	113,887
Transmission Main	2152		WW	Cowesett Ave.	12	Asbestos Cement	476	47	1.14 out of 5	\$442	210,408
Distribution Main	3125	P-1134	WW	Cowesett Ave.	8	Asbestos Cement	5	79	1.29 out of 5	\$442	2,363
Distribution Main	3126	P-1079	WW	Cowesett Ave.	6	Cast Iron	230	124	2.57 out of 5	\$442	101,649
Distribution Main	3879	P-537	WW	Cowesett Ave.	8	Asbestos Cement	306	79	1.29 out of 5	\$442	135,070
Distribution Main	3889	P-540	WW	Cowesett Ave.	8	Asbestos Cement	125	79	1.29 out of 5	\$442	55,285
Distribution Main	3892	P-1135	WW	Cowesett Ave.	4	Cast Iron	995	124	3.29 out of 5	\$442	439,751
Distribution Main	3893	P-1079	WW	Cowesett Ave.	6	Cast Iron	20	124	2.57 out of 5	\$442	9,028
Distribution Main	4665	P-464	WW	Cowesett Ave.	8	Asbestos Cement	143	79	1.29 out of 5	\$442	63,418
Distribution Main	4672	P-1474	WW	Cowesett Ave.	8	Asbestos Cement	8	79	1.29 out of 5	\$442	3,322
Distribution Main	4678	P-538	WW	Cowesett Ave.	8	Asbestos Cement	187	79	1.29 out of 5	\$442	82,540

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	4681	P-1473	WW	Cowesett Ave.	12	Asbestos Cement	257	54	1.14 out of 5	\$442	113,484
Transmission Main	4682	P-1473	WW	Cowesett Ave.	12	Asbestos Cement	201	54	1.14 out of 5	\$442	88,878
Distribution Main	4778		WW	Cowesett Ave.	8	Asbestos Cement	20	54	1.14 out of 5	\$442	9,056
Distribution Main	4783	P-10039	WW	Cowesett Ave.	4	Cast Iron	20	124	3.29 out of 5	\$442	8,628
Transmission Main	4959	P-474	WW	Cowesett Ave.	12	Asbestos Cement	24	47	1.14 out of 5	\$442	10,644
Transmission Main	5078	P-2182	WW	Cowesett Ave.	12	Asbestos Cement	41	47	1.14 out of 5	\$442	17,912
Transmission Main	5079	P-2182	WW	Cowesett Ave.	12	Asbestos Cement	156	47	1.14 out of 5	\$442	68,878
Transmission Main	5080	P-490	WW	Cowesett Ave.	12	Asbestos Cement	10	47	1.14 out of 5	\$442	4,391
Distribution Main	5092	P-1079	WW	Cowesett Ave.	6	Cast Iron	19	124	2.57 out of 5	\$442	8,556
Distribution Main	5093	P-1134	WW	Cowesett Ave.	8	Asbestos Cement	482	79	1.29 out of 5	\$442	213,113
Transmission Main	5099	P-1170	WW	Cowesett Ave.	12	Asbestos Cement	6	54	1.14 out of 5	\$442	2,502
Distribution Main	5101	P-1135	WW	Cowesett Ave.	4	Cast Iron	130	124	3.29 out of 5	\$442	57,346
Distribution Main	5102	P-541	WW	Cowesett Ave.	8	Asbestos Cement	238	79	1.29 out of 5	\$442	105,039
Distribution Main	5103	P-540	WW	Cowesett Ave.	8	Asbestos Cement	89	79	1.29 out of 5	\$442	39,514
Distribution Main	5104	P-10031	WW	Cowesett Ave.	8	Asbestos Cement	22	79	1.29 out of 5	\$442	9,826
Distribution Main	5105	P-10031	WW	Cowesett Ave.	8	Asbestos Cement	166	79	1.29 out of 5	\$442	73,397
Distribution Main	5106	P-533	WW	Cowesett Ave.	8	Asbestos Cement	146	79	1.29 out of 5	\$442	64,440
Distribution Main	5107	P-533	WW	Cowesett Ave.	8	Asbestos Cement	588	79	1.29 out of 5	\$442	259,988
Transmission Main	5111	P-1169	WW	Cowesett Ave.	12	Asbestos Cement	8	54	1.14 out of 5	\$442	3,617
Transmission Main	5112	P-1169	WW	Cowesett Ave.	12	Asbestos Cement	645	54	1.14 out of 5	\$442	285,256
Transmission Main	5113	P-1473	WW	Cowesett Ave.	12	Asbestos Cement	17	54	1.14 out of 5	\$442	7,316
Transmission Main	5114	P-1473	WW	Cowesett Ave.	12	Asbestos Cement	547	54	1.14 out of 5	\$442	241,698
Transmission Main	5115	P-1472	WW	Cowesett Ave.	12	Asbestos Cement	532	54	1.14 out of 5	\$442	235,155
Distribution Main	5125	P-1137	WW	Cowesett Ave.	4	Cast Iron	5	124	3.29 out of 5	\$442	2,140
Distribution Main	5137	P-510	WW	Cowesett Ave.	8	Asbestos Cement	431	79	1.29 out of 5	\$442	190,679
Distribution Main	5144	P-1474	WW	Cowesett Ave.	8	Asbestos Cement	394	79	1.29 out of 5	\$442	174,063
Transmission Main	5147	P-474	WW	Cowesett Ave.	12	Asbestos Cement	538	47	1.14 out of 5	\$442	237,958
Transmission Main	10501	P-489	WW	Cowesett Ave.	12	Asbestos Cement	15	47	1.14 out of 5	\$442	6,642
Transmission Main	10502	P-489	WW	Cowesett Ave.	12	Asbestos Cement	9	47	1.14 out of 5	\$442	4,161
Transmission Main	10503		WW	Cowesett Ave.	12	Asbestos Cement	53	47	1.14 out of 5	\$442	23,467
Distribution Main	10986	P-537	WW	Cowesett Ave.	8	Asbestos Cement	20	79	1.29 out of 5	\$442	8,987
Distribution Main	11288	P-10031	WW	Cowesett Ave.	8	Asbestos Cement	71	79	1.29 out of 5	\$442	31,572
Distribution Main	11289	P-533	WW	Cowesett Ave.	8	Asbestos Cement	3	79	1.29 out of 5	\$442	1,533
Transmission Main	11665	P-489	WW	Cowesett Ave.	12	Asbestos Cement	5	47	1.14 out of 5	\$442	2,426
Distribution Main	12023	P-1079	WW	Cowesett Ave.	6	Cast Iron	219	124	2.57 out of 5	\$442	96,990
Transmission Main	12133	P-489	WW	Cowesett Ave.	12	Asbestos Cement	4	47	1.14 out of 5	\$442	1,809
Transmission Main	164	P-1169	WW	Cowesett Rd.	12	Asbestos Cement	666	54	1.14 out of 5	\$442	294,221
Transmission Main	165	P-1169	WW	Cowesett Rd.	12	Asbestos Cement	6	54	1.14 out of 5	\$442	2,709
Transmission Main	12058	P-1169	WW	Cowesett Rd.	12	Asbestos Cement	281	54	1.14 out of 5	\$442	124,013
Distribution Main	3614	P-745	WW	Crawford St.	6	Cast Iron	197	79	2.28 out of 5	\$442	87,190
Distribution Main	3615	P-745	WW	Crawford St.	6	Cast Iron	63	79	2.28 out of 5	\$442	27,923
Distribution Main	3795	P-745	WW	Crawford St.	6	Cast Iron	30	79	2.28 out of 5	\$442	13,350
Distribution Main	4282	P-730	WW	Crawford St.	6	Cast Iron	237	83	2.43 out of 5	\$442	104,740
Distribution Main	10005	P-745	WW	Crawford St.	6	Cast Iron	10	79	2.28 out of 5	\$442	4,323

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	1554	P-849	WW	Crestwood Dr.	6	Asbestos Cement	227	62	2 out of 5	\$442	100,230
Distribution Main	1769	P-833	WW	Crestwood Dr.	8	PVC	279	31	0.43 out of 5	\$442	123,300
Distribution Main	1771	P-841	WW	Crestwood Dr.	8	PVC	497	31	0.43 out of 5	\$442	219,780
Distribution Main	1772	P-841	WW	Crestwood Dr.	8	PVC	36	31	0.43 out of 5	\$442	15,847
Distribution Main	3198	P-849	WW	Crestwood Dr.	6	Asbestos Cement	11	62	2 out of 5	\$442	4,902
Distribution Main	3511	P-844	WW	Crestwood Dr.	8	PVC	345	31	0.43 out of 5	\$442	152,359
Distribution Main	3516	P-846	WW	Crestwood Dr.	8	PVC	111	31	0.43 out of 5	\$442	48,892
Distribution Main	3517	P-846	WW	Crestwood Dr.	8	PVC	117	31	0.43 out of 5	\$442	51,728
Distribution Main	641	P-452	WW	Crompton Ave.	6	Asbestos Cement	36	69	2 out of 5	\$442	16,019
Distribution Main	642	P-452	WW	Crompton Ave.	6	Asbestos Cement	751	69	2 out of 5	\$442	331,939
Distribution Main	10155		WW	Crompton Ave.	8	Ductile Iron	12	18	0 out of 5	N/A	\$0
Distribution Main	10997	P-452	WW	Crompton Ave.	8	Ductile Iron	8	18	0 out of 5	N/A	\$0
Transmission Main	103		WW	Crompton/Setian Ln. Tank	16	Ductile Iron	14	19	0 out of 5	N/A	\$0
Transmission Main	2172		WW	Crompton/Setian Ln. Tank	12	Ductile Iron	34	19	0 out of 5	N/A	\$0
Transmission Main	2173		WW	Crompton/Setian Ln. Tank	12	Ductile Iron	2	19	0 out of 5	N/A	\$0
Transmission Main	2174		WW	Crompton/Setian Ln. Tank	16	Ductile Iron	29	19	0 out of 5	N/A	\$0
Transmission Main	2319		WW	Crompton/Setian Ln. Tank	16	Ductile Iron	33	19	0 out of 5	N/A	\$0
Transmission Main	2320		WW	Crompton/Setian Ln. Tank	16	Ductile Iron	2	19	0 out of 5	N/A	\$0
Transmission Main	2321		WW	Crompton/Setian Ln. Tank	16	Ductile Iron	22	19	0 out of 5	N/A	\$0
Transmission Main	2322		WW	Crompton/Setian Ln. Tank	20	Ductile Iron	48	19	0 out of 5	N/A	\$0
Transmission Main	2323		WW	Crompton/Setian Ln. Tank	20	Ductile Iron	20	19	0 out of 5	N/A	\$0
Transmission Main	2325		WW	Crompton/Setian Ln. Tank	12	Ductile Iron	21	19	0 out of 5	N/A	\$0
Transmission Main	2326		WW	Crompton/Setian Ln. Tank	16	Ductile Iron	22	19	0 out of 5	N/A	\$0
Transmission Main	2327		WW	Crompton/Setian Ln. Tank	16	Ductile Iron	11	19	0 out of 5	N/A	\$0
Transmission Main	11017		WW	Crompton/Setian Ln. Tank	16	Ductile Iron	10	19	0 out of 5	N/A	\$0
Transmission Main	11018		WW	Crompton/Setian Ln. Tank	20	Ductile Iron	18	19	0 out of 5	N/A	\$0
Transmission Main	11019		WW	Crompton/Setian Ln. Tank	20	Ductile Iron	26	19	0 out of 5	N/A	\$0
Distribution Main	442	P-985	WW	Cross St.	1	Galvanized Iron	22	91	3.43 out of 5	\$442	9,647
Distribution Main	3338	P-985	WW	Cross St.	1	Galvanized Iron	286	91	3.43 out of 5	\$442	126,273
Transmission Main	1356	P-1464	WW	Crossbow La.	16	Ductile Iron	737	19	0 out of 5	N/A	\$0
Distribution Main	3554	P-22	WW	Crossbow La.	8	Asbestos Cement	365	46	1.14 out of 5	\$442	161,428
Distribution Main	3555	P-22	WW	Crossbow La.	8	Asbestos Cement	328	46	1.14 out of 5	\$442	145,164
Distribution Main	3561	P-23	WW	Crossbow La.	8	Asbestos Cement	182	46	1.14 out of 5	\$442	80,286
Distribution Main	3562	P-23	WW	Crossbow La.	8	Asbestos Cement	37	46	1.14 out of 5	\$442	16,440
Distribution Main	4743	P-24	WW	Crossbow La.	8	Ductile Iron	214	28	0.14 out of 5	\$442	94,635
Distribution Main	4746	P-1939	WW	Crossbow La.	8	Ductile Iron	277	28	0.14 out of 5	\$442	122,329
Distribution Main	8628	P-25	WW	Crossbow La.	8	Asbestos Cement	235	46	1.85 out of 5	\$442	103,710
Distribution Main	11263	P-1939	WW	Crossbow La.	8	Ductile Iron	9	28	0.14 out of 5	\$442	4,045
Distribution Main	11486	P-25	WW	Crossbow La.	8	Asbestos Cement	230	46	1.14 out of 5	\$442	101,640
Distribution Main	2886	P-652	WW	Crossen St.	6	Cast Iron	278	134	2.57 out of 5	\$442	122,736
Distribution Main	3108	P-656	WW	Crossen St.	4	Cast Iron	15	134	3.29 out of 5	\$442	6,508
Distribution Main	4322	P-656	WW	Crossen St.	4	Cast Iron	345	134	3.29 out of 5	\$442	152,635
Distribution Main	4323	P-656	WW	Crossen St.	4	Cast Iron	47	134	3.29 out of 5	\$442	20,906
Distribution Main	8908	P-218	WW	Crossland Rd	8	Ductile Iron	256	9	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	8917	P-167	WW	Crossland Rd	8	Ductile Iron	225	9	0 out of 5	N/A	\$0
Distribution Main	8921	P-159	WW	Crossland Rd	8	Ductile Iron	242	9	0 out of 5	N/A	\$0
Distribution Main	9394	P-1721	WW	Crossland Rd	8	Ductile Iron	40	9	0 out of 5	N/A	\$0
Distribution Main	9403	P-1724	WW	Crossland Rd	8	Ductile Iron	157	9	0 out of 5	N/A	\$0
Distribution Main	9404	P-1724	WW	Crossland Rd	8	Ductile Iron	24	9	0 out of 5	N/A	\$0
Distribution Main	9411	P-1731	WW	Crossland Rd	8	Ductile Iron	241	9	0 out of 5	N/A	\$0
Distribution Main	10833	P-145	WW	Crossland Rd	8	Ductile Iron	257	9	0 out of 5	N/A	\$0
Distribution Main	10927	P-220	WW	Crossland Rd	8	Ductile Iron	218	9	0 out of 5	N/A	\$0
Distribution Main	11525	P-1724	WW	Crossland Rd	8	Ductile Iron	55	9	0 out of 5	N/A	\$0
Distribution Main	6557	P-236	WW	Crossland Rd.	6	Asbestos Cement	649	80	2 out of 5	\$442	286,725
Transmission Main	10367	P-76	WW	Crudale Dr (Off-Road)	12	Ductile Iron	369	19	0 out of 5	N/A	\$0
Transmission Main	10368	P-76	WW	Crudale Dr (Off-Road)	12	Ductile Iron	16	19	0 out of 5	N/A	\$0
Transmission Main	1325	P-75	WW	Crudale Dr.	12	Ductile Iron	399	19	0 out of 5	N/A	\$0
Transmission Main	2805	P-76	WW	Crudale Dr.	12	Ductile Iron	411	19	0 out of 5	N/A	\$0
Transmission Main	2803	P-74	WW	Crudale Rd.	12	Ductile Iron	9	19	0 out of 5	N/A	\$0
Transmission Main	2804	P-74	WW	Crudale Rd.	12	Ductile Iron	491	19	0 out of 5	N/A	\$0
Transmission Main	10957	P-71	WW	Crudale Rd.	12	Ductile Iron	93	19	0 out of 5	N/A	\$0
Transmission Main	10958	P-71	WW	Crudale Rd.	12	Ductile Iron	80	19	0 out of 5	N/A	\$0
Distribution Main	1777	P-1052	WW	Curson St.	6	Cast Iron	138	129	2.57 out of 5	\$442	61,053
Distribution Main	1778	P-1052	WW	Curson St.	6	Cast Iron	150	129	2.57 out of 5	\$442	66,173
Distribution Main	1964	P-1052	WW	Curson St.	6	Cast Iron	21	129	2.57 out of 5	\$442	9,228
Distribution Main	1965	P-1051	WW	Curson St.	4	Cast Iron	278	84	3.14 out of 5	\$442	123,062
Distribution Main	1966	P-753	WW	Curson St.	4	Cast Iron	111	84	3.14 out of 5	\$442	49,057
Distribution Main	1967	P-1052	WW	Curson St.	6	Cast Iron	220	129	2.57 out of 5	\$442	97,327
Distribution Main	2383		WW	Curson St.	6	Cast Iron	238	72	2.28 out of 5	\$442	105,055
Distribution Main	2384	P-758	WW	Curson St.	8	Asbestos Cement	512	72	1.29 out of 5	\$442	226,438
Distribution Main	2385	P-758	WW	Curson St.	8	Asbestos Cement	33	72	1.29 out of 5	\$442	14,556
Distribution Main	3254	P-1052	WW	Curson St.	4	Cast Iron	16	84	3.14 out of 5	\$442	7,182
Distribution Main	3264	P-1291	WW	Curson St.	8	Ductile Iron	336	18	0 out of 5	N/A	\$0
Distribution Main	3794		WW	Curson St.	6	Cast Iron	4	72	2.28 out of 5	\$442	1,810
Distribution Main	3805	P-1055	WW	Curson St.	6	Cast Iron	31	72	2.28 out of 5	\$442	13,846
Distribution Main	3806	P-1055	WW	Curson St.	6	Cast Iron	301	72	2.28 out of 5	\$442	133,119
Distribution Main	9521	P-753	WW	Curson St.	4	Cast Iron	35	84	3.14 out of 5	\$442	15,501
Distribution Main	9522	P-753	WW	Curson St.	4	Cast Iron	46	84	3.14 out of 5	\$442	20,175
Distribution Main	9649	P-757	WW	Curson St.	8	Asbestos Cement	60	72	1.29 out of 5	\$442	26,428
Distribution Main	11021	P-1052	WW	Curson St.	6	Cast Iron	15	129	2.57 out of 5	\$442	6,780
Distribution Main	11992	P-1052	WW	Curson St.	6	Cast Iron	6	129	2.57 out of 5	\$442	2,853
Transmission Main	3190	P-853	WW	Cyr Ct.	12	Ductile Iron	104	18	0 out of 5	N/A	\$0
Transmission Main	3191	P-853	WW	Cyr Ct.	12	Ductile Iron	212	18	0 out of 5	N/A	\$0
Transmission Main	8648	P-1327	WW	Dairy Farm Rd.	12	Ductile Iron	456	16	0 out of 5	N/A	\$0
Distribution Main	10730	P-227	WW	Daisy St	8	Ductile Iron	240	1	0 out of 5	N/A	\$0
Distribution Main	11713	P-228	WW	Daisy St	8	Ductile Iron	107	1	0 out of 5	N/A	\$0
Distribution Main	4327		WW	Dale Ave	8	Ductile Iron	36	18	0 out of 5	N/A	\$0
Distribution Main	9624	P-1968	WW	Dale Ave	1	Copper	313	71	2.43 out of 5	\$442	138,184

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10150		WW	Dale Ave	8	Ductile Iron	20	18	0 out of 5	N/A	\$0
Distribution Main	10768	P-10061	WW	Danby St	8	Ductile Iron	80	15	0 out of 5	N/A	\$0
Distribution Main	4331	P-1492	WW	Danby St.	8	Ductile Iron	133	15	0 out of 5	N/A	\$0
Distribution Main	10607	P-408	WW	Davis St	8	Ductile Iron	211	2	0 out of 5	N/A	\$0
Distribution Main	10608	P-408	WW	Davis St	8	Ductile Iron	388	2	0.71 out of 5	N/A	\$0
Distribution Main	10159		WW	Dawes St	6	PVC	5	28	1.14 out of 5	\$442	2,387
Distribution Main	162	P-1480	WW	Dawes St.	1	Copper	215	84	2.57 out of 5	\$442	94,825
Distribution Main	4082	P-519	WW	Dawes St.	6	PVC	73	28	1.14 out of 5	\$442	32,261
Distribution Main	4083	P-519	WW	Dawes St.	6	PVC	297	28	1.14 out of 5	\$442	131,489
Distribution Main	10156	P-10029	WW	Dawes St.	6	PVC	184	33	1.14 out of 5	\$442	81,463
Distribution Main	11241	P-519	WW	Dawes St.	6	PVC	233	28	1.14 out of 5	\$442	102,793
Distribution Main	657	P-453	WW	Deborah Ct.	6	Ductile Iron	216	29	0.85 out of 5	\$442	95,288
Distribution Main	658	P-453	WW	Deborah Ct.	6	Ductile Iron	238	29	0.85 out of 5	\$442	105,123
Distribution Main	2210	P-185	WW	Deer Run Rd	8	PVC	225	35	0.43 out of 5	\$442	99,661
Distribution Main	279	P-1142	WW	Deerfield Dr.	8	Asbestos Cement	466	47	1.14 out of 5	\$442	205,792
Distribution Main	280	P-1142	WW	Deerfield Dr.	8	Asbestos Cement	136	47	1.14 out of 5	\$442	59,933
Distribution Main	3122	P-1146	WW	Deerfield Dr.	8	Asbestos Cement	293	47	1.14 out of 5	\$442	129,492
Distribution Main	3123	P-1146	WW	Deerfield Dr.	8	Asbestos Cement	215	47	1.14 out of 5	\$442	95,101
Distribution Main	4819	P-1145	WW	Deerfield Dr.	8	Asbestos Cement	269	47	1.14 out of 5	\$442	118,707
Distribution Main	4821	P-1148	WW	Deerfield Dr.	8	Asbestos Cement	325	47	1.14 out of 5	\$442	143,811
Distribution Main	4823	P-1144	WW	Deerfield Dr.	8	Asbestos Cement	315	47	1.14 out of 5	\$442	139,441
Distribution Main	10122	P-1141	WW	Deerfield Dr.	8	Asbestos Cement	20	47	1.14 out of 5	\$442	8,818
Distribution Main	10034	P-1766	WW	Diaz Ct	8	Ductile Iron	207	6	0 out of 5	N/A	\$0
Distribution Main	10044	P-1769	WW	Dimasi Ct	8	Ductile Iron	298	6	0 out of 5	N/A	\$0
Distribution Main	1696	P-1013	WW	Dinsdale Ct.	2	Galvanized Iron	364	89	4.14 out of 5	\$442	160,874
Distribution Main	104	P-1217	WW	Douglas St	4	Cast Iron	593	70	3 out of 5	\$442	262,172
Distribution Main	3729	P-1217	WW	Douglas St.	4	Cast Iron	29	70	3 out of 5	\$442	12,757
Distribution Main	4679	P-530	WW	Dounetos St.	8	Asbestos Cement	643	65	1.29 out of 5	\$442	284,300
Distribution Main	4680	P-530	WW	Dounetos St.	8	Asbestos Cement	25	65	1.29 out of 5	\$442	11,072
Distribution Main	4818	P-528	WW	Dounetos St.	6	Asbestos Cement	267	65	2 out of 5	\$442	117,986
Distribution Main	1436	P-1930	WW	Downing Dr.	6	Asbestos Cement	252	41	1.85 out of 5	\$442	111,165
Distribution Main	1437	P-1930	WW	Downing Dr.	6	Asbestos Cement	24	41	1.85 out of 5	\$442	10,586
Distribution Main	1561	P-804	WW	Downing Dr.	6	Asbestos Cement	66	41	1.85 out of 5	\$442	29,288
Distribution Main	1562	P-804	WW	Downing Dr.	6	Asbestos Cement	62	41	1.85 out of 5	\$442	27,368
Distribution Main	1568	P-1932	WW	Downing Dr.	6	Unknown	139	41	1 out of 5	\$442	61,500
Distribution Main	1569	P-1930	WW	Downing Dr.	6	Asbestos Cement	9	41	1.85 out of 5	\$442	3,996
Transmission Main	382	P-1530	WW	Drawbridge Dr.	16	Ductile Iron	315	28	0.14 out of 5	\$442	139,146
Transmission Main	1354	P-1711	WW	Drawbridge Dr.	16	Ductile Iron	33	28	0.14 out of 5	\$442	14,708
Transmission Main	1355	P-1711	WW	Drawbridge Dr.	16	Ductile Iron	147	28	0.14 out of 5	\$442	64,920
Distribution Main	1803	P-1937	WW	Drawbridge Dr.	8	Ductile Iron	122	28	0.14 out of 5	\$442	54,088
Transmission Main	1804	P-12	WW	Drawbridge Dr.	16	Ductile Iron	235	28	0.14 out of 5	\$442	103,833
Transmission Main	2422	P-1936	WW	Drawbridge Dr.	16	Ductile Iron	9	28	0.14 out of 5	\$442	4,105
Transmission Main	2423	P-1936	WW	Drawbridge Dr.	16	Ductile Iron	10	28	0.14 out of 5	\$442	4,596
Distribution Main	2434	P-1386	WW	Drawbridge Dr.	8	Ductile Iron	286	28	0.14 out of 5	\$442	126,377

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2436	P-1387	WW	Drawbridge Dr.	8	Ductile Iron	4	28	0.14 out of 5	\$442	1,764
Distribution Main	2441	P-1387	WW	Drawbridge Dr.	8	Ductile Iron	233	28	0.14 out of 5	\$442	103,072
Distribution Main	2442	P-1387	WW	Drawbridge Dr.	8	Ductile Iron	19	28	0.14 out of 5	\$442	8,461
Transmission Main	2444	P-17	WW	Drawbridge Dr.	16	Ductile Iron	125	28	0.14 out of 5	\$442	55,381
Transmission Main	2445	P-17	WW	Drawbridge Dr.	16	Ductile Iron	230	28	0.14 out of 5	\$442	101,676
Transmission Main	2446	P-18	WW	Drawbridge Dr.	16	Ductile Iron	176	28	0.14 out of 5	\$442	77,619
Transmission Main	2447	P-18	WW	Drawbridge Dr.	16	Ductile Iron	428	28	0.14 out of 5	\$442	189,081
Transmission Main	4448	P-1378	WW	Drawbridge Dr.	16	Ductile Iron	293	28	0.14 out of 5	\$442	129,429
Transmission Main	4744	P-1379	WW	Drawbridge Dr.	16	Asbestos Cement	70	46	1.14 out of 5	\$442	30,984
Transmission Main	4745	P-1379	WW	Drawbridge Dr.	16	Asbestos Cement	3	46	1.14 out of 5	\$442	1,131
Transmission Main	12069	P-1711	WW	Drawbridge Dr.	16	Ductile Iron	6	28	0.14 out of 5	\$442	2,461
Distribution Main	1725	P-1491	WW	Duke St.	8	Ductile Iron	129	15	0 out of 5	N/A	\$0
Distribution Main	3100	P-1490	WW	Duke St.	6	Ductile Iron	7	15	0.71 out of 5	N/A	\$0
Distribution Main	4298	P-1490	WW	Duke St.	8	Ductile Iron	388	15	0 out of 5	N/A	\$0
Distribution Main	4299	P-1490	WW	Duke St.	8	Ductile Iron	7	15	0 out of 5	N/A	\$0
Distribution Main	10288	P-1600	WW	Dyer St	8	Ductile Iron	243	5	0 out of 5	N/A	\$0
Distribution Main	10291	P-1600	WW	Dyer St	6	Ductile Iron	6	5	0.71 out of 5	N/A	\$0
Distribution Main	10443		WW	Dyer St	8	Ductile Iron	21	5	0 out of 5	N/A	\$0
Distribution Main	10444		WW	Dyer St	8	Ductile Iron	107	5	0 out of 5	N/A	\$0
Distribution Main	10258		WW	E Greenwich Av		Unknown	5	UNK	0 out of 5	N/A	\$0
Distribution Main	8613	P-1342	WW	E Main St	6	Ductile Iron	14	12	0.71 out of 5	N/A	\$0
Distribution Main	8627	P-1342	WW	E Main St	8	Ductile Iron	6	12	0 out of 5	N/A	\$0
Distribution Main	10325		WW	E Main St	4	Cast Iron	39	134	3.29 out of 5	\$442	17,455
Distribution Main	8427	P-1803	WW	Eagle St	8	Ductile Iron	20	10	0 out of 5	N/A	\$0
Distribution Main	10772	P-366	WW	Earl St	8	Ductile Iron	347	0	0 out of 5	N/A	\$0
Distribution Main	10773	P-366	WW	Earl St	8	Ductile Iron	295	0	0 out of 5	N/A	\$0
Distribution Main	11724	P-343	WW	Earl St	8	Ductile Iron	286	0	0 out of 5	N/A	\$0
Distribution Main	11725	P-1988	WW	Earl St	8	Ductile Iron	192	0	0 out of 5	N/A	\$0
Distribution Main	11726	P-1988	WW	Earl St	8	Ductile Iron	41	0	0 out of 5	N/A	\$0
Distribution Main	11727	P-353	WW	Earl St	8	Ductile Iron	346	0	0 out of 5	N/A	\$0
Distribution Main	11728	P-360	WW	Earl St	8	Ductile Iron	103	0	0 out of 5	N/A	\$0
Distribution Main	11729	P-10066	WW	Earl St	8	Ductile Iron	194	0	0 out of 5	N/A	\$0
Distribution Main	12034	P-366	WW	Earl St	8	Ductile Iron	484	0	0 out of 5	N/A	\$0
Distribution Main	12035	P-1988	WW	Earl St	8	Ductile Iron	174	0	0 out of 5	N/A	\$0
Distribution Main	12036	P-349	WW	Earl St	8	Ductile Iron	122	0	0 out of 5	N/A	\$0
Distribution Main	12043	P-343	WW	Earl St	8	Ductile Iron	102	0	0 out of 5	N/A	\$0
Distribution Main	12146	P-366	WW	Earl St	8	Ductile Iron	161	0	0 out of 5	N/A	\$0
Distribution Main	12161	P-366	WW	Earl St	8	Ductile Iron	96	0	0 out of 5	N/A	\$0
Distribution Main	12204	P-343	WW	Earl St	8	Ductile Iron	236	0	0 out of 5	N/A	\$0
Distribution Main	394		WW	Earl St.	6	Cast Iron	9	84	2.43 out of 5	\$442	4,059
Distribution Main	1045		WW	Earl St.	6	Cast Iron	356	84	2.43 out of 5	\$442	157,439
Distribution Main	1046		WW	Earl St.	6	Cast Iron	492	84	2.43 out of 5	\$442	217,448
Distribution Main	11900		WW	Earl St.	6	Cast Iron	57	84	2.43 out of 5	\$442	25,139
Distribution Main	2156	P-1156	WW	Easement	8	PVC	402	33	0.43 out of 5	\$442	177,865

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2181	P-1450	WW	Easement	10	PVC	1,390	31	0.43 out of 5	\$442	614,373
Transmission Main	3192	P-1268	WW	Easement	12	Ductile Iron	405	18	0 out of 5	N/A	\$0
Distribution Main	4608	P-1270	WW	Easement	8	Ductile Iron	294	22	0.14 out of 5	N/A	\$0
Distribution Main	4609	P-1270	WW	Easement	8	Ductile Iron	15	22	0.14 out of 5	N/A	\$0
Distribution Main	4613	P-1471	WW	Easement	8	Asbestos Cement	245	50	1.14 out of 5	\$442	108,113
Distribution Main	4614	P-1471	WW	Easement	8	Asbestos Cement	4	50	1.14 out of 5	\$442	1,578
Distribution Main	11102	P-1450	WW	Easement	10	PVC	7	31	0.43 out of 5	\$442	3,185
Transmission Main	1159	P-80	WW	Easement Connection	16	Ductile Iron	8	21	0.14 out of 5	N/A	\$0
Transmission Main	1160	P-80	WW	Easement Connection	16	Ductile Iron	1,401	21	0.14 out of 5	N/A	\$0
Transmission Main	1161	P-80	WW	Easement Connection	16	Ductile Iron	4	21	0.14 out of 5	N/A	\$0
Distribution Main	9647	P-1625	WW	Easement- Wildberry	8	Ductile Iron	320	11	0 out of 5	N/A	\$0
Distribution Main	10287		WW	Easement-Flat Top Condos	8	Ductile Iron	587	5	0 out of 5	N/A	\$0
Distribution Main	10289		WW	Easement-Flat Top Condos	6	Ductile Iron	4	5	0.71 out of 5	N/A	\$0
Distribution Main	10290		WW	Easement-Flat Top Condos	6	Ductile Iron	3	5	0.71 out of 5	N/A	\$0
Transmission Main	10059	P-2850	WW	East Ave	16	Ductile Iron	81	6	0 out of 5	N/A	\$0
Transmission Main	11638	P-230	WW	East Ave	16	Ductile Iron	34	6	0 out of 5	N/A	\$0
Transmission Main	9697	P-10006	WW	East Greenwich Ave	12	Ductile Iron	21	21	0.14 out of 5	N/A	\$0
Transmission Main	10144	P-2970	WW	East Greenwich Ave	12	Ductile Iron	12	21	0.14 out of 5	N/A	\$0
Distribution Main	10255		WW	East Greenwich Ave	8	Asbestos Cement	4	43	1.14 out of 5	\$442	1,906
Transmission Main	10256		WW	East Greenwich Ave	12	Ductile Iron	3	UNK	0 out of 5	N/A	\$0
Transmission Main	10257		WW	East Greenwich Ave	12	Ductile Iron	3	UNK	0 out of 5	N/A	\$0
Distribution Main	10259		WW	East Greenwich Ave	6	Asbestos Cement	2	UNK	1.56 out of 5	\$442	1,058
Distribution Main	10266		WW	East Greenwich Ave	8	Asbestos Cement	11	43	0.85 out of 5	\$442	4,961
Transmission Main	278	P-1197	WW	East Greenwich Ave.	12	Asbestos Cement	141	19	0.85 out of 5	N/A	\$0
Transmission Main	281	P-1411	WW	East Greenwich Ave.	20	Asbestos Cement	274	50	1.14 out of 5	\$442	121,281
Transmission Main	282	P-1411	WW	East Greenwich Ave.	20	Asbestos Cement	16	50	1.14 out of 5	\$442	6,976
Transmission Main	286	P-1411	WW	East Greenwich Ave.	20	Asbestos Cement	227	50	1.14 out of 5	\$442	100,490
Transmission Main	287	P-1435	WW	East Greenwich Ave.	20	Asbestos Cement	87	50	1.14 out of 5	\$442	38,555
Transmission Main	288	P-1197	WW	East Greenwich Ave.	20	Asbestos Cement	485	19	0.85 out of 5	N/A	\$0
Transmission Main	390	P-1188	WW	East Greenwich Ave.	12	Unknown	10	UNK	0 out of 5	N/A	\$0
Distribution Main	536		WW	East Greenwich Ave.	8	Ductile Iron	34	19	0 out of 5	N/A	\$0
Transmission Main	537	P-1157	WW	East Greenwich Ave.	12	Ductile Iron	793	19	0 out of 5	N/A	\$0
Distribution Main	538	P-10017	WW	East Greenwich Ave.	8	Ductile Iron	23	19	0 out of 5	N/A	\$0
Transmission Main	539	P-1414	WW	East Greenwich Ave.	12	Ductile Iron	266	22	0.14 out of 5	N/A	\$0
Transmission Main	540	P-1415	WW	East Greenwich Ave.	12	Ductile Iron	248	22	0.14 out of 5	N/A	\$0
Transmission Main	1105	P-1296	WW	East Greenwich Ave.	12	Ductile Iron	468	19	0 out of 5	N/A	\$0
Transmission Main	1106	P-89	WW	East Greenwich Ave.	12	Ductile Iron	9	22	0.14 out of 5	N/A	\$0
Transmission Main	1107	P-116	WW	East Greenwich Ave.	12	Ductile Iron	223	22	0.14 out of 5	N/A	\$0
Transmission Main	1108	P-116	WW	East Greenwich Ave.	12	Ductile Iron	119	22	0.14 out of 5	N/A	\$0
Transmission Main	1344	P-1435	WW	East Greenwich Ave.	20	Asbestos Cement	541	50	1.14 out of 5	\$442	239,058
Transmission Main	1345	P-1428	WW	East Greenwich Ave.	20	Asbestos Cement	375	50	1.14 out of 5	\$442	165,943
Transmission Main	1346	P-1428	WW	East Greenwich Ave.	20	Asbestos Cement	9	50	1.14 out of 5	\$442	3,904
Transmission Main	1347	P-1421	WW	East Greenwich Ave.	20	Asbestos Cement	242	50	1.14 out of 5	\$442	107,179
Transmission Main	1350	P-1197	WW	East Greenwich Ave.	20	Asbestos Cement	189	19	0.85 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	1352	P-1197	WW	East Greenwich Ave.	12	Asbestos Cement	20	19	0.85 out of 5	N/A	\$0
Transmission Main	2161	P-87	WW	East Greenwich Ave.	12	Ductile Iron	76	19	0 out of 5	N/A	\$0
Transmission Main	2162	P-81	WW	East Greenwich Ave.	12	Ductile Iron	23	22	0.14 out of 5	N/A	\$0
Transmission Main	2163	P-1436	WW	East Greenwich Ave.	20	Asbestos Cement	336	50	1.14 out of 5	\$442	148,385
Transmission Main	2164	P-1436	WW	East Greenwich Ave.	20	Asbestos Cement	166	50	1.14 out of 5	\$442	73,514
Transmission Main	2165	P-116	WW	East Greenwich Ave.	12	Ductile Iron	78	22	0.14 out of 5	N/A	\$0
Transmission Main	2166	P-1400	WW	East Greenwich Ave.	12	Ductile Iron	28	22	0.14 out of 5	N/A	\$0
Transmission Main	2167	P-1182	WW	East Greenwich Ave.	12	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Transmission Main	2168	P-1182	WW	East Greenwich Ave.	12	Ductile Iron	262	22	0.14 out of 5	N/A	\$0
Transmission Main	2169	P-1418	WW	East Greenwich Ave.	12	Ductile Iron	3	22	0.14 out of 5	N/A	\$0
Transmission Main	2170	P-116	WW	East Greenwich Ave.	12	Ductile Iron	7	22	0.14 out of 5	N/A	\$0
Transmission Main	2171	P-1418	WW	East Greenwich Ave.	12	Ductile Iron	567	22	0.14 out of 5	N/A	\$0
Transmission Main	2175	P-1418	WW	East Greenwich Ave.	12	Ductile Iron	378	22	0.14 out of 5	N/A	\$0
Transmission Main	2177	P-187	WW	East Greenwich Ave.	12	Ductile Iron	375	21	0.14 out of 5	N/A	\$0
Transmission Main	2178	P-187	WW	East Greenwich Ave.	12	Ductile Iron	570	21	0.14 out of 5	N/A	\$0
Transmission Main	2254	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	151	50	1.14 out of 5	\$442	66,708
Transmission Main	2255	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	255	50	1.14 out of 5	\$442	112,538
Transmission Main	2305	P-87	WW	East Greenwich Ave.	12	Ductile Iron	116	19	0 out of 5	N/A	\$0
Transmission Main	2308	P-86	WW	East Greenwich Ave.	12	Ductile Iron	170	19	0 out of 5	N/A	\$0
Transmission Main	2309	P-81	WW	East Greenwich Ave.	12	Ductile Iron	16	22	0.14 out of 5	N/A	\$0
Transmission Main	2310	P-1296	WW	East Greenwich Ave.	12	Ductile Iron	17	19	0 out of 5	N/A	\$0
Transmission Main	2311	P-89	WW	East Greenwich Ave.	12	Ductile Iron	232	22	0.14 out of 5	N/A	\$0
Transmission Main	2312	P-89	WW	East Greenwich Ave.	12	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Transmission Main	2313	P-116	WW	East Greenwich Ave.	12	Ductile Iron	8	22	0.14 out of 5	N/A	\$0
Transmission Main	2315	P-116	WW	East Greenwich Ave.	12	Ductile Iron	8	22	0.14 out of 5	N/A	\$0
Transmission Main	2317	P-1418	WW	East Greenwich Ave.	12	Ductile Iron	6	22	0.14 out of 5	N/A	\$0
Distribution Main	2333		WW	East Greenwich Ave.	6	Unknown	11	71	1.14 out of 5	\$442	4,825
Transmission Main	2334	P-1295	WW	East Greenwich Ave.	12	Ductile Iron	300	29	0.14 out of 5	\$442	132,639
Transmission Main	2335	P-1295	WW	East Greenwich Ave.	12	Ductile Iron	335	29	0.14 out of 5	\$442	148,045
Transmission Main	2336	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	174	50	1.14 out of 5	\$442	76,751
Transmission Main	2337	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	104	50	1.14 out of 5	\$442	45,914
Distribution Main	2343	P-1158	WW	East Greenwich Ave.	6	Asbestos Cement	249	71	2 out of 5	\$442	110,064
Distribution Main	2344	P-1158	WW	East Greenwich Ave.	6	Asbestos Cement	27	71	2 out of 5	\$442	11,944
Distribution Main	3894	P-1139	WW	East Greenwich Ave.	4	Cast Iron	352	124	3.29 out of 5	\$442	155,493
Distribution Main	3895	P-1139	WW	East Greenwich Ave.	4	Cast Iron	486	124	3.29 out of 5	\$442	214,999
Distribution Main	4688	P-1140	WW	East Greenwich Ave.	6	Asbestos Cement	138	71	2 out of 5	\$442	61,014
Transmission Main	4696	P-2743	WW	East Greenwich Ave.	20	Asbestos Cement	74	50	1.14 out of 5	\$442	32,572
Transmission Main	4699	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	498	50	1.14 out of 5	\$442	220,080
Transmission Main	4700	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	580	50	1.14 out of 5	\$442	256,566
Transmission Main	4701	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	447	50	1.14 out of 5	\$442	197,497
Distribution Main	4781	P-1599	WW	East Greenwich Ave.	6	Asbestos Cement	7	71	2 out of 5	\$442	2,932
Distribution Main	4782	P-1599	WW	East Greenwich Ave.	6	Asbestos Cement	295	71	2 out of 5	\$442	130,462
Transmission Main	8512	P-187	WW	East Greenwich Ave.	12	Ductile Iron	229	21	0.14 out of 5	N/A	\$0
Transmission Main	8513	P-187	WW	East Greenwich Ave.	12	Ductile Iron	142	21	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	8514	P-187	WW	East Greenwich Ave.	12	Ductile Iron	232	22	0.14 out of 5	N/A	\$0
Transmission Main	8515	P-187	WW	East Greenwich Ave.	12	Ductile Iron	578	21	0.14 out of 5	N/A	\$0
Transmission Main	9496	P-89	WW	East Greenwich Ave.	12	Ductile Iron	61	22	0.14 out of 5	N/A	\$0
Transmission Main	9919	P-1294	WW	East Greenwich Ave.	12	PVC	419	19	0.28 out of 5	N/A	\$0
Transmission Main	10087	P-1157	WW	East Greenwich Ave.	12	Ductile Iron	135	19	0 out of 5	N/A	\$0
Transmission Main	10253	P-1197	WW	East Greenwich Ave.	20	Asbestos Cement	13	19	0.85 out of 5	N/A	\$0
Distribution Main	10254		WW	East Greenwich Ave.	8	Ductile Iron	2	21	0.14 out of 5	N/A	\$0
Transmission Main	10436	P-1197	WW	East Greenwich Ave.	20	Asbestos Cement	6	19	0.85 out of 5	N/A	\$0
Transmission Main	10437	P-1151	WW	East Greenwich Ave.	12	Asbestos Cement	45	19	0.85 out of 5	N/A	\$0
Transmission Main	10438	P-1151	WW	East Greenwich Ave.	12	Asbestos Cement	93	19	0.85 out of 5	N/A	\$0
Transmission Main	11063	P-1436	WW	East Greenwich Ave.	20	Asbestos Cement	12	50	1.14 out of 5	\$442	5,188
Transmission Main	11127	P-1197	WW	East Greenwich Ave.	20	Asbestos Cement	16	19	0.85 out of 5	N/A	\$0
Transmission Main	11156	P-1436	WW	East Greenwich Ave.	20	Asbestos Cement	203	50	1.14 out of 5	\$442	89,923
Transmission Main	11157	P-187	WW	East Greenwich Ave.	12	Ductile Iron	204	21	0.14 out of 5	N/A	\$0
Transmission Main	11158	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	7	50	1.14 out of 5	\$442	3,061
Transmission Main	11159	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	6	50	1.14 out of 5	\$442	2,736
Transmission Main	11162	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	148	50	1.14 out of 5	\$442	65,435
Transmission Main	11473	P-187	WW	East Greenwich Ave.	12	Ductile Iron	144	21	0.14 out of 5	N/A	\$0
Transmission Main	11623	P-1687	WW	East Greenwich Ave.	12	PVC	147	19	0.28 out of 5	N/A	\$0
Transmission Main	11624	P-1579	WW	East Greenwich Ave.	12	PVC	3	19	0.28 out of 5	N/A	\$0
Transmission Main	12074	P-1404	WW	East Greenwich Ave.	20	Asbestos Cement	150	50	1.14 out of 5	\$442	66,413
Transmission Main	12094	P-187	WW	East Greenwich Ave.	12	Ductile Iron	45	19	0 out of 5	N/A	\$0
Transmission Main	12095	P-187	WW	East Greenwich Ave.	12	Ductile Iron	37	21	0.14 out of 5	N/A	\$0
Transmission Main	12155	P-1415	WW	East Greenwich Ave.	12	Ductile Iron	2	22	0.14 out of 5	N/A	\$0
Distribution Main	325	P-1350	WW	East Main St.	6	Cast Iron	283	133	2.57 out of 5	\$442	124,935
Distribution Main	326	P-1350	WW	East Main St.	6	Cast Iron	14	133	2.57 out of 5	\$442	6,257
Distribution Main	435	P-986	WW	East Main St.	6	Cast Iron	188	133	2.57 out of 5	\$442	83,030
Distribution Main	436	P-1351	WW	East Main St.	6	Cast Iron	390	134	2.57 out of 5	\$442	172,200
Distribution Main	437	P-1351	WW	East Main St.	6	Cast Iron	9	133	2.57 out of 5	\$442	4,189
Distribution Main	441	P-995	WW	East Main St.	6	Cast Iron	214	133	2.57 out of 5	\$442	94,532
Distribution Main	958	P-1350	WW	East Main St.	6	Cast Iron	26	133	2.57 out of 5	\$442	11,434
Transmission Main	1168	P-1005	WW	East Main St.	12	Asbestos Cement	377	68	1.29 out of 5	\$442	166,691
Transmission Main	1169	P-1005	WW	East Main St.	12	Asbestos Cement	20	68	1.29 out of 5	\$442	8,786
Distribution Main	1692	P-988	WW	East Main St.	6	Cast Iron	322	133	2.57 out of 5	\$442	142,535
Distribution Main	2206	P-1351	WW	East Main St.	6	Cast Iron	90	134	2.57 out of 5	\$442	39,934
Distribution Main	3335	P-995	WW	East Main St.	6	Cast Iron	8	133	2.57 out of 5	\$442	3,556
Transmission Main	3339	P-1004	WW	East Main St.	12	Asbestos Cement	353	68	1.29 out of 5	\$442	156,094
Transmission Main	3340	P-1004	WW	East Main St.	12	Asbestos Cement	438	68	1.29 out of 5	\$442	193,456
Distribution Main	12001	P-1350	WW	East Main St.	6	Cast Iron	120	133	2.57 out of 5	\$442	53,076
Distribution Main	12002	P-1350	WW	East Main St.	6	Cast Iron	233	133	2.57 out of 5	\$442	102,887
Distribution Main	128	P-1955	WW	East St.	6	Ductile Iron	86	29	0.85 out of 5	\$442	38,112
Distribution Main	129	P-1955	WW	East St.	6	Ductile Iron	141	29	0.85 out of 5	\$442	62,481
Distribution Main	133	P-699	WW	East St.	6	Ductile Iron	23	29	0.85 out of 5	\$442	10,358
Distribution Main	3611	P-700	WW	East St.	6	Ductile Iron	478	29	0.85 out of 5	\$442	211,447

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3761	P-699	WW	East St.	6	Ductile Iron	244	29	0.85 out of 5	\$442	107,644
Distribution Main	8977		WW	Echo Ln	8	Ductile Iron	5	9	0 out of 5	N/A	\$0
Distribution Main	2245	P-659	WW	Eddy St.	6	Cast Iron	424	134	2.57 out of 5	\$442	187,460
Distribution Main	4329	P-660	WW	Eddy St.	6	Cast Iron	33	134	2.57 out of 5	\$442	14,618
Distribution Main	4330	P-660	WW	Eddy St.	6	Cast Iron	447	134	2.57 out of 5	\$442	197,574
Distribution Main	10654	P-385	WW	Edge St	6	Ductile Iron	15	2	0.71 out of 5	N/A	\$0
Distribution Main	10655	P-385	WW	Edge St	6	Ductile Iron	1	2	0.71 out of 5	N/A	\$0
Distribution Main	10656	P-385	WW	Edge St	8	Ductile Iron	5	2	0 out of 5	N/A	\$0
Distribution Main	3539	P-385	WW	Edge St.	6	Ductile Iron	260	31	0.85 out of 5	\$442	114,915
Distribution Main	3540		WW	Edge St.	6	Ductile Iron	10	31	0.85 out of 5	\$442	4,225
Distribution Main	10652	P-385	WW	Edge St.	6	Ductile Iron	18	2	0.71 out of 5	N/A	\$0
Distribution Main	10653	P-385	WW	Edge St.	6	Ductile Iron	16	UNK	0.71 out of 5	\$442	7,266
Distribution Main	10657	P-374	WW	Edith St	8	Ductile Iron	589	2	0 out of 5	N/A	\$0
Distribution Main	3549	P-111	WW	Edwards Ct.	6	Asbestos Cement	139	52	1.85 out of 5	\$442	61,408
Distribution Main	10412	P-606	WW	Eileen Dr	8	Ductile Iron	16	8	0 out of 5	N/A	\$0
Distribution Main	10413	P-606	WW	Eileen Dr	8	Ductile Iron	98	8	0 out of 5	N/A	\$0
Distribution Main	9367	P-606	WW	Eileen Dr.	8	Ductile Iron	17	14	0 out of 5	N/A	\$0
Distribution Main	1793	P-1854	WW	Elbow St	2	Unknown	269	34	1.57 out of 5	\$442	118,737
Distribution Main	4621	P-94	WW	Elizabeth Ct	8	Asbestos Cement	15	49	1.14 out of 5	\$442	6,731
Distribution Main	5184	P-94	WW	Elizabeth Ct	8	Asbestos Cement	418	49	1.14 out of 5	\$442	184,851
Distribution Main	1070	P-1025	WW	Ellison St.	2	Copper	489	79	2.43 out of 5	\$442	216,100
Distribution Main	440	P-987	WW	Elm St.	1	Galvanized Iron	30	91	3.43 out of 5	\$442	13,281
Distribution Main	3337	P-987	WW	Elm St.	1	Galvanized Iron	207	91	3.43 out of 5	\$442	91,470
Distribution Main	8083	P-1514	WW	Emerson Ct	8	Ductile Iron	312	13	0 out of 5	N/A	\$0
Distribution Main	8084	P-1514	WW	Emerson Ct	8	Ductile Iron	200	13	0 out of 5	N/A	\$0
Distribution Main	9802	P-1966	WW	Emile St	8	Ductile Iron	195	8	0 out of 5	N/A	\$0
Transmission Main	1326	P-75	WW	Energy Way	12	Ductile Iron	587	19	0 out of 5	N/A	\$0
Distribution Main	1327		WW	Energy Way	6	PVC	80	UNK	0.99 out of 5	\$442	35,578
Transmission Main	2806	P-75	WW	Energy Way	12	Ductile Iron	72	19	0 out of 5	N/A	\$0
Distribution Main	8928	P-1718	WW	Enfield Dr	8	Ductile Iron	297	9	0 out of 5	N/A	\$0
Distribution Main	8929	P-1718	WW	Enfield Dr	8	Ductile Iron	263	9	0 out of 5	N/A	\$0
Distribution Main	8930	P-1719	WW	Enfield Dr	8	Ductile Iron	169	9	0 out of 5	N/A	\$0
Distribution Main	8931	P-1736	WW	Enfield Dr	8	Ductile Iron	278	9	0 out of 5	N/A	\$0
Distribution Main	9395	P-1718	WW	Enfield Dr	8	Ductile Iron	3	9	0 out of 5	N/A	\$0
Distribution Main	10830	P-1719	WW	Enfield Dr	8	Ductile Iron	150	9	0 out of 5	N/A	\$0
Distribution Main	10831	P-1719	WW	Enfield Dr	8	Ductile Iron	119	9	0 out of 5	N/A	\$0
Distribution Main	10832	P-196	WW	Enfield Dr	8	Ductile Iron	168	9	0 out of 5	N/A	\$0
Distribution Main	11002	P-1718	WW	Enfield Dr	8	Ductile Iron	2	9	0 out of 5	N/A	\$0
Distribution Main	4279	P-16	WW	Enfield Dr.	8	Ductile Iron	29	15	0 out of 5	N/A	\$0
Distribution Main	1729	P-648	WW	Epworth Ave.	6	Cast Iron	412	134	2.57 out of 5	\$442	182,181
Distribution Main	1730	P-648	WW	Epworth Ave.	6	Cast Iron	368	134	2.57 out of 5	\$442	162,626
Distribution Main	3976	P-649	WW	Epworth Ave.	4	Cast Iron	257	134	3.29 out of 5	\$442	113,561
Distribution Main	4003	P-649	WW	Epworth Ave.	4	Cast Iron	23	134	3.29 out of 5	\$442	10,093
Distribution Main	12000	P-648	WW	Epworth Ave.	6	Cast Iron	34	134	2.57 out of 5	\$442	14,886

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2696	P-8028	WW	Ernest St.	8	Ductile Iron	350	18	0 out of 5	N/A	\$0
Distribution Main	3896		WW	Esmond St.	6	Asbestos Cement	9	69	2 out of 5	\$442	3,777
Distribution Main	4689	P-1591	WW	Esmond St.	6	Asbestos Cement	135	69	2 out of 5	\$442	59,660
Distribution Main	4833	P-1165	WW	Esmond St.	6	Asbestos Cement	190	69	2 out of 5	\$442	84,103
Distribution Main	4834	P-1165	WW	Esmond St.	6	Asbestos Cement	419	69	2 out of 5	\$442	185,161
Distribution Main	11261	P-1591	WW	Esmond St.	6	Asbestos Cement	97	69	2 out of 5	\$442	42,910
Distribution Main	10621	P-399	WW	Ethel Av	8	Ductile Iron	428	2	0 out of 5	N/A	\$0
Distribution Main	10622	P-399	WW	Ethel Av	8	Ductile Iron	341	2	0 out of 5	N/A	\$0
Distribution Main	5141	P-427	WW	Evelyn St.	6	Asbestos Cement	256	72	2 out of 5	\$442	113,137
Distribution Main	2540	P-45	WW	Exchange Rd.	8	Asbestos Cement	244	50	1.14 out of 5	\$442	107,862
Distribution Main	2548	P-33	WW	Exchange Rd.	8	Asbestos Cement	270	50	1.14 out of 5	\$442	119,144
Distribution Main	2549	P-39	WW	Exchange Rd.	8	Asbestos Cement	441	50	1.14 out of 5	\$442	195,101
Distribution Main	2550	P-39	WW	Exchange Rd.	8	Asbestos Cement	26	50	1.14 out of 5	\$442	11,325
Distribution Main	4644	P-1377	WW	Exchange Rd.	8	Asbestos Cement	166	44	1.14 out of 5	\$442	73,322
Distribution Main	4966	P-1377	WW	Exchange Rd.	8	Asbestos Cement	105	50	1.14 out of 5	\$442	46,541
Distribution Main	11259	P-1377	WW	Exchange Rd.	8	Asbestos Cement	8	44	1.14 out of 5	\$442	3,533
Distribution Main	10797	P-342	WW	Factory St	8	Ductile Iron	297	0	0 out of 5	N/A	\$0
Distribution Main	10798	P-340	WW	Factory St	8	Ductile Iron	259	0	0 out of 5	N/A	\$0
Distribution Main	10875	P-329	WW	Factory St	8	Ductile Iron	230	0	0 out of 5	N/A	\$0
Distribution Main	10876	P-333	WW	Factory St	8	Ductile Iron	252	0	0 out of 5	N/A	\$0
Distribution Main	10877	P-339	WW	Factory St	8	Ductile Iron	16	0	0 out of 5	N/A	\$0
Distribution Main	11734	P-340	WW	Factory St	8	Ductile Iron	187	0	0 out of 5	N/A	\$0
Distribution Main	12039	P-342	WW	Factory St	8	Ductile Iron	58	0	0 out of 5	N/A	\$0
Distribution Main	12042	P-342	WW	Factory St	8	Ductile Iron	219	0	0 out of 5	N/A	\$0
Distribution Main	12044	P-342	WW	Factory St	8	Ductile Iron	23	0	0 out of 5	N/A	\$0
Distribution Main	12200	P-342	WW	Factory St	8	Ductile Iron	170	0	0 out of 5	N/A	\$0
Distribution Main	12202	P-342	WW	Factory St	8	Ductile Iron	6	0	0 out of 5	N/A	\$0
Distribution Main	12205	P-342	WW	Factory St	8	Ductile Iron	29	0	0 out of 5	N/A	\$0
Distribution Main	1164	P-10070	WW	Factory St.	6	Cast Iron	197	134	2.57 out of 5	\$442	87,119
Distribution Main	1358		WW	Factory St.	6	Unknown	19	UNK	0.71 out of 5	\$442	8,565
Distribution Main	1600	P-1015	WW	Factory St.	6	Cast Iron	222	134	2.57 out of 5	\$442	97,941
Distribution Main	2684	P-10070	WW	Factory St.	6	Cast Iron	161	134	2.57 out of 5	\$442	70,980
Distribution Main	2685	P-1016	WW	Factory St.	6	Cast Iron	16	134	2.57 out of 5	\$442	7,158
Distribution Main	2686	P-1016	WW	Factory St.	6	Cast Iron	161	134	2.57 out of 5	\$442	71,319
Distribution Main	2687		WW	Factory St.	6	Unknown	142	UNK	0.71 out of 5	\$442	62,946
Distribution Main	2688		WW	Factory St.	6	Unknown	161	UNK	0.71 out of 5	\$442	71,032
Distribution Main	3368	P-1015	WW	Factory St.	6	Cast Iron	79	134	2.57 out of 5	\$442	34,750
Distribution Main	11184	P-1016	WW	Factory St.	6	Cast Iron	10	134	2.57 out of 5	\$442	4,498
Distribution Main	12045	P-10070	WW	Factory St.	6	Cast Iron	13	134	2.57 out of 5	\$442	5,939
Distribution Main	9975		WW	Factory Street	6	Ductile Iron	38	12	0.71 out of 5	N/A	\$0
Distribution Main	12040		WW	Factory Street	8	Ductile Iron	69	UNK	0 out of 5	N/A	\$0
Distribution Main	1978	P-482	WW	Fairgreen Dr.	6	Asbestos Cement	265	63	2 out of 5	\$442	117,151
Distribution Main	1979	P-482	WW	Fairgreen Dr.	6	Asbestos Cement	120	63	2 out of 5	\$442	53,115
Distribution Main	1981	P-479	WW	Fairgreen Dr.	6	Asbestos Cement	27	63	2 out of 5	\$442	11,716

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3113	P-479	WW	Fairgreen Dr.	6	Asbestos Cement	505	63	2 out of 5	\$442	223,303
Distribution Main	5073	P-480	WW	Fairgreen Dr.	6	Asbestos Cement	238	63	2 out of 5	\$442	105,285
Distribution Main	5074	P-482	WW	Fairgreen Dr.	6	Asbestos Cement	5	63	2 out of 5	\$442	2,126
Distribution Main	1973	P-1096	WW	Fairmont St.	6	Asbestos Cement	198	57	1.85 out of 5	\$442	87,561
Distribution Main	4209	P-1096	WW	Fairmont St.	6	Asbestos Cement	431	57	1.85 out of 5	\$442	190,484
Distribution Main	4210	P-1096	WW	Fairmont St.	6	Asbestos Cement	14	57	1.85 out of 5	\$442	6,131
Transmission Main	8553	P-1921	WW	Fairview Ave	20	Ductile Iron	32	13	0 out of 5	N/A	\$0
Transmission Main	8554	P-1258	WW	Fairview Ave	12	Ductile Iron	12	13	0 out of 5	N/A	\$0
Transmission Main	8559		WW	Fairview Ave	12	Ductile Iron	8	13	0 out of 5	N/A	\$0
Transmission Main	8967	P-1611	WW	Fairview Ave	16	Ductile Iron	249	9	0 out of 5	N/A	\$0
Transmission Main	8968	P-1611	WW	Fairview Ave	16	Ductile Iron	163	9	0 out of 5	N/A	\$0
Distribution Main	8971		WW	Fairview Ave	6	Ductile Iron	18	9	0.71 out of 5	N/A	\$0
Distribution Main	8972	P-1209	WW	Fairview Ave	6	Ductile Iron	27	9	0.71 out of 5	N/A	\$0
Transmission Main	8973	P-1207	WW	Fairview Ave	16	Ductile Iron	173	9	0 out of 5	N/A	\$0
Transmission Main	8974	P-1205	WW	Fairview Ave	16	Ductile Iron	212	9	0 out of 5	N/A	\$0
Transmission Main	8982	P-1260	WW	Fairview Ave	16	Ductile Iron	121	9	0 out of 5	N/A	\$0
Transmission Main	8983	P-1260	WW	Fairview Ave	16	Ductile Iron	6	9	0 out of 5	N/A	\$0
Transmission Main	8986	P-1922	WW	Fairview Ave	12	Ductile Iron	15	9	0 out of 5	N/A	\$0
Transmission Main	8987	P-1258	WW	Fairview Ave	12	Ductile Iron	10	9	0 out of 5	N/A	\$0
Transmission Main	8989	P-1261	WW	Fairview Ave	12	Ductile Iron	180	9	0 out of 5	N/A	\$0
Transmission Main	8990	P-1261	WW	Fairview Ave	20	Ductile Iron	2	13	0 out of 5	N/A	\$0
Transmission Main	9693	P-1259	WW	Fairview Ave	16	Ductile Iron	87	9	0 out of 5	N/A	\$0
Transmission Main	9694	P-1922	WW	Fairview Ave	16	Ductile Iron	8	9	0 out of 5	N/A	\$0
Transmission Main	11039	P-1260	WW	Fairview Ave	16	Ductile Iron	2	9	0 out of 5	N/A	\$0
Transmission Main	11040	P-1258	WW	Fairview Ave	12	Ductile Iron	2	9	0 out of 5	N/A	\$0
Transmission Main	11531	P-1928	WW	Fairview Ave	16	Ductile Iron	67	9	0 out of 5	N/A	\$0
Transmission Main	11533	P-1207	WW	Fairview Ave	16	Ductile Iron	28	9	0 out of 5	N/A	\$0
Transmission Main	11534	P-1259	WW	Fairview Ave	16	Ductile Iron	126	9	0 out of 5	N/A	\$0
Transmission Main	11535	P-1923	WW	Fairview Ave	16	Ductile Iron	32	9	0 out of 5	N/A	\$0
Transmission Main	12019	P-1928	WW	Fairview Ave	16	Ductile Iron	59	9	0 out of 5	N/A	\$0
Transmission Main	12100	P-1207	WW	Fairview Ave	16	Ductile Iron	41	9	0 out of 5	N/A	\$0
Distribution Main	3115	P-1150	WW	Fawn Ln.	8	Asbestos Cement	634	42	1.14 out of 5	\$442	280,421
Distribution Main	3116	P-1150	WW	Fawn Ln.	8	Asbestos Cement	104	42	1.14 out of 5	\$442	45,780
Distribution Main	10620	P-402	WW	Faxon St	8	Ductile Iron	228	2	0 out of 5	N/A	\$0
Distribution Main	8922	P-155	WW	Fernwood Dr	8	Ductile Iron	466	9	0 out of 5	N/A	\$0
Distribution Main	8923	P-155	WW	Fernwood Dr	8	Ductile Iron	8	9	0 out of 5	N/A	\$0
Distribution Main	9402	P-1726	WW	Fernwood Dr	8	Ductile Iron	14	9	0 out of 5	N/A	\$0
Distribution Main	3586	P-1726	WW	Fernwood Dr.	8	Ductile Iron	22	15	0 out of 5	N/A	\$0
Distribution Main	10796	P-344	WW	First St	8	Ductile Iron	327	0	0 out of 5	N/A	\$0
Distribution Main	10038	P-251	WW	Fiume St	8	Ductile Iron	662	6	0 out of 5	N/A	\$0
Distribution Main	10039	P-252	WW	Fiume St	8	Ductile Iron	240	6	0 out of 5	N/A	\$0
Transmission Main	1104	P-88	WW	Flanders Dr.	12	Ductile Iron	425	19	0 out of 5	N/A	\$0
Distribution Main	2306	P-88	WW	Flanders Dr.	8	Ductile Iron	7	19	0 out of 5	N/A	\$0
Distribution Main	2307	P-88	WW	Flanders Dr.	8	Ductile Iron	20	19	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	2332	P-1298	WW	Flanders Dr.	20	Asbestos Cement	450	50	1.14 out of 5	\$442	199,027
Transmission Main	11104	P-88	WW	Flanders Dr.	12	Ductile Iron	10	19	0 out of 5	N/A	\$0
Distribution Main	1691		WW	Flynn Ter.	4	Unknown	165	UNK	1.42 out of 5	\$442	72,970
Distribution Main	335	P-817	WW	Flynn Ter.	6	Asbestos Cement	11	67	2 out of 5	\$442	4,922
Distribution Main	957	P-816	WW	Flynn Ter.	4	Cast Iron	20	134	3.29 out of 5	\$442	8,932
Distribution Main	2208	P-816	WW	Flynn Ter.	4	Cast Iron	199	134	3.29 out of 5	\$442	88,039
Distribution Main	3350	P-817	WW	Flynn Ter.	6	Asbestos Cement	386	67	2 out of 5	\$442	170,586
Distribution Main	3356	P-816	WW	Flynn Ter.	4	Asbestos Cement	92	67	2.71 out of 5	\$442	40,569
Distribution Main	4167	P-83	WW	Forest Ave.	6	Copper	5	78	1.71 out of 5	\$442	2,288
Distribution Main	4392	P-90	WW	Forest Ave.	6	Asbestos Cement	201	78	2 out of 5	\$442	88,727
Distribution Main	5297	P-83	WW	Forest Ave.	6	Copper	9	78	1.71 out of 5	\$442	4,073
Distribution Main	6547		WW	Forest Ave.	6	Asbestos Cement	3	78	2 out of 5	\$442	1,261
Distribution Main	6548	P-83	WW	Forest Ave.	2	Copper	197	78	2.43 out of 5	\$442	86,875
Distribution Main	860	P-292	WW	Fornelli St.	6	Asbestos Cement	209	78	2 out of 5	\$442	92,443
Distribution Main	861	P-292	WW	Fornelli St.	6	Asbestos Cement	366	78	2 out of 5	\$442	161,567
Distribution Main	4087	P-1087	WW	Fountain St.	6	Asbestos Cement	683	50	1.85 out of 5	\$442	302,043
Distribution Main	2341	P-85	WW	Fox Run	6	Ductile Iron	27	29	0.85 out of 5	\$442	11,806
Distribution Main	2342	P-85	WW	Fox Run	6	Ductile Iron	300	29	0.85 out of 5	\$442	132,460
Distribution Main	4676	P-10032	WW	Freemont St.	6	Unknown	4	69	1.14 out of 5	\$442	1,918
Distribution Main	4677	P-10032	WW	Freemont St.	6	Unknown	335	69	1.14 out of 5	\$442	147,956
Distribution Main	5127	P-10032	WW	Freemont St.	6	Unknown	6	69	1.14 out of 5	\$442	2,482
Distribution Main	4629	P-62	WW	Friar Tuck La.	8	Asbestos Cement	195	46	1.14 out of 5	\$442	86,241
Distribution Main	2400	P-819	WW	Fruit St.	4	Cast Iron	15	134	3.29 out of 5	\$442	6,425
Distribution Main	3346	P-819	WW	Fruit St.	4	Cast Iron	202	134	3.29 out of 5	\$442	89,489
Distribution Main	10018	P-274	WW	Gage St.	8	Ductile Iron	157	6	0 out of 5	N/A	\$0
Distribution Main	10028	P-274	WW	Gage St.	8	Ductile Iron	201	6	0 out of 5	N/A	\$0
Distribution Main	1699	P-1047	WW	Gardner Ave.	4	Cast Iron	506	132	3.29 out of 5	\$442	223,738
Distribution Main	1700	P-1047	WW	Gardner Ave.	4	Cast Iron	10	132	3.29 out of 5	\$442	4,619
Distribution Main	1882	P-747	WW	Gareau St.	6	Cast Iron	269	79	2.28 out of 5	\$442	118,930
Distribution Main	9646	P-748	WW	Gareau St.	8	Ductile Iron	239	11	0 out of 5	N/A	\$0
Distribution Main	1534	P-902	WW	Garfield Ter.	6	Ductile Iron	64	27	0.85 out of 5	\$442	28,311
Distribution Main	1535	P-902	WW	Garfield Ter.	6	Ductile Iron	183	27	0.85 out of 5	\$442	81,055
Distribution Main	487	P-965	WW	Garnet St.	6	Asbestos Cement	313	58	1.85 out of 5	\$442	138,267
Distribution Main	1537	P-963	WW	Garnet St.	6	Asbestos Cement	450	58	1.85 out of 5	\$442	198,907
Distribution Main	8420	P-1805	WW	Garnet St.	8	Ductile Iron	4	10	0 out of 5	N/A	\$0
Distribution Main	8421	P-1805	WW	Garnet St.	8	Ductile Iron	33	10	0 out of 5	N/A	\$0
Distribution Main	3249	P-1083	WW	Gendron Street	2	Copper	38	81	2.57 out of 5	\$442	16,940
Distribution Main	3250	P-1083	WW	Gendron Street	2	Copper	240	81	2.57 out of 5	\$442	106,143
Distribution Main	10787	P-10067	WW	Gerald St	8	Ductile Iron	116	0	0 out of 5	N/A	\$0
Distribution Main	10788	P-1508	WW	Gerald St	8	Ductile Iron	285	0	0 out of 5	N/A	\$0
Distribution Main	501	P-867	WW	Gilcrest Cir.	8	Ductile Iron	57	18	0 out of 5	N/A	\$0
Distribution Main	502	P-867	WW	Gilcrest Cir.	8	Ductile Iron	303	18	0 out of 5	N/A	\$0
Distribution Main	2054	P-870	WW	Gilcrest Cir.	8	Ductile Iron	371	18	0 out of 5	N/A	\$0
Distribution Main	2055	P-870	WW	Gilcrest Cir.	8	Ductile Iron	176	18	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2056	P-871	WW	Gilcrest Cir.	8	Ductile Iron	29	18	0 out of 5	N/A	\$0
Distribution Main	2057	P-871	WW	Gilcrest Cir.	8	Ductile Iron	360	18	0 out of 5	N/A	\$0
Distribution Main	2058	P-869	WW	Gilcrest Cir.	8	Ductile Iron	234	18	0 out of 5	N/A	\$0
Distribution Main	2059	P-1560	WW	Gilcrest Cir.	8	Ductile Iron	4	18	0 out of 5	N/A	\$0
Distribution Main	2073	P-869	WW	Gilcrest Cir.	8	Ductile Iron	130	18	0 out of 5	N/A	\$0
Distribution Main	2077	P-871	WW	Gilcrest Cir.	8	Ductile Iron	26	18	0 out of 5	N/A	\$0
Distribution Main	2079	P-871	WW	Gilcrest Cir.	8	Ductile Iron	364	18	0 out of 5	N/A	\$0
Distribution Main	2080	P-871	WW	Gilcrest Cir.	8	Ductile Iron	28	18	0 out of 5	N/A	\$0
Distribution Main	2081	P-871	WW	Gilcrest Cir.	8	Ductile Iron	8	18	0 out of 5	N/A	\$0
Distribution Main	2082	P-1560	WW	Gilcrest Cir.	8	Ductile Iron	172	18	0 out of 5	N/A	\$0
Distribution Main	2083	P-1560	WW	Gilcrest Cir.	8	Ductile Iron	5	18	0 out of 5	N/A	\$0
Distribution Main	2084		WW	Gilcrest Cir.	8	Ductile Iron	13	18	0 out of 5	N/A	\$0
Distribution Main	2085		WW	Gilcrest Cir.	8	Ductile Iron	3	18	0 out of 5	N/A	\$0
Distribution Main	2093	P-871	WW	Gilcrest Cir.	8	Ductile Iron	10	18	0 out of 5	N/A	\$0
Distribution Main	2099	P-869	WW	Gilcrest Cir.	8	Ductile Iron	4	18	0 out of 5	N/A	\$0
Distribution Main	8056		WW	Gilcrest Cir.	8	Ductile Iron	4	18	0 out of 5	N/A	\$0
Distribution Main	8057	P-871	WW	Gilcrest Cir.	8	Ductile Iron	4	18	0 out of 5	N/A	\$0
Distribution Main	9427	P-871	WW	Gilcrest Cir.	8	Ductile Iron	4	18	0 out of 5	N/A	\$0
Distribution Main	10982	P-871	WW	Gilcrest Cir.	8	Ductile Iron	4	18	0 out of 5	N/A	\$0
Distribution Main	10983	P-1560	WW	Gilcrest Cir.	8	Ductile Iron	5	18	0 out of 5	N/A	\$0
Distribution Main	12048	P-870	WW	Gilcrest Cir.	8	Ductile Iron	27	18	0 out of 5	N/A	\$0
Distribution Main	2078		WW	Gilcrest Dr.	8	Ductile Iron	23	UNK	0 out of 5	N/A	\$0
Distribution Main	8995		WW	Giorgio Dr	6	Unknown	5	UNK	0.71 out of 5	\$442	2,149
Distribution Main	811	P-435	WW	Glen Dr.	6	Asbestos Cement	548	53	1.85 out of 5	\$442	242,348
Distribution Main	2968	P-440	WW	Glen Dr.	6	PVC	286	32	1.14 out of 5	\$442	126,195
Distribution Main	2969	P-440	WW	Glen Dr.	6	PVC	518	32	1.14 out of 5	\$442	229,021
Distribution Main	9134	P-440	WW	Glen Dr.	6	Asbestos Cement	223	53	1.85 out of 5	\$442	98,715
Distribution Main	8932	P-194	WW	Glendale Dr	8	Ductile Iron	237	9	0 out of 5	N/A	\$0
Distribution Main	8941	P-195	WW	Glendale Dr	8	Ductile Iron	217	9	0 out of 5	N/A	\$0
Distribution Main	8942	P-195	WW	Glendale Dr	8	Ductile Iron	15	9	0 out of 5	N/A	\$0
Distribution Main	8947	P-208	WW	Glendale Dr	8	Ductile Iron	613	9	0 out of 5	N/A	\$0
Distribution Main	8948	P-208	WW	Glendale Dr	8	Ductile Iron	431	9	0 out of 5	N/A	\$0
Distribution Main	8951	P-206	WW	Glendale Dr	8	Ductile Iron	108	9	0 out of 5	N/A	\$0
Distribution Main	10932	P-206	WW	Glendale Dr	8	Ductile Iron	136	9	0 out of 5	N/A	\$0
Distribution Main	11528	P-209	WW	Glendale Dr	8	Ductile Iron	74	9	0 out of 5	N/A	\$0
Distribution Main	316	P-1077	WW	Gough Ave.	6	Cast Iron	103	133	2.57 out of 5	\$442	45,508
Distribution Main	380	P-775	WW	Gough Ave.	6	Cast Iron	188	82	2.43 out of 5	\$442	82,963
Distribution Main	381	P-774	WW	Gough Ave.	6	Asbestos Cement	16	75	2 out of 5	\$442	7,083
Distribution Main	388	P-1883	WW	Gough Ave.	6	Cast Iron	16	UNK	1.85 out of 5	\$442	6,952
Distribution Main	444	P-1879	WW	Gough Ave.	6	Cast Iron	731	133	2.57 out of 5	\$442	323,272
Distribution Main	1074	P-1036	WW	Gough Ave.	6	Cast Iron	203	133	2.57 out of 5	\$442	89,819
Transmission Main	1209	P-770	WW	Gough Ave.	16	Asbestos Cement	404	75	1.29 out of 5	\$442	178,555
Distribution Main	1970	P-1076	WW	Gough Ave.	6	Cast Iron	379	133	2.57 out of 5	\$442	167,385
Distribution Main	2391		WW	Gough Ave.	8	Unknown	18	75	0.43 out of 5	\$442	8,064

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2483		WW	Gough Ave.	6	Unknown	223	UNK	0.71 out of 5	\$442	98,670
Distribution Main	2484		WW	Gough Ave.	6	Unknown	149	UNK	0.71 out of 5	\$442	65,876
Distribution Main	2492	P-784	WW	Gough Ave.	6	Cast Iron	27	82	2.43 out of 5	\$442	11,936
Distribution Main	2495	P-1072	WW	Gough Ave.	6	Cast Iron	210	133	2.57 out of 5	\$442	92,922
Distribution Main	2862	P-1069	WW	Gough Ave.	6	Cast Iron	366	82	2.43 out of 5	\$442	161,738
Distribution Main	2863	P-777	WW	Gough Ave.	6	Cast Iron	21	82	2.43 out of 5	\$442	9,387
Distribution Main	2864	P-777	WW	Gough Ave.	6	Cast Iron	215	82	2.43 out of 5	\$442	95,208
Distribution Main	3372	P-1882	WW	Gough Ave.	6	Cast Iron	156	133	2.57 out of 5	\$442	69,173
Distribution Main	3373	P-1882	WW	Gough Ave.	6	Cast Iron	489	133	2.57 out of 5	\$442	215,921
Distribution Main	3375	P-1045	WW	Gough Ave.	6	Cast Iron	200	133	2.57 out of 5	\$442	88,491
Distribution Main	3377	P-1036	WW	Gough Ave.	6	Cast Iron	26	133	2.57 out of 5	\$442	11,649
Distribution Main	3670	P-1075	WW	Gough Ave.	6	Cast Iron	260	83	2.43 out of 5	\$442	115,071
Distribution Main	3788	P-784	WW	Gough Ave.	6	Cast Iron	381	82	2.43 out of 5	\$442	168,263
Transmission Main	3789	P-8044	WW	Gough Ave.	16	Asbestos Cement	17	75	1.29 out of 5	\$442	7,493
Transmission Main	3790	P-8044	WW	Gough Ave.	16	Asbestos Cement	656	75	2 out of 5	\$442	289,739
Transmission Main	8047		WW	Gough Ave.	16	Asbestos Cement	3	75	1.29 out of 5	\$442	1,527
Distribution Main	8809	P-1045	WW	Gough Ave.	6	Cast Iron	36	133	2.57 out of 5	\$442	16,074
Transmission Main	8992	P-8044	WW	Gough Ave.	16	Asbestos Cement	27	75	1.29 out of 5	\$442	12,064
Distribution Main	9538	P-1076	WW	Gough Ave.	6	Cast Iron	99	133	2.57 out of 5	\$442	43,978
Distribution Main	9539	P-1076	WW	Gough Ave.	6	Cast Iron	46	133	2.57 out of 5	\$442	20,421
Distribution Main	9540	P-1074	WW	Gough Ave.	6	Cast Iron	111	83	2.43 out of 5	\$442	48,852
Distribution Main	9898	P-1074	WW	Gough Ave.	6	Cast Iron	41	82	2.43 out of 5	\$442	18,228
Transmission Main	10880	P-771	WW	Gough Ave.	16	Asbestos Cement	122	75	1.29 out of 5	\$442	53,928
Distribution Main	11054	P-1077	WW	Gough Ave.	6	Cast Iron	14	133	2.57 out of 5	\$442	6,162
Distribution Main	11059	P-1879	WW	Gough Ave.	6	Cast Iron	19	133	2.57 out of 5	\$442	8,323
Transmission Main	11105	P-770	WW	Gough Ave.	16	Asbestos Cement	32	75	1.29 out of 5	\$442	14,244
Distribution Main	11230	P-784	WW	Gough Ave.	6	Cast Iron	11	82	2.43 out of 5	\$442	4,670
Transmission Main	11231	P-771	WW	Gough Ave.	16	Asbestos Cement	117	75	1.29 out of 5	\$442	51,765
Distribution Main	11622	P-1069	WW	Gough Ave.	6	Cast Iron	29	82	2.43 out of 5	\$442	13,016
Distribution Main	11759	P-1882	WW	Gough Ave.	6	Cast Iron	289	133	2.57 out of 5	\$442	127,615
Distribution Main	1439	P-900	WW	Grace Ct.	6	Asbestos Cement	163	51	1.85 out of 5	\$442	72,263
Distribution Main	1512	P-911	WW	Grandview Dr.	6	Asbestos Cement	17	61	2 out of 5	\$442	7,516
Distribution Main	1513	P-911	WW	Grandview Dr.	6	Asbestos Cement	603	61	2 out of 5	\$442	266,333
Distribution Main	3733	P-911	WW	Grandview Dr.	6	Asbestos Cement	4	61	2 out of 5	\$442	1,946
Distribution Main	3203	P-731	WW	Granite St.	4	Cast Iron	255	133	3.29 out of 5	\$442	112,682
Distribution Main	3204	P-731	WW	Granite St.	4	Cast Iron	4	133	3.29 out of 5	\$442	1,572
Distribution Main	3240	P-731	WW	Granite St.	4	Cast Iron	307	133	3.29 out of 5	\$442	135,582
Distribution Main	4441	P-1505	WW	Grant St	2	Copper	205	33	2.14 out of 5	\$442	90,779
Distribution Main	10343	P-1505	WW	Grant St	1.5	Copper	126	33	2.14 out of 5	\$442	55,524
Distribution Main	10344	P-1505	WW	Grant St	1.5	Copper	18	33	2.14 out of 5	\$442	7,843
Distribution Main	4440	P-15303	WW	Grant St.	2	Copper	161	33	2.14 out of 5	\$442	71,050
Distribution Main	11144	P-15303	WW	Grant St.	2	Copper	3	33	2.14 out of 5	\$442	1,522
Distribution Main	8705		WW	Great Lane	2	HDPE	25	12	1.71 out of 5	N/A	\$0
Transmission Main	472	P-1453	WW	Green Bush Rd.	12	Ductile Iron	354	22	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	473	P-1438	WW	Green Bush Rd.	16	Ductile Iron	300	22	0.14 out of 5	N/A	\$0
Transmission Main	474	P-1438	WW	Green Bush Rd.	16	Ductile Iron	1,229	22	0.14 out of 5	N/A	\$0
Transmission Main	980	P-48	WW	Green Bush Rd.	16	Asbestos Cement	682	46	1.14 out of 5	\$442	301,471
Transmission Main	981	P-48	WW	Green Bush Rd.	16	Asbestos Cement	219	46	1.14 out of 5	\$442	96,897
Transmission Main	982	P-1448	WW	Green Bush Rd.	16	Asbestos Cement	196	46	1.14 out of 5	\$442	86,627
Transmission Main	989	P-10044	WW	Green Bush Rd.	16	Asbestos Cement	293	46	1.14 out of 5	\$442	129,552
Transmission Main	990	P-10044	WW	Green Bush Rd.	16	Asbestos Cement	486	46	1.14 out of 5	\$442	214,932
Transmission Main	991	P-50	WW	Green Bush Rd.	16	Asbestos Cement	173	46	1.14 out of 5	\$442	76,503
Transmission Main	992	P-50	WW	Green Bush Rd.	16	Asbestos Cement	442	46	1.14 out of 5	\$442	195,297
Transmission Main	1078	P-1449	WW	Green Bush Rd.	16	Asbestos Cement	572	46	1.14 out of 5	\$442	252,675
Distribution Main	1080		WW	Green Bush Rd.	10	Ductile Iron	28	22	0.14 out of 5	N/A	\$0
Transmission Main	1353	P-1452	WW	Green Bush Rd.	12	Ductile Iron	551	22	0.14 out of 5	N/A	\$0
Transmission Main	2357	P-1455	WW	Green Bush Rd.	12	Ductile Iron	803	22	0.14 out of 5	N/A	\$0
Transmission Main	2358	P-1455	WW	Green Bush Rd.	12	Ductile Iron	640	22	0.14 out of 5	N/A	\$0
Transmission Main	10162	P-1448	WW	Green Bush Rd.	16	Asbestos Cement	137	46	1.14 out of 5	\$442	60,730
Transmission Main	10165	P-50	WW	Green Bush Rd.	16	Asbestos Cement	143	46	1.14 out of 5	\$442	63,260
Transmission Main	10167	P-1396	WW	Green Bush Rd.	12	Asbestos Cement	181	46	1.14 out of 5	\$442	79,854
Transmission Main	11062	P-1438	WW	Green Bush Rd.	16	Ductile Iron	2	22	0.14 out of 5	N/A	\$0
Transmission Main	11096	P-48	WW	Green Bush Rd.	16	Asbestos Cement	268	46	1.14 out of 5	\$442	118,633
Transmission Main	11100	P-1449	WW	Green Bush Rd.	16	Asbestos Cement	9	46	1.14 out of 5	\$442	3,792
Transmission Main	11101	P-1452	WW	Green Bush Rd.	12	Ductile Iron	12	22	0.14 out of 5	N/A	\$0
Transmission Main	11170	P-1396	WW	Green Bush Rd.	12	Asbestos Cement	170	46	1.14 out of 5	\$442	75,197
Transmission Main	11171	P-1455	WW	Green Bush Rd.	12	Ductile Iron	209	22	0.14 out of 5	N/A	\$0
Transmission Main	12050	P-48	WW	Green Bush Rd.	16	Asbestos Cement	122	46	1.14 out of 5	\$442	53,922
Distribution Main	5374		WW	Green Ct.	8	Unknown	6	16	0 out of 5	N/A	\$0
Distribution Main	148	P-320	WW	Greenbrier Rd.	8	Asbestos Cement	507	43	1.14 out of 5	\$442	223,984
Distribution Main	149	P-321	WW	Greenbrier Rd.	8	Asbestos Cement	402	43	1.14 out of 5	\$442	177,837
Distribution Main	926		WW	Greenbush Rd.	8	Ductile Iron	33	19	0 out of 5	N/A	\$0
Distribution Main	10163	P-1451	WW	Greenbush Road	10	PVC	3	31	0.43 out of 5	\$442	1,487
Distribution Main	203		WW	Greene St.	6	Unknown	7	UNK	0.71 out of 5	\$442	3,229
Distribution Main	207	P-783	WW	Greene St.	8	Asbestos Cement	512	86	1.43 out of 5	\$442	226,155
Distribution Main	383	P-1533	WW	Greene St.	8	Ductile Iron	337	UNK	0 out of 5	N/A	\$0
Distribution Main	1206	P-800	WW	Greene St.	4	Cast Iron	307	86	3.14 out of 5	\$442	135,559
Distribution Main	1207	P-800	WW	Greene St.	4	Cast Iron	279	86	3.14 out of 5	\$442	123,164
Distribution Main	1208	P-800	WW	Greene St.	4	Cast Iron	84	86	3.14 out of 5	\$442	37,101
Distribution Main	2176	P-809	WW	Greene St.	6	Asbestos Cement	107	67	2 out of 5	\$442	47,414
Distribution Main	2449	P-1398	WW	Greene St.	8	Asbestos Cement	301	86	1.43 out of 5	\$442	133,180
Distribution Main	3465	P-797	WW	Greene St.	8	Asbestos Cement	9	86	1.43 out of 5	\$442	3,989
Distribution Main	3468	P-796	WW	Greene St.	8	Asbestos Cement	224	86	1.43 out of 5	\$442	98,871
Distribution Main	3718	P-809	WW	Greene St.	6	Asbestos Cement	302	67	2 out of 5	\$442	133,586
Distribution Main	3746	P-797	WW	Greene St.	4	Cast Iron	231	132	3.29 out of 5	\$442	102,110
Distribution Main	3747	P-797	WW	Greene St.	4	Cast Iron	20	132	3.29 out of 5	\$442	8,664
Distribution Main	3748	P-797	WW	Greene St.	8	Asbestos Cement	14	86	1.43 out of 5	\$442	6,118
Distribution Main	3749	P-1397	WW	Greene St.	4	Cast Iron	25	86	3.14 out of 5	\$442	10,927

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3750	P-1397	WW	Greene St.	4	Cast Iron	615	86	3.14 out of 5	\$442	271,734
Distribution Main	3754	P-796	WW	Greene St.	4	Cast Iron	19	86	3.14 out of 5	\$442	8,310
Distribution Main	3802	P-783	WW	Greene St.	8	Asbestos Cement	23	86	1.43 out of 5	\$442	10,252
Distribution Main	2937	P-8049	WW	Greenwood Ave.	6	Asbestos Cement	315	56	1.85 out of 5	\$442	139,276
Distribution Main	2938	P-8049	WW	Greenwood Ave.	6	Asbestos Cement	509	56	1.85 out of 5	\$442	225,115
Distribution Main	3760	P-1976	WW	Grove Street	2	Copper	249	81	2.57 out of 5	\$442	110,050
Distribution Main	3617	P-760	WW	Guertin St.	2	Galvanized Iron	163	69	3.28 out of 5	\$442	72,044
Distribution Main	3673	P-760	WW	Guertin St.	2	Galvanized Iron	187	69	3.28 out of 5	\$442	82,734
Distribution Main	3784	P-7610	WW	Guertin St.	2	Galvanized Iron	17	69	3.28 out of 5	\$442	7,310
Distribution Main	3798	P-1068	WW	Hall St.	6	PVC	240	32	1.14 out of 5	\$442	105,862
Distribution Main	4668	P-428	WW	Hamilton St.	6	Asbestos Cement	156	66	2 out of 5	\$442	68,927
Distribution Main	4669	P-444	WW	Hamilton St.	6	Asbestos Cement	475	66	2 out of 5	\$442	209,853
Distribution Main	5142	P-426	WW	Hamilton St.	6	Asbestos Cement	307	66	2 out of 5	\$442	135,782
Distribution Main	2137	P-574	WW	Harbour Ave.	2	Copper	228	73	2.43 out of 5	\$442	100,685
Distribution Main	2893	P-551	WW	Harbour Ave.	6	Cast Iron	310	73	2.28 out of 5	\$442	137,097
Distribution Main	2894	P-551	WW	Harbour Ave.	6	Cast Iron	149	73	2.28 out of 5	\$442	65,832
Distribution Main	3098	P-568	WW	Harbour Ave.	6	Asbestos Cement	260	73	2 out of 5	\$442	114,775
Distribution Main	3099	P-568	WW	Harbour Ave.	6	Asbestos Cement	9	73	2 out of 5	\$442	3,852
Distribution Main	3974	P-576	WW	Harbour Ave.	2	Copper	16	73	2.43 out of 5	\$442	7,241
Distribution Main	4103	P-568	WW	Harbour Ave.	8	Asbestos Cement	16	73	1.29 out of 5	\$442	7,247
Distribution Main	4104	P-568	WW	Harbour Ave.	6	Asbestos Cement	14	73	2 out of 5	\$442	6,290
Distribution Main	4105	P-564	WW	Harbour Ave.	6	Asbestos Cement	234	73	2 out of 5	\$442	103,297
Distribution Main	4303	P-576	WW	Harbour Ave.	2	Copper	120	73	2.43 out of 5	\$442	52,889
Distribution Main	8013	P-1603	WW	Harbour Ave.	8	Ductile Iron	22	14	0 out of 5	N/A	\$0
Distribution Main	8014	P-1605	WW	Harbour Ave.	8	Ductile Iron	234	14	0 out of 5	N/A	\$0
Distribution Main	8015	P-1606	WW	Harbour Ave.	8	Ductile Iron	278	14	0 out of 5	N/A	\$0
Distribution Main	9352	P-1606	WW	Harbour Ave.	6	Ductile Iron	14	14	0.71 out of 5	N/A	\$0
Distribution Main	11244	P-568	WW	Harbour Ave.	8	Asbestos Cement	4	73	1.29 out of 5	\$442	1,984
Distribution Main	11417	P-1603	WW	Harbour Ave.	8	Ductile Iron	7	14	0 out of 5	N/A	\$0
Transmission Main	8432	P-1676	WW	Harding St	12	Ductile Iron	439	10	0 out of 5	N/A	\$0
Transmission Main	8437	P-896	WW	Harding St	16	Ductile Iron	180	10	0 out of 5	N/A	\$0
Transmission Main	8438	P-896	WW	Harding St	16	Ductile Iron	805	10	0 out of 5	N/A	\$0
Transmission Main	8439	P-1699	WW	Harding St	20	Ductile Iron	20	10	0 out of 5	N/A	\$0
Transmission Main	8502	P-1790	WW	Harding St	12	Ductile Iron	188	10	0 out of 5	N/A	\$0
Transmission Main	8504	P-891	WW	Harding St	12	Ductile Iron	212	10	0 out of 5	N/A	\$0
Transmission Main	8506	P-895	WW	Harding St	12	Ductile Iron	169	10	0 out of 5	N/A	\$0
Transmission Main	8507	P-895	WW	Harding St	12	Ductile Iron	42	10	0 out of 5	N/A	\$0
Transmission Main	8508	P-1676	WW	Harding St	12	Ductile Iron	24	10	0 out of 5	N/A	\$0
Transmission Main	8509	P-1676	WW	Harding St	16	Ductile Iron	39	10	0 out of 5	N/A	\$0
Transmission Main	8510	P-1699	WW	Harding St	16	Ductile Iron	15	10	0 out of 5	N/A	\$0
Distribution Main	2884	P-662	WW	Hare St.	1	Galvanized Iron	398	134	3.57 out of 5	\$442	175,856
Distribution Main	2885	P-662	WW	Hare St.	1	Galvanized Iron	23	134	3.57 out of 5	\$442	10,129
Distribution Main	3530	P-662	WW	Hare St.	1	Galvanized Iron	27	134	3.57 out of 5	\$442	12,012
Distribution Main	9788	P-631	WW	Harley St	8	Ductile Iron	308	8	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9789	P-631	WW	Harley St	8	Ductile Iron	36	8	0 out of 5	N/A	\$0
Distribution Main	9796	P-638	WW	Harley St	8	Ductile Iron	219	8	0 out of 5	N/A	\$0
Distribution Main	9797	P-621	WW	Harley St	8	Ductile Iron	547	8	0 out of 5	N/A	\$0
Distribution Main	9894	P-629	WW	Harley St	8	Ductile Iron	22	8	0 out of 5	N/A	\$0
Distribution Main	10409	P-629	WW	Harley St	8	Ductile Iron	96	8	0 out of 5	N/A	\$0
Distribution Main	10883	P-636	WW	Harley St	8	Ductile Iron	413	8	0 out of 5	N/A	\$0
Distribution Main	10884	P-633	WW	Harley St	8	Ductile Iron	281	8	0 out of 5	N/A	\$0
Distribution Main	11608	P-638	WW	Harley St	8	Ductile Iron	24	8	0 out of 5	N/A	\$0
Distribution Main	12109	P-638	WW	Harley St	8	Ductile Iron	295	8	0 out of 5	N/A	\$0
Distribution Main	12110	P-1965	WW	Harley St	8	Ductile Iron	166	8	0 out of 5	N/A	\$0
Distribution Main	9363	P-621	WW	Harley St.	8	Ductile Iron	8	14	0 out of 5	N/A	\$0
Distribution Main	9364	P-621	WW	Harley St.	8	Ductile Iron	5	14	0 out of 5	N/A	\$0
Distribution Main	1795	P-918	WW	Harmony St.	6	Cast Iron	361	129	2.57 out of 5	\$442	159,386
Distribution Main	1796	P-918	WW	Harmony St.	6	Cast Iron	32	129	2.57 out of 5	\$442	13,957
Distribution Main	3734	P-917	WW	Harmony St.	4	Cast Iron	526	129	3.29 out of 5	\$442	232,374
Distribution Main	201	P-799	WW	Harris Ave.	8	Asbestos Cement	541	73	1.29 out of 5	\$442	239,033
Distribution Main	202	P-799	WW	Harris Ave.	8	Asbestos Cement	285	73	1.29 out of 5	\$442	126,113
Distribution Main	1604	P-792	WW	Harris Ave.	6	Cast Iron	422	134	2.57 out of 5	\$442	186,713
Distribution Main	1605	P-792	WW	Harris Ave.	6	Cast Iron	436	134	2.57 out of 5	\$442	192,921
Distribution Main	3383	P-794	WW	Harris Ave.	6	Cast Iron	440	134	2.57 out of 5	\$442	194,274
Distribution Main	8740	P-792	WW	Harris Ave.	6	Cast Iron	153	134	2.57 out of 5	\$442	67,684
Distribution Main	8741	P-10090	WW	Harris Ave.	6	Cast Iron	71	134	2.57 out of 5	\$442	31,393
Distribution Main	8742	P-10090	WW	Harris Ave.	6	Cast Iron	239	134	2.57 out of 5	\$442	105,512
Distribution Main	8743	P-799	WW	Harris Ave.	8	Asbestos Cement	36	73	1.29 out of 5	\$442	15,706
Distribution Main	8744	P-7074	WW	Harris Ave.	8	Asbestos Cement	309	69	1.29 out of 5	\$442	136,426
Distribution Main	8745	P-7074	WW	Harris Ave.	8	Asbestos Cement	511	69	1.29 out of 5	\$442	225,765
Distribution Main	12012	P-792	WW	Harris Ave.	6	Cast Iron	73	134	2.57 out of 5	\$442	32,374
Distribution Main	8445	P-1628	WW	Harris St	6	Ductile Iron	22	10	0.71 out of 5	N/A	\$0
Transmission Main	8446	P-8752	WW	Harris St	12	Ductile Iron	27	10	0 out of 5	N/A	\$0
Transmission Main	8447	P-1912	WW	Harris St	12	Ductile Iron	8	10	0 out of 5	N/A	\$0
Distribution Main	240	P-8129	WW	Harris St.	6	Cast Iron	31	119	2.57 out of 5	\$442	13,830
Distribution Main	241	P-8129	WW	Harris St.	6	Cast Iron	162	119	2.57 out of 5	\$442	71,702
Distribution Main	1098	P-8124	WW	Harris St.	6	Cast Iron	219	119	2.57 out of 5	\$442	96,992
Distribution Main	3523	P-8133	WW	Harris St.	4	Cast Iron	13	119	3.29 out of 5	\$442	5,724
Distribution Main	3602	P-8133	WW	Harris St.	6	Cast Iron	14	119	2.57 out of 5	\$442	6,116
Distribution Main	3603	P-8133	WW	Harris St.	6	Cast Iron	513	119	2.57 out of 5	\$442	226,923
Distribution Main	11103	P-8124	WW	Harris St.	6	Cast Iron	3	119	2.57 out of 5	\$442	1,516
Distribution Main	9104		WW	Hartman Court	2	Unknown	24	UNK	1.42 out of 5	\$442	10,699
Distribution Main	4133	P-96	WW	Hatheway Dr.	8	Asbestos Cement	49	41	1.14 out of 5	\$442	21,645
Distribution Main	4135	P-96	WW	Hatheway Dr.	8	Asbestos Cement	93	41	1.14 out of 5	\$442	40,978
Distribution Main	4136	P-96	WW	Hatheway Dr.	8	Asbestos Cement	563	41	1.14 out of 5	\$442	249,046
Distribution Main	5159	P-96	WW	Hatheway Dr.	8	Asbestos Cement	8	41	1.14 out of 5	\$442	3,717
Distribution Main	5162	P-10016	WW	Hatheway Dr.	8	Asbestos Cement	219	41	1.14 out of 5	\$442	96,582
Distribution Main	11773	P-96	WW	Hatheway Dr.	8	Asbestos Cement	368	41	1.14 out of 5	\$442	162,623

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10174		WW	Havens Ct	1	Copper	273	72	2.43 out of 5	\$442	120,883
Distribution Main	8616	P-1870	WW	Hay St	8	Ductile Iron	70	12	0 out of 5	N/A	\$0
Distribution Main	9424		WW	Hay St	6	Ductile Iron	1	11	0.71 out of 5	N/A	\$0
Distribution Main	321	P-1345	WW	Hay St.	6	PVC	233	46	1.28 out of 5	\$442	103,169
Distribution Main	1876		WW	Hay St.	6	Ductile Iron	52	UNK	0.71 out of 5	\$442	22,784
Distribution Main	3341	P-992	WW	Hay St.	6	PVC	273	46	1.28 out of 5	\$442	120,811
Distribution Main	3342	P-992	WW	Hay St.	6	PVC	243	46	1.28 out of 5	\$442	107,281
Distribution Main	8049	P-1933	WW	Hebert St	1.5	HDPE	4	91	2.29 out of 5	\$442	1,795
Distribution Main	2489	P-1951	WW	Hebert St.	2	Galvanized Iron	33	91	3.43 out of 5	\$442	14,458
Distribution Main	3616	P-1933	WW	Hebert St.	2	Galvanized Iron	823	91	3.43 out of 5	\$442	363,583
Distribution Main	3792	P-773	WW	Hebert St.	6	Asbestos Cement	281	53	1.85 out of 5	\$442	124,354
Distribution Main	10893	P-716	WW	Hebert St.	2	Galvanized Iron	7	91	3.43 out of 5	\$442	2,875
Distribution Main	11232	P-773	WW	Hebert St.	6	Asbestos Cement	1	53	1.85 out of 5	\$442	637
Distribution Main	4652	P-149	WW	Hemlock Ln.	8	Asbestos Cement	414	50	1.14 out of 5	\$442	183,159
Distribution Main	922	P-1124	WW	Hepburn St.	2	PVC	523	30	1.85 out of 5	\$442	231,105
Distribution Main	923	P-1113	WW	Hepburn St.	6	Cast Iron	288	134	2.57 out of 5	\$442	127,153
Distribution Main	924	P-1113	WW	Hepburn St.	6	Cast Iron	211	134	2.57 out of 5	\$442	93,397
Distribution Main	1908	P-1123	WW	Hepburn St.	4	Cast Iron	342	134	3.29 out of 5	\$442	151,167
Distribution Main	12008	P-1113	WW	Hepburn St.	6	Cast Iron	113	134	2.57 out of 5	\$442	49,738
Distribution Main	4683	P-534	WW	High View Dr.	8	Asbestos Cement	232	52	1.14 out of 5	\$442	102,463
Distribution Main	5133	P-536	WW	High View Dr.	8	Asbestos Cement	38	52	1.14 out of 5	\$442	16,743
Distribution Main	5134	P-536	WW	High View Dr.	8	Asbestos Cement	885	52	1.14 out of 5	\$442	391,276
Distribution Main	8534	P-1843	WW	Highland St	8	Ductile Iron	19	13	0 out of 5	N/A	\$0
Distribution Main	8564	P-1843	WW	Highland St	6	Ductile Iron	3	13	0.71 out of 5	N/A	\$0
Distribution Main	2942	P-1915	WW	Highland St.	6	Cast Iron	248	134	2.57 out of 5	\$442	109,621
Distribution Main	2943	P-1915	WW	Highland St.	6	Cast Iron	136	134	2.57 out of 5	\$442	60,136
Distribution Main	2944	P-1253	WW	Highland St.	6	Cast Iron	132	134	2.57 out of 5	\$442	58,517
Distribution Main	3480	P-981	WW	Highland St.	6	Cast Iron	300	134	2.57 out of 5	\$442	132,714
Distribution Main	3481	P-981	WW	Highland St.	6	Cast Iron	258	134	2.57 out of 5	\$442	114,053
Distribution Main	11193	P-1915	WW	Highland St.	6	Cast Iron	99	134	2.57 out of 5	\$442	43,725
Distribution Main	12006	P-981	WW	Highland St.	6	Cast Iron	12	134	2.57 out of 5	\$442	5,354
Distribution Main	2382	P-754	WW	Hillcrest Dr.	6	Cast Iron	225	70	2.28 out of 5	\$442	99,523
Distribution Main	2482	P-1954	WW	Hillcrest Dr.	1	Copper	20	UNK	1.99 out of 5	\$442	8,905
Distribution Main	2855		WW	Hillcrest Dr.	6	Cast Iron	7	70	2.28 out of 5	\$442	3,029
Distribution Main	3796	P-756	WW	Hillcrest Dr.	6	Cast Iron	210	70	2.28 out of 5	\$442	92,908
Transmission Main	8969	P-1212	WW	Hillside Ave	12	Ductile Iron	15	9	0 out of 5	N/A	\$0
Transmission Main	8970	P-1212	WW	Hillside Ave	12	Ductile Iron	16	9	0 out of 5	N/A	\$0
Distribution Main	9213	P-1212	WW	Hillside Ave	8	Ductile Iron	199	9	0 out of 5	N/A	\$0
Transmission Main	11532	P-1212	WW	Hillside Ave	12	Ductile Iron	4	9	0 out of 5	N/A	\$0
Distribution Main	10784	P-359	WW	Hilltop Av	8	Ductile Iron	528	0	0 out of 5	N/A	\$0
Distribution Main	10785	P-330	WW	Hilltop Av	8	Ductile Iron	770	0	0 out of 5	N/A	\$0
Distribution Main	11731	P-330	WW	Hilltop Av	8	Ductile Iron	9	0	0 out of 5	N/A	\$0
Distribution Main	1590	P-532	WW	Hollow Cir.	6	Asbestos Cement	5	51	1.85 out of 5	\$442	2,320
Distribution Main	5131	P-532	WW	Hollow Cir.	6	Asbestos Cement	124	51	1.85 out of 5	\$442	54,725

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	5132	P-532	WW	Hollow Cir.	6	Asbestos Cement	422	51	1.85 out of 5	\$442	186,614
Distribution Main	2848	P-733	WW	Home St.	6	Cast Iron	183	79	2.28 out of 5	\$442	81,011
Distribution Main	2849	P-733	WW	Home St.	6	Cast Iron	397	79	2.28 out of 5	\$442	175,499
Distribution Main	10003	P-733	WW	Home St.	6	Cast Iron	7	79	2.28 out of 5	\$442	3,003
Distribution Main	1552	P-894	WW	Hoover St.	6	Ductile Iron	489	18	0.71 out of 5	N/A	\$0
Distribution Main	9428	P-1300	WW	Hoover St.	6	Ductile Iron	389	18	0.71 out of 5	N/A	\$0
Distribution Main	8937	P-193	WW	Hopedale Dr	8	Ductile Iron	439	9	0 out of 5	N/A	\$0
Distribution Main	9406	P-1729	WW	Hopedale Dr	8	Ductile Iron	13	9	0 out of 5	N/A	\$0
Distribution Main	9407	P-169	WW	Hopedale Dr	8	Ductile Iron	8	9	0 out of 5	N/A	\$0
Distribution Main	9408	P-169	WW	Hopedale Dr	8	Ductile Iron	193	9	0 out of 5	N/A	\$0
Distribution Main	9409	P-193	WW	Hopedale Dr	8	Ductile Iron	4	9	0 out of 5	N/A	\$0
Distribution Main	3581	P-1730	WW	Hopedale Dr.	8	Ductile Iron	23	15	0 out of 5	N/A	\$0
Distribution Main	3872	P-152	WW	Hornbeam Ln.	8	Asbestos Cement	257	42	1.14 out of 5	\$442	113,801
Distribution Main	8433	P-1789	WW	Horta Dr	8	Ductile Iron	27	10	0 out of 5	N/A	\$0
Distribution Main	8503	P-1789	WW	Horta Dr	6	Ductile Iron	19	10	0.71 out of 5	N/A	\$0
Distribution Main	1006	P-892	WW	Horta Dr.	6	Asbestos Cement	547	55	1.85 out of 5	\$442	241,676
Distribution Main	1410	P-893	WW	Horta Dr.	6	Asbestos Cement	83	55	1.85 out of 5	\$442	36,733
Distribution Main	1411	P-893	WW	Horta Dr.	6	Asbestos Cement	114	55	1.85 out of 5	\$442	50,313
Distribution Main	8975	P-1927	WW	Hoxie Ct	8	Ductile Iron	7	9	0 out of 5	N/A	\$0
Distribution Main	8976	P-1927	WW	Hoxie Ct	8	Ductile Iron	38	9	0 out of 5	N/A	\$0
Distribution Main	1994	P-1208	WW	Hoxie Ct.	8	Ductile Iron	355	17	0 out of 5	N/A	\$0
Distribution Main	4660	P-160	WW	Huckleberry Dr.	8	Asbestos Cement	423	42	1.14 out of 5	\$442	187,166
Distribution Main	9829	P-830	WW	Industrial Ln	8	Ductile Iron	334	7	0 out of 5	N/A	\$0
Distribution Main	9830	P-830	WW	Industrial Ln	8	Ductile Iron	391	7	0 out of 5	N/A	\$0
Distribution Main	10414		WW	Industrial Ln	8	Ductile Iron	6	7	0 out of 5	N/A	\$0
Distribution Main	10810		WW	Industrial Ln	6	Ductile Iron	1	7	0.71 out of 5	N/A	\$0
Distribution Main	12020	P-830	WW	Industrial Ln	8	Ductile Iron	520	7	0 out of 5	N/A	\$0
Distribution Main	12021	P-830	WW	Industrial Ln	8	Ductile Iron	23	7	0 out of 5	N/A	\$0
Distribution Main	12111	P-830	WW	Industrial Ln	8	Ductile Iron	131	7	0 out of 5	N/A	\$0
Distribution Main	12112	P-830	WW	Industrial Ln	8	Ductile Iron	351	7	0 out of 5	N/A	\$0
Distribution Main	5643	P-234	WW	Intervale Rd.	6	Asbestos Cement	543	55	1.85 out of 5	\$442	240,068
Distribution Main	5644	P-234	WW	Intervale Rd.	6	Asbestos Cement	16	55	1.85 out of 5	\$442	7,121
Distribution Main	4009	P-325	WW	Iron Dr.	8	Asbestos Cement	37	47	1.14 out of 5	\$442	16,329
Distribution Main	4010	P-325	WW	Iron Dr.	8	Asbestos Cement	319	47	1.14 out of 5	\$442	141,064
Distribution Main	5191	P-322	WW	Iron Dr.	8	Asbestos Cement	211	47	1.14 out of 5	\$442	93,045
Distribution Main	2147	P-295	WW	Ivy St.	6	Asbestos Cement	171	71	2 out of 5	\$442	75,519
Distribution Main	2148	P-295	WW	Ivy St.	6	Asbestos Cement	405	71	2 out of 5	\$442	179,171
Distribution Main	11155	P-295	WW	Ivy St.	6	Asbestos Cement	8	71	2 out of 5	\$442	3,572
Transmission Main	46	P-1550	WW	J.P. Murphy Hwy	16	Asbestos Cement	8	39	1 out of 5	\$442	3,477
Transmission Main	47	P-1315	WW	J.P. Murphy Hwy	16	Asbestos Cement	5	39	1 out of 5	\$442	2,272
Transmission Main	48	P-1315	WW	J.P. Murphy Hwy	16	Asbestos Cement	174	39	1 out of 5	\$442	76,794
Transmission Main	9078	P-1550	WW	J.P. Murphy Hwy	16	Asbestos Cement	3	39	1 out of 5	\$442	1,510
Transmission Main	9079	P-1550	WW	J.P. Murphy Hwy	16	Asbestos Cement	7	39	1 out of 5	\$442	2,997
Transmission Main	9842	P-1550	WW	J.P. Murphy Hwy	16	Asbestos Cement	9	39	1 out of 5	\$442	3,833

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11011	P-1550	WW	J.P. Murphy Hwy	16	Asbestos Cement	6	39	1 out of 5	\$442	2,837
Transmission Main	11012	P-1550	WW	J.P. Murphy Hwy	16	Asbestos Cement	3	39	1 out of 5	\$442	1,147
Distribution Main	655	P-466	WW	Jacques St.	6	Asbestos Cement	444	64	2 out of 5	\$442	196,414
Distribution Main	9055		WW	James P Murphy Hwy	4	Ductile Iron	2	22	1.57 out of 5	N/A	\$0
Distribution Main	42		WW	James P Murphy Ind Rd	10	Ductile Iron	5	UNK	0 out of 5	N/A	\$0
Distribution Main	43		WW	James P Murphy Ind Rd	10	Ductile Iron	5	UNK	0 out of 5	N/A	\$0
Distribution Main	44		WW	James P Murphy Ind Rd	10	Ductile Iron	26	UNK	0 out of 5	N/A	\$0
Distribution Main	45		WW	James P Murphy Ind Rd	10	Ductile Iron	7	UNK	0 out of 5	N/A	\$0
Distribution Main	49		WW	James P Murphy Ind Rd	10	Ductile Iron	17	UNK	0 out of 5	N/A	\$0
Distribution Main	50		WW	James P Murphy Ind Rd	10	Ductile Iron	17	UNK	0 out of 5	N/A	\$0
Transmission Main	356		WW	James P Murphy Ind Rd	16	Ductile Iron	195	15	0 out of 5	N/A	\$0
Distribution Main	1322		WW	James P Murphy Ind Rd	6	Ductile Iron	2	22	0.85 out of 5	N/A	\$0
Transmission Main	9843	P-65	WW	James P Murphy Ind Rd	16	Ductile Iron	630	7	0 out of 5	N/A	\$0
Transmission Main	9844	P-65	WW	James P Murphy Ind Rd	16	Ductile Iron	59	7	0 out of 5	N/A	\$0
Transmission Main	9845	P-65	WW	James P Murphy Ind Rd	16	Ductile Iron	77	7	0 out of 5	N/A	\$0
Transmission Main	9846	P-65	WW	James P Murphy Ind Rd	16	Ductile Iron	699	7	0 out of 5	N/A	\$0
Transmission Main	9847	P-66	WW	James P Murphy Ind Rd	16	Ductile Iron	107	7	0 out of 5	N/A	\$0
Transmission Main	9848	P-66	WW	James P Murphy Ind Rd	16	Ductile Iron	787	7	0 out of 5	N/A	\$0
Transmission Main	9849	P-1573	WW	James P Murphy Ind Rd	16	Ductile Iron	271	7	0 out of 5	N/A	\$0
Transmission Main	9850	P-1573	WW	James P Murphy Ind Rd	16	Ductile Iron	611	7	0 out of 5	N/A	\$0
Transmission Main	9851	P-1573	WW	James P Murphy Ind Rd	16	Ductile Iron	105	7	0 out of 5	N/A	\$0
Transmission Main	9852	P-1573	WW	James P Murphy Ind Rd	16	Ductile Iron	792	7	0 out of 5	N/A	\$0
Transmission Main	9853	P-67	WW	James P Murphy Ind Rd	16	Ductile Iron	407	7	0 out of 5	N/A	\$0
Transmission Main	9854	P-67	WW	James P Murphy Ind Rd	16	Ductile Iron	150	7	0 out of 5	N/A	\$0
Transmission Main	9855	P-1549	WW	James P Murphy Ind Rd	16	Ductile Iron	234	7	0 out of 5	N/A	\$0
Transmission Main	9856	P-1549	WW	James P Murphy Ind Rd	16	Ductile Iron	710	7	0 out of 5	N/A	\$0
Transmission Main	9857	P-10007	WW	James P Murphy Ind Rd	12	Ductile Iron	25	7	0 out of 5	N/A	\$0
Transmission Main	9858	P-72	WW	James P Murphy Ind Rd	12	Ductile Iron	45	7	0 out of 5	N/A	\$0
Transmission Main	9859	P-10009	WW	James P Murphy Ind Rd	12	Ductile Iron	33	7	0 out of 5	N/A	\$0
Transmission Main	10956	P-66	WW	James P Murphy Ind Rd	16	Ductile Iron	326	7	0 out of 5	N/A	\$0
Transmission Main	11617	P-65	WW	James P Murphy Ind Rd	16	Ductile Iron	41	7	0 out of 5	N/A	\$0
Transmission Main	11987	P-1573	WW	James P Murphy Ind Rd	16	Ductile Iron	366	7	0 out of 5	N/A	\$0
Transmission Main	11988	P-66	WW	James P Murphy Ind Rd	16	Ductile Iron	166	7	0 out of 5	N/A	\$0
Transmission Main	11989	P-65	WW	James P Murphy Ind Rd	16	Ductile Iron	425	7	0 out of 5	N/A	\$0
Transmission Main	11990	P-65	WW	James P Murphy Ind Rd	16	Ductile Iron	516	7	0 out of 5	N/A	\$0
Transmission Main	12114	P-67	WW	James P Murphy Ind Rd	16	Ductile Iron	83	7	0 out of 5	N/A	\$0
Transmission Main	12115	P-67	WW	James P Murphy Ind Rd	16	Ductile Iron	185	7	0 out of 5	N/A	\$0
Transmission Main	12116	P-67	WW	James P Murphy Ind Rd	16	Ductile Iron	108	7	0 out of 5	N/A	\$0
Distribution Main	8963	P-198	WW	Janet Dr	8	Ductile Iron	17	9	0 out of 5	N/A	\$0
Distribution Main	8964	P-198	WW	Janet Dr	6	Ductile Iron	11	9	0.71 out of 5	N/A	\$0
Distribution Main	4169	P-198	WW	Janet Dr.	6	Asbestos Cement	479	69	2 out of 5	\$442	211,545
Distribution Main	4944	P-198	WW	Janet Dr.	6	Asbestos Cement	26	69	2 out of 5	\$442	11,450
Distribution Main	2546	P-34	WW	Jaycee Dr.	8	Asbestos Cement	582	57	1.14 out of 5	\$442	257,098
Distribution Main	4968	P-1390	WW	Jaycee Dr.	8	Asbestos Cement	60	57	1.14 out of 5	\$442	26,575

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4969	P-1390	WW	Jaycee Dr.	8	Asbestos Cement	303	57	1.14 out of 5	\$442	134,099
Distribution Main	10166	P-1391	WW	Jaycee Dr.	8	Asbestos Cement	8	57	1.14 out of 5	\$442	3,559
Distribution Main	11172	P-1390	WW	Jaycee Dr.	8	Asbestos Cement	6	57	1.14 out of 5	\$442	2,530
Distribution Main	2160	P-581	WW	Jefferson St.	6	Asbestos Cement	151	70	2 out of 5	\$442	66,938
Distribution Main	9368	P-581	WW	Jefferson St.	8	Ductile Iron	31	14	0 out of 5	N/A	\$0
Distribution Main	9369	P-581	WW	Jefferson St.	6	Ductile Iron	5	14	0.71 out of 5	N/A	\$0
Distribution Main	2260	P-460	WW	Joaquin Ct.	8	Asbestos Cement	531	40	1 out of 5	\$442	234,767
Distribution Main	2261	P-460	WW	Joaquin Ct.	8	Asbestos Cement	61	40	1 out of 5	\$442	26,928
Distribution Main	4602	P-459	WW	Joaquin Ct.	8	Asbestos Cement	122	40	1 out of 5	\$442	53,941
Distribution Main	3243	P-750	WW	Jodoin St.	6	Cast Iron	549	74	2.28 out of 5	\$442	242,539
Distribution Main	3255	P-750	WW	Jodoin St.	6	Cast Iron	15	74	2.28 out of 5	\$442	6,534
Distribution Main	1775	P-1067	WW	John St.	1	Copper	122	74	2.43 out of 5	\$442	53,711
Distribution Main	2854	P-1067	WW	John St.	1	Copper	34	74	2.43 out of 5	\$442	14,982
Distribution Main	3202	P-1064	WW	John St.	6	Cast Iron	213	74	2.28 out of 5	\$442	94,167
Distribution Main	3263	P-1067	WW	John St.	1	Copper	93	74	2.43 out of 5	\$442	41,291
Distribution Main	3612	P-1065	WW	John St.	6	Cast Iron	98	74	2.28 out of 5	\$442	43,113
Distribution Main	3613	P-1065	WW	John St.	6	Cast Iron	63	74	2.28 out of 5	\$442	27,781
Distribution Main	645	P-470	WW	Judy Ter.	6	Asbestos Cement	190	54	1.85 out of 5	\$442	84,048
Distribution Main	659	P-471	WW	Judy Ter.	6	Asbestos Cement	372	54	1.85 out of 5	\$442	164,405
Distribution Main	5154	P-469	WW	Judy Ter.	6	Asbestos Cement	6	54	1.85 out of 5	\$442	2,833
Distribution Main	5155	P-469	WW	Judy Ter.	6	Asbestos Cement	260	54	1.85 out of 5	\$442	114,833
Distribution Main	10173	P-990	WW	Junior St	6	Ductile Iron	3	11	0.71 out of 5	N/A	\$0
Distribution Main	426	P-991	WW	Junior St.	6	Cast Iron	192	97	2.43 out of 5	\$442	85,036
Distribution Main	427	P-989	WW	Junior St.	6	Cast Iron	82	97	2.43 out of 5	\$442	36,025
Distribution Main	428	P-989	WW	Junior St.	6	Cast Iron	297	97	2.43 out of 5	\$442	131,067
Distribution Main	3361	P-990	WW	Junior St.	6	Cast Iron	200	97	2.43 out of 5	\$442	88,228
Distribution Main	3362	P-990	WW	Junior St.	6	Cast Iron	167	97	2.43 out of 5	\$442	73,839
Distribution Main	8587	P-1867	WW	Junior St.	6	Cast Iron	119	97	2.43 out of 5	\$442	52,808
Distribution Main	8588	P-1343	WW	Junior St.	6	Cast Iron	102	97	2.43 out of 5	\$442	44,867
Distribution Main	8589	P-991	WW	Junior St.	6	Cast Iron	84	97	2.43 out of 5	\$442	36,923
Distribution Main	8590	P-1347	WW	Junior St.	8	Ductile Iron	154	17	0 out of 5	N/A	\$0
Distribution Main	9419	P-1868	WW	Junior St.	6	Cast Iron	5	97	2.43 out of 5	\$442	2,022
Distribution Main	9420	P-991	WW	Junior St.	6	Cast Iron	6	97	2.43 out of 5	\$442	2,577
Distribution Main	11214	P-990	WW	Junior St.	6	Cast Iron	62	97	2.43 out of 5	\$442	27,208
Distribution Main	2211	P-10012	WW	Juniper Dr.	8	Asbestos Cement	68	42	1.14 out of 5	\$442	30,093
Distribution Main	2213	P-178	WW	Juniper Dr.	8	Asbestos Cement	425	42	1.14 out of 5	\$442	187,907
Distribution Main	3434	P-181	WW	Juniper Dr.	8	Asbestos Cement	241	42	1.14 out of 5	\$442	106,711
Distribution Main	3572	P-1402	WW	Juniper Dr.	8	Asbestos Cement	988	42	1.14 out of 5	\$442	436,565
Distribution Main	3573	P-1402	WW	Juniper Dr.	8	Asbestos Cement	140	42	1.14 out of 5	\$442	62,059
Distribution Main	10260	P-1403	WW	Juniper Dr.	8	Asbestos Cement	9	42	1.14 out of 5	\$442	3,888
Distribution Main	10262		WW	Juniper Dr.	8	Ductile Iron	20	UNK	0 out of 5	N/A	\$0
Distribution Main	9653	P-1902	WW	Kenmore St / Hall St	1.5	Copper	183	70	2.43 out of 5	\$442	80,748
Distribution Main	9654	P-1904	WW	Kenmore St / Hall St	1	Copper	145	70	2.43 out of 5	\$442	64,222
Distribution Main	11589	P-1903	WW	Kenmore St / Hall St	1.5	Copper	62	70	2.43 out of 5	\$442	27,590

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2493	P-1901	WW	Kenmore St.	1	Copper	304	70	2.43 out of 5	\$442	134,550
Distribution Main	3207	P-1066	WW	Kenmore St.	2	Copper	225	70	2.43 out of 5	\$442	99,320
Distribution Main	9652	P-1066	WW	Kenmore St.	6	Asbestos Cement	87	70	2 out of 5	\$442	38,420
Distribution Main	12218	P-1066	WW	Kenmore St.	6	Asbestos Cement	13	70	2 out of 5	\$442	5,874
Distribution Main	2135	P-573	WW	Kent St.	8	Ductile Iron	145	18	0 out of 5	N/A	\$0
Distribution Main	2136	P-573	WW	Kent St.	8	Ductile Iron	79	18	0 out of 5	N/A	\$0
Distribution Main	2892	P-567	WW	Kent St.	6	Ductile Iron	17	18	0.71 out of 5	N/A	\$0
Distribution Main	3983	P-567	WW	Kent St.	8	Ductile Iron	242	18	0 out of 5	N/A	\$0
Distribution Main	3984	P-567	WW	Kent St.	8	Ductile Iron	538	18	0 out of 5	N/A	\$0
Distribution Main	4328	P-573	WW	Kent St.	8	Ductile Iron	12	18	0 out of 5	N/A	\$0
Distribution Main	11154	P-573	WW	Kent St.	8	Ductile Iron	15	18	0 out of 5	N/A	\$0
Distribution Main	1705	P-789	WW	Kenyon St.	1.25	Galvanized Iron	264	81	3.43 out of 5	\$442	116,872
Transmission Main	1083	P-10089	WW	Keyes Way	12	Ductile Iron	337	21	0.14 out of 5	N/A	\$0
Transmission Main	1084	P-10089	WW	Keyes Way	12	Ductile Iron	45	21	0.14 out of 5	N/A	\$0
Distribution Main	1241		WW	Keyes Way	8	Ductile Iron	1	22	0.14 out of 5	N/A	\$0
Transmission Main	1242	P-10089	WW	Keyes Way	12	Ductile Iron	94	21	0.14 out of 5	N/A	\$0
Transmission Main	1243	P-10089	WW	Keyes Way	12	Ductile Iron	105	21	0.14 out of 5	N/A	\$0
Distribution Main	1247		WW	Keyes Way	8	Ductile Iron	32	21	0.14 out of 5	N/A	\$0
Transmission Main	1323	P-69	WW	Keyes Way	12	Ductile Iron	302	21	0.14 out of 5	N/A	\$0
Transmission Main	1324	P-69	WW	Keyes Way	12	Ductile Iron	8	21	0.14 out of 5	N/A	\$0
Transmission Main	12158	P-69	WW	Keyes Way	12	Ductile Iron	16	21	0.14 out of 5	N/A	\$0
Distribution Main	276	P-1191	WW	Kimberly Ln.	8	Asbestos Cement	34	49	1.14 out of 5	\$442	14,970
Distribution Main	277	P-1191	WW	Kimberly Ln.	8	Asbestos Cement	361	49	1.14 out of 5	\$442	159,366
Distribution Main	391		WW	Kimberly Ln.	8	Unknown	8	UNK	0 out of 5	N/A	\$0
Distribution Main	3566	P-101	WW	Kimberly Ln.	8	Asbestos Cement	184	44	1.14 out of 5	\$442	81,310
Distribution Main	4127	P-100	WW	Kimberly Ln.	6	Asbestos Cement	441	44	1.85 out of 5	\$442	194,868
Distribution Main	4128	P-100	WW	Kimberly Ln.	6	Asbestos Cement	143	44	1.85 out of 5	\$442	63,142
Distribution Main	5156	P-99	WW	Kimberly Ln.	8	Asbestos Cement	351	44	1.14 out of 5	\$442	155,114
Distribution Main	5157	P-1193	WW	Kimberly Ln.	8	Asbestos Cement	6	49	1.14 out of 5	\$442	2,472
Distribution Main	5158	P-1193	WW	Kimberly Ln.	8	Asbestos Cement	353	49	1.14 out of 5	\$442	155,848
Distribution Main	9978	P-1193	WW	Kimberly Ln.	6	Asbestos Cement	529	49	1.85 out of 5	\$442	233,996
Distribution Main	10095	P-100	WW	Kimberly Ln.	8	Ductile Iron	147	27	0.14 out of 5	\$442	64,759
Distribution Main	10251	P-1191	WW	Kimberly Ln.	8	Asbestos Cement	1	49	1.14 out of 5	\$442	520
Distribution Main	11048	P-1191	WW	Kimberly Ln.	8	Asbestos Cement	16	49	1.14 out of 5	\$442	7,226
Distribution Main	12056	P-1193	WW	Kimberly Ln.	8	Asbestos Cement	99	49	1.14 out of 5	\$442	43,810
Distribution Main	2427	P-8	WW	Kings Forest	8	Ductile Iron	672	28	0.14 out of 5	\$442	296,819
Distribution Main	2428	P-8	WW	Kings Forest	8	Ductile Iron	67	28	0.14 out of 5	\$442	29,525
Distribution Main	3466	P-778	WW	Kinne St.	4	Cast Iron	284	70	3 out of 5	\$442	125,583
Distribution Main	3756	P-781	WW	Kinne St.	6	Asbestos Cement	2	70	2 out of 5	\$442	934
Distribution Main	3757	P-781	WW	Kinne St.	6	Asbestos Cement	326	70	2 out of 5	\$442	144,213
Distribution Main	3803	P-778	WW	Kinne St.	4	Cast Iron	398	70	3 out of 5	\$442	175,900
Distribution Main	8747		WW	Kinne St.	8	Ductile Iron	18	18	0 out of 5	N/A	\$0
Distribution Main	8749	P-779	WW	Kinne St.	8	Ductile Iron	19	18	0 out of 5	N/A	\$0
Distribution Main	10973	P-781	WW	Kinne St.	8	Ductile Iron	8	18	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4733	P-36	WW	Kiwanis Road	8	Asbestos Cement	451	57	1.14 out of 5	\$442	199,410
Transmission Main	8542	P-928	WW	Knight St	12	Ductile Iron	38	13	0 out of 5	N/A	\$0
Transmission Main	8568	P-1845	WW	Knight St	20	Ductile Iron	205	13	0 out of 5	N/A	\$0
Transmission Main	8569	P-1845	WW	Knight St	20	Ductile Iron	52	13	0 out of 5	N/A	\$0
Transmission Main	8572	P-926	WW	Knight St	20	Ductile Iron	400	13	0 out of 5	N/A	\$0
Transmission Main	11479	P-1845	WW	Knight St	20	Ductile Iron	180	13	0 out of 5	N/A	\$0
Transmission Main	11480	P-1845	WW	Knight St	20	Ductile Iron	14	13	0 out of 5	N/A	\$0
Transmission Main	11481	P-926	WW	Knight St	20	Ductile Iron	3	13	0 out of 5	N/A	\$0
Distribution Main	9765	P-1964	WW	Koch St	8	Ductile Iron	257	8	0 out of 5	N/A	\$0
Distribution Main	9776	P-632	WW	Kowalik Dr	8	Ductile Iron	119	8	0 out of 5	N/A	\$0
Distribution Main	9777	P-632	WW	Kowalik Dr	8	Ductile Iron	8	8	0 out of 5	N/A	\$0
Distribution Main	9791	P-632	WW	Kowalik Dr	8	Ductile Iron	464	8	0 out of 5	N/A	\$0
Distribution Main	995		WW	Krystal Pond Dr.	8	Unknown	10	UNK	0 out of 5	N/A	\$0
Distribution Main	996		WW	Krystal Pond Dr.	8	Unknown	3	UNK	0 out of 5	N/A	\$0
Distribution Main	997	P-1324	WW	Krystal Pond Dr.	8	Ductile Iron	137	16	0 out of 5	N/A	\$0
Distribution Main	8657		WW	Krystal Pond Dr.	8	Unknown	2	UNK	0 out of 5	N/A	\$0
Distribution Main	8658		WW	Krystal Pond Dr.	8	Ductile Iron	12	29	0.14 out of 5	\$442	5,157
Distribution Main	8659	P-1324	WW	Krystal Pond Dr.	8	Ductile Iron	252	16	0 out of 5	N/A	\$0
Distribution Main	8662	P-1322	WW	Krystal Pond Dr.	8	PVC	24	29	0.43 out of 5	\$442	10,611
Distribution Main	8663	P-1321	WW	Krystal Pond Dr.	8	PVC	250	29	0.43 out of 5	\$442	110,486
Distribution Main	8664	P-1321	WW	Krystal Pond Dr.	8	PVC	59	29	0.43 out of 5	\$442	26,080
Distribution Main	8806		WW	Krystal Pond Dr.	8	Cast Iron	16	UNK	1.14 out of 5	\$442	7,041
Distribution Main	11006	P-1322	WW	Krystal Pond Dr.	8	PVC	12	29	0.43 out of 5	\$442	5,367
Distribution Main	11490	P-1324	WW	Krystal Pond Dr.	8	Ductile Iron	208	16	0 out of 5	N/A	\$0
Distribution Main	1571	P-499	WW	Kulas Rd.	8	Asbestos Cement	6	49	1.14 out of 5	\$442	2,860
Transmission Main	3414	P-138	WW	Kulas Rd.	12	Asbestos Cement	668	49	1.14 out of 5	\$442	295,461
Transmission Main	3415	P-138	WW	Kulas Rd.	12	Asbestos Cement	172	49	1.14 out of 5	\$442	76,225
Distribution Main	3416	P-139	WW	Kulas Rd.	8	Asbestos Cement	361	49	1.14 out of 5	\$442	159,409
Transmission Main	4124	P-10014	WW	Kulas Rd.	12	Asbestos Cement	206	49	1.14 out of 5	\$442	90,928
Distribution Main	4125	P-139	WW	Kulas Rd.	8	Asbestos Cement	238	49	1.14 out of 5	\$442	105,366
Distribution Main	4658	P-499	WW	Kulas Rd.	8	Asbestos Cement	1,038	49	1.14 out of 5	\$442	458,843
Distribution Main	10151	P-1609	WW	Kulas Rd.	8	Asbestos Cement	4	49	1.14 out of 5	\$442	1,915
Distribution Main	10153	P-10013	WW	Kulas Rd.	8	Asbestos Cement	28	49	1.14 out of 5	\$442	12,575
Distribution Main	10154	P-10013	WW	Kulas Rd.	8	Asbestos Cement	1	49	1.14 out of 5	\$442	613
Distribution Main	10453	P-139	WW	Kulas Rd.	8	Asbestos Cement	4	49	1.14 out of 5	\$442	1,662
Distribution Main	2850	P-719	WW	Lachance St.	6	Cast Iron	224	81	2.43 out of 5	\$442	98,881
Distribution Main	3266	P-1365	WW	Lachance St.	6	Cast Iron	259	81	3.14 out of 5	\$442	114,263
Transmission Main	1244	P-73	WW	Lacroix Dr.	12	Ductile Iron	4	19	0 out of 5	N/A	\$0
Transmission Main	1245	P-73	WW	Lacroix Dr.	12	Ductile Iron	25	19	0 out of 5	N/A	\$0
Transmission Main	1328	P-73	WW	Lacroix Dr.	12	Ductile Iron	656	19	0 out of 5	N/A	\$0
Distribution Main	9779	P-635	WW	Lada Dr	8	Ductile Iron	108	8	0 out of 5	N/A	\$0
Distribution Main	9792	P-635	WW	Lada Dr	8	Ductile Iron	117	8	0 out of 5	N/A	\$0
Distribution Main	9793	P-634	WW	Lada Dr	8	Ductile Iron	184	8	0 out of 5	N/A	\$0
Distribution Main	11607	P-635	WW	Lada Dr	8	Ductile Iron	28	8	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	864	P-289	WW	Lafayette St.	6	Ductile Iron	243	26	0.85 out of 5	\$442	107,350
Distribution Main	2140	P-289	WW	Lafayette St.	6	Ductile Iron	250	26	0.85 out of 5	\$442	110,331
Distribution Main	2141	P-289	WW	Lafayette St.	6	Ductile Iron	246	26	0.85 out of 5	\$442	108,692
Distribution Main	10051	P-263	WW	Lancelotta St	8	Ductile Iron	22	6	0 out of 5	N/A	\$0
Distribution Main	10052	P-263	WW	Lancelotta St	8	Ductile Iron	427	6	0 out of 5	N/A	\$0
Distribution Main	11637	P-263	WW	Lancelotta St	8	Ductile Iron	278	6	0 out of 5	N/A	\$0
Distribution Main	3550	P-1447	WW	Lancer Ln.	8	Asbestos Cement	290	41	1.14 out of 5	\$442	128,123
Distribution Main	3551	P-1447	WW	Lancer Ln.	8	Asbestos Cement	422	41	1.14 out of 5	\$442	186,724
Distribution Main	2934	P-1225	WW	Lanphear St.	6	Cast Iron	189	134	2.57 out of 5	\$442	83,585
Distribution Main	2935	P-1225	WW	Lanphear St.	6	Cast Iron	411	134	2.57 out of 5	\$442	181,487
Distribution Main	3696	P-1224	WW	Lanphear St.	6	Cast Iron	164	134	2.57 out of 5	\$442	72,302
Distribution Main	11192	P-1225	WW	Lanphear St.	6	Cast Iron	2	134	2.57 out of 5	\$442	736
Distribution Main	4333	P-572	WW	Laramee Ave.	6	PVC	236	30	1.14 out of 5	\$442	104,351
Distribution Main	4334	P-572	WW	Laramee Ave.	6	PVC	53	30	1.14 out of 5	\$442	23,440
Distribution Main	4335	P-563	WW	Laramee Ave.	6	Ductile Iron	485	28	0.85 out of 5	\$442	214,225
Distribution Main	4654	P-147	WW	Laural Ln.	8	Asbestos Cement	345	50	1.14 out of 5	\$442	152,530
Distribution Main	4655	P-147	WW	Laural Ln.	8	Asbestos Cement	96	50	1.14 out of 5	\$442	42,462
Transmission Main	392		WW	Lauren Ln.	12	Ductile Iron	6	22	0.14 out of 5	N/A	\$0
Transmission Main	2316		WW	Lauren Ln.	12	Ductile Iron	15	22	0.14 out of 5	N/A	\$0
Transmission Main	2339	P-1426	WW	Lauren Ln.	12	PVC	15	32	0.43 out of 5	\$442	6,743
Transmission Main	4758	P-1427	WW	Lauren Ln.	12	PVC	189	32	0.43 out of 5	\$442	83,714
Transmission Main	4759	P-1427	WW	Lauren Ln.	12	PVC	379	32	0.43 out of 5	\$442	167,359
Transmission Main	10261	P-1426	WW	Lauren Ln.	12	PVC	3	32	0.43 out of 5	\$442	1,418
Distribution Main	2852	P-1978	WW	Lavoie Street	2	Unknown	185	51	1.71 out of 5	\$442	81,884
Distribution Main	8415	P-1820	WW	Lawrence St	8	Ductile Iron	22	10	0 out of 5	N/A	\$0
Distribution Main	8416	P-1818	WW	Lawrence St	8	Ductile Iron	29	10	0 out of 5	N/A	\$0
Distribution Main	8490	P-1818	WW	Lawrence St	6	Ductile Iron	2	10	0.71 out of 5	N/A	\$0
Distribution Main	9713	P-1811	WW	Lawrence St	6	Ductile Iron	7	27	0.85 out of 5	\$442	2,989
Distribution Main	9714	P-1811	WW	Lawrence St	6	Ductile Iron	200	27	0.85 out of 5	\$442	88,367
Distribution Main	3506	P-1818	WW	Lawrence Street	6	Asbestos Cement	362	64	2 out of 5	\$442	159,843
Distribution Main	1787	P-1221	WW	Le Valley St.	4	Cast Iron	24	134	3.29 out of 5	\$442	10,422
Distribution Main	1789	P-1220	WW	Le Valley St.	4	Cast Iron	73	134	3.29 out of 5	\$442	32,050
Distribution Main	1790	P-1220	WW	Le Valley St.	4	Cast Iron	22	134	3.29 out of 5	\$442	9,919
Distribution Main	1960	P-1221	WW	Le Valley St.	4	Cast Iron	69	134	3.29 out of 5	\$442	30,710
Distribution Main	1961	P-1226	WW	Le Valley St.	4	Cast Iron	130	134	3.29 out of 5	\$442	57,494
Distribution Main	1962	P-1226	WW	Le Valley St.	4	Cast Iron	120	134	3.29 out of 5	\$442	52,843
Distribution Main	3094	P-1502	WW	Le Valley St.	4	Cast Iron	64	134	3.29 out of 5	\$442	28,201
Distribution Main	3095	P-1502	WW	Le Valley St.	4	Cast Iron	165	134	3.29 out of 5	\$442	73,100
Distribution Main	3524	P-1220	WW	Le Valley St.	4	Cast Iron	29	134	3.29 out of 5	\$442	12,672
Distribution Main	9683	P-1502	WW	Le Valley St.	4	Cast Iron	17	134	3.29 out of 5	\$442	7,557
Distribution Main	10663	P-377	WW	Leaf St	8	Ductile Iron	309	2	0 out of 5	N/A	\$0
Distribution Main	10664	P-377	WW	Leaf St	8	Ductile Iron	481	2	0 out of 5	N/A	\$0
Distribution Main	10902	P-10034	WW	Leaf St	8	Ductile Iron	189	2	0 out of 5	N/A	\$0
Distribution Main	11701	P-377	WW	Leaf St	8	Ductile Iron	92	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9928	P-10035	WW	Leaf St.	1	Copper	146	69	2.43 out of 5	\$442	64,468
Distribution Main	3197	P-905	WW	Ledge Dr.	6	Asbestos Cement	358	64	2 out of 5	\$442	158,286
Distribution Main	10774	P-365	WW	Ledgemont Ct	8	Ductile Iron	331	0	0 out of 5	N/A	\$0
Distribution Main	4816	P-517	WW	Lee St.	6	Asbestos Cement	284	69	2 out of 5	\$442	125,702
Distribution Main	4817	P-517	WW	Lee St.	6	Asbestos Cement	116	69	2 out of 5	\$442	51,304
Distribution Main	5094	P-527	WW	Lee St.	6	Asbestos Cement	92	69	2 out of 5	\$442	40,553
Distribution Main	5136	P-514	WW	Lee St.	6	Asbestos Cement	596	69	2 out of 5	\$442	263,392
Distribution Main	5146	P-513	WW	Lee St.	8	Ductile Iron	17	18	0 out of 5	N/A	\$0
Distribution Main	2889	P-570	WW	Leeder St.	2	Galvanized Iron	80	91	3.43 out of 5	\$442	35,546
Distribution Main	3968	P-570	WW	Leeder St.	2	Galvanized Iron	265	91	3.43 out of 5	\$442	117,309
Distribution Main	4316		WW	Leeder St.	2	Galvanized Iron	8	91	3.43 out of 5	\$442	3,678
Transmission Main	1032	P-79	WW	Legend Way	16	Ductile Iron	212	28	0.14 out of 5	\$442	93,839
Transmission Main	10667	P-1108	WW	Legris Av	12	Ductile Iron	22	2	0 out of 5	N/A	\$0
Transmission Main	10668	P-1108	WW	Legris Av	12	Ductile Iron	340	2	0 out of 5	N/A	\$0
Transmission Main	10669	P-1497	WW	Legris Av	12	Ductile Iron	443	2	0 out of 5	N/A	\$0
Transmission Main	10670	P-1495	WW	Legris Av	12	Ductile Iron	253	2	0 out of 5	N/A	\$0
Transmission Main	10676	P-1581	WW	Legris Av	12	Ductile Iron	305	2	0 out of 5	N/A	\$0
Transmission Main	10677	P-1581	WW	Legris Av	12	Ductile Iron	421	2	0 out of 5	N/A	\$0
Transmission Main	10678	P-1498	WW	Legris Av	12	Ductile Iron	46	2	0 out of 5	N/A	\$0
Transmission Main	10679	P-1498	WW	Legris Av	12	Ductile Iron	269	2	0 out of 5	N/A	\$0
Transmission Main	10889	P-1496	WW	Legris Av	12	Ductile Iron	32	2	0 out of 5	N/A	\$0
Transmission Main	10890	P-1496	WW	Legris Av	12	Ductile Iron	256	2	0 out of 5	N/A	\$0
Transmission Main	10892	P-1107	WW	Legris Av	12	Ductile Iron	25	2	0 out of 5	N/A	\$0
Transmission Main	11702	P-1108	WW	Legris Av	12	Ductile Iron	21	2	0 out of 5	N/A	\$0
Transmission Main	11706	P-1499	WW	Legris Av	12	Ductile Iron	44	2	0 out of 5	N/A	\$0
Transmission Main	12030	P-1108	WW	Legris Av	12	Ductile Iron	61	2	0 out of 5	N/A	\$0
Transmission Main	12142	P-1581	WW	Legris Av	12	Ductile Iron	31	2	0 out of 5	N/A	\$0
Distribution Main	881	P-1499	WW	Legris Ave.	8	Asbestos Cement	49	60	1.14 out of 5	\$442	21,579
Distribution Main	882	P-1499	WW	Legris Ave.	8	Asbestos Cement	884	60	1.14 out of 5	\$442	390,781
Distribution Main	1433		WW	Legris Ave.	8	Unknown	8	UNK	0 out of 5	N/A	\$0
Distribution Main	1723	P-641	WW	Legris Ave.	6	Ductile Iron	44	25	0.85 out of 5	N/A	\$0
Distribution Main	1724	P-641	WW	Legris Ave.	6	Ductile Iron	35	25	0.85 out of 5	N/A	\$0
Distribution Main	2883	P-642	WW	Legris Ave.	6	Ductile Iron	63	25	0.85 out of 5	N/A	\$0
Distribution Main	3531	P-2775	WW	Legris Ave.	8	Asbestos Cement	95	60	1.14 out of 5	\$442	41,902
Distribution Main	3537		WW	Legris Ave.	8	Asbestos Cement	21	60	1.14 out of 5	\$442	9,156
Distribution Main	3964	P-2775	WW	Legris Ave.	8	Asbestos Cement	350	60	1.14 out of 5	\$442	154,909
Distribution Main	3965	P-1499	WW	Legris Ave.	8	Asbestos Cement	150	60	1.14 out of 5	\$442	66,458
Distribution Main	3966	P-1499	WW	Legris Ave.	8	Asbestos Cement	605	60	1.14 out of 5	\$442	267,434
Distribution Main	4302	P-1107	WW	Legris Ave.	6	Ductile Iron	361	25	0.85 out of 5	N/A	\$0
Distribution Main	4324	P-1107	WW	Legris Ave.	6	Ductile Iron	35	UNK	0.71 out of 5	\$442	15,480
Distribution Main	11935	P-1499	WW	Legris Ave.	8	Asbestos Cement	469	60	1.14 out of 5	\$442	207,485
Distribution Main	8840	P-704	WW	Lemoine Ct.	2	Galvanized Iron	269	130	3.57 out of 5	\$442	118,850
Distribution Main	10634	P-391	WW	Lenox Av	8	Ductile Iron	272	2	0 out of 5	N/A	\$0
Distribution Main	10635	P-396	WW	Lenox Av	8	Ductile Iron	339	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10636	P-10033	WW	Lenox Av	8	Ductile Iron	410	2	0 out of 5	N/A	\$0
Distribution Main	10637	P-391	WW	Lenox Av	8	Ductile Iron	197	2	0 out of 5	N/A	\$0
Distribution Main	11695	P-395	WW	Lenox Av	8	Ductile Iron	228	2	0 out of 5	N/A	\$0
Distribution Main	4702	P-388	WW	Lenox Ave.	6	Ductile Iron	90	26	0.85 out of 5	\$442	39,768
Distribution Main	4705	P-388	WW	Lenox Ave.	8	Ductile Iron	298	26	0.14 out of 5	\$442	131,526
Distribution Main	4710	P-388	WW	Lenox Ave.	6	Ductile Iron	104	26	0.85 out of 5	\$442	46,025
Distribution Main	10638		WW	Lexington Av	8	Ductile Iron	739	2	0.71 out of 5	N/A	\$0
Distribution Main	10639	P-383	WW	Lexington Av	8	Ductile Iron	526	2	0 out of 5	N/A	\$0
Distribution Main	10640	P-381	WW	Lexington Av	8	Ductile Iron	169	2	0 out of 5	N/A	\$0
Distribution Main	10641	P-382	WW	Lexington Av	8	Ductile Iron	276	2	0 out of 5	N/A	\$0
Distribution Main	11696	P-386	WW	Lexington Av	8	Ductile Iron	5	2	0 out of 5	N/A	\$0
Distribution Main	11697	P-383	WW	Lexington Av	8	Ductile Iron	154	2	0 out of 5	N/A	\$0
Distribution Main	11698	P-382	WW	Lexington Av	8	Ductile Iron	6	2	0 out of 5	N/A	\$0
Distribution Main	12139	P-386	WW	Lexington Av	8	Ductile Iron	25	2	0 out of 5	N/A	\$0
Distribution Main	12140	P-383	WW	Lexington Av	8	Ductile Iron	9	2	0 out of 5	N/A	\$0
Distribution Main	8926	P-119	WW	Linden Dr	8	Ductile Iron	45	9	0 out of 5	N/A	\$0
Distribution Main	8927	P-119	WW	Linden Dr	8	Ductile Iron	446	9	0 out of 5	N/A	\$0
Distribution Main	2962	P-1720	WW	Linden Dr.	8	Ductile Iron	22	15	0 out of 5	N/A	\$0
Distribution Main	1536		WW	Linwood St.	6	Asbestos Cement	16	77	2 out of 5	\$442	6,928
Distribution Main	3697	P-952	WW	Linwood St.	6	Asbestos Cement	402	77	2 out of 5	\$442	177,849
Distribution Main	10644	P-380	WW	Lionel Av	8	Ductile Iron	141	2	0 out of 5	N/A	\$0
Distribution Main	10645	P-380	WW	Lionel Av	8	Ductile Iron	132	2	0 out of 5	N/A	\$0
Distribution Main	2551	P-37	WW	Lions Dr.	8	Asbestos Cement	183	50	1.14 out of 5	\$442	81,085
Distribution Main	4730	P-35	WW	Lions Dr.	8	Asbestos Cement	296	50	1.14 out of 5	\$442	130,976
Distribution Main	4731	P-35	WW	Lions Dr.	8	Asbestos Cement	44	50	1.14 out of 5	\$442	19,551
Distribution Main	4964	P-1941	WW	Lions Dr.	8	Asbestos Cement	105	50	1.14 out of 5	\$442	46,401
Distribution Main	4965	P-1942	WW	Lions Dr.	6	Asbestos Cement	67	50	1.85 out of 5	\$442	29,535
Distribution Main	3236	P-5126	WW	Lippitt Ave.	6	Asbestos Cement	722	44	1.85 out of 5	\$442	319,172
Distribution Main	3237	P-5126	WW	Lippitt Ave.	6	Asbestos Cement	326	44	1.85 out of 5	\$442	144,260
Distribution Main	9430	P-5126	WW	Lippitt Ave.	6	Asbestos Cement	563	44	1.85 out of 5	\$442	248,869
Distribution Main	9431	P-5126	WW	Lippitt Ave.	6	Asbestos Cement	44	44	1.85 out of 5	\$442	19,387
Distribution Main	1805	P-2	WW	Little John La.	8	Ductile Iron	303	28	0.14 out of 5	\$442	133,854
Distribution Main	1806	P-2	WW	Little John La.	8	Ductile Iron	14	28	0.14 out of 5	\$442	6,167
Distribution Main	2429	P-4	WW	Little John La.	8	Ductile Iron	32	28	0.14 out of 5	\$442	14,182
Distribution Main	2430	P-4	WW	Little John La.	8	Ductile Iron	464	28	0.14 out of 5	\$442	204,919
Distribution Main	646	P-450	WW	Lockwood St.	6	Asbestos Cement	567	69	2 out of 5	\$442	250,823
Distribution Main	647	P-450	WW	Lockwood St.	6	Asbestos Cement	982	69	2 out of 5	\$442	433,845
Distribution Main	648	P-443	WW	Lockwood St.	6	Asbestos Cement	234	69	2 out of 5	\$442	103,471
Distribution Main	649	P-441	WW	Lockwood St.	6	PVC	82	33	1.14 out of 5	\$442	36,355
Distribution Main	650	P-441	WW	Lockwood St.	6	PVC	167	33	1.14 out of 5	\$442	73,950
Distribution Main	656	P-463	WW	Lockwood St.	6	Asbestos Cement	61	69	2 out of 5	\$442	27,097
Distribution Main	809	P-436	WW	Lockwood St.	6	PVC	352	33	1.14 out of 5	\$442	155,545
Distribution Main	810	P-436	WW	Lockwood St.	6	PVC	216	33	1.14 out of 5	\$442	95,544
Distribution Main	1750	P-438	WW	Lockwood St.	6	PVC	239	33	1.14 out of 5	\$442	105,747

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3884	P-463	WW	Lockwood St.	6	Asbestos Cement	429	69	2 out of 5	\$442	189,641
Distribution Main	4666	P-463	WW	Lockwood St.	6	Asbestos Cement	18	69	2 out of 5	\$442	7,844
Distribution Main	4674	P-443	WW	Lockwood St.	6	Asbestos Cement	9	69	2 out of 5	\$442	4,143
Distribution Main	11143	P-438	WW	Lockwood St.	6	PVC	7	33	1.14 out of 5	\$442	3,018
Distribution Main	12028	P-450	WW	Lockwood St.	6	Asbestos Cement	119	69	2 out of 5	\$442	52,504
Distribution Main	4777	P-1465	WW	Locust Dr.	8	PVC	444	33	0.43 out of 5	\$442	196,237
Distribution Main	4622	P-131	WW	Loggers Run	8	Ductile Iron	228	22	0.14 out of 5	N/A	\$0
Distribution Main	4623	P-131	WW	Loggers Run	8	Ductile Iron	595	22	0.14 out of 5	N/A	\$0
Distribution Main	4624	P-1269	WW	Loggers Run	8	Ductile Iron	493	22	0.14 out of 5	N/A	\$0
Distribution Main	4625	P-132	WW	Loggers Run	8	Ductile Iron	288	22	0.14 out of 5	N/A	\$0
Distribution Main	4626	P-132	WW	Loggers Run	8	Ductile Iron	318	22	0.14 out of 5	N/A	\$0
Transmission Main	2088	P-875	WW	Lombardi Ln.	12	PVC	637	30	0.43 out of 5	\$442	281,575
Distribution Main	1807	P-9	WW	Longbow Dr.	8	Ductile Iron	4	28	0.14 out of 5	\$442	1,804
Distribution Main	2425	P-10	WW	Longbow Dr.	8	Ductile Iron	51	28	0.14 out of 5	\$442	22,428
Distribution Main	2426	P-10	WW	Longbow Dr.	8	Ductile Iron	387	28	0.14 out of 5	\$442	170,915
Distribution Main	2433	P-7	WW	Longbow Dr.	8	Ductile Iron	240	28	0.14 out of 5	\$442	105,936
Distribution Main	2439	P-9	WW	Longbow Dr.	8	Ductile Iron	282	28	0.14 out of 5	\$442	124,629
Distribution Main	4451	P-15	WW	Longbow Dr.	8	Ductile Iron	241	28	0.14 out of 5	\$442	106,301
Distribution Main	4742	P-21	WW	Longbow Dr.	8	Ductile Iron	425	28	0.14 out of 5	\$442	187,661
Transmission Main	1591	P-135	WW	Lonsdale St.	12	Asbestos Cement	3	50	1.14 out of 5	\$442	1,136
Transmission Main	2154	P-1155	WW	Lonsdale St.	12	Asbestos Cement	216	50	1.14 out of 5	\$442	95,287
Transmission Main	2155	P-1155	WW	Lonsdale St.	12	Asbestos Cement	409	50	1.14 out of 5	\$442	180,915
Transmission Main	3898	P-1149	WW	Lonsdale St.	12	Asbestos Cement	558	50	1.14 out of 5	\$442	246,676
Transmission Main	5108	P-135	WW	Lonsdale St.	12	Asbestos Cement	155	50	1.14 out of 5	\$442	68,412
Transmission Main	5109	P-135	WW	Lonsdale St.	12	Asbestos Cement	720	50	1.14 out of 5	\$442	318,432
Transmission Main	5172	P-136	WW	Lonsdale St.	12	Asbestos Cement	251	50	1.14 out of 5	\$442	110,821
Transmission Main	5173	P-136	WW	Lonsdale St.	12	Asbestos Cement	741	50	1.14 out of 5	\$442	327,380
Distribution Main	4822	P-1143	WW	Lori Ct.	8	Asbestos Cement	228	47	1.14 out of 5	\$442	100,711
Distribution Main	1530	P-847	WW	Louise Dr.	6	Asbestos Cement	536	64	2 out of 5	\$442	236,915
Distribution Main	1531	P-847	WW	Louise Dr.	6	Asbestos Cement	16	64	2 out of 5	\$442	7,264
Distribution Main	9753	P-610	WW	Loven Ct	8	Ductile Iron	126	8	0 out of 5	N/A	\$0
Distribution Main	9754	P-1383	WW	Loven Ct	8	Ductile Iron	15	14	0 out of 5	N/A	\$0
Distribution Main	9758	P-610	WW	Loven Ct	8	Ductile Iron	229	8	0 out of 5	N/A	\$0
Distribution Main	8417	P-1812	WW	Lowell St	8	Ductile Iron	27	10	0 out of 5	N/A	\$0
Distribution Main	9453	P-1813	WW	Lowell St	1	Copper	237	10	1.99 out of 5	N/A	\$0
Distribution Main	488	P-966	WW	Lowell St.	6	Asbestos Cement	297	57	1.85 out of 5	\$442	131,396
Distribution Main	2356	P-1445	WW	Maid Marian Ln.	8	Asbestos Cement	290	41	1.14 out of 5	\$442	127,995
Distribution Main	3552	P-1446	WW	Maid Marian Ln.	8	Asbestos Cement	292	41	1.14 out of 5	\$442	128,978
Distribution Main	3553	P-1446	WW	Maid Marian Ln.	8	Asbestos Cement	270	41	1.14 out of 5	\$442	119,173
Transmission Main	8535	P-941	WW	Main St	20	Ductile Iron	102	13	0 out of 5	N/A	\$0
Transmission Main	8543	P-925	WW	Main St	20	Ductile Iron	174	13	0 out of 5	N/A	\$0
Transmission Main	8544	P-925	WW	Main St	20	Ductile Iron	357	13	0 out of 5	N/A	\$0
Distribution Main	8547	P-1850	WW	Main St	8	Ductile Iron	26	13	0 out of 5	N/A	\$0
Transmission Main	8560	P-1256	WW	Main St	20	Ductile Iron	18	13	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	8561	P-1256	WW	Main St	20	Ductile Iron	12	13	0 out of 5	N/A	\$0
Transmission Main	8562	P-1256	WW	Main St	20	Ductile Iron	362	13	0 out of 5	N/A	\$0
Transmission Main	8563	P-1256	WW	Main St	20	Ductile Iron	320	13	0 out of 5	N/A	\$0
Transmission Main	8565	P-982	WW	Main St	20	Ductile Iron	140	13	0 out of 5	N/A	\$0
Transmission Main	8567	P-941	WW	Main St	20	Ductile Iron	109	13	0 out of 5	N/A	\$0
Transmission Main	8576	P-925	WW	Main St	12	Ductile Iron	18	13	0 out of 5	N/A	\$0
Transmission Main	8577	P-925	WW	Main St	12	Ductile Iron	13	13	0 out of 5	N/A	\$0
Distribution Main	8578	P-828	WW	Main St	8	Ductile Iron	10	13	0 out of 5	N/A	\$0
Distribution Main	8629	P-1865	WW	Main St	10	Ductile Iron	180	20	0 out of 5	N/A	\$0
Transmission Main	8988		WW	Main St	12	Ductile Iron	8	13	0 out of 5	N/A	\$0
Distribution Main	9327	P-1009	WW	Main St	6	Ductile Iron	5	9	0.71 out of 5	N/A	\$0
Transmission Main	9695	P-1256	WW	Main St	20	Ductile Iron	15	13	0 out of 5	N/A	\$0
Distribution Main	10355		WW	Main St		Cast Iron	20	UNK	1.14 out of 5	\$442	8,850
Transmission Main	10964	P-941	WW	Main St	20	Ductile Iron	75	13	0 out of 5	N/A	\$0
Transmission Main	11476	P-941	WW	Main St	20	Ductile Iron	9	13	0 out of 5	N/A	\$0
Transmission Main	11483	P-925	WW	Main St	12	Ductile Iron	20	13	0 out of 5	N/A	\$0
Transmission Main	12004	P-1256	WW	Main St	20	Ductile Iron	91	13	0 out of 5	N/A	\$0
Transmission Main	12005	P-1256	WW	Main St	20	Ductile Iron	286	13	0 out of 5	N/A	\$0
Distribution Main	137	P-1975	WW	Main St.	6	Cast Iron	224	134	2.57 out of 5	\$442	98,927
Distribution Main	256	P-1500	WW	Main St.	8	Cast Iron	304	84	1.72 out of 5	\$442	134,192
Distribution Main	293	P-1895	WW	Main St.	6	Cast Iron	12	83	2.43 out of 5	\$442	5,478
Distribution Main	294	P-1885	WW	Main St.	8	Cast Iron	14	83	1.72 out of 5	\$442	6,187
Distribution Main	317	P-1037	WW	Main St.	6	Cast Iron	251	134	2.57 out of 5	\$442	110,824
Distribution Main	318	P-1020	WW	Main St.	6	Cast Iron	328	134	2.57 out of 5	\$442	144,947
Distribution Main	320	P-1885	WW	Main St.	8	Cast Iron	3	83	1.72 out of 5	\$442	1,144
Distribution Main	329	P-1009	WW	Main St.	6	Cast Iron	132	134	2.57 out of 5	\$442	58,440
Distribution Main	330	P-1009	WW	Main St.	6	Cast Iron	193	134	2.57 out of 5	\$442	85,400
Distribution Main	336	P-1894	WW	Main St.	6	Cast Iron	209	83	2.43 out of 5	\$442	92,555
Distribution Main	434	P-1007	WW	Main St.	10	Cast Iron	212	134	1.86 out of 5	\$442	93,553
Distribution Main	445	P-790	WW	Main St.	6	Cast Iron	25	83	2.43 out of 5	\$442	10,877
Distribution Main	446	P-1039	WW	Main St.	6	Cast Iron	345	134	2.57 out of 5	\$442	152,376
Distribution Main	605	P-1033	WW	Main St.	8	Cast Iron	371	84	1.72 out of 5	\$442	163,846
Distribution Main	606	P-1030	WW	Main St.	8	Cast Iron	171	84	1.72 out of 5	\$442	75,361
Distribution Main	607	P-1030	WW	Main St.	8	Cast Iron	178	84	1.72 out of 5	\$442	78,459
Distribution Main	917	P-1117	WW	Main St.	8	Cast Iron	30	134	1.86 out of 5	\$442	13,241
Distribution Main	918	P-1117	WW	Main St.	8	Cast Iron	175	134	1.86 out of 5	\$442	77,161
Distribution Main	919	P-1482	WW	Main St.	8	Cast Iron	262	134	1.86 out of 5	\$442	115,998
Distribution Main	920	P-1115	WW	Main St.	8	Cast Iron	395	134	1.86 out of 5	\$442	174,798
Distribution Main	961	P-827	WW	Main St.	10	Cast Iron	95	134	1.86 out of 5	\$442	42,062
Distribution Main	962	P-827	WW	Main St.	10	Cast Iron	170	134	1.86 out of 5	\$442	74,987
Distribution Main	1071	P-1026	WW	Main St.	6	Cast Iron	405	124	2.57 out of 5	\$442	179,075
Distribution Main	1072	P-1026	WW	Main St.	6	Cast Iron	32	134	2.57 out of 5	\$442	14,311
Distribution Main	1075	P-1037	WW	Main St.	6	Cast Iron	16	134	2.57 out of 5	\$442	7,255
Distribution Main	1515	P-1501	WW	Main St.	8	Cast Iron	308	134	1.86 out of 5	\$442	136,105

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	1516	P-1501	WW	Main St.	8	Cast Iron	198	134	1.86 out of 5	\$442	87,603
Distribution Main	1610	P-1033	WW	Main St.	8	Cast Iron	362	84	1.72 out of 5	\$442	160,006
Distribution Main	1701	P-1035	WW	Main St.	6	Cast Iron	401	134	2.57 out of 5	\$442	177,342
Distribution Main	1702	P-1078	WW	Main St.	6	Cast Iron	75	134	2.57 out of 5	\$442	33,282
Distribution Main	1703	P-1285	WW	Main St.	6	Cast Iron	373	134	2.57 out of 5	\$442	164,672
Distribution Main	1704	P-1285	WW	Main St.	6	Cast Iron	166	134	2.57 out of 5	\$442	73,505
Distribution Main	1722		WW	Main St.	6	Unknown	30	UNK	0.71 out of 5	\$442	13,144
Distribution Main	1785	P-1251	WW	Main St.	8	Cast Iron	306	134	1.86 out of 5	\$442	135,427
Distribution Main	1786	P-1251	WW	Main St.	8	Cast Iron	321	84	1.72 out of 5	\$442	142,093
Distribution Main	1879	P-1027	WW	Main St.	8	Cast Iron	13	84	1.72 out of 5	\$442	5,823
Distribution Main	1880	P-1027	WW	Main St.	8	Cast Iron	231	84	1.72 out of 5	\$442	101,945
Distribution Main	1884	P-1116	WW	Main St.	8	Cast Iron	114	134	1.86 out of 5	\$442	50,540
Distribution Main	1885	P-1130	WW	Main St.	8	Cast Iron	110	134	1.86 out of 5	\$442	48,505
Distribution Main	1888	P-1125	WW	Main St.	8	Cast Iron	482	134	1.86 out of 5	\$442	213,083
Distribution Main	1890	P-1116	WW	Main St.	8	Cast Iron	175	134	1.86 out of 5	\$442	77,278
Distribution Main	1891	P-1116	WW	Main St.	8	Cast Iron	16	134	1.86 out of 5	\$442	7,199
Distribution Main	1963	P-1500	WW	Main St.	8	Cast Iron	278	84	1.72 out of 5	\$442	122,833
Distribution Main	2182	P-828	WW	Main St.	10	Cast Iron	169	134	1.86 out of 5	\$442	74,763
Distribution Main	2207	P-1336	WW	Main St.	8	Cast Iron	10	84	1.72 out of 5	\$442	4,616
Distribution Main	2247	P-1105	WW	Main St.	8	Cast Iron	802	134	1.86 out of 5	\$442	354,494
Distribution Main	2248	P-1105	WW	Main St.	8	Cast Iron	84	134	1.86 out of 5	\$442	36,931
Distribution Main	2249	P-1105	WW	Main St.	8	Cast Iron	357	134	1.86 out of 5	\$442	157,833
Distribution Main	2396	P-1008	WW	Main St.	10	Cast Iron	81	134	1.86 out of 5	\$442	35,959
Distribution Main	2397	P-1008	WW	Main St.	10	Cast Iron	63	134	1.86 out of 5	\$442	28,009
Distribution Main	2450	P-1884	WW	Main St.	6	Cast Iron	4	83	2.43 out of 5	\$442	1,650
Distribution Main	2451	P-1884	WW	Main St.	6	Cast Iron	14	83	2.43 out of 5	\$442	6,155
Distribution Main	2452	P-1265	WW	Main St.	6	Cast Iron	20	83	2.43 out of 5	\$442	8,630
Distribution Main	2453	P-1265	WW	Main St.	6	Cast Iron	53	83	2.43 out of 5	\$442	23,622
Distribution Main	2897	P-641	WW	Main St.	8	Cast Iron	33	84	1.72 out of 5	\$442	14,775
Distribution Main	2898	P-646	WW	Main St.	6	Cast Iron	154	134	2.57 out of 5	\$442	68,279
Distribution Main	2952	P-1846	WW	Main St.	8	Cast Iron	88	134	1.86 out of 5	\$442	38,897
Distribution Main	2953	P-1846	WW	Main St.	8	Cast Iron	126	134	1.86 out of 5	\$442	55,696
Distribution Main	2954	P-930	WW	Main St.	8	Cast Iron	201	134	1.86 out of 5	\$442	88,665
Distribution Main	2955	P-930	WW	Main St.	8	Cast Iron	168	134	1.86 out of 5	\$442	74,293
Distribution Main	3101		WW	Main St.	4	Unknown	10	UNK	1.42 out of 5	\$442	4,369
Distribution Main	3102		WW	Main St.	4	Unknown	10	UNK	1.42 out of 5	\$442	4,567
Distribution Main	3103		WW	Main St.	4	Unknown	6	UNK	1.42 out of 5	\$442	2,530
Distribution Main	3104		WW	Main St.	4	Unknown	123	UNK	1.42 out of 5	\$442	54,302
Distribution Main	3134	P-1033	WW	Main St.	8	Cast Iron	30	84	1.72 out of 5	\$442	13,050
Distribution Main	3353	P-1035	WW	Main St.	8	Cast Iron	10	84	1.72 out of 5	\$442	4,289
Distribution Main	3354	P-1033	WW	Main St.	8	Cast Iron	180	84	1.72 out of 5	\$442	79,437
Distribution Main	3358	P-788	WW	Main St.	6	Cast Iron	99	83	2.43 out of 5	\$442	43,697
Distribution Main	3359	P-788	WW	Main St.	6	Cast Iron	28	83	2.43 out of 5	\$442	12,596
Distribution Main	3360	P-1865	WW	Main St.	10	Cast Iron	12	134	1.86 out of 5	\$442	5,176

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3376	P-1021	WW	Main St.	6	Cast Iron	241	134	2.57 out of 5	\$442	106,668
Distribution Main	3380	P-1285	WW	Main St.	6	Cast Iron	235	134	2.57 out of 5	\$442	104,062
Distribution Main	3381	P-1035	WW	Main St.	6	Cast Iron	10	134	2.57 out of 5	\$442	4,536
Distribution Main	3382	P-1892	WW	Main St.	6	Cast Iron	5	134	2.57 out of 5	\$442	2,371
Distribution Main	3384	P-1019	WW	Main St.	6	Cast Iron	17	84	2.43 out of 5	\$442	7,475
Distribution Main	3385	P-1019	WW	Main St.	6	Cast Iron	348	134	2.57 out of 5	\$442	153,779
Distribution Main	3390	P-826	WW	Main St.	10	Cast Iron	73	134	1.86 out of 5	\$442	32,193
Distribution Main	3470	P-931	WW	Main St.	8	Cast Iron	233	134	1.86 out of 5	\$442	102,912
Distribution Main	3526	P-1251	WW	Main St.	8	Cast Iron	839	84	1.72 out of 5	\$442	370,681
Distribution Main	3605	P-1033	WW	Main St.	8	Cast Iron	196	84	1.72 out of 5	\$442	86,415
Distribution Main	3606	P-1033	WW	Main St.	8	Cast Iron	155	84	1.72 out of 5	\$442	68,486
Distribution Main	3607	P-1030	WW	Main St.	8	Cast Iron	11	84	1.72 out of 5	\$442	5,014
Distribution Main	3608	P-1030	WW	Main St.	8	Cast Iron	41	84	1.72 out of 5	\$442	18,046
Distribution Main	3609	P-1031	WW	Main St.	8	Cast Iron	275	84	1.72 out of 5	\$442	121,628
Distribution Main	3610	P-1031	WW	Main St.	8	Cast Iron	51	84	1.72 out of 5	\$442	22,644
Distribution Main	3723	P-1501	WW	Main St.	8	Cast Iron	341	134	1.86 out of 5	\$442	150,564
Distribution Main	3724	P-1501	WW	Main St.	8	Cast Iron	7	134	1.86 out of 5	\$442	3,075
Distribution Main	3758	P-667	WW	Main St.	6	Cast Iron	270	134	2.57 out of 5	\$442	119,561
Distribution Main	3759	P-667	WW	Main St.	6	Cast Iron	92	134	2.57 out of 5	\$442	40,467
Distribution Main	3765	P-668	WW	Main St.	8	Cast Iron	30	84	1.72 out of 5	\$442	13,171
Distribution Main	3957	P-1110	WW	Main St.	8	Cast Iron	34	134	1.86 out of 5	\$442	15,174
Distribution Main	3967	P-651	WW	Main St.	6	Cast Iron	10	134	2.57 out of 5	\$442	4,272
Distribution Main	3977	P-641	WW	Main St.	8	Ductile Iron	169	0	0 out of 5	N/A	\$0
Distribution Main	3978	P-646	WW	Main St.	6	Cast Iron	91	134	2.57 out of 5	\$442	40,254
Distribution Main	3979	P-646	WW	Main St.	6	Cast Iron	443	134	2.57 out of 5	\$442	195,946
Distribution Main	3980	P-646	WW	Main St.	6	Cast Iron	33	134	2.57 out of 5	\$442	14,696
Distribution Main	3981		WW	Main St.	6	Unknown	18	UNK	0.71 out of 5	\$442	7,806
Distribution Main	3982		WW	Main St.	4	Unknown	42	UNK	1.42 out of 5	\$442	18,461
Distribution Main	4106	P-661	WW	Main St.	6	Cast Iron	123	134	2.57 out of 5	\$442	54,291
Distribution Main	4107	P-661	WW	Main St.	6	Cast Iron	72	134	2.57 out of 5	\$442	31,785
Distribution Main	4108	P-663	WW	Main St.	6	Cast Iron	131	134	2.57 out of 5	\$442	57,738
Distribution Main	4109	P-663	WW	Main St.	6	Cast Iron	14	134	2.57 out of 5	\$442	6,170
Distribution Main	4110	P-651	WW	Main St.	6	Cast Iron	18	134	2.57 out of 5	\$442	7,898
Distribution Main	4111	P-651	WW	Main St.	6	Cast Iron	138	134	2.57 out of 5	\$442	61,215
Distribution Main	4112	P-650	WW	Main St.	6	Cast Iron	238	134	2.57 out of 5	\$442	105,218
Distribution Main	4113	P-650	WW	Main St.	6	Cast Iron	340	134	2.57 out of 5	\$442	150,118
Distribution Main	4114	P-1481	WW	Main St.	8	Cast Iron	24	134	1.86 out of 5	\$442	10,591
Distribution Main	4115	P-1481	WW	Main St.	8	Cast Iron	10	134	1.86 out of 5	\$442	4,280
Distribution Main	4211		WW	Main St.	8	Cast Iron	3	134	1.86 out of 5	\$442	1,452
Distribution Main	4288	P-1337	WW	Main St.	8	Cast Iron	343	84	1.72 out of 5	\$442	151,444
Distribution Main	4297	P-1481	WW	Main St.	8	Cast Iron	18	134	1.86 out of 5	\$442	7,879
Distribution Main	4300		WW	Main St.	6	Unknown	128	UNK	0.71 out of 5	\$442	56,436
Distribution Main	4301	P-646	WW	Main St.	6	Unknown	21	UNK	0.71 out of 5	\$442	9,395
Distribution Main	4325		WW	Main St.	6	Unknown	59	UNK	0.71 out of 5	\$442	26,213

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4343	P-1137	WW	Main St.	8	Cast Iron	304	134	1.86 out of 5	\$442	134,461
Distribution Main	4344	P-1137	WW	Main St.	8	Cast Iron	422	134	1.86 out of 5	\$442	186,549
Distribution Main	4349	P-1112	WW	Main St.	8	Cast Iron	409	134	1.86 out of 5	\$442	180,756
Distribution Main	4350	P-1112	WW	Main St.	8	Cast Iron	23	134	1.86 out of 5	\$442	10,307
Distribution Main	4351	P-1119	WW	Main St.	8	Cast Iron	156	134	1.86 out of 5	\$442	68,891
Distribution Main	4352	P-1119	WW	Main St.	8	Cast Iron	283	134	1.86 out of 5	\$442	125,086
Distribution Main	4353	P-1119	WW	Main St.	8	Cast Iron	141	134	1.86 out of 5	\$442	62,224
Distribution Main	4354	P-1481	WW	Main St.	8	Cast Iron	344	134	1.86 out of 5	\$442	152,039
Distribution Main	4711	P-1137	WW	Main St.	8	Cast Iron	12	84	1.72 out of 5	\$442	5,362
Distribution Main	4712	P-1125	WW	Main St.	8	Cast Iron	35	134	1.86 out of 5	\$442	15,311
Distribution Main	5086	P-1119	WW	Main St.	8	Cast Iron	6	134	1.86 out of 5	\$442	2,549
Distribution Main	5087	P-1137	WW	Main St.	8	Cast Iron	138	134	1.86 out of 5	\$442	60,855
Distribution Main	5119	P-1137	WW	Main St.	8	Cast Iron	167	134	1.86 out of 5	\$442	73,600
Distribution Main	8137	P-1125	WW	Main St.	8	Cast Iron	117	134	1.86 out of 5	\$442	51,572
Distribution Main	8138	P-1116	WW	Main St.	8	Cast Iron	101	134	1.86 out of 5	\$442	44,747
Distribution Main	8139	P-1130	WW	Main St.	8	Cast Iron	75	134	1.86 out of 5	\$442	33,226
Distribution Main	8140	P-1130	WW	Main St.	8	Cast Iron	20	134	1.86 out of 5	\$442	9,024
Distribution Main	9354	P-1116	WW	Main St.	8	Ductile Iron	3	14	0 out of 5	N/A	\$0
Transmission Main	9355	P-1116	WW	Main St.	12	Ductile Iron	5	14	0 out of 5	N/A	\$0
Transmission Main	9356	P-1116	WW	Main St.	12	Ductile Iron	7	14	0 out of 5	N/A	\$0
Distribution Main	9357	P-1116	WW	Main St.	8	Ductile Iron	4	14	0 out of 5	N/A	\$0
Distribution Main	9533	P-1892	WW	Main St.	6	Cast Iron	30	134	2.57 out of 5	\$442	13,182
Distribution Main	9534	P-1895	WW	Main St.	6	Cast Iron	28	83	2.43 out of 5	\$442	12,484
Distribution Main	9535	P-1886	WW	Main St.	6	Cast Iron	67	134	2.57 out of 5	\$442	29,693
Distribution Main	9536	P-1886	WW	Main St.	6	Cast Iron	30	134	2.57 out of 5	\$442	13,361
Distribution Main	9588		WW	Main St.	8	Cast Iron	69	84	1.72 out of 5	\$442	30,282
Distribution Main	10356		WW	Main St.	6	Cast Iron	6	84	2.43 out of 5	\$442	2,573
Distribution Main	11055	P-1009	WW	Main St.	6	Cast Iron	35	134	2.57 out of 5	\$442	15,570
Distribution Main	11058	P-1007	WW	Main St.	10	Cast Iron	8	134	1.86 out of 5	\$442	3,681
Distribution Main	11245	P-1481	WW	Main St.	8	Cast Iron	2	134	1.86 out of 5	\$442	1,059
Distribution Main	11584	P-1039	WW	Main St.	6	Cast Iron	26	134	2.57 out of 5	\$442	11,579
Distribution Main	11585	P-1888	WW	Main St.	6	Cast Iron	14	134	2.57 out of 5	\$442	6,230
Distribution Main	12009	P-646	WW	Main St.	6	Cast Iron	100	134	2.57 out of 5	\$442	44,414
Distribution Main	12013	P-1030	WW	Main St.	8	Cast Iron	18	84	1.72 out of 5	\$442	8,151
Distribution Main	12016	P-1112	WW	Main St.	8	Cast Iron	163	134	1.86 out of 5	\$442	72,025
Distribution Main	12189		WW	Main St.	6	Cast Iron	68	134	2.57 out of 5	\$442	30,145
Distribution Main	12220	P-641	WW	Main St.	8	Cast Iron	65	84	1.72 out of 5	\$442	28,612
Distribution Main	12237	P-641	WW	Main St.	8	Cast Iron	49	84	1.72 out of 5	\$442	21,846
Distribution Main	3121	P-1168	WW	Main Street	8	Cast Iron	25	91	1.72 out of 5	\$442	10,885
Distribution Main	3891	P-1137	WW	Main Street	4	Cast Iron	7	132	3.29 out of 5	\$442	3,140
Transmission Main	4684	P-1170	WW	Main Street	12	Asbestos Cement	479	54	1.14 out of 5	\$442	211,874
Transmission Main	4685	P-1170	WW	Main Street	12	Asbestos Cement	522	54	1.14 out of 5	\$442	230,607
Transmission Main	4691	P-1170	WW	Main Street	12	Asbestos Cement	322	54	1.14 out of 5	\$442	142,126
Transmission Main	4692	P-1170	WW	Main Street	12	Asbestos Cement	68	54	1.14 out of 5	\$442	30,011

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4830	P-1166	WW	Main Street	8	Cast Iron	1,073	91	1.72 out of 5	\$442	474,396
Distribution Main	4831	P-1166	WW	Main Street	8	Cast Iron	379	91	1.72 out of 5	\$442	167,389
Transmission Main	4962	P-1170	WW	Main Street	12	Asbestos Cement	37	54	1.14 out of 5	\$442	16,217
Distribution Main	5116	P-1168	WW	Main Street	4	Cast Iron	500	132	3.29 out of 5	\$442	220,906
Distribution Main	5117	P-1168	WW	Main Street	4	Cast Iron	887	132	3.29 out of 5	\$442	391,853
Distribution Main	5118		WW	Main Street	4	Cast Iron	83	132	3.29 out of 5	\$442	36,648
Distribution Main	5120	P-1166	WW	Main Street	8	Cast Iron	36	91	1.72 out of 5	\$442	16,021
Transmission Main	11278	P-1170	WW	Main Street	12	Asbestos Cement	36	54	1.14 out of 5	\$442	15,731
Distribution Main	9252	P-1132	WW	Manchester St	8	Ductile Iron	161	13	0 out of 5	N/A	\$0
Distribution Main	9253	P-1132	WW	Manchester St	8	Ductile Iron	10	13	0 out of 5	N/A	\$0
Distribution Main	163		WW	Manchester St.	6	Asbestos Cement	24	134	2.29 out of 5	\$442	10,644
Transmission Main	166	P-1136	WW	Manchester St.	12	PVC	179	32	0.43 out of 5	\$442	79,258
Transmission Main	167	P-1136	WW	Manchester St.	12	PVC	249	32	0.43 out of 5	\$442	110,057
Distribution Main	1992		WW	Manchester St.	8	Ductile Iron	7	14	0 out of 5	N/A	\$0
Distribution Main	1993	P-1122	WW	Manchester St.	4	Cast Iron	237	134	3.29 out of 5	\$442	104,937
Distribution Main	4090	P-1121	WW	Manchester St.	4	Cast Iron	491	134	3.29 out of 5	\$442	216,915
Distribution Main	4091	P-1120	WW	Manchester St.	4	Cast Iron	242	134	3.29 out of 5	\$442	107,127
Distribution Main	4570		WW	Manchester St.	8	Cast Iron	249	134	1.86 out of 5	\$442	110,006
Distribution Main	9249		WW	Manchester St.	8	Cast Iron	78	134	1.86 out of 5	\$442	34,601
Distribution Main	9324		WW	Manchester St.	10	PVC	59	32	0.43 out of 5	\$442	26,283
Distribution Main	9359	P-1992	WW	Manchester St.	4	Ductile Iron	14	14	1.42 out of 5	N/A	\$0
Distribution Main	9360	P-1992	WW	Manchester St.	8	Ductile Iron	5	14	0 out of 5	N/A	\$0
Distribution Main	9361		WW	Manchester St.	6	Ductile Iron	12	14	0.71 out of 5	N/A	\$0
Distribution Main	11242	P-1121	WW	Manchester St.	4	Cast Iron	4	134	3.29 out of 5	\$442	1,653
Transmission Main	12055	P-1136	WW	Manchester St.	12	PVC	20	32	0.43 out of 5	\$442	8,939
Distribution Main	10271	P-1200	WW	Maple Av		Unknown	8	UNK	0 out of 5	N/A	\$0
Transmission Main	8979	P-1925	WW	Maple Ave	12	Ductile Iron	26	9	0 out of 5	N/A	\$0
Transmission Main	8980	P-1925	WW	Maple Ave	16	Ductile Iron	4	9	0 out of 5	N/A	\$0
Distribution Main	8981	P-1926	WW	Maple Ave	6	Ductile Iron	20	9	0.71 out of 5	N/A	\$0
Distribution Main	10341	P-1200	WW	Maple Ave	1.5	Copper	20	UNK	1.99 out of 5	\$442	9,044
Distribution Main	2398	P-822	WW	Maple Ave.	6	Cast Iron	19	134	2.57 out of 5	\$442	8,415
Distribution Main	2399	P-822	WW	Maple Ave.	6	Cast Iron	205	134	2.57 out of 5	\$442	90,558
Distribution Main	2947	P-1200	WW	Maple Ave.	6	Cast Iron	479	134	2.57 out of 5	\$442	211,587
Distribution Main	2948	P-823	WW	Maple Ave.	6	Cast Iron	371	134	2.57 out of 5	\$442	164,145
Distribution Main	2949	P-823	WW	Maple Ave.	6	Cast Iron	10	134	2.57 out of 5	\$442	4,552
Distribution Main	3345	P-822	WW	Maple Ave.	6	Cast Iron	44	134	2.57 out of 5	\$442	19,321
Distribution Main	3472	P-1200	WW	Maple Ave.	6	Cast Iron	136	134	2.57 out of 5	\$442	60,304
Distribution Main	3473	P-1200	WW	Maple Ave.	6	Cast Iron	114	134	2.57 out of 5	\$442	50,202
Distribution Main	11194	P-1200	WW	Maple Ave.	6	Cast Iron	4	134	2.57 out of 5	\$442	1,722
Distribution Main	11195	P-823	WW	Maple Ave.	6	Cast Iron	3	134	2.57 out of 5	\$442	1,286
Distribution Main	11220	P-1200	WW	Maple Ave.	6	Cast Iron	108	134	2.57 out of 5	\$442	47,631
Distribution Main	12014	P-823	WW	Maple Ave.	6	Cast Iron	245	134	2.57 out of 5	\$442	108,417
Distribution Main	12017	P-1200	WW	Maple Ave.	6	Cast Iron	109	134	2.57 out of 5	\$442	48,220
Distribution Main	1511	P-1204	WW	Maple St.	6	Cast Iron	202	89	2.43 out of 5	\$442	89,286

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2945	P-1202	WW	Maple St.	6	Cast Iron	395	134	2.57 out of 5	\$442	174,744
Distribution Main	2946	P-1202	WW	Maple St.	6	Cast Iron	43	134	2.57 out of 5	\$442	19,174
Distribution Main	3744	P-1204	WW	Maple St.	6	Cast Iron	397	89	2.43 out of 5	\$442	175,518
Distribution Main	3745	P-1204	WW	Maple St.	6	Cast Iron	52	89	2.43 out of 5	\$442	22,856
Distribution Main	12018	P-1202	WW	Maple St.	6	Cast Iron	277	134	2.57 out of 5	\$442	122,434
Distribution Main	3438	P-163	WW	Marco Dr.	8	Asbestos Cement	246	42	1.14 out of 5	\$442	108,900
Distribution Main	3869	P-174	WW	Marco Dr.	8	Asbestos Cement	190	42	1.14 out of 5	\$442	84,071
Distribution Main	5163	P-173	WW	Marco Dr.	8	Asbestos Cement	248	42	1.14 out of 5	\$442	109,782
Distribution Main	5164	P-168	WW	Marco Dr.	8	Asbestos Cement	136	42	1.14 out of 5	\$442	59,930
Distribution Main	5165	P-168	WW	Marco Dr.	8	Asbestos Cement	111	42	1.14 out of 5	\$442	49,264
Distribution Main	5166	P-158	WW	Marco Dr.	8	Asbestos Cement	148	42	1.14 out of 5	\$442	65,604
Distribution Main	5167	P-158	WW	Marco Dr.	8	Asbestos Cement	95	42	1.14 out of 5	\$442	41,912
Distribution Main	146	P-319	WW	Mark Fore Dr.	8	Asbestos Cement	834	39	1 out of 5	\$442	368,753
Distribution Main	147	P-319	WW	Mark Fore Dr.	8	Asbestos Cement	35	39	1 out of 5	\$442	15,441
Distribution Main	10298	P-240	WW	Market St	8	Ductile Iron	225	5	0 out of 5	N/A	\$0
Distribution Main	10299	P-240	WW	Market St	8	Ductile Iron	339	5	0 out of 5	N/A	\$0
Distribution Main	11996	P-240	WW	Market St	8	Ductile Iron	313	5	0 out of 5	N/A	\$0
Distribution Main	10618	P-10026	WW	Mary Av	8	Ductile Iron	212	2	0 out of 5	N/A	\$0
Distribution Main	10619	P-401	WW	Mary Av	8	Ductile Iron	404	2	0 out of 5	N/A	\$0
Distribution Main	11691	P-403	WW	Mary Av	8	Ductile Iron	171	2	0 out of 5	N/A	\$0
Distribution Main	8924	P-140	WW	Maryland Dr	8	Ductile Iron	26	9	0 out of 5	N/A	\$0
Distribution Main	8925	P-140	WW	Maryland Dr	8	Ductile Iron	464	9	0 out of 5	N/A	\$0
Distribution Main	3587	P-1723	WW	Maryland Dr.	8	Ductile Iron	20	15	0 out of 5	N/A	\$0
Distribution Main	3588	P-1723	WW	Maryland Dr.	8	Ductile Iron	4	15	0 out of 5	N/A	\$0
Distribution Main	10623	P-398	WW	Mason St	8	Ductile Iron	248	2	0 out of 5	N/A	\$0
Distribution Main	10885	P-404	WW	Mason St	8	Ductile Iron	248	2	0 out of 5	N/A	\$0
Distribution Main	10886	P-406	WW	Mason St	8	Ductile Iron	186	2	0 out of 5	N/A	\$0
Distribution Main	10887	P-400	WW	Mason St	8	Ductile Iron	18	2	0 out of 5	N/A	\$0
Distribution Main	10888	P-400	WW	Mason St	8	Ductile Iron	213	2	0 out of 5	N/A	\$0
Distribution Main	12147	P-400	WW	Mason St	8	Ductile Iron	10	2	0 out of 5	N/A	\$0
Distribution Main	8010	P-554	WW	Matteson Ave.	8	Cast Iron	203	119	1.86 out of 5	\$442	89,903
Distribution Main	8011	P-574	WW	Matteson Ave.	8	Ductile Iron	41	14	0 out of 5	N/A	\$0
Distribution Main	8016	P-1604	WW	Matteson Ave.	8	Cast Iron	435	119	1.86 out of 5	\$442	192,268
Distribution Main	8017	P-1604	WW	Matteson Ave.	8	Ductile Iron	18	14	0 out of 5	N/A	\$0
Distribution Main	8018	P-553	WW	Matteson Ave.	8	Ductile Iron	21	14	0 out of 5	N/A	\$0
Distribution Main	8019	P-553	WW	Matteson Ave.	8	Ductile Iron	3	14	0 out of 5	N/A	\$0
Distribution Main	8020	P-553	WW	Matteson Ave.	8	Cast Iron	240	119	1.86 out of 5	\$442	105,951
Distribution Main	8152	P-1604	WW	Matteson Ave.	8	Cast Iron	43	119	1.86 out of 5	\$442	19,169
Distribution Main	8169	P-553	WW	Matteson Ave.	8	Cast Iron	76	119	1.86 out of 5	\$442	33,378
Distribution Main	8920	P-1727	WW	Maywood Dr.	8	Ductile Iron	14	15	0 out of 5	N/A	\$0
Distribution Main	9209	P-1053	WW	Mcelroy St	8	Ductile Iron	31	8	0 out of 5	N/A	\$0
Distribution Main	9210	P-1053	WW	Mcelroy St	8	Ductile Iron	331	8	0 out of 5	N/A	\$0
Distribution Main	3238	P-740	WW	Mcglynn St.	1.5	Copper	461	78	3.14 out of 5	\$442	203,695
Distribution Main	1776	P-749	WW	Mcniff St.	6	Cast Iron	132	79	2.28 out of 5	\$442	58,432

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3239	P-742	WW	Mcniff St.	4	Cast Iron	61	79	3 out of 5	\$442	27,076
Distribution Main	3247	P-743	WW	Mcniff St.	6	Cast Iron	313	79	2.28 out of 5	\$442	138,554
Distribution Main	3248	P-743	WW	Mcniff St.	6	Cast Iron	24	79	2.28 out of 5	\$442	10,799
Distribution Main	3256	P-751	WW	Mcniff St.	6	Cast Iron	154	79	3 out of 5	\$442	68,240
Distribution Main	3799	P-742	WW	Mcniff St.	4	Cast Iron	15	79	3 out of 5	\$442	6,713
Distribution Main	10035	P-247	WW	Mcteers Ct	8	Ductile Iron	372	6	0 out of 5	N/A	\$0
Distribution Main	4214	P-481	WW	Meadow Dr.	6	Asbestos Cement	655	63	2 out of 5	\$442	289,399
Distribution Main	1773	P-845	WW	Meadowchase Ln.	8	PVC	330	31	0.43 out of 5	\$442	145,892
Distribution Main	2424	P-6	WW	Medeival Way	8	Ductile Iron	241	28	0.14 out of 5	\$442	106,395
Distribution Main	2431	P-13	WW	Medeival Way	8	Ductile Iron	323	28	0.14 out of 5	\$442	142,938
Distribution Main	2432	P-13	WW	Medeival Way	8	Ductile Iron	212	28	0.14 out of 5	\$442	93,897
Distribution Main	2443	P-5	WW	Medeival Way	8	Ductile Iron	442	28	0.14 out of 5	\$442	195,439
Distribution Main	4449	P-20	WW	Medeival Way	8	Ductile Iron	259	28	0.14 out of 5	\$442	114,566
Distribution Main	4450	P-20	WW	Medeival Way	8	Ductile Iron	33	28	0.14 out of 5	\$442	14,384
Distribution Main	4554	P-14	WW	Medeival Way	8	Ductile Iron	248	28	0.14 out of 5	\$442	109,671
Distribution Main	4555	P-14	WW	Medeival Way	8	Ductile Iron	403	28	0.14 out of 5	\$442	178,111
Distribution Main	1779	P-838	WW	Medinah Dr.	8	Ductile Iron	214	18	0 out of 5	N/A	\$0
Distribution Main	1780	P-838	WW	Medinah Dr.	8	Ductile Iron	240	18	0 out of 5	N/A	\$0
Distribution Main	9417	P-838	WW	Medinah Dr.	8	Ductile Iron	4	18	0 out of 5	N/A	\$0
Transmission Main	2318		WW	Meggan Ct.	12	Ductile Iron	23	22	0.14 out of 5	N/A	\$0
Transmission Main	2338	P-1419	WW	Meggan Ct.	12	PVC	13	32	0.43 out of 5	\$442	5,739
Transmission Main	4755	P-1187	WW	Meggan Ct.	12	PVC	308	32	0.43 out of 5	\$442	136,190
Transmission Main	4756	P-1420	WW	Meggan Ct.	12	PVC	308	32	0.43 out of 5	\$442	136,019
Transmission Main	4757	P-1420	WW	Meggan Ct.	12	PVC	25	32	0.43 out of 5	\$442	10,949
Transmission Main	10263	P-1419	WW	Meggan Ct.	12	PVC	3	32	0.43 out of 5	\$442	1,134
Transmission Main	11167	P-1419	WW	Meggan Ct.	12	PVC	8	32	0.43 out of 5	\$442	3,378
Distribution Main	8418	P-1807	WW	Mello St	8	Ductile Iron	9	10	0 out of 5	N/A	\$0
Distribution Main	8419	P-1807	WW	Mello St	8	Ductile Iron	9	10	0 out of 5	N/A	\$0
Distribution Main	1526	P-943	WW	Mello St.	6	Asbestos Cement	66	68	2 out of 5	\$442	29,250
Distribution Main	1555	P-942	WW	Mello St.	6	Asbestos Cement	164	68	2 out of 5	\$442	72,509
Distribution Main	1556	P-944	WW	Mello St.	6	Asbestos Cement	325	68	2 out of 5	\$442	143,504
Distribution Main	1557	P-944	WW	Mello St.	6	Asbestos Cement	192	68	2 out of 5	\$442	84,931
Distribution Main	3518	P-1808	WW	Mello Street	6	Unknown	37	68	1.14 out of 5	\$442	16,406
Distribution Main	9423	P-1808	WW	Mello Street	6	Unknown	10	68	1.14 out of 5	\$442	4,606
Distribution Main	9454	P-1814	WW	Mello Street	1	Unknown	249	68	1.86 out of 5	\$442	110,277
Distribution Main	8497	P-1800	WW	Melrose St	6	Ductile Iron	8	10	0.71 out of 5	N/A	\$0
Distribution Main	9710	P-1801	WW	Melrose St	8	Ductile Iron	6	10	0 out of 5	N/A	\$0
Distribution Main	9711	P-1801	WW	Melrose St	8	Ductile Iron	20	10	0 out of 5	N/A	\$0
Distribution Main	483	P-1799	WW	Melrose St.	6	Cast Iron	12	81	2.43 out of 5	\$442	5,270
Distribution Main	1538	P-959	WW	Melrose St.	6	Cast Iron	270	81	2.43 out of 5	\$442	119,172
Distribution Main	1539	P-959	WW	Melrose St.	6	Cast Iron	472	81	2.43 out of 5	\$442	208,723
Distribution Main	1558	P-958	WW	Melrose St.	6	Cast Iron	54	81	2.43 out of 5	\$442	24,006
Distribution Main	10605		WW	Miami St	8	Ductile Iron	143	2	0 out of 5	N/A	\$0
Distribution Main	10606	P-410	WW	Miami St	8	Ductile Iron	247	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3567	P-107	WW	Michael St.	6	Asbestos Cement	240	48	1.85 out of 5	\$442	106,064
Distribution Main	3570	P-108	WW	Michael St.	6	Asbestos Cement	232	48	1.85 out of 5	\$442	102,325
Distribution Main	3271	P-752	WW	Middle St.	2	Galvanized Iron	299	86	3.43 out of 5	\$442	132,349
Distribution Main	4653	P-165	WW	Midlands Dr.	8	Asbestos Cement	423	42	1.14 out of 5	\$442	186,814
Distribution Main	8933	P-1738	WW	Midway Dr	8	Ductile Iron	15	9	0 out of 5	N/A	\$0
Distribution Main	8940	P-1738	WW	Midway Dr	6	Ductile Iron	4	9	0.71 out of 5	N/A	\$0
Distribution Main	8944	P-191	WW	Midway Dr	8	Ductile Iron	4	9	0 out of 5	N/A	\$0
Distribution Main	8945	P-191	WW	Midway Dr	6	Ductile Iron	7	9	0.71 out of 5	N/A	\$0
Distribution Main	9396	P-1738	WW	Midway Dr	8	Ductile Iron	17	9	0 out of 5	N/A	\$0
Distribution Main	4523	P-1738	WW	Midway Dr.	6	Asbestos Cement	358	67	2 out of 5	\$442	158,035
Distribution Main	127	P-677	WW	Mill St.	4	Cast Iron	265	134	3.29 out of 5	\$442	117,070
Distribution Main	1280	P-8130	WW	Mill St.	6	Cast Iron	295	119	2.57 out of 5	\$442	130,184
Distribution Main	1281	P-8130	WW	Mill St.	6	Cast Iron	226	119	2.57 out of 5	\$442	99,990
Distribution Main	4283	P-676	WW	Mill St.	4	Cast Iron	438	134	3.29 out of 5	\$442	193,719
Distribution Main	4284	P-676	WW	Mill St.	4	Cast Iron	27	134	3.29 out of 5	\$442	11,783
Distribution Main	8412	P-1826	WW	Miller Dr	8	Ductile Iron	16	10	0 out of 5	N/A	\$0
Distribution Main	8482	P-1827	WW	Miller Dr	6	Ductile Iron	10	10	0.71 out of 5	N/A	\$0
Distribution Main	3691	P-969	WW	Miller Dr.	6	Asbestos Cement	348	64	2 out of 5	\$442	153,715
Distribution Main	3692	P-969	WW	Miller Dr.	6	Asbestos Cement	385	64	2 out of 5	\$442	170,276
Distribution Main	4447	P-1380	WW	Misty Oak Ct.	6	Ductile Iron	137	28	0.85 out of 5	\$442	60,740
Distribution Main	1824	P-509	WW	Monterey Dr.	8	Asbestos Cement	403	56	1.14 out of 5	\$442	177,990
Distribution Main	1825	P-509	WW	Monterey Dr.	8	Asbestos Cement	940	56	1.14 out of 5	\$442	415,435
Distribution Main	3436	P-505	WW	Monterey Dr.	8	Asbestos Cement	66	56	1.14 out of 5	\$442	29,358
Distribution Main	3437	P-505	WW	Monterey Dr.	8	Asbestos Cement	202	56	1.14 out of 5	\$442	89,480
Distribution Main	3867	P-503	WW	Monterey Dr.	8	Asbestos Cement	236	56	1.14 out of 5	\$442	104,230
Distribution Main	3868	P-508	WW	Monterey Dr.	8	Asbestos Cement	234	56	1.14 out of 5	\$442	103,598
Distribution Main	4120	P-506	WW	Monterey Dr.	8	Asbestos Cement	86	56	1.14 out of 5	\$442	37,816
Distribution Main	4121	P-506	WW	Monterey Dr.	8	Asbestos Cement	155	56	1.14 out of 5	\$442	68,415
Distribution Main	4126	P-500	WW	Monterey Dr.	8	Asbestos Cement	5	56	1.14 out of 5	\$442	2,075
Distribution Main	4603	P-500	WW	Monterey Dr.	8	Asbestos Cement	563	56	1.14 out of 5	\$442	248,747
Distribution Main	4604	P-500	WW	Monterey Dr.	8	Asbestos Cement	73	56	1.14 out of 5	\$442	32,321
Distribution Main	1155	P-302	WW	Moran St.	8	Asbestos Cement	20	52	1.14 out of 5	\$442	9,057
Distribution Main	1156	P-302	WW	Moran St.	8	Asbestos Cement	224	52	1.14 out of 5	\$442	98,881
Distribution Main	1583	P-586	WW	Moretti Dr.	8	Ductile Iron	90	14	0 out of 5	N/A	\$0
Distribution Main	8150	P-586	WW	Moretti Dr.	8	Ductile Iron	225	14	0 out of 5	N/A	\$0
Distribution Main	2503	P-318	WW	Morningside Dr.	8	Asbestos Cement	25	41	1.14 out of 5	\$442	11,038
Distribution Main	2504	P-318	WW	Morningside Dr.	8	Asbestos Cement	773	41	1.85 out of 5	\$442	341,566
Distribution Main	4014	P-323	WW	Morningside Dr.	8	Asbestos Cement	296	41	1.14 out of 5	\$442	130,856
Distribution Main	5188	P-308	WW	Morningside Dr.	8	Asbestos Cement	16	41	1.14 out of 5	\$442	7,245
Distribution Main	5198	P-308	WW	Morningside Dr.	8	Asbestos Cement	11	41	1.14 out of 5	\$442	4,990
Distribution Main	5199	P-308	WW	Morningside Dr.	8	Asbestos Cement	293	41	1.14 out of 5	\$442	129,321
Distribution Main	8005	P-583	WW	Morris St.	6	Ductile Iron	19	14	0.71 out of 5	N/A	\$0
Distribution Main	8006	P-583	WW	Morris St.	6	Asbestos Cement	601	71	2 out of 5	\$442	265,747
Distribution Main	9622	P-1382	WW	Morris St.	8	Ductile Iron	225	13	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	9623	P-1382	WW	Morris St.	6	Ductile Iron	2	13	0.71 out of 5	N/A	\$0
Distribution Main	10115	P-585	WW	Morris St.	8	Ductile Iron	6	14	0 out of 5	N/A	\$0
Distribution Main	3124	P-10030	WW	Mosalyk Street	1	Copper	223	47	2.28 out of 5	\$442	98,716
Distribution Main	145	P-314	WW	Musket Rd.	8	Asbestos Cement	703	39	1 out of 5	\$442	310,579
Distribution Main	2501	P-310	WW	Musket Rd.	8	Asbestos Cement	38	39	1 out of 5	\$442	16,622
Distribution Main	2502	P-310	WW	Musket Rd.	8	Asbestos Cement	220	39	1 out of 5	\$442	97,399
Distribution Main	806	P-417	WW	Myron St.	6	Asbestos Cement	253	43	1.85 out of 5	\$442	111,960
Distribution Main	807	P-417	WW	Myron St.	6	Asbestos Cement	338	43	1.85 out of 5	\$442	149,180
Distribution Main	4444	P-417	WW	Myron St.	6	Asbestos Cement	6	43	1.85 out of 5	\$442	2,543
Distribution Main	1157	P-299	WW	Napolean St.	6	Asbestos Cement	292	52	1.85 out of 5	\$442	129,100
Distribution Main	1158	P-299	WW	Napolean St.	6	Asbestos Cement	62	52	1.85 out of 5	\$442	27,421
Distribution Main	643	P-512	WW	Narragansett Ave.	8	Ductile Iron	97	18	0 out of 5	N/A	\$0
Distribution Main	4663	P-513	WW	Narragansett Ave.	8	Ductile Iron	322	18	0 out of 5	N/A	\$0
Distribution Main	4664	P-513	WW	Narragansett Ave.	8	Ductile Iron	99	18	0 out of 5	N/A	\$0
Distribution Main	4673	P-512	WW	Narragansett Ave.	8	Ductile Iron	843	18	0 out of 5	N/A	\$0
Distribution Main	3502	P-1837	WW	Navarre St	6	Cast Iron	173	84	2.43 out of 5	\$442	76,642
Distribution Main	3503	P-1837	WW	Navarre St	6	Cast Iron	214	84	2.43 out of 5	\$442	94,515
Distribution Main	8405	P-1835	WW	Navarre St	8	Ductile Iron	19	10	0 out of 5	N/A	\$0
Distribution Main	8473	P-1836	WW	Navarre St	6	Ductile Iron	17	10	0.71 out of 5	N/A	\$0
Distribution Main	9429	P-1837	WW	Navarre St	6	Asbestos Cement	290	84	2.14 out of 5	\$442	128,227
Distribution Main	915	P-1082	WW	Nestor St.	6	Cast Iron	11	134	2.57 out of 5	\$442	4,988
Distribution Main	916		WW	Nestor St.	2	Galvanized Iron	143	134	3.57 out of 5	\$442	63,413
Distribution Main	4714	P-1083	WW	Nestor St.	6	Cast Iron	282	134	2.57 out of 5	\$442	124,747
Distribution Main	4715	P-1083	WW	Nestor St.	6	Cast Iron	20	134	2.57 out of 5	\$442	8,811
Distribution Main	4717	P-1083	WW	Nestor St.	6	Cast Iron	150	134	2.57 out of 5	\$442	66,081
Distribution Main	4718		WW	Nestor St.	2	Galvanized Iron	145	UNK	2.85 out of 5	\$442	64,057
Distribution Main	5088		WW	Nestor St.	2	Galvanized Iron	10	134	3.57 out of 5	\$442	4,370
Distribution Main	11262	P-1083	WW	Nestor St.	6	Cast Iron	135	134	2.57 out of 5	\$442	59,450
Distribution Main	10357		WW	New London Av	8	PVC	60	UNK	0.28 out of 5	\$442	26,475
Transmission Main	10671	P-371	WW	New London Av	12	Ductile Iron	459	2	0 out of 5	N/A	\$0
Transmission Main	10672	P-1104	WW	New London Av	12	Ductile Iron	396	2	0 out of 5	N/A	\$0
Transmission Main	10673	P-1110	WW	New London Av	12	Ductile Iron	16	2	0 out of 5	N/A	\$0
Transmission Main	10674	P-370	WW	New London Av	12	Ductile Iron	65	2	0 out of 5	N/A	\$0
Transmission Main	10765	P-10060	WW	New London Av	12	Ductile Iron	355	0	0 out of 5	N/A	\$0
Transmission Main	10766	P-370	WW	New London Av	12	Ductile Iron	11	0	0 out of 5	N/A	\$0
Transmission Main	10767	P-370	WW	New London Av	12	Ductile Iron	338	2	0 out of 5	N/A	\$0
Transmission Main	10770	P-1308	WW	New London Av	12	Ductile Iron	433	20	0 out of 5	N/A	\$0
Transmission Main	10771	P-332	WW	New London Av	12	Ductile Iron	566	0	0 out of 5	N/A	\$0
Transmission Main	10891	P-645	WW	New London Av	12	Ductile Iron	10	0	0 out of 5	N/A	\$0
Transmission Main	11700	P-372	WW	New London Av	12	Ductile Iron	64	2	0 out of 5	N/A	\$0
Transmission Main	11703	P-372	WW	New London Av	12	Ductile Iron	254	2	0 out of 5	N/A	\$0
Transmission Main	11704	P-1105	WW	New London Av	12	Ductile Iron	221	2	0 out of 5	N/A	\$0
Transmission Main	11705	P-1103	WW	New London Av	12	Ductile Iron	29	2	0 out of 5	N/A	\$0
Transmission Main	11720	P-10060	WW	New London Av	12	Ductile Iron	423	0	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11721	P-10062	WW	New London Av	12	Ductile Iron	133	0	0 out of 5	N/A	\$0
Transmission Main	11722	P-10062	WW	New London Av	12	Ductile Iron	527	0	0 out of 5	N/A	\$0
Transmission Main	11723	P-1312	WW	New London Av	12	Ductile Iron	226	20	0 out of 5	N/A	\$0
Transmission Main	11749	P-332	WW	New London Av	12	Ductile Iron	170	0	0 out of 5	N/A	\$0
Transmission Main	11913	P-10062	WW	New London Av	12	Ductile Iron	38	0	0 out of 5	N/A	\$0
Transmission Main	11919	P-332	WW	New London Av	12	Ductile Iron	48	0	0 out of 5	N/A	\$0
Transmission Main	12025	P-1105	WW	New London Av	12	Ductile Iron	12	2	0 out of 5	N/A	\$0
Transmission Main	12145	P-332	WW	New London Av	12	Ductile Iron	410	0	0 out of 5	N/A	\$0
Transmission Main	12157	P-1312	WW	New London Av	12	Ductile Iron	26	20	0 out of 5	N/A	\$0
Transmission Main	12166	P-370	WW	New London Av	12	Ductile Iron	37	0	0 out of 5	N/A	\$0
Transmission Main	12169	P-1308	WW	New London Av	12	Ductile Iron	13	20	0 out of 5	N/A	\$0
Transmission Main	12178	P-332	WW	New London Av	12	Ductile Iron	55	0	0 out of 5	N/A	\$0
Transmission Main	12190	P-332	WW	New London Av	12	Ductile Iron	9	0	0 out of 5	N/A	\$0
Distribution Main	395	P-10055	WW	New London Ave.	8	Unknown	12	UNK	0 out of 5	N/A	\$0
Distribution Main	955	P-10054	WW	New London Ave.	8	Asbestos Cement	373	47	1.14 out of 5	\$442	164,656
Distribution Main	1043	P-10057	WW	New London Ave.	8	Asbestos Cement	355	UNK	0.85 out of 5	\$442	156,836
Distribution Main	1044	P-10054	WW	New London Ave.	8	Asbestos Cement	23	47	1.14 out of 5	\$442	10,017
Distribution Main	1145		WW	New London Ave.	6	Ductile Iron	38	UNK	0.71 out of 5	\$442	16,695
Distribution Main	1413		WW	New London Ave.	6	Unknown	449	UNK	0.71 out of 5	\$442	198,365
Distribution Main	1414	P-10058	WW	New London Ave.	8	Unknown	48	UNK	0 out of 5	N/A	\$0
Distribution Main	1737	P-326	WW	New London Ave.	8	Asbestos Cement	651	47	1.14 out of 5	\$442	287,778
Distribution Main	4011	P-326	WW	New London Ave.	8	Asbestos Cement	43	47	1.14 out of 5	\$442	18,888
Distribution Main	4012	P-324	WW	New London Ave.	8	Asbestos Cement	835	47	1.14 out of 5	\$442	369,204
Distribution Main	4013	P-324	WW	New London Ave.	8	Asbestos Cement	244	47	1.14 out of 5	\$442	108,013
Distribution Main	4016	P-328	WW	New London Ave.	8	Asbestos Cement	68	47	1.14 out of 5	\$442	30,025
Distribution Main	4017	P-324	WW	New London Ave.	8	Asbestos Cement	25	47	1.14 out of 5	\$442	11,248
Distribution Main	4018	P-328	WW	New London Ave.	8	Asbestos Cement	406	47	1.14 out of 5	\$442	179,254
Distribution Main	4341		WW	New London Ave.	4	Unknown	65	UNK	1.42 out of 5	\$442	28,594
Distribution Main	4342		WW	New London Ave.	6	Unknown	55	UNK	0.71 out of 5	\$442	24,210
Distribution Main	5194		WW	New London Ave.	8	Asbestos Cement	10	47	1.14 out of 5	\$442	4,345
Distribution Main	5195	P-324	WW	New London Ave.	8	Asbestos Cement	11	47	1.14 out of 5	\$442	4,791
Transmission Main	628	P-1163	WW	New London Tpk.	12	Asbestos Cement	183	60	1.14 out of 5	\$442	80,875
Transmission Main	927	P-26	WW	New London Tpk.	12	Ductile Iron	17	22	0.14 out of 5	N/A	\$0
Transmission Main	1135	P-1171	WW	New London Tpk.	12	Asbestos Cement	610	41	1.14 out of 5	\$442	269,783
Transmission Main	2353	P-113	WW	New London Tpk.	12	Asbestos Cement	8	60	1.14 out of 5	\$442	3,693
Transmission Main	3087	P-112	WW	New London Tpk.	12	Asbestos Cement	672	60	1.14 out of 5	\$442	296,819
Transmission Main	3088	P-112	WW	New London Tpk.	12	Asbestos Cement	85	60	1.14 out of 5	\$442	37,626
Transmission Main	3089	P-1171	WW	New London Tpk.	12	Asbestos Cement	174	41	1.14 out of 5	\$442	76,959
Transmission Main	3276	P-1995	WW	New London Tpk.	12	Asbestos Cement	309	60	1.14 out of 5	\$442	136,491
Transmission Main	3277	P-1995	WW	New London Tpk.	12	Asbestos Cement	310	60	1.14 out of 5	\$442	136,917
Distribution Main	3897		WW	New London Tpk.	8	Unknown	12	UNK	0 out of 5	N/A	\$0
Transmission Main	4719	P-1993	WW	New London Tpk.	12	Asbestos Cement	239	60	1.14 out of 5	\$442	105,483
Transmission Main	4720	P-1993	WW	New London Tpk.	12	Asbestos Cement	474	60	1.14 out of 5	\$442	209,350
Transmission Main	4722	P-1510	WW	New London Tpk.	12	Asbestos Cement	117	60	1.14 out of 5	\$442	51,680

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	4729	P-26	WW	New London Tpk.	12	Asbestos Cement	307	59	1.14 out of 5	\$442	135,511
Distribution Main	4832		WW	New London Tpk.	8	Unknown	9	UNK	0 out of 5	N/A	\$0
Transmission Main	4958	P-114	WW	New London Tpk.	12	Asbestos Cement	576	60	1.14 out of 5	\$442	254,755
Distribution Main	5121	P-1164	WW	New London Tpk.	8	Cast Iron	34	91	1.72 out of 5	\$442	14,839
Distribution Main	5122	P-1164	WW	New London Tpk.	8	Cast Iron	505	91	1.72 out of 5	\$442	223,231
Transmission Main	5123	P-1162	WW	New London Tpk.	12	Asbestos Cement	65	41	1.14 out of 5	\$442	28,543
Transmission Main	11081	P-1163	WW	New London Tpk.	12	Asbestos Cement	13	60	1.14 out of 5	\$442	5,736
Transmission Main	11095	P-26	WW	New London Tpk.	12	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Transmission Main	11169	P-113	WW	New London Tpk.	12	Asbestos Cement	4	60	1.14 out of 5	\$442	1,603
Distribution Main	12207	P-1164	WW	New London Tpk.	8	Cast Iron	34	91	1.72 out of 5	\$442	15,092
Distribution Main	859	P-301	WW	Newell St.	6	Asbestos Cement	774	39	1.71 out of 5	\$442	341,926
Distribution Main	862	P-291	WW	Newell St.	6	Ductile Iron	247	26	0.85 out of 5	\$442	109,011
Distribution Main	2151	P-286	WW	Newell St.	6	Ductile Iron	195	26	0.85 out of 5	\$442	86,261
Distribution Main	9903	P-303	WW	Newell St.	8	Asbestos Cement	193	52	1.14 out of 5	\$442	85,440
Distribution Main	10924	P-294	WW	Newell St.	6	Ductile Iron	207	26	0.85 out of 5	\$442	91,351
Distribution Main	10925	P-290	WW	Newell St.	6	Ductile Iron	193	26	0.85 out of 5	\$442	85,328
Distribution Main	10926	P-290	WW	Newell St.	6	Ductile Iron	22	26	0.85 out of 5	\$442	9,618
Distribution Main	8414	P-1321	WW	Newlight St	8	Ductile Iron	23	10	0 out of 5	N/A	\$0
Distribution Main	8422	P-1824	WW	Newlight St	8	Ductile Iron	10	10	0 out of 5	N/A	\$0
Distribution Main	8423	P-1824	WW	Newlight St	8	Ductile Iron	3	10	0 out of 5	N/A	\$0
Distribution Main	8488	P-1822	WW	Newlight St	6	Ductile Iron	10	10	0.71 out of 5	N/A	\$0
Distribution Main	3693	P-1362	WW	Newlight St.	6	Asbestos Cement	618	53	1.85 out of 5	\$442	273,019
Distribution Main	3330	P-1878	WW	Nichols Ct	1	Copper	277	65	2.43 out of 5	\$442	122,475
Distribution Main	813	P-1180	WW	Nicole Dr.	8	Asbestos Cement	237	39	1 out of 5	\$442	104,832
Distribution Main	4760	P-1181	WW	Nicole Dr.	8	Asbestos Cement	751	39	1 out of 5	\$442	332,137
Distribution Main	4761	P-1181	WW	Nicole Dr.	8	Asbestos Cement	148	39	1 out of 5	\$442	65,573
Transmission Main	7496	P-266	WW	Nobile St.	12	Ductile Iron	362	25	0.14 out of 5	N/A	\$0
Transmission Main	7497	P-266	WW	Nobile St.	12	Ductile Iron	6	25	0.14 out of 5	N/A	\$0
Transmission Main	11380	P-266	WW	Nobile St.	12	Ductile Iron	6	25	0.14 out of 5	N/A	\$0
Distribution Main	4286	P-685	WW	Nolan St.	2	PVC	408	41	2 out of 5	\$442	180,258
Distribution Main	4671	P-446	WW	North Gate Dr.	6	Asbestos Cement	759	44	1.85 out of 5	\$442	335,279
Transmission Main	8385	P-1242	WW	North Pleasant St	12	Ductile Iron	243	10	0 out of 5	N/A	\$0
Transmission Main	8392	P-1242	WW	North Pleasant St	12	Ductile Iron	111	10	0 out of 5	N/A	\$0
Transmission Main	8393	P-1242	WW	North Pleasant St	12	Ductile Iron	225	10	0 out of 5	N/A	\$0
Distribution Main	8448	P-1628	WW	North Pleasant St	6	Ductile Iron	17	10	0.71 out of 5	N/A	\$0
Transmission Main	8449	P-1245	WW	North Pleasant St	12	Ductile Iron	391	10	0 out of 5	N/A	\$0
Transmission Main	8451	P-1658	WW	North Pleasant St	12	Ductile Iron	16	10	0 out of 5	N/A	\$0
Transmission Main	8452	P-1658	WW	North Pleasant St	12	Ductile Iron	82	10	0 out of 5	N/A	\$0
Transmission Main	8453	P-1658	WW	North Pleasant St	12	Ductile Iron	173	10	0 out of 5	N/A	\$0
Transmission Main	8454	P-1911	WW	North Pleasant St	12	Ductile Iron	84	10	0 out of 5	N/A	\$0
Transmission Main	8455	P-1911	WW	North Pleasant St	12	Ductile Iron	31	10	0 out of 5	N/A	\$0
Transmission Main	11468	P-1658	WW	North Pleasant St	12	Ductile Iron	69	10	0 out of 5	N/A	\$0
Transmission Main	11469	P-1242	WW	North Pleasant St	12	Ductile Iron	3	10	0 out of 5	N/A	\$0
Distribution Main	1203	P-1246	WW	North Pleasant St.	6	Asbestos Cement	610	44	1.85 out of 5	\$442	269,701

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	1204	P-1246	WW	North Pleasant St.	6	Asbestos Cement	21	44	1.85 out of 5	\$442	9,074
Distribution Main	8380	P-1628	WW	North Pleasant St.	6	Asbestos Cement	37	44	1.85 out of 5	\$442	16,559
Transmission Main	470	P-1277	WW	Nottingham Dr.	16	Ductile Iron	572	19	0 out of 5	N/A	\$0
Distribution Main	475	P-1441	WW	Nottingham Dr.	8	Asbestos Cement	424	46	1.14 out of 5	\$442	187,395
Transmission Main	985	P-1277	WW	Nottingham Dr.	16	Ductile Iron	4	19	0 out of 5	N/A	\$0
Distribution Main	1079		WW	Nottingham Dr.	8	Ductile Iron	7	22	0.14 out of 5	N/A	\$0
Distribution Main	1831	P-10004	WW	Nottingham Dr.	8	Asbestos Cement	167	46	1.14 out of 5	\$442	73,961
Distribution Main	2354	P-63	WW	Nottingham Dr.	8	Asbestos Cement	513	46	1.14 out of 5	\$442	226,953
Distribution Main	2355	P-63	WW	Nottingham Dr.	8	Asbestos Cement	27	46	1.14 out of 5	\$442	11,926
Distribution Main	3556	P-10001	WW	Nottingham Dr.	8	Asbestos Cement	159	46	1.14 out of 5	\$442	70,415
Distribution Main	3557	P-10002	WW	Nottingham Dr.	6	Asbestos Cement	97	46	1.85 out of 5	\$442	42,657
Distribution Main	3563	P-10003	WW	Nottingham Dr.	8	Asbestos Cement	6	46	1.14 out of 5	\$442	2,451
Distribution Main	4630	P-64	WW	Nottingham Dr.	8	Asbestos Cement	355	46	1.14 out of 5	\$442	156,871
Distribution Main	4637	P-10003	WW	Nottingham Dr.	8	Asbestos Cement	435	46	1.14 out of 5	\$442	192,419
Distribution Main	4638	P-10003	WW	Nottingham Dr.	8	Asbestos Cement	120	46	1.14 out of 5	\$442	53,092
Distribution Main	4639	P-10001	WW	Nottingham Dr.	8	Asbestos Cement	94	46	1.14 out of 5	\$442	41,351
Distribution Main	4640	P-10001	WW	Nottingham Dr.	8	Asbestos Cement	139	46	1.14 out of 5	\$442	61,654
Distribution Main	10161	P-10000	WW	Nottingham Dr.	8	Asbestos Cement	2	46	1.14 out of 5	\$442	837
Distribution Main	11097	P-10000	WW	Nottingham Dr.	8	Asbestos Cement	16	46	1.14 out of 5	\$442	7,087
Distribution Main	12052	P-63	WW	Nottingham Dr.	8	Asbestos Cement	27	46	1.14 out of 5	\$442	11,924
Distribution Main	10615		WW	Noxon St	8	Ductile Iron	269	2	0 out of 5	N/A	\$0
Distribution Main	12203		WW	Noxon St	8	Ductile Iron	190	2	0 out of 5	N/A	\$0
Distribution Main	802	P-415	WW	Noxon St.	6	Asbestos Cement	23	46	1.85 out of 5	\$442	10,086
Distribution Main	808	P-416	WW	Noxon St.	6	Asbestos Cement	290	46	1.85 out of 5	\$442	128,245
Distribution Main	4442	P-415	WW	Noxon St.	6	Asbestos Cement	236	46	1.85 out of 5	\$442	104,400
Distribution Main	4443	P-415	WW	Noxon St.	6	Asbestos Cement	30	46	1.85 out of 5	\$442	13,458
Distribution Main	3492	P-914	WW	Oak St.	6	Cast Iron	76	134	2.57 out of 5	\$442	33,469
Distribution Main	3493	P-914	WW	Oak St.	6	Cast Iron	102	129	2.57 out of 5	\$442	45,250
Distribution Main	3735	P-1851	WW	Oak St.	6	Cast Iron	122	134	2.57 out of 5	\$442	54,121
Distribution Main	9731	P-915	WW	Oak St.	6	Cast Iron	115	134	2.57 out of 5	\$442	50,921
Distribution Main	8906		WW	Oakland Dr	8	Ductile Iron	27	9	0 out of 5	N/A	\$0
Distribution Main	8954	P-1744	WW	Oakland Dr	8	Ductile Iron	310	9	0 out of 5	N/A	\$0
Distribution Main	8956	P-1746	WW	Oakland Dr	6	Ductile Iron	2	9	0.71 out of 5	N/A	\$0
Distribution Main	10928	P-212	WW	Oakland Dr	8	Ductile Iron	11	9	0 out of 5	N/A	\$0
Distribution Main	11530	P-1746	WW	Oakland Dr	8	Ductile Iron	23	9	0 out of 5	N/A	\$0
Distribution Main	12099	P-1744	WW	Oakland Dr	8	Ductile Iron	17	9	0 out of 5	N/A	\$0
Distribution Main	3578	P-222	WW	Oakland Dr.	8	Ductile Iron	32	15	0 out of 5	N/A	\$0
Distribution Main	3584	P-222	WW	Oakland Dr.	6	Asbestos Cement	367	72	2 out of 5	\$442	162,428
Distribution Main	6537	P-211	WW	Oakland Dr.	6	Asbestos Cement	127	69	2 out of 5	\$442	56,161
Distribution Main	6538	P-211	WW	Oakland Dr.	6	Asbestos Cement	119	69	2 out of 5	\$442	52,566
Distribution Main	8157	P-222	WW	Oakland Dr.	6	Ductile Iron	29	15	0.71 out of 5	N/A	\$0
Distribution Main	8903	P-211	WW	Oakland Dr.	6	Asbestos Cement	96	69	2 out of 5	\$442	42,379
Distribution Main	8904	P-212	WW	Oakland Dr.	6	Asbestos Cement	200	69	2 out of 5	\$442	88,373
Distribution Main	8905	P-212	WW	Oakland Dr.	6	Asbestos Cement	20	69	2 out of 5	\$442	9,014

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	109	P-1154	WW	Oakridge Dr	8	PVC	253	33	0.43 out of 5	\$442	112,030
Distribution Main	110	P-1154	WW	Oakridge Dr	8	PVC	374	33	0.43 out of 5	\$442	165,471
Distribution Main	2153	P-10020	WW	Oakridge Dr.	8	PVC	166	33	0.43 out of 5	\$442	73,415
Distribution Main	4775	P-1152	WW	Oakridge Dr.	8	PVC	145	33	0.43 out of 5	\$442	64,090
Distribution Main	4776	P-1152	WW	Oakridge Dr.	8	PVC	15	33	0.43 out of 5	\$442	6,433
Distribution Main	5067	P-488	WW	Old Carriage Rd.	8	Asbestos Cement	455	43	1.14 out of 5	\$442	201,141
Distribution Main	5068	P-488	WW	Old Carriage Rd.	8	Asbestos Cement	230	43	1.14 out of 5	\$442	101,788
Distribution Main	5069	P-488	WW	Old Carriage Rd.	8	Asbestos Cement	450	43	1.14 out of 5	\$442	198,798
Distribution Main	5070	P-488	WW	Old Carriage Rd.	8	Asbestos Cement	55	43	1.14 out of 5	\$442	24,271
Distribution Main	8997		WW	Old Quaker Ln	10	Ductile Iron	14	16	0 out of 5	N/A	\$0
Distribution Main	8998		WW	Old Quaker Ln	10	Ductile Iron	9	16	0 out of 5	N/A	\$0
Distribution Main	9001	P-4708	WW	Old Quaker Ln	8	Ductile Iron	193	16	0 out of 5	N/A	\$0
Distribution Main	9059		WW	Old Quaker Ln	8	Ductile Iron	8	16	0 out of 5	N/A	\$0
Distribution Main	11537		WW	Old Quaker Ln	10	Ductile Iron	13	16	0 out of 5	N/A	\$0
Distribution Main	5145	P-1507	WW	Ontario St.	2	Galvanized Iron	235	56	3.14 out of 5	\$442	103,978
Distribution Main	5148	P-1506	WW	Ontario St.	6	PVC	243	56	1.28 out of 5	\$442	107,499
Distribution Main	1974	P-10038	WW	Orchard St.	2	Copper	103	48	2.28 out of 5	\$442	45,624
Distribution Main	4346	P-1098	WW	Orchard St.	6	Asbestos Cement	200	48	1.85 out of 5	\$442	88,541
Distribution Main	4348	P-1099	WW	Orchard St.	6	Asbestos Cement	120	48	1.85 out of 5	\$442	53,054
Distribution Main	9621	P-584	WW	Orrin St	8	Ductile Iron	5	13	0 out of 5	N/A	\$0
Distribution Main	10999		WW	Orrin St	8	Ductile Iron	4	13	0 out of 5	N/A	\$0
Distribution Main	173	P-584	WW	Orrin St.	8	Ductile Iron	40	14	0 out of 5	N/A	\$0
Distribution Main	1886	P-584	WW	Orrin St.	6	Ductile Iron	7	14	0.71 out of 5	N/A	\$0
Distribution Main	8027	P-584	WW	Orrin St.	6	Asbestos Cement	165	70	2.71 out of 5	\$442	72,869
Distribution Main	9353	P-584	WW	Orrin St.	6	Asbestos Cement	38	70	2 out of 5	\$442	16,863
Distribution Main	10116	P-584	WW	Orrin St.	6	Ductile Iron	8	13	0.71 out of 5	N/A	\$0
Distribution Main	9833	P-1973	WW	Ottawa St	8	Ductile Iron	263	19	0 out of 5	N/A	\$0
Distribution Main	9834	P-1973	WW	Ottawa St	8	Ductile Iron	15	7	0 out of 5	N/A	\$0
Distribution Main	9837	P-675	WW	Ottawa St	8	Ductile Iron	22	7	0 out of 5	N/A	\$0
Distribution Main	9838	P-675	WW	Ottawa St	8	Ductile Iron	222	7	0 out of 5	N/A	\$0
Distribution Main	9839	P-676	WW	Ottawa St	4	Ductile Iron	4	7	1.42 out of 5	N/A	\$0
Distribution Main	9916		WW	Ottawa St	8	Ductile Iron	11	7	0 out of 5	N/A	\$0
Distribution Main	11616	P-1973	WW	Ottawa St	8	Ductile Iron	3	19	0 out of 5	N/A	\$0
Distribution Main	12113	P-675	WW	Ottawa St	8	Ductile Iron	21	7	0 out of 5	N/A	\$0
Distribution Main	125	P-727	WW	Ottawa St.	6	Cast Iron	101	134	2.57 out of 5	\$442	44,551
Distribution Main	126	P-727	WW	Ottawa St.	6	Cast Iron	128	134	2.57 out of 5	\$442	56,360
Distribution Main	138	P-727	WW	Ottawa St.	6	Cast Iron	6	134	2.57 out of 5	\$442	2,721
Distribution Main	139	P-727	WW	Ottawa St.	6	Cast Iron	10	134	2.57 out of 5	\$442	4,601
Distribution Main	869	P-725	WW	Ottawa St.	6	Cast Iron	238	134	2.57 out of 5	\$442	105,204
Distribution Main	3265	P-728	WW	Ottawa St.	6	Cast Iron	102	133	2.57 out of 5	\$442	45,241
Distribution Main	3763	P-725	WW	Ottawa St.	6	Cast Iron	12	134	2.57 out of 5	\$442	5,124
Distribution Main	12064	P-725	WW	Ottawa St.	6	Cast Iron	3	134	2.57 out of 5	\$442	1,188
Distribution Main	8909	P-217	WW	Overhill Dr	8	Ductile Iron	210	9	0 out of 5	N/A	\$0
Distribution Main	8910	P-216	WW	Overhill Dr	8	Ductile Iron	6	9	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	8911	P-216	WW	Overhill Dr	8	Ductile Iron	454	9	0 out of 5	N/A	\$0
Distribution Main	8955	P-1745	WW	Overhill Dr	8	Ductile Iron	319	9	0 out of 5	N/A	\$0
Distribution Main	9399	P-1734	WW	Overhill Dr	8	Ductile Iron	25	9	0 out of 5	N/A	\$0
Distribution Main	5377	P-1734	WW	Overhill Dr.	8	Ductile Iron	22	15	0 out of 5	N/A	\$0
Distribution Main	8571	P-933	WW	Packard St	8	Ductile Iron	29	13	0 out of 5	N/A	\$0
Distribution Main	8573	P-933	WW	Packard St	6	Ductile Iron	10	13	0.71 out of 5	N/A	\$0
Distribution Main	3736	P-933	WW	Packard St.	6	Cast Iron	283	134	2.57 out of 5	\$442	125,168
Distribution Main	8038		WW	Park	6	Unknown	18	UNK	0.71 out of 5	\$442	7,998
Distribution Main	8039		WW	Park	6	Unknown	50	UNK	0.71 out of 5	\$442	22,003
Distribution Main	9467		WW	Park Ave	1.5	Copper	381	UNK	1.99 out of 5	\$442	168,397
Distribution Main	10789	P-331	WW	Park Ave.	8	Ductile Iron	253	0	0 out of 5	N/A	\$0
Distribution Main	10790	P-339	WW	Park Blvd	8	Ductile Iron	252	0	0 out of 5	N/A	\$0
Distribution Main	12162	P-339	WW	Park Blvd	8	Ductile Iron	315	0	0 out of 5	N/A	\$0
Distribution Main	12198	P-339	WW	Park Blvd	8	Ductile Iron	249	0	0 out of 5	N/A	\$0
Transmission Main	8466	P-979	WW	Parker St	12	Ductile Iron	144	10	0 out of 5	N/A	\$0
Distribution Main	8467	P-980	WW	Parker St	4	Ductile Iron	22	10	1.42 out of 5	N/A	\$0
Transmission Main	8468	P-980	WW	Parker St	12	Ductile Iron	8	10	0 out of 5	N/A	\$0
Transmission Main	11000	P-979	WW	Parker St	12	Ductile Iron	3	10	0 out of 5	N/A	\$0
Distribution Main	1521	P-980	WW	Parker St.	6	Cast Iron	9	134	2.57 out of 5	\$442	4,152
Distribution Main	1522	P-980	WW	Parker St.	6	Cast Iron	441	134	2.57 out of 5	\$442	194,863
Distribution Main	2481	P-980	WW	Parker St.	6	Cast Iron	413	134	2.57 out of 5	\$442	182,470
Distribution Main	3698	P-980	WW	Parker St.	6	Cast Iron	50	134	2.57 out of 5	\$442	22,288
Distribution Main	12029	P-980	WW	Parker St.	6	Cast Iron	367	134	2.57 out of 5	\$442	162,089
Distribution Main	8737	P-806	WW	Patrick Quinn Drive	6	Asbestos Cement	55	41	1.85 out of 5	\$442	24,417
Distribution Main	8738	P-806	WW	Patrick Quinn Drive	6	Asbestos Cement	234	41	1.85 out of 5	\$442	103,461
Distribution Main	1438	P-810	WW	Patrick Rd.	6	Asbestos Cement	251	41	1.85 out of 5	\$442	110,959
Distribution Main	3717	P-807	WW	Patrick Rd.	6	Asbestos Cement	214	41	1.85 out of 5	\$442	94,595
Distribution Main	3719	P-810	WW	Patrick Rd.	6	Asbestos Cement	7	41	1.85 out of 5	\$442	3,089
Distribution Main	10660		WW	Pauline St	8	Ductile Iron	128	2	0 out of 5	N/A	\$0
Distribution Main	10661		WW	Pauline St	8	Ductile Iron	35	2	0 out of 5	N/A	\$0
Distribution Main	10662		WW	Pauline St	8	Ductile Iron	194	2	0 out of 5	N/A	\$0
Transmission Main	1577	P-580	WW	Pawtuxet Ter.	12	Ductile Iron	252	14	0 out of 5	N/A	\$0
Transmission Main	1578	P-580	WW	Pawtuxet Ter.	12	Ductile Iron	22	14	0 out of 5	N/A	\$0
Transmission Main	1579	P-582	WW	Pawtuxet Ter.	12	Ductile Iron	306	14	0 out of 5	N/A	\$0
Transmission Main	1580	P-585	WW	Pawtuxet Ter.	12	Ductile Iron	67	14	0 out of 5	N/A	\$0
Transmission Main	1581	P-585	WW	Pawtuxet Ter.	12	Ductile Iron	215	14	0 out of 5	N/A	\$0
Transmission Main	1582	P-592	WW	Pawtuxet Ter.	12	Ductile Iron	470	14	0 out of 5	N/A	\$0
Transmission Main	4308	P-556	WW	Pawtuxet Ter.	12	Ductile Iron	492	14	0 out of 5	N/A	\$0
Transmission Main	8007	P-580	WW	Pawtuxet Ter.	12	Ductile Iron	186	14	0 out of 5	N/A	\$0
Transmission Main	8008	P-580	WW	Pawtuxet Ter.	12	Ductile Iron	41	14	0 out of 5	N/A	\$0
Transmission Main	8009	P-577	WW	Pawtuxet Ter.	12	Ductile Iron	134	14	0 out of 5	N/A	\$0
Transmission Main	8012	P-1367	WW	Pawtuxet Ter.	12	Ductile Iron	337	14	0 out of 5	N/A	\$0
Transmission Main	8141	P-592	WW	Pawtuxet Ter.	12	Ductile Iron	379	14	0 out of 5	N/A	\$0
Transmission Main	8151	P-580	WW	Pawtuxet Ter.	12	Ductile Iron	112	14	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10060		WW	Payan St	4	Ductile Iron	1	26	1.57 out of 5	\$442	525
Distribution Main	2388	P-1063	WW	Payan St.	6	Cast Iron	147	83	2.43 out of 5	\$442	64,767
Distribution Main	2490	P-1056	WW	Payan St.	6	Cast Iron	134	83	2.43 out of 5	\$442	59,138
Distribution Main	3241	P-1062	WW	Payan St.	6	Cast Iron	230	83	2.43 out of 5	\$442	101,543
Distribution Main	3253	P-1982	WW	Payan St.	6	Cast Iron	248	83	2.43 out of 5	\$442	109,570
Distribution Main	3257	P-1062	WW	Payan St.	6	Cast Iron	27	83	2.43 out of 5	\$442	11,714
Distribution Main	3374	P-1071	WW	Payan St.	6	Cast Iron	314	83	2.43 out of 5	\$442	138,921
Distribution Main	3797	P-1059	WW	Payan St.	6	Cast Iron	160	83	2.43 out of 5	\$442	70,692
Distribution Main	3807	P-1056	WW	Payan St.	6	Cast Iron	21	83	2.43 out of 5	\$442	9,132
Distribution Main	3808	P-1057	WW	Payan St.	6	Cast Iron	77	83	2.43 out of 5	\$442	34,107
Distribution Main	12076	P-1063	WW	Payan St.	6	Cast Iron	90	83	2.43 out of 5	\$442	39,582
Distribution Main	9679		WW	Pearce St	8	Ductile Iron	26	10	0 out of 5	N/A	\$0
Distribution Main	3865	P-1484	WW	Pearson St.	2	Cast Iron	11	134	3.29 out of 5	\$442	4,975
Distribution Main	3866	P-1484	WW	Pearson St.	2	Cast Iron	290	134	4 out of 5	\$442	128,155
Distribution Main	11237	P-1484	WW	Pearson St.	2	Cast Iron	10	134	3.29 out of 5	\$442	4,213
Distribution Main	10613	P-421	WW	Penel Dr	8	Ductile Iron	28	2	0 out of 5	N/A	\$0
Distribution Main	10614	P-421	WW	Penel Dr	6	Ductile Iron	3	2	0.71 out of 5	N/A	\$0
Distribution Main	3136	P-421	WW	Penel Dr.	6	Asbestos Cement	459	56	1.85 out of 5	\$442	202,840
Distribution Main	9644	P-10041	WW	Pennsylvania Ave	1	Copper	11	35	2.14 out of 5	\$442	4,739
Distribution Main	9645	P-10041	WW	Pennsylvania Ave	1	Copper	91	35	2.14 out of 5	\$442	40,070
Distribution Main	4345	P-1090	WW	Pennsylvania Ave.	6	Cast Iron	223	134	2.57 out of 5	\$442	98,551
Distribution Main	9642	P-1478	WW	Pennsylvania Ave.	6	PVC	106	35	1.14 out of 5	\$442	46,983
Distribution Main	9643	P-1478	WW	Pennsylvania Ave.	6	PVC	5	35	1.14 out of 5	\$442	2,158
Distribution Main	11588	P-10041	WW	Pennsylvania Ave.	6	PVC	9	35	1.14 out of 5	\$442	4,046
Transmission Main	10306	P-264	WW	Penta St	12	Ductile Iron	31	5	0 out of 5	N/A	\$0
Transmission Main	7377	P-264	WW	Penta St.	12	Ductile Iron	297	25	0.14 out of 5	N/A	\$0
Transmission Main	7378	P-264	WW	Penta St.	12	Ductile Iron	31	25	0.14 out of 5	N/A	\$0
Transmission Main	10320	P-267	WW	Penta St.	12	Ductile Iron	1	25	0.14 out of 5	N/A	\$0
Distribution Main	1975	P-487	WW	Pepin St.	8	Asbestos Cement	28	55	1.14 out of 5	\$442	12,578
Distribution Main	1982	P-486	WW	Pepin St.	8	Asbestos Cement	369	55	1.14 out of 5	\$442	163,285
Distribution Main	1983	P-486	WW	Pepin St.	8	Asbestos Cement	317	55	1.14 out of 5	\$442	140,286
Distribution Main	5064	P-487	WW	Pepin St.	8	Asbestos Cement	296	55	1.14 out of 5	\$442	130,805
Distribution Main	5065	P-487	WW	Pepin St.	8	Asbestos Cement	525	55	1.14 out of 5	\$442	232,260
Distribution Main	5066		WW	Pepin St.	8	Asbestos Cement	92	55	1.14 out of 5	\$442	40,598
Distribution Main	11875	P-486	WW	Pepin St.	8	Asbestos Cement	221	55	1.14 out of 5	\$442	97,494
Distribution Main	10646	P-378	WW	Perkins St	8	Ductile Iron	252	2	0 out of 5	N/A	\$0
Distribution Main	10647	P-378	WW	Perkins St	8	Ductile Iron	335	2	0 out of 5	N/A	\$0
Distribution Main	10901	P-378	WW	Perkins St	8	Ductile Iron	193	2	0 out of 5	N/A	\$0
Distribution Main	12141	P-379	WW	Perkins St	8	Ductile Iron	159	2	0 out of 5	N/A	\$0
Distribution Main	1435	P-1931	WW	Peters Ln.	8	Asbestos Cement	390	59	1.14 out of 5	\$442	172,188
Distribution Main	1563	P-801	WW	Peters Ln.	8	Asbestos Cement	462	59	1.14 out of 5	\$442	204,154
Distribution Main	500	P-293	WW	Petti Dr.	6	Ductile Iron	419	26	0.85 out of 5	\$442	185,147
Distribution Main	8815	P-288	WW	Petti Dr.	6	Ductile Iron	204	26	0.85 out of 5	\$442	90,278
Distribution Main	8816	P-288	WW	Petti Dr.	6	Ductile Iron	12	26	0.85 out of 5	\$442	5,414

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11513	P-288	WW	Petti Dr.	6	Ductile Iron	8	26	0.85 out of 5	\$442	3,608
Distribution Main	106	P-951	WW	Phenix Ave	6	Cast Iron	66	134	2.57 out of 5	\$442	29,335
Distribution Main	107	P-1825	WW	Phenix Ave	8	Cast Iron	463	87	1.72 out of 5	\$442	204,767
Distribution Main	108	P-1825	WW	Phenix Ave	8	Cast Iron	285	87	1.72 out of 5	\$442	126,023
Transmission Main	8413	P-1806	WW	Phenix Ave	12	Ductile Iron	163	10	0 out of 5	N/A	\$0
Transmission Main	8425	P-956	WW	Phenix Ave	12	Ductile Iron	59	10	0 out of 5	N/A	\$0
Transmission Main	8426	P-956	WW	Phenix Ave	12	Ductile Iron	408	10	0 out of 5	N/A	\$0
Distribution Main	8430	P-1798	WW	Phenix Ave	8	Ductile Iron	111	10	0 out of 5	N/A	\$0
Distribution Main	8431	P-1798	WW	Phenix Ave	8	Ductile Iron	6	10	0 out of 5	N/A	\$0
Distribution Main	8483	P-952	WW	Phenix Ave	8	Ductile Iron	15	10	0 out of 5	N/A	\$0
Transmission Main	8484	P-952	WW	Phenix Ave	12	Ductile Iron	8	10	0 out of 5	N/A	\$0
Transmission Main	8485	P-1360	WW	Phenix Ave	12	Ductile Iron	49	10	0 out of 5	N/A	\$0
Transmission Main	8486	P-1360	WW	Phenix Ave	12	Ductile Iron	23	10	0 out of 5	N/A	\$0
Transmission Main	8487	P-1824	WW	Phenix Ave	12	Ductile Iron	17	10	0 out of 5	N/A	\$0
Transmission Main	8489	P-1361	WW	Phenix Ave	12	Ductile Iron	202	10	0 out of 5	N/A	\$0
Transmission Main	8491	P-1815	WW	Phenix Ave	12	Ductile Iron	195	10	0 out of 5	N/A	\$0
Transmission Main	8492	P-1363	WW	Phenix Ave	12	Ductile Iron	16	10	0 out of 5	N/A	\$0
Transmission Main	8493	P-1363	WW	Phenix Ave	12	Ductile Iron	15	10	0 out of 5	N/A	\$0
Transmission Main	8494	P-1802	WW	Phenix Ave	12	Ductile Iron	94	10	0 out of 5	N/A	\$0
Transmission Main	8495	P-955	WW	Phenix Ave	12	Ductile Iron	122	10	0 out of 5	N/A	\$0
Transmission Main	8496	P-955	WW	Phenix Ave	12	Ductile Iron	102	10	0 out of 5	N/A	\$0
Transmission Main	8498	P-957	WW	Phenix Ave	12	Ductile Iron	185	10	0 out of 5	N/A	\$0
Transmission Main	8500	P-1797	WW	Phenix Ave	12	Ductile Iron	126	10	0 out of 5	N/A	\$0
Transmission Main	8501	P-1798	WW	Phenix Ave	12	Ductile Iron	13	10	0 out of 5	N/A	\$0
Transmission Main	9712	P-1802	WW	Phenix Ave	12	Ductile Iron	64	10	0 out of 5	N/A	\$0
Transmission Main	11470	P-1361	WW	Phenix Ave	12	Ductile Iron	7	10	0 out of 5	N/A	\$0
Transmission Main	11471	P-957	WW	Phenix Ave	12	Ductile Iron	63	10	0 out of 5	N/A	\$0
Transmission Main	11590	P-1804	WW	Phenix Ave	12	Ductile Iron	31	10	0 out of 5	N/A	\$0
Distribution Main	482	P-961	WW	Phenix Ave.	8	Asbestos Cement	591	54	1.14 out of 5	\$442	261,160
Distribution Main	1523	P-1842	WW	Phenix Ave.	6	Cast Iron	156	134	2.57 out of 5	\$442	69,153
Distribution Main	1801	P-939	WW	Phenix Ave.	6	Cast Iron	242	134	2.57 out of 5	\$442	107,019
Distribution Main	3701	P-949	WW	Phenix Ave.	6	Cast Iron	22	134	2.57 out of 5	\$442	9,686
Distribution Main	3702	P-949	WW	Phenix Ave.	6	Cast Iron	164	134	2.57 out of 5	\$442	72,706
Distribution Main	3703	P-950	WW	Phenix Ave.	8	Cast Iron	214	87	1.72 out of 5	\$442	94,417
Distribution Main	3731	P-940	WW	Phenix Ave.	6	Cast Iron	130	134	2.57 out of 5	\$442	57,494
Distribution Main	3732	P-940	WW	Phenix Ave.	6	Cast Iron	296	134	2.57 out of 5	\$442	130,642
Distribution Main	8552	P-1841	WW	Phenix Ave.	8	Ductile Iron	23	13	0 out of 5	N/A	\$0
Distribution Main	8566	P-1842	WW	Phenix Ave.	4	Ductile Iron	11	13	1.42 out of 5	N/A	\$0
Distribution Main	11146	P-939	WW	Phenix Ave.	6	Cast Iron	3	134	2.57 out of 5	\$442	1,260
Distribution Main	11147	P-940	WW	Phenix Ave.	6	Cast Iron	2	134	2.57 out of 5	\$442	968
Distribution Main	327	P-1352	WW	Pike St.	4	Cast Iron	320	134	3.29 out of 5	\$442	141,516
Distribution Main	328	P-1352	WW	Pike St.	4	Cast Iron	299	134	3.29 out of 5	\$442	132,043
Distribution Main	3343	P-1352	WW	Pike St.	4	Cast Iron	10	134	3.29 out of 5	\$442	4,573
Transmission Main	432	P-1348	WW	Pike Street	12	Asbestos Cement	185	68	1.29 out of 5	\$442	81,828

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	433	P-1348	WW	Pike Street	12	Asbestos Cement	317	68	1.29 out of 5	\$442	140,057
Transmission Main	3365	P-1005	WW	Pike Street	12	Asbestos Cement	133	68	1.29 out of 5	\$442	58,767
Transmission Main	10243	P-1005	WW	Pike Street	12	Asbestos Cement	39	68	1.29 out of 5	\$442	17,039
Distribution Main	8994	P-1994	WW	Pine Hollow Rd	8	Ductile Iron	348	15	0 out of 5	N/A	\$0
Distribution Main	12057	P-1994	WW	Pine Hollow Rd	8	Ductile Iron	302	15	0 out of 5	N/A	\$0
Distribution Main	1834	P-125	WW	Pine Orchard Rd.	8	Asbestos Cement	497	42	1.14 out of 5	\$442	219,657
Distribution Main	1835	P-125	WW	Pine Orchard Rd.	8	Asbestos Cement	24	42	1.14 out of 5	\$442	10,810
Distribution Main	4605	P-134	WW	Pine Orchard Rd.	8	Asbestos Cement	14	42	1.14 out of 5	\$442	6,182
Transmission Main	4606	P-134	WW	Pine Orchard Rd.	12	Asbestos Cement	515	42	1.14 out of 5	\$442	227,518
Distribution Main	4607	P-124	WW	Pine Orchard Rd.	8	Asbestos Cement	524	42	1.14 out of 5	\$442	231,648
Distribution Main	4620	P-123	WW	Pine Orchard Rd.	8	Asbestos Cement	544	44	1.14 out of 5	\$442	240,658
Distribution Main	5185	P-124	WW	Pine Orchard Rd.	8	Asbestos Cement	57	42	1.14 out of 5	\$442	25,104
Distribution Main	12054	P-125	WW	Pine Orchard Rd.	8	Asbestos Cement	48	42	1.14 out of 5	\$442	21,056
Distribution Main	3740	P-825	WW	Pine St.	6	Ductile Iron	504	14	0.71 out of 5	N/A	\$0
Distribution Main	1818	P-156	WW	Pinewood Dr.	8	Asbestos Cement	95	42	1.14 out of 5	\$442	42,112
Distribution Main	1819	P-176	WW	Pinewood Dr.	8	Asbestos Cement	99	42	1.14 out of 5	\$442	43,952
Distribution Main	1820	P-176	WW	Pinewood Dr.	8	Asbestos Cement	49	42	1.14 out of 5	\$442	21,492
Distribution Main	3870	P-172	WW	Pinewood Dr.	8	Asbestos Cement	118	42	1.14 out of 5	\$442	52,196
Distribution Main	4659	P-177	WW	Pinewood Dr.	8	Asbestos Cement	126	42	1.14 out of 5	\$442	55,642
Distribution Main	5168	P-171	WW	Pinewood Dr.	8	Asbestos Cement	143	42	1.14 out of 5	\$442	63,057
Distribution Main	5169	P-171	WW	Pinewood Dr.	8	Asbestos Cement	104	42	1.14 out of 5	\$442	45,961
Distribution Main	5170	P-166	WW	Pinewood Dr.	8	Asbestos Cement	247	42	1.14 out of 5	\$442	109,231
Distribution Main	5171	P-161	WW	Pinewood Dr.	8	Asbestos Cement	246	42	1.14 out of 5	\$442	108,712
Distribution Main	1774	P-714	WW	Plante St.	2	PVC	320	38	1.85 out of 5	\$442	141,350
Distribution Main	8395	P-1236	WW	Pleasant St	8	Ductile Iron	22	10	0 out of 5	N/A	\$0
Distribution Main	8463	P-1236	WW	Pleasant St	6	Ductile Iron	13	10	0.71 out of 5	N/A	\$0
Transmission Main	8555	P-1920	WW	Pleasant St	12	Ductile Iron	36	13	0 out of 5	N/A	\$0
Transmission Main	8556	P-1918	WW	Pleasant St	12	Ductile Iron	11	13	0 out of 5	N/A	\$0
Transmission Main	8557	P-1917	WW	Pleasant St	12	Ductile Iron	14	13	0 out of 5	N/A	\$0
Distribution Main	8558	P-1918	WW	Pleasant St	8	Ductile Iron	32	13	0 out of 5	N/A	\$0
Transmission Main	9704	P-1919	WW	Pleasant St	12	Ductile Iron	11	13	0 out of 5	N/A	\$0
Distribution Main	1788	P-1908	WW	Pleasant St.	4	Cast Iron	19	134	3.29 out of 5	\$442	8,521
Distribution Main	2479	P-1908	WW	Pleasant St.	6	Cast Iron	432	134	2.57 out of 5	\$442	190,900
Distribution Main	3520	P-1229	WW	Pleasant St.	6	Cast Iron	153	134	2.57 out of 5	\$442	67,831
Distribution Main	3521	P-1229	WW	Pleasant St.	6	Cast Iron	61	134	2.57 out of 5	\$442	26,781
Distribution Main	3706	P-1254	WW	Pleasant St.	6	Cast Iron	8	134	2.57 out of 5	\$442	3,444
Distribution Main	3707	P-1254	WW	Pleasant St.	6	Cast Iron	339	134	2.57 out of 5	\$442	149,631
Distribution Main	3708	P-1254	WW	Pleasant St.	6	Cast Iron	218	134	2.57 out of 5	\$442	96,566
Distribution Main	8530	P-1257	WW	Pleasant St.	8	Cast Iron	109	134	1.86 out of 5	\$442	48,047
Distribution Main	8531	P-1254	WW	Pleasant St.	6	Cast Iron	25	134	2.57 out of 5	\$442	11,233
Distribution Main	8532	P-1254	WW	Pleasant St.	6	Cast Iron	3	134	2.57 out of 5	\$442	1,414
Transmission Main	8533	P-1255	WW	Pleasant St.	12	Cast Iron	114	134	1.86 out of 5	\$442	50,208
Distribution Main	9705	P-1916	WW	Pleasant St.	8	Cast Iron	11	134	1.86 out of 5	\$442	4,819
Distribution Main	11474	P-1257	WW	Pleasant St.	8	Cast Iron	17	134	1.86 out of 5	\$442	7,340

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11475	P-1255	WW	Pleasant St.	12	Cast Iron	46	134	1.86 out of 5	\$442	20,334
Distribution Main	9049	P-1957	WW	Podgurski St	6	Ductile Iron	46	15	0.71 out of 5	N/A	\$0
Distribution Main	1136	P-589	WW	Podgurski St.	8	Ductile Iron	40	14	0 out of 5	N/A	\$0
Distribution Main	5386	P-589	WW	Podgurski St.	6	Asbestos Cement	297	65	2 out of 5	\$442	131,336
Distribution Main	8026	P-589	WW	Podgurski St.	6	Ductile Iron	4	14	0.71 out of 5	N/A	\$0
Transmission Main	610	P-722	WW	Pond St.	12	Cast Iron	149	134	1.86 out of 5	\$442	65,650
Transmission Main	611	P-722	WW	Pond St.	12	Cast Iron	249	134	1.86 out of 5	\$442	109,947
Transmission Main	1968	P-721	WW	Pond St.	12	Cast Iron	273	134	1.86 out of 5	\$442	120,743
Transmission Main	2158	P-723	WW	Pond St.	12	Cast Iron	187	134	1.86 out of 5	\$442	82,581
Transmission Main	3267	P-718	WW	Pond St.	12	Cast Iron	507	89	1.72 out of 5	\$442	223,981
Transmission Main	3268	P-718	WW	Pond St.	12	Cast Iron	28	89	1.72 out of 5	\$442	12,284
Transmission Main	3804	P-720	WW	Pond St.	12	Cast Iron	283	89	1.72 out of 5	\$442	125,045
Distribution Main	1588	P-1475	WW	Pond View Dr.	8	Ductile Iron	26	21	0.14 out of 5	N/A	\$0
Distribution Main	1589	P-1475	WW	Pond View Dr.	8	Ductile Iron	317	21	0.14 out of 5	N/A	\$0
Distribution Main	3881	P-457	WW	Pond View Dr.	8	Ductile Iron	303	21	0.14 out of 5	N/A	\$0
Distribution Main	4118	P-507	WW	Ponderosa Dr.	6	Asbestos Cement	200	50	1.85 out of 5	\$442	88,322
Distribution Main	4119	P-507	WW	Ponderosa Dr.	6	Asbestos Cement	561	50	1.85 out of 5	\$442	247,993
Distribution Main	2218	P-1749	WW	Pontiac Av	10	Ductile Iron	707	29	0.14 out of 5	\$442	312,434
Distribution Main	5359	P-1749	WW	Pontiac Av	10	Ductile Iron	77	29	0.14 out of 5	\$442	34,085
Distribution Main	8155	P-1749	WW	Pontiac Av	10	Ductile Iron	8	29	0.14 out of 5	\$442	3,363
Distribution Main	8156	P-1749	WW	Pontiac Av	10	Ductile Iron	125	29	0.14 out of 5	\$442	55,423
Distribution Main	10386	P-1749	WW	Pontiac Av	10	Ductile Iron	29	15	0 out of 5	N/A	\$0
Distribution Main	3331	P-1044	WW	Potter Ave.	8	Ductile Iron	289	18	0 out of 5	N/A	\$0
Distribution Main	3332	P-1044	WW	Potter Ave.	8	Ductile Iron	4	18	0 out of 5	N/A	\$0
Distribution Main	3333	P-1043	WW	Potter Ave.	6	Cast Iron	31	134	2.57 out of 5	\$442	13,765
Distribution Main	3334	P-1043	WW	Potter Ave.	6	Cast Iron	474	134	2.57 out of 5	\$442	209,394
Distribution Main	3344	P-1043	WW	Potter Ave.	6	Cast Iron	17	134	2.57 out of 5	\$442	7,660
Distribution Main	8848	P-1043	WW	Potter Ave.	6	Cast Iron	160	134	2.57 out of 5	\$442	70,783
Distribution Main	8849	P-1043	WW	Potter Ave.	6	Cast Iron	282	134	2.57 out of 5	\$442	124,861
Distribution Main	8850	P-1043	WW	Potter Ave.	6	Cast Iron	20	134	2.57 out of 5	\$442	8,654
Distribution Main	8851	P-1043	WW	Potter Ave.	6	Cast Iron	80	134	2.57 out of 5	\$442	35,219
Distribution Main	10378	P-1044	WW	Potter Ave.	6	Cast Iron	68	18	1.85 out of 5	N/A	\$0
Transmission Main	10032	P-248	WW	Prospect Hill Ave	12	Ductile Iron	24	6	0 out of 5	N/A	\$0
Transmission Main	10033	P-248	WW	Prospect Hill Ave	12	Ductile Iron	264	6	0 out of 5	N/A	\$0
Transmission Main	10036	P-249	WW	Prospect Hill Ave	12	Ductile Iron	45	6	0 out of 5	N/A	\$0
Transmission Main	10037	P-254	WW	Prospect Hill Ave	12	Ductile Iron	525	6	0 out of 5	N/A	\$0
Transmission Main	10040	P-255	WW	Prospect Hill Ave	12	Ductile Iron	91	6	0 out of 5	N/A	\$0
Transmission Main	10041	P-257	WW	Prospect Hill Ave	12	Ductile Iron	254	6	0 out of 5	N/A	\$0
Distribution Main	10043	P-1768	WW	Prospect Hill Ave	8	Ductile Iron	67	6	0 out of 5	N/A	\$0
Distribution Main	10050	P-1520	WW	Prospect Hill Ave	8	Ductile Iron	423	6	0 out of 5	N/A	\$0
Transmission Main	10301	P-244	WW	Prospect Hill Ave	12	Ductile Iron	253	5	0 out of 5	N/A	\$0
Transmission Main	10307	P-246	WW	Prospect Hill Ave	12	Ductile Iron	305	5	0 out of 5	N/A	\$0
Transmission Main	10308	P-246	WW	Prospect Hill Ave	12	Ductile Iron	178	5	0 out of 5	N/A	\$0
Transmission Main	11631	P-254	WW	Prospect Hill Ave	12	Ductile Iron	3	6	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11632	P-254	WW	Prospect Hill Ave	12	Ductile Iron	35	6	0 out of 5	N/A	\$0
Transmission Main	11633	P-255	WW	Prospect Hill Ave	12	Ductile Iron	47	6	0 out of 5	N/A	\$0
Distribution Main	11634	P-258	WW	Prospect Hill Ave	8	Ductile Iron	8	6	0 out of 5	N/A	\$0
Transmission Main	11997	P-246	WW	Prospect Hill Ave	12	Ductile Iron	19	5	0 out of 5	N/A	\$0
Transmission Main	12122	P-248	WW	Prospect Hill Ave	12	Ductile Iron	7	6	0 out of 5	N/A	\$0
Transmission Main	12123	P-257	WW	Prospect Hill Ave	12	Ductile Iron	16	6	0 out of 5	N/A	\$0
Distribution Main	9342	P-245	WW	Prospect St	8	Ductile Iron	216	10	0 out of 5	N/A	\$0
Distribution Main	9343	P-245	WW	Prospect St	8	Ductile Iron	307	10	0 out of 5	N/A	\$0
Distribution Main	10309	P-245	WW	Prospect St	8	Ductile Iron	29	5	0 out of 5	N/A	\$0
Transmission Main	8607	P-1873	WW	Providence St	12	Ductile Iron	47	12	0 out of 5	N/A	\$0
Transmission Main	8608	P-1873	WW	Providence St	12	Ductile Iron	9	12	0 out of 5	N/A	\$0
Transmission Main	8610	P-1340	WW	Providence St	12	Ductile Iron	18	12	0 out of 5	N/A	\$0
Transmission Main	8611	P-1340	WW	Providence St	12	Ductile Iron	313	12	0 out of 5	N/A	\$0
Distribution Main	8614	P-1344	WW	Providence St	8	Ductile Iron	5	12	0 out of 5	N/A	\$0
Distribution Main	8615	P-1344	WW	Providence St	8	Ductile Iron	23	12	0 out of 5	N/A	\$0
Transmission Main	8622	P-1871	WW	Providence St	12	Ductile Iron	100	12	0 out of 5	N/A	\$0
Distribution Main	8623	P-1868	WW	Providence St	6	Ductile Iron	5	12	0.71 out of 5	N/A	\$0
Transmission Main	8624	P-1869	WW	Providence St	12	Ductile Iron	5	12	0 out of 5	N/A	\$0
Transmission Main	8625	P-1869	WW	Providence St	12	Ductile Iron	85	12	0 out of 5	N/A	\$0
Distribution Main	8626	P-1872	WW	Providence St	6	Ductile Iron	3	12	0.71 out of 5	N/A	\$0
Distribution Main	9414	P-1714	WW	Providence St	8	Ductile Iron	33	8	0 out of 5	N/A	\$0
Distribution Main	10013	P-1318	WW	Providence St	8	Ductile Iron	275	6	0 out of 5	N/A	\$0
Distribution Main	10014	P-1307	WW	Providence St	8	Ductile Iron	323	6	0 out of 5	N/A	\$0
Distribution Main	10054	P-2563	WW	Providence St	8	Ductile Iron	5	6	0 out of 5	N/A	\$0
Transmission Main	10296	P-269	WW	Providence St	12	Ductile Iron	72	5	0 out of 5	N/A	\$0
Transmission Main	10297	P-242	WW	Providence St	12	Ductile Iron	275	5	0 out of 5	N/A	\$0
Distribution Main	10305	P-271	WW	Providence St	8	Ductile Iron	46	5	0 out of 5	N/A	\$0
Transmission Main	10310	P-238	WW	Providence St	12	Ductile Iron	258	5	0 out of 5	N/A	\$0
Transmission Main	10311	P-238	WW	Providence St	12	Ductile Iron	282	5	0 out of 5	N/A	\$0
Transmission Main	10314	P-232	WW	Providence St	12	Ductile Iron	384	5	0 out of 5	N/A	\$0
Transmission Main	10318	P-232	WW	Providence St	16	Ductile Iron	27	5	0 out of 5	N/A	\$0
Distribution Main	10609		WW	Providence St	6	Ductile Iron	3	UNK	0.71 out of 5	\$442	1,316
Distribution Main	10814	P-1317	WW	Providence St	8	Ductile Iron	68	6	0 out of 5	N/A	\$0
Distribution Main	10815	P-1317	WW	Providence St	8	Ductile Iron	99	6	0 out of 5	N/A	\$0
Distribution Main	10816	P-1758	WW	Providence St	8	Ductile Iron	135	6	0 out of 5	N/A	\$0
Transmission Main	10817	P-238	WW	Providence St	12	Ductile Iron	211	5	0 out of 5	N/A	\$0
Transmission Main	10818	P-238	WW	Providence St	12	Ductile Iron	43	5	0 out of 5	N/A	\$0
Transmission Main	10819	P-232	WW	Providence St	12	Ductile Iron	36	5	0 out of 5	N/A	\$0
Transmission Main	10820	P-232	WW	Providence St	12	Ductile Iron	389	5	0 out of 5	N/A	\$0
Transmission Main	11485	P-1873	WW	Providence St	12	Ductile Iron	7	12	0 out of 5	N/A	\$0
Distribution Main	11628	P-1307	WW	Providence St	8	Ductile Iron	19	6	0 out of 5	N/A	\$0
Distribution Main	11629	P-1318	WW	Providence St	8	Ductile Iron	44	8	0 out of 5	N/A	\$0
Transmission Main	11649	P-269	WW	Providence St	12	Ductile Iron	118	5	0 out of 5	N/A	\$0
Transmission Main	11650	P-232	WW	Providence St	12	Ductile Iron	14	5	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11651	P-223	WW	Providence St	16	Ductile Iron	6	5	0 out of 5	N/A	\$0
Transmission Main	11991	P-232	WW	Providence St	12	Ductile Iron	136	5	0 out of 5	N/A	\$0
Transmission Main	11994	P-239	WW	Providence St	12	Ductile Iron	46	5	0 out of 5	N/A	\$0
Transmission Main	11995	P-242	WW	Providence St	12	Ductile Iron	162	5	0 out of 5	N/A	\$0
Distribution Main	11999	P-1307	WW	Providence St	8	Ductile Iron	138	6	0 out of 5	N/A	\$0
Distribution Main	12119	P-1307	WW	Providence St	8	Ductile Iron	76	23	0.14 out of 5	N/A	\$0
Distribution Main	12120	P-1307	WW	Providence St	8	Ductile Iron	28	6	0 out of 5	N/A	\$0
Distribution Main	12121	P-1307	WW	Providence St	8	Ductile Iron	31	6	0 out of 5	N/A	\$0
Transmission Main	12126	P-270	WW	Providence St	12	Ductile Iron	27	23	0.14 out of 5	N/A	\$0
Transmission Main	12127	P-269	WW	Providence St	12	Ductile Iron	7	5	0 out of 5	N/A	\$0
Transmission Main	12128	P-242	WW	Providence St	12	Ductile Iron	10	5	0 out of 5	N/A	\$0
Transmission Main	12129	P-232	WW	Providence St	16	Ductile Iron	16	5	0 out of 5	N/A	\$0
Transmission Main	12153	P-269	WW	Providence St	12	Ductile Iron	11	5	0 out of 5	N/A	\$0
Distribution Main	324	P-1686	WW	Providence St.	6	Ductile Iron	54	30	0.85 out of 5	\$442	23,898
Distribution Main	863	P-1227	WW	Providence St.	8	Ductile Iron	394	25	0.14 out of 5	N/A	\$0
Distribution Main	956	P-1870	WW	Providence St.	6	Ductile Iron	43	30	0.85 out of 5	\$442	18,947
Distribution Main	1067	P-994	WW	Providence St.	10	Cast Iron	919	91	1.72 out of 5	\$442	406,187
Distribution Main	1073	P-1032	WW	Providence St.	6	Cast Iron	81	134	2.57 out of 5	\$442	35,849
Distribution Main	1150	P-1227	WW	Providence St.	8	Ductile Iron	149	25	0.14 out of 5	N/A	\$0
Distribution Main	1693	P-1018	WW	Providence St.	6	Cast Iron	189	134	2.57 out of 5	\$442	83,560
Distribution Main	1694	P-1018	WW	Providence St.	6	Cast Iron	620	134	2.57 out of 5	\$442	274,075
Distribution Main	1695	P-1877	WW	Providence St.	6	Cast Iron	154	84	2.43 out of 5	\$442	67,976
Distribution Main	1697	P-1012	WW	Providence St.	6	Cast Iron	47	134	2.57 out of 5	\$442	20,745
Distribution Main	1698	P-1012	WW	Providence St.	6	Cast Iron	755	134	2.57 out of 5	\$442	333,675
Distribution Main	2142	P-304	WW	Providence St.	6	Cast Iron	14	91	2.43 out of 5	\$442	6,007
Distribution Main	2143	P-304	WW	Providence St.	6	Cast Iron	250	91	2.43 out of 5	\$442	110,574
Distribution Main	2144	P-1701	WW	Providence St.	10	Cast Iron	873	91	1.72 out of 5	\$442	385,951
Distribution Main	2145	P-1701	WW	Providence St.	10	Cast Iron	325	91	1.72 out of 5	\$442	143,624
Transmission Main	2219	P-154	WW	Providence St.	12	Ductile Iron	219	15	0 out of 5	N/A	\$0
Transmission Main	2220	P-162	WW	Providence St.	12	Ductile Iron	237	15	0 out of 5	N/A	\$0
Distribution Main	2676	P-1023	WW	Providence St.	6	Cast Iron	199	134	2.57 out of 5	\$442	87,761
Transmission Main	2964	P-117	WW	Providence St.	12	Ductile Iron	3	15	0 out of 5	N/A	\$0
Transmission Main	2966	P-154	WW	Providence St.	12	Ductile Iron	5	15	0 out of 5	N/A	\$0
Distribution Main	3347	P-998	WW	Providence St.	6	Cast Iron	417	134	2.57 out of 5	\$442	184,139
Distribution Main	3348	P-998	WW	Providence St.	6	Cast Iron	162	134	2.57 out of 5	\$442	71,814
Distribution Main	3355	P-994	WW	Providence St.	10	Cast Iron	11	91	1.72 out of 5	\$442	5,058
Distribution Main	3366	P-1014	WW	Providence St.	6	Cast Iron	102	134	2.57 out of 5	\$442	45,207
Distribution Main	3367	P-1014	WW	Providence St.	6	Cast Iron	136	134	2.57 out of 5	\$442	60,008
Distribution Main	3369	P-1022	WW	Providence St.	6	Cast Iron	126	134	2.57 out of 5	\$442	55,586
Distribution Main	3370		WW	Providence St.	6	Unknown	16	UNK	0.71 out of 5	\$442	7,057
Distribution Main	3371	P-1022	WW	Providence St.	6	Cast Iron	191	134	2.57 out of 5	\$442	84,462
Distribution Main	3403	P-1227	WW	Providence St.	8	Ductile Iron	80	25	0.14 out of 5	N/A	\$0
Distribution Main	3404	P-1227	WW	Providence St.	8	Ductile Iron	70	25	0.14 out of 5	N/A	\$0
Distribution Main	3405	P-1316	WW	Providence St.	8	Ductile Iron	402	25	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	3406	P-1316	WW	Providence St.	8	Ductile Iron	276	25	0.14 out of 5	N/A	\$0
Transmission Main	3575	P-154	WW	Providence St.	12	Ductile Iron	4	15	0 out of 5	N/A	\$0
Transmission Main	3576	P-153	WW	Providence St.	12	Ductile Iron	251	15	0 out of 5	N/A	\$0
Transmission Main	3577	P-215	WW	Providence St.	12	Ductile Iron	209	15	0 out of 5	N/A	\$0
Transmission Main	3579	P-221	WW	Providence St.	12	Ductile Iron	241	15	0 out of 5	N/A	\$0
Transmission Main	3580	P-1748	WW	Providence St.	12	Ductile Iron	3	15	0 out of 5	N/A	\$0
Transmission Main	3582	P-1750	WW	Providence St.	12	Ductile Iron	347	15	0 out of 5	N/A	\$0
Distribution Main	3583	P-1750	WW	Providence St.	10	Cast Iron	18	UNK	1.14 out of 5	\$442	8,045
Distribution Main	4019	P-994	WW	Providence St.	10	Cast Iron	150	91	1.72 out of 5	\$442	66,334
Transmission Main	4278	P-1713	WW	Providence St.	12	Ductile Iron	233	15	0 out of 5	N/A	\$0
Transmission Main	4280	P-70	WW	Providence St.	12	Cast Iron	57	51	1.43 out of 5	\$442	25,054
Transmission Main	4386	P-1763	WW	Providence St.	12	Ductile Iron	152	15	0 out of 5	N/A	\$0
Transmission Main	4387	P-270	WW	Providence St.	12	Ductile Iron	203	23	0.14 out of 5	N/A	\$0
Transmission Main	5376	P-221	WW	Providence St.	12	Ductile Iron	3	15	0 out of 5	N/A	\$0
Distribution Main	5378	P-223	WW	Providence St.	10	Cast Iron	36	UNK	1.14 out of 5	\$442	15,742
Distribution Main	5379	P-223	WW	Providence St.	10	Cast Iron	51	UNK	1.14 out of 5	\$442	22,528
Transmission Main	5460	P-213	WW	Providence St.	12	Ductile Iron	259	15	0 out of 5	N/A	\$0
Transmission Main	8028	P-1748	WW	Providence St.	12	Ductile Iron	73	15	0 out of 5	N/A	\$0
Transmission Main	8029	P-1748	WW	Providence St.	12	Ductile Iron	220	15	0 out of 5	N/A	\$0
Transmission Main	8030	P-117	WW	Providence St.	12	Ductile Iron	21	15	0 out of 5	N/A	\$0
Transmission Main	8031	P-46	WW	Providence St.	12	Ductile Iron	3	15	0 out of 5	N/A	\$0
Distribution Main	8583	P-994	WW	Providence St.	10	Cast Iron	102	91	1.72 out of 5	\$442	45,018
Distribution Main	8584	P-994	WW	Providence St.	10	Cast Iron	136	91	1.72 out of 5	\$442	60,077
Distribution Main	8585	P-994	WW	Providence St.	10	Cast Iron	79	91	1.72 out of 5	\$442	34,867
Distribution Main	8586	P-994	WW	Providence St.	10	Cast Iron	298	91	1.72 out of 5	\$442	131,881
Distribution Main	8591	P-1685	WW	Providence St.	6	Cast Iron	342	134	2.57 out of 5	\$442	151,288
Distribution Main	8592	P-994	WW	Providence St.	10	Cast Iron	12	91	1.72 out of 5	\$442	5,395
Distribution Main	8593	P-994	WW	Providence St.	10	Cast Iron	69	91	1.72 out of 5	\$442	30,310
Distribution Main	8594	P-994	WW	Providence St.	10	Cast Iron	105	91	1.72 out of 5	\$442	46,272
Distribution Main	9057		WW	Providence St.	8	Ductile Iron	1	25	0.14 out of 5	N/A	\$0
Distribution Main	9088		WW	Providence St.	8	Ductile Iron	3	12	0 out of 5	N/A	\$0
Transmission Main	9393	P-153	WW	Providence St.	12	Ductile Iron	4	15	0 out of 5	N/A	\$0
Transmission Main	9398	P-215	WW	Providence St.	12	Ductile Iron	18	15	0 out of 5	N/A	\$0
Distribution Main	9410	P-70	WW	Providence St.	10	Cast Iron	397	UNK	1.14 out of 5	\$442	175,536
Distribution Main	9418	P-998	WW	Providence St.	6	Cast Iron	11	134	2.57 out of 5	\$442	4,851
Distribution Main	9523	P-305	WW	Providence St.	10	Cast Iron	116	91	1.72 out of 5	\$442	51,251
Distribution Main	9524	P-305	WW	Providence St.	10	Cast Iron	470	91	1.72 out of 5	\$442	207,897
Distribution Main	9525	P-1227	WW	Providence St.	8	Ductile Iron	70	25	0.14 out of 5	N/A	\$0
Distribution Main	9526	P-1227	WW	Providence St.	8	Ductile Iron	74	25	0.14 out of 5	N/A	\$0
Distribution Main	9527	P-1685	WW	Providence St.	6	Cast Iron	91	134	2.57 out of 5	\$442	40,300
Distribution Main	9528	P-1685	WW	Providence St.	6	Cast Iron	59	134	2.57 out of 5	\$442	25,859
Distribution Main	9867	P-1764	WW	Providence St.	8	Cast Iron	32	15	1.14 out of 5	N/A	\$0
Distribution Main	9868	P-1762	WW	Providence St.	8	Cast Iron	54	91	1.72 out of 5	\$442	23,698
Distribution Main	9869	P-1762	WW	Providence St.	8	Ductile Iron	24	15	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10417	P-1764	WW	Providence St.	8	Ductile Iron	21	15	0 out of 5	N/A	\$0
Distribution Main	10419	P-223	WW	Providence St.	10	Ductile Iron	28	15	0 out of 5	N/A	\$0
Transmission Main	10970	P-117	WW	Providence St.	12	Ductile Iron	234	15	0 out of 5	N/A	\$0
Transmission Main	10971	P-46	WW	Providence St.	12	Ductile Iron	200	15	0 out of 5	N/A	\$0
Transmission Main	11010	P-117	WW	Providence St.	12	Ductile Iron	3	15	0 out of 5	N/A	\$0
Distribution Main	11180	P-1023	WW	Providence St.	6	Cast Iron	81	134	2.57 out of 5	\$442	35,797
Distribution Main	11181	P-1023	WW	Providence St.	6	Cast Iron	36	134	2.57 out of 5	\$442	15,727
Distribution Main	11182	P-1023	WW	Providence St.	6	Cast Iron	11	134	2.57 out of 5	\$442	4,979
Distribution Main	11215	P-1316	WW	Providence St.	8	Ductile Iron	32	25	0.14 out of 5	N/A	\$0
Distribution Main	11580	P-1714	WW	Providence St.	10	Cast Iron	41	UNK	1.14 out of 5	\$442	18,148
Distribution Main	11581	P-70	WW	Providence St.	10	Cast Iron	32	UNK	1.14 out of 5	\$442	14,330
Distribution Main	11751	P-1701	WW	Providence St.	10	Cast Iron	264	91	1.72 out of 5	\$442	116,897
Distribution Main	11752	P-1701	WW	Providence St.	10	Cast Iron	248	91	1.72 out of 5	\$442	109,783
Distribution Main	12003	P-1018	WW	Providence St.	6	Cast Iron	373	134	2.57 out of 5	\$442	164,758
Distribution Main	12061	P-1686	WW	Providence St.	6	Ductile Iron	48	30	0.85 out of 5	\$442	21,008
Distribution Main	9362		WW	Pulaski St	6	Ductile Iron	16	14	0.71 out of 5	N/A	\$0
Transmission Main	170	P-1127	WW	Pulaski St.	12	Ductile Iron	126	14	0 out of 5	N/A	\$0
Transmission Main	171	P-1127	WW	Pulaski St.	12	Ductile Iron	168	14	0 out of 5	N/A	\$0
Transmission Main	172	P-1602	WW	Pulaski St.	12	Ductile Iron	127	14	0 out of 5	N/A	\$0
Transmission Main	928	P-596	WW	Pulaski St.	12	Ductile Iron	220	14	0 out of 5	N/A	\$0
Transmission Main	929	P-594	WW	Pulaski St.	12	Ductile Iron	220	14	0 out of 5	N/A	\$0
Transmission Main	930	P-1126	WW	Pulaski St.	12	Ductile Iron	167	14	0 out of 5	N/A	\$0
Transmission Main	931	P-1126	WW	Pulaski St.	12	Ductile Iron	346	14	0 out of 5	N/A	\$0
Transmission Main	933	P-593	WW	Pulaski St.	12	Ductile Iron	141	14	0 out of 5	N/A	\$0
Transmission Main	934	P-602	WW	Pulaski St.	12	Ductile Iron	143	14	0 out of 5	N/A	\$0
Transmission Main	935	P-602	WW	Pulaski St.	12	Ductile Iron	45	14	0 out of 5	N/A	\$0
Transmission Main	1573	P-601	WW	Pulaski St.	12	Ductile Iron	146	14	0 out of 5	N/A	\$0
Transmission Main	1574	P-605	WW	Pulaski St.	12	Ductile Iron	396	14	0 out of 5	N/A	\$0
Transmission Main	1575	P-605	WW	Pulaski St.	12	Ductile Iron	221	14	0 out of 5	N/A	\$0
Transmission Main	1576	P-609	WW	Pulaski St.	12	Ductile Iron	243	14	0 out of 5	N/A	\$0
Transmission Main	1887	P-1990	WW	Pulaski St.	12	Ductile Iron	26	14	0 out of 5	N/A	\$0
Transmission Main	1889	P-1990	WW	Pulaski St.	12	Ductile Iron	384	14	0 out of 5	N/A	\$0
Transmission Main	1892	P-1990	WW	Pulaski St.	12	Ductile Iron	25	14	0 out of 5	N/A	\$0
Distribution Main	5383		WW	Pulaski St.	8	Ductile Iron	30	14	0 out of 5	N/A	\$0
Transmission Main	5384	P-599	WW	Pulaski St.	12	Ductile Iron	42	14	0 out of 5	N/A	\$0
Transmission Main	5385	P-599	WW	Pulaski St.	12	Ductile Iron	198	14	0 out of 5	N/A	\$0
Transmission Main	8143	P-601	WW	Pulaski St.	12	Ductile Iron	108	14	0 out of 5	N/A	\$0
Transmission Main	8144	P-609	WW	Pulaski St.	12	Ductile Iron	41	14	0 out of 5	N/A	\$0
Distribution Main	9358		WW	Pulaski St.	8	Ductile Iron	27	14	0 out of 5	N/A	\$0
Distribution Main	9375		WW	Pulaski St.	8	Ductile Iron	3	14	0 out of 5	N/A	\$0
Distribution Main	9895	P-8012	WW	Pulaski St.	6	Cast Iron	10	UNK	1.85 out of 5	\$442	4,494
Transmission Main	11044	P-1127	WW	Pulaski St.	12	Ductile Iron	46	14	0 out of 5	N/A	\$0
Transmission Main	11149	P-1990	WW	Pulaski St.	12	Ductile Iron	8	14	0 out of 5	N/A	\$0
Transmission Main	11150	P-1990	WW	Pulaski St.	12	Ductile Iron	15	14	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11301	P-599	WW	Pulaski St.	12	Ductile Iron	11	14	0 out of 5	N/A	\$0
Transmission Main	11563	P-1126	WW	Pulaski St.	12	Ductile Iron	6	14	0 out of 5	N/A	\$0
Transmission Main	11747	P-1127	WW	Pulaski St.	12	Ductile Iron	71	14	0 out of 5	N/A	\$0
Transmission Main	11750	P-1990	WW	Pulaski St.	12	Ductile Iron	8	14	0 out of 5	N/A	\$0
Transmission Main	12007	P-1126	WW	Pulaski St.	12	Ductile Iron	103	14	0 out of 5	N/A	\$0
Distribution Main	1830	P-491	WW	Quaker Dr.	8	Asbestos Cement	245	54	1.14 out of 5	\$442	108,342
Distribution Main	3428	P-494	WW	Quaker Dr.	8	Asbestos Cement	238	54	1.14 out of 5	\$442	105,002
Distribution Main	3429	P-494	WW	Quaker Dr.	8	Asbestos Cement	437	54	1.14 out of 5	\$442	193,181
Distribution Main	3545	P-492	WW	Quaker Dr.	8	Asbestos Cement	434	54	1.14 out of 5	\$442	192,044
Distribution Main	4647	P-491	WW	Quaker Dr.	8	Asbestos Cement	364	54	1.14 out of 5	\$442	161,050
Distribution Main	10152	P-491	WW	Quaker Dr.	8	Asbestos Cement	42	54	1.14 out of 5	\$442	18,516
Distribution Main	8517	P-2895	WW	Quaker Lane	6	Ductile Iron	383	17	0.71 out of 5	N/A	\$0
Distribution Main	8518	P-2895	WW	Quaker Lane	6	Ductile Iron	20	17	0.71 out of 5	N/A	\$0
Distribution Main	8519	P-2894	WW	Quaker Lane	6	Ductile Iron	54	20	0.71 out of 5	N/A	\$0
Distribution Main	8520	P-2894	WW	Quaker Lane	6	Ductile Iron	37	20	0.71 out of 5	N/A	\$0
Transmission Main	66	P-10006	WW	Quaker Ln	12	Ductile Iron	180	15	0 out of 5	N/A	\$0
Transmission Main	67	P-10006	WW	Quaker Ln	12	Ductile Iron	75	15	0 out of 5	N/A	\$0
Transmission Main	9069	P-10006	WW	Quaker Ln	12	Ductile Iron	197	15	0 out of 5	N/A	\$0
Distribution Main	9070		WW	Quaker Ln	6	Ductile Iron	24	15	0.71 out of 5	N/A	\$0
Distribution Main	9698		WW	Quaker Ln	6	Ductile Iron	64	UNK	0.71 out of 5	\$442	28,269
Distribution Main	9699		WW	Quaker Ln	6	Ductile Iron	12	16	0.71 out of 5	N/A	\$0
Distribution Main	9700		WW	Quaker Ln	6	Ductile Iron	57	UNK	0.71 out of 5	\$442	25,220
Transmission Main	9860	P-10006	WW	Quaker Ln	12	Ductile Iron	338	15	0 out of 5	N/A	\$0
Transmission Main	9861	P-10006	WW	Quaker Ln	16	Ductile Iron	23	15	0 out of 5	N/A	\$0
Transmission Main	10141	P-2892	WW	Quaker Ln	16	Ductile Iron	303	5	0 out of 5	N/A	\$0
Transmission Main	10142	P-2892	WW	Quaker Ln	16	Ductile Iron	795	5	0 out of 5	N/A	\$0
Transmission Main	10143	P-2970	WW	Quaker Ln	12	Ductile Iron	21	5	0 out of 5	N/A	\$0
Distribution Main	10145		WW	Quaker Ln	6	Ductile Iron	6	5	0.71 out of 5	N/A	\$0
Distribution Main	10146		WW	Quaker Ln	6	Ductile Iron	16	5	0.71 out of 5	N/A	\$0
Transmission Main	11014	P-10006	WW	Quaker Ln	12	Ductile Iron	33	15	0 out of 5	N/A	\$0
Transmission Main	11022	P-10006	WW	Quaker Ln	12	Ductile Iron	26	15	0 out of 5	N/A	\$0
Transmission Main	11216	P-2892	WW	Quaker Ln	16	Ductile Iron	211	5	0 out of 5	N/A	\$0
Transmission Main	11618	P-10006	WW	Quaker Ln	16	Ductile Iron	6	15	0 out of 5	N/A	\$0
Distribution Main	1875	P-485	WW	Quaker Ln.	8	PVC	86	38	0.43 out of 5	\$442	38,122
Distribution Main	1984		WW	Quaker Ln.	8	Asbestos Cement	8	39	1 out of 5	\$442	3,539
Distribution Main	3394	P-485	WW	Quaker Ln.	8	PVC	385	38	0.43 out of 5	\$442	170,276
Distribution Main	3395	P-485	WW	Quaker Ln.	8	PVC	351	38	0.43 out of 5	\$442	155,164
Distribution Main	3535	P-10084	WW	Quaker Ln.	8	Asbestos Cement	271	45	1.14 out of 5	\$442	120,000
Distribution Main	3536	P-10084	WW	Quaker Ln.	8	Asbestos Cement	1,090	45	1.14 out of 5	\$442	481,637
Distribution Main	3958	P-485	WW	Quaker Ln.	8	PVC	38	38	0.43 out of 5	\$442	16,771
Distribution Main	3959	P-485	WW	Quaker Ln.	8	PVC	104	38	0.43 out of 5	\$442	46,051
Distribution Main	5063	P-484	WW	Quaker Ln.	8	PVC	355	38	0.43 out of 5	\$442	157,085
Distribution Main	5081		WW	Quaker Ln.	8	Asbestos Cement	15	39	1 out of 5	\$442	6,546
Distribution Main	9071		WW	Quaker Ln.	6	Ductile Iron	16	15	0.71 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11285	P-484	WW	Quaker Ln.	8	PVC	31	38	0.43 out of 5	\$442	13,681
Distribution Main	11286	P-484	WW	Quaker Ln.	8	PVC	17	38	0.43 out of 5	\$442	7,412
Distribution Main	11763	P-485	WW	Quaker Ln.	8	PVC	42	38	0.43 out of 5	\$442	18,461
Distribution Main	8660	P-879	WW	Queen Ann Ct.	8	Ductile Iron	16	16	0 out of 5	N/A	\$0
Distribution Main	8661	P-879	WW	Queen Ann Ct.	8	Ductile Iron	255	16	0 out of 5	N/A	\$0
Distribution Main	10786	P-338	WW	Queen Av	8	Ductile Iron	435	0	0 out of 5	N/A	\$0
Distribution Main	10878	P-334	WW	Queen Av	8	Ductile Iron	13	0	0 out of 5	N/A	\$0
Distribution Main	11744	P-338	WW	Queen Av	8	Ductile Iron	224	0	0 out of 5	N/A	\$0
Distribution Main	12154	P-338	WW	Queen Av	8	Ductile Iron	299	0	0 out of 5	N/A	\$0
Distribution Main	12197	P-338	WW	Queen Av	8	Ductile Iron	367	0	0 out of 5	N/A	\$0
Distribution Main	1802	P-1389	WW	Quill Dr.	8	Ductile Iron	226	28	0.14 out of 5	\$442	99,757
Distribution Main	4452	P-41	WW	Quill Dr.	8	Ductile Iron	5	28	0.14 out of 5	\$442	2,037
Distribution Main	4453	P-41	WW	Quill Dr.	8	Ductile Iron	44	28	0.14 out of 5	\$442	19,616
Distribution Main	4556	P-41	WW	Quill Dr.	6	Ductile Iron	412	28	0.85 out of 5	\$442	182,017
Distribution Main	10642		WW	Quinlan St	8	Ductile Iron	150	2	0 out of 5	N/A	\$0
Distribution Main	10643		WW	Quinlan St	8	Ductile Iron	170	2	0 out of 5	N/A	\$0
Distribution Main	9499		WW	Quiver Dr	8	Asbestos Cement	85	46	1.14 out of 5	\$442	37,451
Distribution Main	1126	P-43	WW	Quiver Dr.	8	Ductile Iron	338	28	0.14 out of 5	\$442	149,539
Distribution Main	1127	P-43	WW	Quiver Dr.	8	Ductile Iron	212	28	0.14 out of 5	\$442	93,533
Distribution Main	8847	P-692	WW	Rathburn St.	6	Asbestos Cement	542	63	2 out of 5	\$442	239,744
Distribution Main	9907	P-1946	WW	Red Brook Ln	8	Ductile Iron	90	13	0 out of 5	N/A	\$0
Distribution Main	9908		WW	Red Brook Ln	8	Ductile Iron	37	13	0 out of 5	N/A	\$0
Distribution Main	9909	P-1946	WW	Red Brook Ln	8	Ductile Iron	58	13	0 out of 5	N/A	\$0
Distribution Main	8048	P-776	WW	Regnaiere Ct	6	PVC	206	UNK	0.99 out of 5	\$442	90,951
Distribution Main	4828	P-518	WW	Rei St.	6	Asbestos Cement	134	72	2 out of 5	\$442	59,185
Distribution Main	9250	P-1131	WW	Remington St	8	Ductile Iron	8	13	0 out of 5	N/A	\$0
Distribution Main	9251	P-1131	WW	Remington St	8	Ductile Iron	24	13	0 out of 5	N/A	\$0
Distribution Main	9254		WW	Remington St	8	Ductile Iron	8	13	0 out of 5	N/A	\$0
Distribution Main	9255		WW	Remington St	6	Ductile Iron	12	13	0.71 out of 5	N/A	\$0
Distribution Main	11562	P-1131	WW	Remington St	8	Ductile Iron	8	13	0 out of 5	N/A	\$0
Distribution Main	925		WW	Remington St.	6	Cast Iron	248	124	3.29 out of 5	\$442	109,683
Distribution Main	3501	P-1906	WW	Renaudet St	0.75	Unknown	416	UNK	1.42 out of 5	\$442	183,831
Distribution Main	8400	P-1906	WW	Renaudet St	8	Ductile Iron	30	10	0 out of 5	N/A	\$0
Distribution Main	8401	P-1906	WW	Renaudet St	8	Ductile Iron	11	10	0 out of 5	N/A	\$0
Distribution Main	9675	P-1906	WW	Renaudet St	0.75	Unknown	2	10	1.42 out of 5	N/A	\$0
Distribution Main	322		WW	Renehan Ct	2	Unknown	163	UNK	1.42 out of 5	\$442	71,957
Distribution Main	3118	P-526	WW	Revere Av	6	Asbestos Cement	39	78	2 out of 5	\$442	17,084
Distribution Main	3119	P-526	WW	Revere Av	6	Asbestos Cement	206	78	2 out of 5	\$442	91,043
Distribution Main	9492	P-526	WW	Revere Av	6	Asbestos Cement	188	78	2 out of 5	\$442	83,309
Distribution Main	10624	P-397	WW	Revere Av	8	Ductile Iron	350	2	0 out of 5	N/A	\$0
Distribution Main	10625	P-397	WW	Revere Av	8	Ductile Iron	402	2	0 out of 5	N/A	\$0
Distribution Main	10626	P-392	WW	Revere Av	8	Ductile Iron	156	2	0 out of 5	N/A	\$0
Distribution Main	10627	P-390	WW	Revere Av	8	Ductile Iron	172	2	0 out of 5	N/A	\$0
Distribution Main	10628	P-390	WW	Revere Av	8	Ductile Iron	272	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10898	P-392	WW	Revere Av	8	Ductile Iron	287	2	0 out of 5	N/A	\$0
Distribution Main	11692	P-10028	WW	Revere Av	8	Ductile Iron	185	2	0 out of 5	N/A	\$0
Distribution Main	11693	P-393	WW	Revere Av	8	Ductile Iron	56	2	0 out of 5	N/A	\$0
Distribution Main	213	P-335	WW	Rex St.	8	Ductile Iron	34	19	0 out of 5	N/A	\$0
Distribution Main	4337	P-336	WW	Rex St.	8	Ductile Iron	205	19	0 out of 5	N/A	\$0
Distribution Main	4338	P-336	WW	Rex St.	8	Ductile Iron	253	19	0 out of 5	N/A	\$0
Distribution Main	10879	P-335	WW	Rex St.	8	Ductile Iron	264	19	0 out of 5	N/A	\$0
Distribution Main	8398	P-1232	WW	Richard St	8	Ductile Iron	17	10	0 out of 5	N/A	\$0
Distribution Main	8399	P-1232	WW	Richard St	8	Ductile Iron	3	10	0 out of 5	N/A	\$0
Distribution Main	8465	P-1232	WW	Richard St	6	Ductile Iron	4	10	0.71 out of 5	N/A	\$0
Distribution Main	3527	P-1232	WW	Richard St.	6	Asbestos Cement	505	64	2 out of 5	\$442	223,322
Distribution Main	10629	P-389	WW	Ridge St	8	Ductile Iron	220	2	0 out of 5	N/A	\$0
Distribution Main	10630	P-387	WW	Ridge St	8	Ductile Iron	178	2	0 out of 5	N/A	\$0
Distribution Main	11694	P-387	WW	Ridge St	8	Ductile Iron	66	2	0 out of 5	N/A	\$0
Distribution Main	12177	P-389	WW	Ridge St	8	Ductile Iron	7	2	0 out of 5	N/A	\$0
Distribution Main	3269	P-738	WW	Rita St.	8	Ductile Iron	492	18	0 out of 5	N/A	\$0
Distribution Main	35	P-1953	WW	Ritchotte Court	6	Asbestos Cement	33	39	1.71 out of 5	\$442	14,462
Distribution Main	8841	P-1953	WW	Ritchotte Court	6	Asbestos Cement	184	39	1.71 out of 5	\$442	81,184
Distribution Main	8842	P-1953	WW	Ritchotte Court	6	Asbestos Cement	177	39	1.71 out of 5	\$442	78,416
Distribution Main	2138	P-287	WW	River Ave.	6	Ductile Iron	304	26	0.85 out of 5	\$442	134,236
Distribution Main	2139	P-287	WW	River Ave.	6	Ductile Iron	508	26	0.85 out of 5	\$442	224,475
Distribution Main	524		WW	River Farm Lane	6	PVC	324	UNK	0.99 out of 5	\$442	143,148
Transmission Main	525	P-1776	WW	River Farms Dr.	12	PVC	254	30	0.43 out of 5	\$442	112,133
Transmission Main	993	P-1778	WW	River Farms Dr.	12	PVC	247	30	0.43 out of 5	\$442	109,329
Transmission Main	994	P-1780	WW	River Farms Dr.	12	PVC	413	30	0.43 out of 5	\$442	182,466
Distribution Main	2089	P-884	WW	River Farms Dr.	8	PVC	278	29	0.43 out of 5	\$442	123,047
Distribution Main	2090	P-884	WW	River Farms Dr.	8	PVC	135	29	0.43 out of 5	\$442	59,491
Transmission Main	2091	P-881	WW	River Farms Dr.	12	PVC	153	30	0.43 out of 5	\$442	67,840
Transmission Main	2092	P-1773	WW	River Farms Dr.	12	PVC	191	30	0.43 out of 5	\$442	84,609
Transmission Main	8646	P-1325	WW	River Farms Dr.	12	PVC	75	30	0.43 out of 5	\$442	33,163
Transmission Main	8647	P-1325	WW	River Farms Dr.	12	PVC	160	30	0.43 out of 5	\$442	70,704
Transmission Main	8649	P-1325	WW	River Farms Dr.	12	PVC	244	30	0.43 out of 5	\$442	107,954
Transmission Main	8650	P-1326	WW	River Farms Dr.	12	PVC	353	30	0.43 out of 5	\$442	156,136
Transmission Main	8651	P-1326	WW	River Farms Dr.	12	PVC	175	30	0.43 out of 5	\$442	77,197
Transmission Main	8654	P-878	WW	River Farms Dr.	12	PVC	151	30	0.43 out of 5	\$442	66,589
Transmission Main	8655	P-878	WW	River Farms Dr.	12	PVC	119	30	0.43 out of 5	\$442	52,459
Transmission Main	8656	P-1780	WW	River Farms Dr.	12	PVC	149	30	0.43 out of 5	\$442	65,993
Transmission Main	8665	P-1325	WW	River Farms Dr.	12	PVC	121	30	0.43 out of 5	\$442	53,389
Transmission Main	8666	P-885	WW	River Farms Dr.	12	PVC	113	30	0.43 out of 5	\$442	49,860
Transmission Main	8671	P-1320	WW	River Farms Dr.	12	PVC	39	30	0.43 out of 5	\$442	17,309
Transmission Main	8672	P-1320	WW	River Farms Dr.	12	PVC	481	30	0.43 out of 5	\$442	212,607
Transmission Main	8807	P-1778	WW	River Farms Dr.	12	PVC	188	30	0.43 out of 5	\$442	83,221
Transmission Main	8808	P-881	WW	River Farms Dr.	12	PVC	194	30	0.43 out of 5	\$442	85,886
Transmission Main	8810	P-1319	WW	River Farms Dr.	12	PVC	295	30	0.43 out of 5	\$442	130,321

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	8817	P-886	WW	River Farms Dr.	12	PVC	345	30	0.43 out of 5	\$442	152,499
Transmission Main	8818	P-1709	WW	River Farms Dr.	12	PVC	403	30	0.43 out of 5	\$442	177,972
Transmission Main	10840	P-1772	WW	River Farms Dr.	12	PVC	7	30	0.43 out of 5	\$442	2,950
Transmission Main	10841	P-1772	WW	River Farms Dr.	12	PVC	145	30	0.43 out of 5	\$442	63,909
Transmission Main	11153	P-1773	WW	River Farms Dr.	12	PVC	59	30	0.43 out of 5	\$442	26,083
Transmission Main	11489	P-1326	WW	River Farms Dr.	12	PVC	12	30	0.43 out of 5	\$442	5,226
Transmission Main	1997	P-1264	WW	River Farms Dr. Easement	12	PVC	894	30	0.43 out of 5	\$442	395,224
Transmission Main	10694		WW	River Rd.	42	Asbestos Cement	273	UNK	0.85 out of 5	\$442	120,622
Distribution Main	10312	P-231	WW	River St	8	Ductile Iron	65	5	0 out of 5	N/A	\$0
Transmission Main	10319		WW	River St	16	Ductile Iron	34	5	0 out of 5	N/A	\$0
Distribution Main	10418	P-224	WW	River St	10	Ductile Iron	19	5	0 out of 5	N/A	\$0
Transmission Main	10724		WW	River St	16	Ductile Iron	297	1	0 out of 5	N/A	\$0
Transmission Main	10725		WW	River St	16	Ductile Iron	235	1	0 out of 5	N/A	\$0
Distribution Main	10726	P-231	WW	River St	8	Ductile Iron	286	1	0 out of 5	N/A	\$0
Distribution Main	10727	P-231	WW	River St	8	Ductile Iron	337	1	0 out of 5	N/A	\$0
Transmission Main	11712		WW	River St	16	Ductile Iron	166	5	0 out of 5	N/A	\$0
Transmission Main	12144		WW	River St	16	Ductile Iron	10	1	0 out of 5	N/A	\$0
Distribution Main	1731	P-657	WW	Riverdale Ave.	2	Cast Iron	149	134	3.29 out of 5	\$442	65,712
Distribution Main	4318	P-658	WW	Riverdale Ave.	4	Cast Iron	235	134	3.29 out of 5	\$442	103,879
Distribution Main	4319	P-658	WW	Riverdale Ave.	4	Cast Iron	386	134	3.29 out of 5	\$442	170,827
Distribution Main	4002	P-1970	WW	Riverside Terrace	1	Copper	198	69	2.43 out of 5	\$442	87,633
Distribution Main	181	P-665	WW	Robert St	6	Ductile Iron	12	15	0.71 out of 5	N/A	\$0
Distribution Main	9835	P-1971	WW	Robert St	8	Ductile Iron	13	7	0 out of 5	N/A	\$0
Distribution Main	9836	P-1971	WW	Robert St	8	Ductile Iron	21	7	0 out of 5	N/A	\$0
Distribution Main	9840	P-678	WW	Robert St	6	Ductile Iron	4	7	0.71 out of 5	N/A	\$0
Distribution Main	9841	P-1972	WW	Robert St	6	Ductile Iron	11	7	0.71 out of 5	N/A	\$0
Distribution Main	9999		WW	Robert St	6	Ductile Iron	28	15	0.71 out of 5	N/A	\$0
Distribution Main	10006	P-666	WW	Robert St	6	Ductile Iron	9	15	0.71 out of 5	N/A	\$0
Distribution Main	135	P-678	WW	Robert St.	6	Cast Iron	444	90	2.43 out of 5	\$442	196,409
Distribution Main	136	P-678	WW	Robert St.	6	Cast Iron	34	90	2.43 out of 5	\$442	14,850
Distribution Main	179	P-666	WW	Robert St.	4	Cast Iron	229	90	3.14 out of 5	\$442	101,371
Distribution Main	344	P-673	WW	Robert St.	6	Cast Iron	402	90	2.43 out of 5	\$442	177,716
Distribution Main	345	P-665	WW	Robert St.	4	Cast Iron	40	90	3.14 out of 5	\$442	17,495
Distribution Main	688	P-665	WW	Robert St.	4	Cast Iron	232	90	3.14 out of 5	\$442	102,430
Distribution Main	4281	P-678	WW	Robert St.	6	Cast Iron	59	90	2.43 out of 5	\$442	26,186
Distribution Main	1822	P-143	WW	Robin Ln.	8	Asbestos Cement	111	50	1.14 out of 5	\$442	49,142
Distribution Main	1823	P-143	WW	Robin Ln.	8	Asbestos Cement	51	50	1.14 out of 5	\$442	22,423
Distribution Main	2209	P-144	WW	Robin Ln.	8	Asbestos Cement	331	50	1.14 out of 5	\$442	146,224
Distribution Main	2214	P-146	WW	Robin Ln.	8	Asbestos Cement	93	50	1.14 out of 5	\$442	40,953
Distribution Main	2215	P-146	WW	Robin Ln.	8	Asbestos Cement	340	50	1.14 out of 5	\$442	150,411
Distribution Main	2217	P-497	WW	Robin Ln.	8	Asbestos Cement	56	51	1.14 out of 5	\$442	24,722
Distribution Main	3871		WW	Robin Ln.	8	Asbestos Cement	10	51	1.14 out of 5	\$442	4,415
Distribution Main	4138	P-148	WW	Robin Ln.	8	Asbestos Cement	547	50	1.14 out of 5	\$442	241,655
Distribution Main	627	P-1700	WW	Robinson Way	8	Ductile Iron	155	14	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	932	P-595	WW	Robinson Way	8	Ductile Iron	513	14	0 out of 5	N/A	\$0
Distribution Main	4706	P-588	WW	Robinson Way	8	Ductile Iron	257	14	0 out of 5	N/A	\$0
Distribution Main	4707	P-590	WW	Robinson Way	8	Ductile Iron	153	14	0 out of 5	N/A	\$0
Distribution Main	4709	P-587	WW	Robinson Way	8	Ductile Iron	223	14	0 out of 5	N/A	\$0
Distribution Main	8142	P-595	WW	Robinson Way	8	Ductile Iron	165	14	0 out of 5	N/A	\$0
Distribution Main	8145	P-590	WW	Robinson Way	8	Ductile Iron	19	14	0 out of 5	N/A	\$0
Distribution Main	8146	P-590	WW	Robinson Way	8	Ductile Iron	37	14	0 out of 5	N/A	\$0
Distribution Main	8147	P-587	WW	Robinson Way	8	Ductile Iron	38	14	0 out of 5	N/A	\$0
Distribution Main	8148	P-587	WW	Robinson Way	8	Ductile Iron	3	14	0 out of 5	N/A	\$0
Distribution Main	8167	P-1700	WW	Robinson Way	8	Ductile Iron	130	14	0 out of 5	N/A	\$0
Distribution Main	9365	P-595	WW	Robinson Way	8	Ductile Iron	39	14	0 out of 5	N/A	\$0
Distribution Main	9366	P-595	WW	Robinson Way	8	Ductile Iron	33	14	0 out of 5	N/A	\$0
Distribution Main	10385	P-1700	WW	Robinson Way	8	Ductile Iron	12	14	0 out of 5	N/A	\$0
Distribution Main	5190	P-312	WW	Rolling Green Ln.	8	Asbestos Cement	660	47	1.14 out of 5	\$442	291,764
Distribution Main	5264	P-312	WW	Rolling Green Ln.	8	Asbestos Cement	9	47	1.14 out of 5	\$442	3,913
Distribution Main	348	P-674	WW	Roosevelt St.	1	PVC	170	19	1.71 out of 5	N/A	\$0
Distribution Main	2541	P-31	WW	Rotary Dr.	8	Asbestos Cement	89	57	1.14 out of 5	\$442	39,508
Distribution Main	2542	P-1943	WW	Rotary Dr.	8	Asbestos Cement	36	57	1.14 out of 5	\$442	15,979
Distribution Main	2543	P-1943	WW	Rotary Dr.	8	Asbestos Cement	384	57	1.14 out of 5	\$442	169,646
Distribution Main	2544	P-1944	WW	Rotary Dr.	6	Asbestos Cement	71	57	1.85 out of 5	\$442	31,298
Distribution Main	2547	P-29	WW	Rotary Dr.	8	Asbestos Cement	244	57	1.14 out of 5	\$442	107,855
Distribution Main	4560	P-32	WW	Rotary Dr.	8	Asbestos Cement	324	57	1.14 out of 5	\$442	143,383
Distribution Main	4561	P-31	WW	Rotary Dr.	8	Asbestos Cement	137	57	1.14 out of 5	\$442	60,766
Distribution Main	4347	P-1097	WW	Rowland St.	6	Asbestos Cement	196	57	1.85 out of 5	\$442	86,444
Distribution Main	2345	P-95	WW	Royal Dr.	8	Asbestos Cement	594	42	1.14 out of 5	\$442	262,740
Distribution Main	2346	P-95	WW	Royal Dr.	8	Asbestos Cement	258	42	1.14 out of 5	\$442	114,153
Distribution Main	11168	P-95	WW	Royal Dr.	8	Asbestos Cement	19	42	1.14 out of 5	\$442	8,490
Distribution Main	1770	P-842	WW	Saddlebrook Dr.	8	PVC	365	31	0.43 out of 5	\$442	161,445
Distribution Main	3509	P-840	WW	Saddlebrook Dr.	8	PVC	315	31	0.43 out of 5	\$442	139,222
Distribution Main	3510	P-840	WW	Saddlebrook Dr.	8	PVC	83	31	0.43 out of 5	\$442	36,611
Distribution Main	11761	P-840	WW	Saddlebrook Dr.	8	PVC	251	31	0.43 out of 5	\$442	111,009
Transmission Main	2086	P-1779	WW	Sandpiper Drive	12	Ductile Iron	578	15	0 out of 5	N/A	\$0
Transmission Main	2087	P-1779	WW	Sandpiper Drive	12	Ductile Iron	14	15	0 out of 5	N/A	\$0
Distribution Main	8429	P-1796	WW	Schofield St	8	Ductile Iron	36	10	0 out of 5	N/A	\$0
Distribution Main	484	P-964	WW	Schofield St.	6	Asbestos Cement	177	58	1.85 out of 5	\$442	78,108
Distribution Main	485	P-964	WW	Schofield St.	6	Asbestos Cement	27	58	1.85 out of 5	\$442	11,909
Distribution Main	10120		WW	School St	1	Copper	11	89	2.57 out of 5	\$442	4,722
Distribution Main	3400		WW	School St.	2	Galvanized Iron	79	92	3.43 out of 5	\$442	35,077
Distribution Main	4078	P-1089	WW	School St.	6	Cast Iron	73	134	2.57 out of 5	\$442	32,361
Distribution Main	4079	P-1091	WW	School St.	6	Cast Iron	25	134	2.57 out of 5	\$442	10,853
Distribution Main	4080	P-1091	WW	School St.	6	Cast Iron	281	134	2.57 out of 5	\$442	124,081
Distribution Main	4086	P-1088	WW	School St.	6	Cast Iron	177	134	2.57 out of 5	\$442	78,068
Distribution Main	4716		WW	School St.	4	Cast Iron	282	89	3.14 out of 5	\$442	124,480
Distribution Main	5089	P-1091	WW	School St.	4	Cast Iron	80	89	3.14 out of 5	\$442	35,578

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11240	P-1091	WW	School St.	6	Cast Iron	54	134	2.57 out of 5	\$442	23,812
Distribution Main	10795	P-1989	WW	Second St	8	Ductile Iron	326	0	0 out of 5	N/A	\$0
Distribution Main	2545	P-38	WW	Service Rd.	6	Asbestos Cement	14	50	1.85 out of 5	\$442	6,394
Distribution Main	4454	P-40	WW	Service Rd.	8	Ductile Iron	225	28	0.14 out of 5	\$442	99,332
Distribution Main	4557	P-38	WW	Service Rd.	6	Asbestos Cement	476	50	1.85 out of 5	\$442	210,172
Distribution Main	4558	P-38	WW	Service Rd.	6	Asbestos Cement	8	50	1.85 out of 5	\$442	3,469
Distribution Main	4732	P-44	WW	Service Rd.	8	Ductile Iron	156	28	0.14 out of 5	\$442	69,099
Distribution Main	4747	P-42	WW	Service Rd.	8	Ductile Iron	3	28	0.14 out of 5	\$442	1,494
Distribution Main	4748	P-42	WW	Service Rd.	8	Ductile Iron	321	28	0.14 out of 5	\$442	141,863
Distribution Main	4749	P-1940	WW	Service Rd.	8	Ductile Iron	92	28	0.14 out of 5	\$442	40,599
Distribution Main	4750	P-1940	WW	Service Rd.	8	Ductile Iron	38	28	0.14 out of 5	\$442	17,007
Distribution Main	4432	P-362	WW	Seth Dr.	6	PVC	128	32	1.14 out of 5	\$442	56,750
Distribution Main	4434	P-361	WW	Seth Dr.	6	PVC	121	32	1.14 out of 5	\$442	53,543
Distribution Main	4435	P-361	WW	Seth Dr.	6	PVC	139	32	1.14 out of 5	\$442	61,507
Transmission Main	283	P-92	WW	Setian Ln.	20	Asbestos Cement	120	50	1.14 out of 5	\$442	53,025
Transmission Main	284	P-92	WW	Setian Ln.	12	Asbestos Cement	398	50	1.14 out of 5	\$442	176,072
Transmission Main	285	P-92	WW	Setian Ln.	12	Asbestos Cement	9	50	1.14 out of 5	\$442	3,950
Distribution Main	1348	P-121	WW	Setian Ln.	8	Asbestos Cement	11	43	1.14 out of 5	\$442	4,940
Transmission Main	1349	P-92	WW	Setian Ln.	12	Asbestos Cement	10	50	1.14 out of 5	\$442	4,494
Transmission Main	2324	P-1548	WW	Setian Ln.	12	Ductile Iron	172	19	0 out of 5	N/A	\$0
Transmission Main	2347	P-121	WW	Setian Ln.	20	Asbestos Cement	8	43	1.14 out of 5	\$442	3,561
Transmission Main	2348	P-92	WW	Setian Ln.	20	Asbestos Cement	19	50	1.14 out of 5	\$442	8,523
Transmission Main	2349	P-92	WW	Setian Ln.	20	Asbestos Cement	18	50	1.14 out of 5	\$442	7,903
Distribution Main	2350	P-121	WW	Setian Ln.	8	Asbestos Cement	86	43	1.14 out of 5	\$442	38,068
Transmission Main	5175	P-1468	WW	Setian Ln.	12	Asbestos Cement	371	50	1.14 out of 5	\$442	163,911
Transmission Main	5176	P-1468	WW	Setian Ln.	12	Asbestos Cement	581	50	1.14 out of 5	\$442	256,800
Transmission Main	5186	P-1467	WW	Setian Ln.	12	Asbestos Cement	513	50	1.14 out of 5	\$442	226,638
Distribution Main	10252	P-121	WW	Setian Ln.	8	Asbestos Cement	6	43	1.14 out of 5	\$442	2,467
Transmission Main	11020	P-92	WW	Setian Ln.	20	Asbestos Cement	7	50	1.14 out of 5	\$442	3,121
Distribution Main	389	P-496	WW	Shady Hill Dr.	8	Asbestos Cement	276	54	1.14 out of 5	\$442	122,201
Distribution Main	3541	P-493	WW	Shady Hill Dr.	8	Asbestos Cement	17	54	1.14 out of 5	\$442	7,303
Distribution Main	3542	P-493	WW	Shady Hill Dr.	8	Asbestos Cement	268	54	1.14 out of 5	\$442	118,458
Distribution Main	4648	P-493	WW	Shady Hill Dr.	8	Asbestos Cement	235	54	1.14 out of 5	\$442	103,819
Distribution Main	4649	P-493	WW	Shady Hill Dr.	8	Asbestos Cement	593	54	1.14 out of 5	\$442	262,090
Distribution Main	12046	P-493	WW	Shady Hill Dr.	8	Asbestos Cement	470	54	1.14 out of 5	\$442	207,528
Distribution Main	4433	P-363	WW	Shane Dr.	6	PVC	260	32	1.14 out of 5	\$442	114,735
Distribution Main	2075	P-866	WW	Shannon Ln.	8	Ductile Iron	20	26	0.14 out of 5	\$442	8,633
Distribution Main	2096	P-866	WW	Shannon Ln.	8	Ductile Iron	422	26	0.14 out of 5	\$442	186,495
Distribution Main	9771	P-614	WW	Sheffield Ave	8	Ductile Iron	199	8	0 out of 5	N/A	\$0
Distribution Main	9772	P-614	WW	Sheffield Ave	8	Ductile Iron	33	8	0 out of 5	N/A	\$0
Distribution Main	9781	P-630	WW	Sheffield Ave	8	Ductile Iron	93	8	0 out of 5	N/A	\$0
Distribution Main	9790	P-630	WW	Sheffield Ave	8	Ductile Iron	581	8	0 out of 5	N/A	\$0
Distribution Main	11604	P-615	WW	Sheffield Ave	8	Ductile Iron	19	8	0 out of 5	N/A	\$0
Distribution Main	11605	P-1385	WW	Sheffield Ave	8	Ductile Iron	29	8	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10313	P-243	WW	Sheldon St	8	Ductile Iron	580	5	0 out of 5	N/A	\$0
Distribution Main	9761	P-613	WW	Sherwood Ave	8	Ductile Iron	295	8	0 out of 5	N/A	\$0
Distribution Main	9773	P-613	WW	Sherwood Ave	8	Ductile Iron	27	8	0 out of 5	N/A	\$0
Distribution Main	9774	P-613	WW	Sherwood Ave	8	Ductile Iron	425	8	0 out of 5	N/A	\$0
Distribution Main	572	P-8040	WW	Shippee Ave.	8	Cast Iron	291	130	1.86 out of 5	\$442	128,409
Distribution Main	1972	P-741	WW	Shippee Ave.	6	Cast Iron	297	80	2.28 out of 5	\$442	131,288
Distribution Main	2494	P-737	WW	Shippee Ave.	8	Cast Iron	7	80	1.57 out of 5	\$442	2,882
Distribution Main	2865	P-737	WW	Shippee Ave.	8	Cast Iron	6	80	1.57 out of 5	\$442	2,525
Distribution Main	2866	P-736	WW	Shippee Ave.	6	Cast Iron	25	80	2.28 out of 5	\$442	10,843
Transmission Main	2867	P-717	WW	Shippee Ave.	12	Cast Iron	199	89	1.72 out of 5	\$442	88,069
Transmission Main	2868	P-717	WW	Shippee Ave.	12	Cast Iron	83	89	1.72 out of 5	\$442	36,758
Distribution Main	2869	P-709	WW	Shippee Ave.	8	Cast Iron	4	130	1.86 out of 5	\$442	1,655
Distribution Main	2870	P-709	WW	Shippee Ave.	8	Cast Iron	184	130	1.86 out of 5	\$442	81,323
Distribution Main	2871	P-711	WW	Shippee Ave.	8	Cast Iron	187	130	1.86 out of 5	\$442	82,679
Distribution Main	2872	P-713	WW	Shippee Ave.	8	Cast Iron	257	130	1.86 out of 5	\$442	113,422
Distribution Main	3201	P-737	WW	Shippee Ave.	6	Cast Iron	174	80	2.28 out of 5	\$442	77,008
Distribution Main	3260	P-712	WW	Shippee Ave.	8	Cast Iron	229	130	2.57 out of 5	\$442	101,190
Distribution Main	3270	P-737	WW	Shippee Ave.	8	Cast Iron	7	80	1.57 out of 5	\$442	2,930
Distribution Main	8824	P-739	WW	Shippee Ave.	6	Cast Iron	132	80	2.28 out of 5	\$442	58,391
Distribution Main	8825	P-739	WW	Shippee Ave.	6	Cast Iron	34	80	2.28 out of 5	\$442	15,233
Distribution Main	8826	P-739	WW	Shippee Ave.	8	Cast Iron	5	80	1.57 out of 5	\$442	2,245
Distribution Main	8827	P-736	WW	Shippee Ave.	6	Cast Iron	60	80	2.28 out of 5	\$442	26,587
Distribution Main	8828	P-709	WW	Shippee Ave.	8	Cast Iron	12	130	1.86 out of 5	\$442	5,431
Transmission Main	8829	P-717	WW	Shippee Ave.	12	Cast Iron	20	89	1.72 out of 5	\$442	8,950
Distribution Main	8936	P-192	WW	Shortway Dr	8	Ductile Iron	234	9	0 out of 5	N/A	\$0
Distribution Main	8943	P-197	WW	Shortway Dr	6	Ductile Iron	6	9	0.71 out of 5	N/A	\$0
Distribution Main	8962	P-200	WW	Shortway Dr	8	Ductile Iron	26	9	0 out of 5	N/A	\$0
Distribution Main	8965	P-200	WW	Shortway Dr	6	Ductile Iron	8	9	0.71 out of 5	N/A	\$0
Distribution Main	11526	P-1739	WW	Shortway Dr	8	Ductile Iron	28	9	0 out of 5	N/A	\$0
Distribution Main	11527	P-197	WW	Shortway Dr	8	Ductile Iron	17	9	0 out of 5	N/A	\$0
Distribution Main	3090	P-190	WW	Shortway Dr.	6	Asbestos Cement	185	69	2 out of 5	\$442	81,649
Distribution Main	5293	P-200	WW	Shortway Dr.	6	Asbestos Cement	214	62	2 out of 5	\$442	94,574
Distribution Main	5479	P-197	WW	Shortway Dr.	6	Asbestos Cement	222	69	2 out of 5	\$442	97,911
Distribution Main	9782	P-626	WW	Sidney St	8	Ductile Iron	63	8	0 out of 5	N/A	\$0
Distribution Main	9783	P-625	WW	Sidney St	8	Ductile Iron	241	8	0 out of 5	N/A	\$0
Distribution Main	9799	P-1963	WW	Sidney St	8	Ductile Iron	295	8	0 out of 5	N/A	\$0
Distribution Main	9800	P-1963	WW	Sidney St	8	Ductile Iron	15	8	0 out of 5	N/A	\$0
Distribution Main	10411	P-627	WW	Sidney St	8	Ductile Iron	61	8	0 out of 5	N/A	\$0
Distribution Main	10881	P-623	WW	Sidney St	8	Ductile Iron	148	8	0 out of 5	N/A	\$0
Distribution Main	10882	P-623	WW	Sidney St	8	Ductile Iron	192	8	0 out of 5	N/A	\$0
Distribution Main	11606	P-626	WW	Sidney St	8	Ductile Iron	158	8	0 out of 5	N/A	\$0
Transmission Main	8178	P-1710	WW	Silvercup Cir	12	Ductile Iron	530	12	0 out of 5	N/A	\$0
Transmission Main	10056	P-1522	WW	Silvercup Cir	12	Ductile Iron	210	12	0 out of 5	N/A	\$0
Transmission Main	10057	P-1522	WW	Silvercup Cir	12	Ductile Iron	294	12	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	10704	P-1521	WW	Silvercup Cir	12	Ductile Iron	14	12	0 out of 5	N/A	\$0
Transmission Main	10836	P-1521	WW	Silvercup Cir	12	Ductile Iron	11	12	0 out of 5	N/A	\$0
Transmission Main	10837	P-1521	WW	Silvercup Cir	12	Ductile Iron	363	12	0 out of 5	N/A	\$0
Transmission Main	10838	P-1523	WW	Silvercup Cir	12	Ductile Iron	222	12	0 out of 5	N/A	\$0
Transmission Main	10839	P-1523	WW	Silvercup Cir	12	Ductile Iron	160	12	0 out of 5	N/A	\$0
Distribution Main	4615	P-1469	WW	Silverwood Lane	8	Asbestos Cement	51	42	1.14 out of 5	\$442	22,518
Distribution Main	4616	P-1469	WW	Silverwood Lane	8	Asbestos Cement	791	42	1.14 out of 5	\$442	349,726
Distribution Main	4617	P-1469	WW	Silverwood Lane	8	Asbestos Cement	333	42	1.14 out of 5	\$442	147,348
Distribution Main	4618	P-126	WW	Silverwood Lane	8	Asbestos Cement	192	42	1.14 out of 5	\$442	84,887
Distribution Main	4619	P-126	WW	Silverwood Lane	8	Asbestos Cement	795	42	1.14 out of 5	\$442	351,209
Distribution Main	5177	P-1469	WW	Silverwood Lane	8	Asbestos Cement	10	42	1.14 out of 5	\$442	4,431
Distribution Main	12051	P-126	WW	Silverwood Lane	8	Asbestos Cement	328	42	1.14 out of 5	\$442	145,177
Distribution Main	9462	P-1857	WW	Simon Street	1.5	Unknown	135	UNK	1.42 out of 5	\$442	59,472
Distribution Main	105	P-1218	WW	Sisson St	1	Galvanized Iron	154	78	3.28 out of 5	\$442	68,244
Distribution Main	1517	P-919	WW	Smith St.	6	Cast Iron	130	134	2.57 out of 5	\$442	57,466
Distribution Main	1799	P-916	WW	Smith St.	6	Cast Iron	93	134	2.57 out of 5	\$442	41,118
Distribution Main	1800	P-916	WW	Smith St.	6	Cast Iron	428	134	2.57 out of 5	\$442	189,123
Distribution Main	9048	P-1957	WW	Solty'S Ct	6	Ductile Iron	87	15	0.71 out of 5	N/A	\$0
Distribution Main	11541		WW	Solty'S Ct	6	Ductile Iron	4	15	0.71 out of 5	N/A	\$0
Distribution Main	3351	P-793	WW	South St.	6	Asbestos Cement	180	65	2 out of 5	\$442	79,358
Distribution Main	3352	P-793	WW	South St.	6	Asbestos Cement	100	65	2 out of 5	\$442	44,328
Distribution Main	4276	P-5104	WW	Southview Ter.	8	Asbestos Cement	208	39	1 out of 5	\$442	92,110
Distribution Main	4277	P-5104	WW	Southview Ter.	8	Asbestos Cement	101	39	1 out of 5	\$442	44,644
Distribution Main	8159	P-5104	WW	Southview Ter.	8	Ductile Iron	66	15	0 out of 5	N/A	\$0
Distribution Main	8652	P-877	WW	Sparrow Cir	8	PVC	147	29	0.43 out of 5	\$442	65,145
Distribution Main	8653	P-877	WW	Sparrow Cir	8	PVC	2	29	0.43 out of 5	\$442	926
Distribution Main	2936	P-811	WW	Spencer St.	6	Asbestos Cement	515	69	2 out of 5	\$442	227,838
Distribution Main	3716	P-812	WW	Spencer St.	6	Asbestos Cement	365	69	2 out of 5	\$442	161,463
Distribution Main	3720	P-812	WW	Spencer St.	6	Asbestos Cement	129	69	2 out of 5	\$442	56,874
Distribution Main	8811	P-811	WW	Spencer St.	6	Asbestos Cement	19	69	2 out of 5	\$442	8,304
Distribution Main	8812	P-811	WW	Spencer St.	6	Asbestos Cement	7	69	2 out of 5	\$442	2,982
Distribution Main	3880	P-456	WW	Spring Meadow Circle	8	Ductile Iron	201	21	0.14 out of 5	N/A	\$0
Distribution Main	914		WW	Spring St.	2	Galvanized Iron	314	91	3.43 out of 5	\$442	138,633
Distribution Main	4081	P-1094	WW	Spring St.	2	Galvanized Iron	169	134	3.57 out of 5	\$442	74,728
Distribution Main	4084	P-1092	WW	Spring St.	6	Cast Iron	15	134	2.57 out of 5	\$442	6,608
Distribution Main	4085	P-1092	WW	Spring St.	6	Cast Iron	254	134	2.57 out of 5	\$442	112,072
Distribution Main	4713	P-1092	WW	Spring St.	6	Cast Iron	18	134	2.57 out of 5	\$442	7,877
Distribution Main	11772	P-1092	WW	Spring St.	6	Cast Iron	4	134	2.57 out of 5	\$442	1,706
Distribution Main	3571	P-104	WW	Spruce Ct	6	Asbestos Cement	13	41	1.85 out of 5	\$442	5,881
Distribution Main	4131	P-104	WW	Spruce Ct	6	Asbestos Cement	160	41	1.85 out of 5	\$442	70,574
Distribution Main	10400	P-1980	WW	St James St	8	Ductile Iron	206	8	0 out of 5	N/A	\$0
Distribution Main	9207	P-1034	WW	St Mary	8	Ductile Iron	136	8	0 out of 5	N/A	\$0
Distribution Main	9208	P-1034	WW	St Mary	8	Ductile Iron	230	8	0 out of 5	N/A	\$0
Distribution Main	10780	P-10065	WW	St. George St	8	Ductile Iron	140	0	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10781	P-10063	WW	St. George St	8	Ductile Iron	37	0	0 out of 5	N/A	\$0
Distribution Main	10782	P-10063	WW	St. George St	8	Ductile Iron	9	0	0 out of 5	N/A	\$0
Distribution Main	10783	P-357	WW	St. George St	8	Ductile Iron	239	0	0 out of 5	N/A	\$0
Distribution Main	10921	P-10065	WW	St. George St	8	Ductile Iron	37	0	0 out of 5	N/A	\$0
Distribution Main	10922	P-10065	WW	St. George St	8	Ductile Iron	84	0	0 out of 5	N/A	\$0
Distribution Main	11730	P-358	WW	St. George St	8	Ductile Iron	234	0	0 out of 5	N/A	\$0
Distribution Main	177	P-670	WW	St. John St.	6	Cast Iron	182	129	2.57 out of 5	\$442	80,598
Distribution Main	178	P-670	WW	St. John St.	6	Cast Iron	22	129	2.57 out of 5	\$442	9,746
Distribution Main	180	P-670	WW	St. John St.	6	Ductile Iron	11	15	0.71 out of 5	N/A	\$0
Distribution Main	3766	P-670	WW	St. John St.	6	Cast Iron	284	129	2.57 out of 5	\$442	125,458
Distribution Main	3767	P-670	WW	St. John St.	6	Cast Iron	112	129	2.57 out of 5	\$442	49,439
Distribution Main	12188		WW	St. Mary St.	6	Cast Iron	87	129	2.57 out of 5	\$442	38,360
Distribution Main	393	P-1437	WW	St. Onge Dr.	8	Ductile Iron	44	22	0.14 out of 5	N/A	\$0
Distribution Main	2314	P-1437	WW	St. Onge Dr.	8	Ductile Iron	5	22	0.14 out of 5	N/A	\$0
Distribution Main	2340	P-1433	WW	St. Onge Dr.	8	Asbestos Cement	23	39	1 out of 5	\$442	9,985
Distribution Main	4762	P-1434	WW	St. Onge Dr.	8	Asbestos Cement	402	39	1 out of 5	\$442	177,670
Distribution Main	4763	P-1434	WW	St. Onge Dr.	8	Asbestos Cement	112	39	1 out of 5	\$442	49,703
Distribution Main	4961	P-1179	WW	St. Onge Dr.	8	Asbestos Cement	342	39	1 out of 5	\$442	150,982
Distribution Main	3110	P-546	WW	Standard Ave.	2	Galvanized Iron	11	109	3.57 out of 5	\$442	4,936
Distribution Main	3970	P-546	WW	Standard Ave.	2	Galvanized Iron	324	109	3.57 out of 5	\$442	143,177
Distribution Main	4311	P-547	WW	Standard Ave.	6	Cast Iron	21	109	2.57 out of 5	\$442	9,148
Distribution Main	4312	P-547	WW	Standard Ave.	6	Cast Iron	668	109	2.57 out of 5	\$442	295,071
Distribution Main	8669	P-1777	WW	Starling Way	8	Ductile Iron	4	15	0 out of 5	N/A	\$0
Distribution Main	8670	P-1777	WW	Starling Way	8	Ductile Iron	399	15	0 out of 5	N/A	\$0
Distribution Main	9067	P-10015	WW	Starlite Ct	8	Ductile Iron	6	15	0 out of 5	N/A	\$0
Distribution Main	9068	P-10015	WW	Starlite Ct	8	Ductile Iron	186	15	0 out of 5	N/A	\$0
Distribution Main	10023	P-1757	WW	State St	8	Ductile Iron	325	6	0 out of 5	N/A	\$0
Distribution Main	4390	P-204	WW	Steven Dr.	8	Asbestos Cement	301	42	1.14 out of 5	\$442	133,024
Distribution Main	4391	P-204	WW	Steven Dr.	8	Asbestos Cement	632	42	1.14 out of 5	\$442	279,308
Distribution Main	3439	P-170	WW	Stoney Creek Dr.	8	Asbestos Cement	422	42	1.14 out of 5	\$442	186,308
Transmission Main	8396	P-1231	WW	Summit Ave	12	Ductile Iron	312	10	0 out of 5	N/A	\$0
Transmission Main	8397	P-1231	WW	Summit Ave	12	Ductile Iron	28	10	0 out of 5	N/A	\$0
Distribution Main	8404	P-1838	WW	Summit Ave	8	Ductile Iron	9	10	0 out of 5	N/A	\$0
Transmission Main	8440	P-1235	WW	Summit Ave	12	Ductile Iron	164	10	0 out of 5	N/A	\$0
Transmission Main	8464	P-1235	WW	Summit Ave	12	Ductile Iron	69	10	0 out of 5	N/A	\$0
Transmission Main	8469	P-978	WW	Summit Ave	12	Ductile Iron	255	10	0 out of 5	N/A	\$0
Transmission Main	8470	P-978	WW	Summit Ave	12	Ductile Iron	26	10	0 out of 5	N/A	\$0
Distribution Main	8471	P-1838	WW	Summit Ave	6	Ductile Iron	10	10	0.71 out of 5	N/A	\$0
Transmission Main	9673	P-1235	WW	Summit Ave	12	Ductile Iron	21	10	0 out of 5	N/A	\$0
Distribution Main	8462	P-1233	WW	Summit Ave / N Pleasant	6	Ductile Iron	26	10	0.71 out of 5	N/A	\$0
Transmission Main	9674	P-1233	WW	Summit Ave / N Pleasant	12	Ductile Iron	5	10	0 out of 5	N/A	\$0
Transmission Main	8394	P-1907	WW	Summit Ave / Pleasant St	12	Ductile Iron	142	10	0 out of 5	N/A	\$0
Distribution Main	1524	P-976	WW	Summit Ave.	6	Cast Iron	110	134	2.57 out of 5	\$442	48,785
Distribution Main	1525	P-976	WW	Summit Ave.	6	Cast Iron	274	134	2.57 out of 5	\$442	121,083

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	2480	P-1223	WW	Summit Ave.	6	Cast Iron	243	134	2.57 out of 5	\$442	107,200
Distribution Main	3477	P-977	WW	Summit Ave.	6	Cast Iron	258	134	2.57 out of 5	\$442	114,135
Distribution Main	3528	P-1223	WW	Summit Ave.	6	Cast Iron	62	134	2.57 out of 5	\$442	27,363
Distribution Main	3529	P-1223	WW	Summit Ave.	6	Cast Iron	199	134	2.57 out of 5	\$442	87,968
Distribution Main	3704	P-975	WW	Summit Ave.	6	Cast Iron	584	134	2.57 out of 5	\$442	258,118
Distribution Main	9671	P-977	WW	Summit Ave.	6	Cast Iron	18	134	2.57 out of 5	\$442	7,928
Distribution Main	8949	P-210	WW	Suncrest Dr	8	Ductile Iron	36	9	0 out of 5	N/A	\$0
Distribution Main	8957		WW	Suncrest Dr	6	Ductile Iron	3	9	0.71 out of 5	N/A	\$0
Distribution Main	8958	P-210	WW	Suncrest Dr.	6	Asbestos Cement	244	69	2 out of 5	\$442	107,632
Distribution Main	378	P-813	WW	Sunrise Ave.	6	Asbestos Cement	206	54	1.85 out of 5	\$442	91,112
Distribution Main	379	P-813	WW	Sunrise Ave.	6	Asbestos Cement	125	54	1.85 out of 5	\$442	55,471
Distribution Main	384	P-1513	WW	Sunrise Ave.	8	Ductile Iron	60	UNK	0 out of 5	N/A	\$0
Distribution Main	385	P-1513	WW	Sunrise Ave.	8	Ductile Iron	202	UNK	0 out of 5	N/A	\$0
Distribution Main	1798	P-7914	WW	Sunrise Ave.	6	Asbestos Cement	11	66	2 out of 5	\$442	4,798
Distribution Main	3471	P-824	WW	Sunrise Ave.	4	Cast Iron	499	134	3.29 out of 5	\$442	220,717
Distribution Main	3479	P-1516	WW	Sunrise Ave.	6	Asbestos Cement	201	54	1.85 out of 5	\$442	88,850
Distribution Main	3721	P-813	WW	Sunrise Ave.	6	Asbestos Cement	454	54	1.85 out of 5	\$442	200,512
Distribution Main	3741		WW	Sunrise Ave.	4	Cast Iron	26	134	3.29 out of 5	\$442	11,603
Distribution Main	11056	P-1513	WW	Sunrise Ave.	8	Ductile Iron	30	UNK	0 out of 5	N/A	\$0
Distribution Main	331	P-820	WW	Sunset Ave.	6	Cast Iron	189	134	2.57 out of 5	\$442	83,457
Distribution Main	332	P-820	WW	Sunset Ave.	6	Cast Iron	226	134	2.57 out of 5	\$442	100,032
Distribution Main	959	P-821	WW	Sunset Ave.	6	Cast Iron	332	134	2.57 out of 5	\$442	146,790
Distribution Main	960	P-821	WW	Sunset Ave.	6	Cast Iron	218	134	2.57 out of 5	\$442	96,300
Distribution Main	8835	P-821	WW	Sunset Ave.	6	Cast Iron	37	134	2.57 out of 5	\$442	16,570
Distribution Main	9433	P-1607	WW	Sunset Ave.	6	Cast Iron	101	134	2.57 out of 5	\$442	44,451
Distribution Main	5174	P-1409	WW	Surrey La	8	Asbestos Cement	208	44	1.14 out of 5	\$442	92,156
Distribution Main	5178	P-1410	WW	Surrey La	8	Asbestos Cement	217	44	1.14 out of 5	\$442	95,724
Distribution Main	5179	P-1410	WW	Surrey La	8	Asbestos Cement	44	44	1.14 out of 5	\$442	19,590
Distribution Main	5180		WW	Surrey La	8	Asbestos Cement	65	44	1.14 out of 5	\$442	28,664
Distribution Main	5181		WW	Surrey La	8	Asbestos Cement	13	44	1.14 out of 5	\$442	5,682
Distribution Main	10265	P-1409	WW	Surrey La	8	Asbestos Cement	15	44	1.14 out of 5	\$442	6,714
Distribution Main	5182	P-122	WW	Surrey Ln.	8	Asbestos Cement	911	44	1.14 out of 5	\$442	402,556
Distribution Main	5183	P-122	WW	Surrey Ln.	8	Asbestos Cement	640	44	1.14 out of 5	\$442	282,683
Distribution Main	10264		WW	Surrey Ln.	8	Ductile Iron	33	22	0.14 out of 5	N/A	\$0
Distribution Main	1827	P-497	WW	Sycamore Dr.	8	Asbestos Cement	873	51	1.14 out of 5	\$442	385,884
Distribution Main	1828	P-495	WW	Sycamore Dr.	8	Asbestos Cement	848	51	1.14 out of 5	\$442	374,844
Distribution Main	1829	P-495	WW	Sycamore Dr.	8	Asbestos Cement	157	54	1.14 out of 5	\$442	69,568
Transmission Main	1082	P-72	WW	Szydlo Dr.	12	Ductile Iron	591	19	0 out of 5	N/A	\$0
Distribution Main	10610	P-411	WW	Tampa St	8	Ductile Iron	269	2	0 out of 5	N/A	\$0
Distribution Main	10611	P-411	WW	Tampa St	8	Ductile Iron	343	2	0 out of 5	N/A	\$0
Distribution Main	10612		WW	Tampa St	8	Ductile Iron	330	2	0 out of 5	N/A	\$0
Distribution Main	11686	P-414	WW	Tampa St	8	Ductile Iron	208	2	0 out of 5	N/A	\$0
Distribution Main	11687	P-407	WW	Tampa St	8	Ductile Iron	193	2	0 out of 5	N/A	\$0
Distribution Main	11688	P-409	WW	Tampa St	8	Ductile Iron	210	2	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11689	P-411	WW	Tampa St	8	Ductile Iron	5	2	0 out of 5	N/A	\$0
Distribution Main	11690		WW	Tampa St	8	Ductile Iron	19	2	0 out of 5	N/A	\$0
Distribution Main	5138	P-424	WW	Tampa St.	6	Asbestos Cement	170	58	1.85 out of 5	\$442	74,975
Distribution Main	5139	P-424	WW	Tampa St.	6	Asbestos Cement	237	58	1.85 out of 5	\$442	104,944
Distribution Main	5140	P-425	WW	Tampa St.	6	Asbestos Cement	295	58	1.85 out of 5	\$442	130,515
Distribution Main	151	P-317	WW	Tanglewood Dr.	8	Asbestos Cement	700	41	1.14 out of 5	\$442	309,439
Distribution Main	1734	P-307	WW	Tanglewood Dr.	8	Asbestos Cement	56	41	1.14 out of 5	\$442	24,744
Distribution Main	1735	P-327	WW	Tanglewood Dr.	8	Asbestos Cement	310	41	1.14 out of 5	\$442	137,105
Distribution Main	1736	P-327	WW	Tanglewood Dr.	8	Asbestos Cement	42	41	1.14 out of 5	\$442	18,488
Distribution Main	4015	P-306	WW	Tanglewood Dr.	8	Asbestos Cement	26	41	1.14 out of 5	\$442	11,430
Distribution Main	5187	P-306	WW	Tanglewood Dr.	8	Asbestos Cement	363	41	1.14 out of 5	\$442	160,392
Distribution Main	5192	P-307	WW	Tanglewood Dr.	8	Asbestos Cement	354	41	1.14 out of 5	\$442	156,433
Distribution Main	5193	P-307	WW	Tanglewood Dr.	8	Asbestos Cement	14	41	1.14 out of 5	\$442	6,083
Distribution Main	5196	P-316	WW	Tanglewood Dr.	8	Asbestos Cement	55	41	1.14 out of 5	\$442	24,466
Distribution Main	5197	P-316	WW	Tanglewood Dr.	8	Asbestos Cement	436	41	1.14 out of 5	\$442	192,887
Distribution Main	5200	P-306	WW	Tanglewood Dr.	8	Asbestos Cement	352	41	1.14 out of 5	\$442	155,632
Distribution Main	5201	P-306	WW	Tanglewood Dr.	8	Asbestos Cement	107	41	1.14 out of 5	\$442	47,265
Distribution Main	9718	P-10022	WW	Teddy Ct	8	Ductile Iron	24	9	0 out of 5	N/A	\$0
Distribution Main	9719	P-10022	WW	Teddy Ct	8	Ductile Iron	237	9	0 out of 5	N/A	\$0
Distribution Main	9678	P-1244	WW	Terrace Ave	8	Ductile Iron	33	10	0 out of 5	N/A	\$0
Distribution Main	3378	P-1880	WW	Terrance Court	2	Unknown	288	77	1.86 out of 5	\$442	127,250
Distribution Main	12077	P-1880	WW	Terrance Court	2	Unknown	1	77	1.86 out of 5	\$442	601
Distribution Main	4721	P-115	WW	Terre Mar Dr.	8	Asbestos Cement	467	44	1.14 out of 5	\$442	206,242
Distribution Main	10793	P-348	WW	Third St	8	Ductile Iron	254	0	0 out of 5	N/A	\$0
Distribution Main	10794	P-348	WW	Third St	8	Ductile Iron	72	0	0 out of 5	N/A	\$0
Distribution Main	1570	P-525	WW	Tiffany Ave.	6	Asbestos Cement	151	51	1.85 out of 5	\$442	66,959
Distribution Main	5129	P-524	WW	Tiffany Ave.	6	Asbestos Cement	92	51	1.85 out of 5	\$442	40,729
Distribution Main	5130	P-524	WW	Tiffany Ave.	6	Asbestos Cement	34	51	1.85 out of 5	\$442	14,927
Distribution Main	921	P-1100	WW	Tilton St.	6	Asbestos Cement	484	48	1.85 out of 5	\$442	213,735
Distribution Main	2330	P-1416	WW	Timber Walk	8	Ductile Iron	58	17	0 out of 5	N/A	\$0
Distribution Main	2331	P-1416	WW	Timber Walk	8	Ductile Iron	485	17	0 out of 5	N/A	\$0
Distribution Main	8516	P-188	WW	Timber Walk	6	Ductile Iron	23	21	0.85 out of 5	N/A	\$0
Distribution Main	9899	P-1900	WW	Tobin St	6	Ductile Iron	30	11	0.71 out of 5	N/A	\$0
Distribution Main	9900	P-1899	WW	Tobin St	8	Ductile Iron	158	11	0 out of 5	N/A	\$0
Distribution Main	9901	P-1898	WW	Tobin St	6	Ductile Iron	17	11	0.71 out of 5	N/A	\$0
Distribution Main	206	P-786	WW	Tobin St.	6	Cast Iron	263	74	2.28 out of 5	\$442	116,212
Distribution Main	9902	P-786	WW	Tobin St.	6	Cast Iron	140	74	2.28 out of 5	\$442	61,964
Distribution Main	150	P-315	WW	Tower Rd.	8	Asbestos Cement	361	43	1.14 out of 5	\$442	159,682
Distribution Main	2499	P-311	WW	Tower Rd.	8	Asbestos Cement	277	43	1.14 out of 5	\$442	122,486
Distribution Main	2500	P-311	WW	Tower Rd.	8	Asbestos Cement	640	43	1.14 out of 5	\$442	282,838
Distribution Main	5189	P-309	WW	Tower Rd.	8	Asbestos Cement	321	43	1.14 out of 5	\$442	141,867
Distribution Main	5265	P-313	WW	Tower Rd.	8	Asbestos Cement	58	43	1.14 out of 5	\$442	25,733
Distribution Main	5266	P-313	WW	Tower Rd.	8	Asbestos Cement	599	43	1.14 out of 5	\$442	264,586
Distribution Main	12049	P-313	WW	Tower Rd.	8	Asbestos Cement	7	43	1.14 out of 5	\$442	3,080

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10042	P-259	WW	Tripoli St	8	Ductile Iron	183	6	0 out of 5	N/A	\$0
Distribution Main	10834	P-1768	WW	Tripoli St	8	Ductile Iron	97	6	0 out of 5	N/A	\$0
Distribution Main	10835	P-1768	WW	Tripoli St	8	Ductile Iron	58	6	0 out of 5	N/A	\$0
Distribution Main	2846	P-1905	WW	Tuckerman Street	2	Unknown	124	75	1.86 out of 5	\$442	54,880
Distribution Main	3568	P-105	WW	Turner Dr.	8	Asbestos Cement	121	44	1.14 out of 5	\$442	53,410
Distribution Main	3569	P-106	WW	Turner Dr.	8	Asbestos Cement	215	44	1.14 out of 5	\$442	95,072
Distribution Main	4129	P-103	WW	Turner Dr.	8	Asbestos Cement	775	44	1.14 out of 5	\$442	342,331
Distribution Main	4130	P-103	WW	Turner Dr.	8	Asbestos Cement	42	44	1.14 out of 5	\$442	18,420
Distribution Main	4132	P-105	WW	Turner Dr.	8	Asbestos Cement	130	44	1.14 out of 5	\$442	57,243
Distribution Main	9458	P-1914	WW	Urquhart St		Unknown	46	UNK	0 out of 5	N/A	\$0
Distribution Main	9459	P-1914	WW	Urquhart St		Unknown	314	UNK	0 out of 5	N/A	\$0
Distribution Main	9460	P-1913	WW	Urquhart St		Unknown	317	UNK	0 out of 5	N/A	\$0
Distribution Main	9461	P-1913	WW	Urquhart St		Unknown	21	UNK	0 out of 5	N/A	\$0
Distribution Main	2853	P-755	WW	Valley View Dr.	1	Copper	206	69	2.43 out of 5	\$442	91,093
Distribution Main	8541	P-934	WW	Ventura St	8	Ductile Iron	13	13	0 out of 5	N/A	\$0
Distribution Main	8570	P-934	WW	Ventura St	6	Ductile Iron	7	13	0.71 out of 5	N/A	\$0
Distribution Main	3486	P-1848	WW	Ventura St.	6	Cast Iron	356	134	2.57 out of 5	\$442	157,475
Distribution Main	8667	P-1781	WW	Victoria Way	8	Ductile Iron	19	15	0 out of 5	N/A	\$0
Distribution Main	8668	P-1781	WW	Victoria Way	8	Ductile Iron	107	15	0 out of 5	N/A	\$0
Distribution Main	4166	P-91	WW	Victory Ave.	6	Asbestos Cement	302	78	2 out of 5	\$442	133,332
Distribution Main	8434	P-890	WW	Vincenzo Dr	8	Ductile Iron	36	10	0 out of 5	N/A	\$0
Distribution Main	8505	P-890	WW	Vincenzo Dr	6	Ductile Iron	14	10	0.71 out of 5	N/A	\$0
Distribution Main	1005	P-889	WW	Vincenzo Dr.	6	PVC	289	38	1.14 out of 5	\$442	127,564
Distribution Main	1412	P-1791	WW	Vincenzo Dr.	6	Asbestos Cement	517	55	1.85 out of 5	\$442	228,636
Distribution Main	2950	P-1359	WW	Vine St.	4	Cast Iron	4	133	3.29 out of 5	\$442	1,829
Distribution Main	2951	P-1359	WW	Vine St.	4	Cast Iron	480	133	3.29 out of 5	\$442	212,075
Distribution Main	1969		WW	Virginia Ave.	6	Asbestos Cement	7	52	1.85 out of 5	\$442	3,238
Distribution Main	3791	P-762	WW	Virginia Ave.	6	Asbestos Cement	233	52	1.85 out of 5	\$442	103,095
Distribution Main	8640	P-1783	WW	W.W. Elementary School	8	Ductile Iron	161	17	0 out of 5	N/A	\$0
Transmission Main	8641		WW	W.W. Elementary School	12	Ductile Iron	2	17	0 out of 5	N/A	\$0
Transmission Main	8642	P-133Y	WW	W.W. Elementary School	12	Ductile Iron	403	17	0 out of 5	N/A	\$0
Transmission Main	8643	P-1328	WW	W.W. Elementary School	12	Ductile Iron	42	17	0 out of 5	N/A	\$0
Transmission Main	8644	P-1329	WW	W.W. Elementary School	12	Ductile Iron	236	17	0 out of 5	N/A	\$0
Transmission Main	8645	P-1329	WW	W.W. Elementary School	12	Ductile Iron	105	17	0 out of 5	N/A	\$0
Distribution Main	9053		WW	W.W. Elementary School	6	Ductile Iron	3	17	0.71 out of 5	N/A	\$0
Distribution Main	9054		WW	W.W. Elementary School	4	Ductile Iron	2	17	1.42 out of 5	N/A	\$0
Transmission Main	11487	P-1329	WW	W.W. Elementary School	12	Ductile Iron	9	17	0 out of 5	N/A	\$0
Transmission Main	11488	P-1329	WW	W.W. Elementary School	12	Ductile Iron	2	17	0 out of 5	N/A	\$0
Transmission Main	12096	P-1329	WW	W.W. Elementary School	12	Ductile Iron	75	17	0 out of 5	N/A	\$0
Transmission Main	8539	P-1847	WW	Wakefield St	20	Ductile Iron	296	13	0 out of 5	N/A	\$0
Transmission Main	8540	P-1847	WW	Wakefield St	20	Ductile Iron	136	13	0 out of 5	N/A	\$0
Transmission Main	10049	P-1751	WW	Wakefield St	16	Ductile Iron	214	6	0 out of 5	N/A	\$0
Transmission Main	10315		WW	Wakefield St	16	Ductile Iron	6	5	0 out of 5	N/A	\$0
Transmission Main	10316		WW	Wakefield St	16	Ductile Iron	4	5	0 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	10317	P-233	WW	Wakefield St	8	Ductile Iron	6	5	0 out of 5	N/A	\$0
Transmission Main	10693		WW	Wakefield St	42	Asbestos Cement	1,061	UNK	0.85 out of 5	\$442	469,096
Transmission Main	10702		WW	Wakefield St	16	Ductile Iron	2,022	1	0 out of 5	N/A	\$0
Transmission Main	10713	P-874	WW	Wakefield St	12	Ductile Iron	7	1	0 out of 5	N/A	\$0
Transmission Main	11636	P-1752	WW	Wakefield St	16	Ductile Iron	47	6	0 out of 5	N/A	\$0
Transmission Main	503	P-1330	WW	Wakefield St.	12	Asbestos Cement	227	39	1 out of 5	\$442	100,379
Transmission Main	1197	P-909	WW	Wakefield St.	12	Ductile Iron	430	22	0.14 out of 5	N/A	\$0
Transmission Main	1198	P-909	WW	Wakefield St.	12	Ductile Iron	10	22	0.14 out of 5	N/A	\$0
Transmission Main	1199	P-908	WW	Wakefield St.	12	Ductile Iron	437	22	0.14 out of 5	N/A	\$0
Transmission Main	1200	P-908	WW	Wakefield St.	12	Ductile Iron	487	22	0.14 out of 5	N/A	\$0
Transmission Main	1202	P-1333	WW	Wakefield St.	12	Ductile Iron	292	22	0.14 out of 5	N/A	\$0
Transmission Main	1518	P-929	WW	Wakefield St.	12	Ductile Iron	14	22	0.14 out of 5	N/A	\$0
Transmission Main	1543	P-854	WW	Wakefield St.	12	Ductile Iron	7	22	0.14 out of 5	N/A	\$0
Transmission Main	1544	P-852	WW	Wakefield St.	12	Ductile Iron	142	22	0.14 out of 5	N/A	\$0
Transmission Main	1545	P-852	WW	Wakefield St.	12	Ductile Iron	211	22	0.14 out of 5	N/A	\$0
Transmission Main	1546	P-887	WW	Wakefield St.	12	Ductile Iron	75	22	0.14 out of 5	N/A	\$0
Transmission Main	1547	P-851	WW	Wakefield St.	12	Ductile Iron	179	22	0.14 out of 5	N/A	\$0
Transmission Main	1548	P-850	WW	Wakefield St.	12	Ductile Iron	335	22	0.14 out of 5	N/A	\$0
Transmission Main	1549	P-850	WW	Wakefield St.	12	Ductile Iron	33	22	0.14 out of 5	N/A	\$0
Transmission Main	1782	P-855	WW	Wakefield St.	12	Ductile Iron	570	22	0.14 out of 5	N/A	\$0
Transmission Main	1783	P-855	WW	Wakefield St.	12	Ductile Iron	140	22	0.14 out of 5	N/A	\$0
Transmission Main	1784	P-907	WW	Wakefield St.	12	Ductile Iron	236	22	0.14 out of 5	N/A	\$0
Transmission Main	1998	P-1330	WW	Wakefield St.	12	Asbestos Cement	7	39	1 out of 5	\$442	2,964
Transmission Main	2094	P-1305	WW	Wakefield St.	12	Asbestos Cement	58	39	1 out of 5	\$442	25,513
Transmission Main	2097	P-10049	WW	Wakefield St.	12	Asbestos Cement	844	39	1 out of 5	\$442	373,115
Transmission Main	2102	P-855	WW	Wakefield St.	12	Asbestos Cement	690	39	1 out of 5	\$442	304,998
Transmission Main	2103	P-855	WW	Wakefield St.	12	Asbestos Cement	857	39	1 out of 5	\$442	378,651
Transmission Main	2959	P-920	WW	Wakefield St.	12	Ductile Iron	57	22	0.14 out of 5	N/A	\$0
Transmission Main	2960	P-920	WW	Wakefield St.	12	Ductile Iron	88	22	0.14 out of 5	N/A	\$0
Transmission Main	3498	P-854	WW	Wakefield St.	12	Ductile Iron	135	22	0.14 out of 5	N/A	\$0
Distribution Main	5631	P-233	WW	Wakefield St	8	Ductile Iron	450	22	0.14 out of 5	N/A	\$0
Distribution Main	5632	P-237	WW	Wakefield St.	8	Ductile Iron	15	22	0.14 out of 5	N/A	\$0
Distribution Main	5633	P-237	WW	Wakefield St.	8	Ductile Iron	399	22	0.14 out of 5	N/A	\$0
Distribution Main	5645	P-233	WW	Wakefield St.	8	Ductile Iron	93	22	0.14 out of 5	N/A	\$0
Distribution Main	7134	P-237	WW	Wakefield St.	8	Ductile Iron	190	22	0.14 out of 5	N/A	\$0
Distribution Main	7135	P-237	WW	Wakefield St.	8	Ductile Iron	92	22	0.14 out of 5	N/A	\$0
Distribution Main	7495	P-236	WW	Wakefield St.	8	Ductile Iron	222	22	0.14 out of 5	N/A	\$0
Distribution Main	8123		WW	Wakefield St.	8	Ductile Iron	3	22	0.14 out of 5	N/A	\$0
Transmission Main	8511	P-850	WW	Wakefield St.	16	Ductile Iron	4	22	0.14 out of 5	N/A	\$0
Transmission Main	8536	P-929	WW	Wakefield St.	12	Ductile Iron	116	22	0.14 out of 5	N/A	\$0
Transmission Main	8537	P-935	WW	Wakefield St.	12	Ductile Iron	298	22	0.14 out of 5	N/A	\$0
Transmission Main	8538	P-935	WW	Wakefield St.	12	Ductile Iron	141	22	0.14 out of 5	N/A	\$0
Transmission Main	9132	P-874	WW	Wakefield St.	12	PVC	158	30	0.43 out of 5	\$442	70,019
Transmission Main	9422	P-850	WW	Wakefield St.	12	Ductile Iron	2	22	0.14 out of 5	N/A	\$0

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	11133	P-850	WW	Wakefield St.	12	Ductile Iron	18	22	0.14 out of 5	N/A	\$0
Distribution Main	11310	P-233	WW	Wakefield St.	8	Ductile Iron	31	22	0.14 out of 5	N/A	\$0
Transmission Main	11472	P-850	WW	Wakefield St.	16	Ductile Iron	2	10	0 out of 5	N/A	\$0
Transmission Main	11477	P-935	WW	Wakefield St.	12	Ductile Iron	96	22	0.14 out of 5	N/A	\$0
Transmission Main	11478	P-935	WW	Wakefield St.	12	Ductile Iron	14	22	0.14 out of 5	N/A	\$0
Transmission Main	12026	P-907	WW	Wakefield St.	12	Ductile Iron	20	22	0.14 out of 5	N/A	\$0
Transmission Main	12027	P-855	WW	Wakefield St.	12	Ductile Iron	179	22	0.14 out of 5	N/A	\$0
Transmission Main	254	P-1267	WW	Wakefield St. Tank	12	Ductile Iron	11	29	0.14 out of 5	\$442	4,852
Transmission Main	255	P-1267	WW	Wakefield St. Tank	12	Ductile Iron	106	29	0.14 out of 5	\$442	46,952
Transmission Main	8054	P-1267	WW	Wakefield St. Tank	12	Ductile Iron	9	29	0.14 out of 5	\$442	3,847
Distribution Main	9530	P-1891	WW	Walker St	0.75	Copper	19	18	1.99 out of 5	N/A	\$0
Distribution Main	9531	P-1893	WW	Walker St	2	Copper	38	18	1.99 out of 5	N/A	\$0
Distribution Main	10379	P-1891	WW	Walker St	0.75	Copper	16	18	1.99 out of 5	N/A	\$0
Distribution Main	319	P-1897	WW	Walker St.	4	Cast Iron	29	18	2.56 out of 5	N/A	\$0
Distribution Main	3326	P-1402	WW	Walker St.	8	Ductile Iron	434	18	0 out of 5	N/A	\$0
Distribution Main	3327	P-1040	WW	Walker St.	8	Ductile Iron	350	18	0 out of 5	N/A	\$0
Distribution Main	3357	P-1890	WW	Walker St.	8	Ductile Iron	4	18	0 out of 5	N/A	\$0
Distribution Main	9532	P-1897	WW	Walker St.	8	Ductile Iron	24	18	0 out of 5	N/A	\$0
Distribution Main	9537	P-1890	WW	Walker St.	8	Ductile Iron	46	18	0 out of 5	N/A	\$0
Distribution Main	11583	P-1897	WW	Walker St.	8	Ductile Iron	12	18	0 out of 5	N/A	\$0
Distribution Main	609	P-683	WW	Walnut St.	6	Asbestos Cement	401	47	1.85 out of 5	\$442	177,255
Distribution Main	4285	P-683	WW	Walnut St.	1	Unknown	22	47	1.71 out of 5	\$442	9,612
Distribution Main	123	P-729	WW	Washington St.	8	Cast Iron	89	134	1.86 out of 5	\$442	39,363
Distribution Main	124	P-729	WW	Washington St.	8	Cast Iron	105	134	1.86 out of 5	\$442	46,515
Transmission Main	867	P-689	WW	Washington St.	12	Cast Iron	359	134	1.86 out of 5	\$442	158,458
Transmission Main	2967	P-687	WW	Washington St.	12	Cast Iron	44	134	1.86 out of 5	\$442	19,240
Distribution Main	3675	P-1681	WW	Washington St.	8	Cast Iron	14	134	1.86 out of 5	\$442	6,399
Distribution Main	3676	P-1681	WW	Washington St.	8	Cast Iron	289	134	1.86 out of 5	\$442	127,941
Distribution Main	3764	P-1974	WW	Washington St.	8	Cast Iron	111	88	1.72 out of 5	\$442	48,997
Distribution Main	3770	P-724	WW	Washington St.	8	Cast Iron	470	134	1.86 out of 5	\$442	207,737
Distribution Main	3771	P-668	WW	Washington St.	8	Cast Iron	38	134	1.86 out of 5	\$442	16,658
Transmission Main	3779	P-687	WW	Washington St.	12	Cast Iron	74	134	1.86 out of 5	\$442	32,514
Transmission Main	3780	P-687	WW	Washington St.	12	Cast Iron	211	134	1.86 out of 5	\$442	93,415
Distribution Main	3945	P-669	WW	Washington St.	8	Cast Iron	83	88	1.72 out of 5	\$442	36,835
Distribution Main	3946	P-669	WW	Washington St.	8	Cast Iron	116	88	1.72 out of 5	\$442	51,323
Distribution Main	3947	P-671	WW	Washington St.	8	Cast Iron	157	88	1.72 out of 5	\$442	69,177
Distribution Main	3948	P-671	WW	Washington St.	8	Cast Iron	150	88	1.72 out of 5	\$442	66,287
Transmission Main	3949	P-680	WW	Washington St.	12	Cast Iron	80	134	1.86 out of 5	\$442	35,557
Transmission Main	3950	P-682	WW	Washington St.	12	Cast Iron	266	133	1.86 out of 5	\$442	117,719
Transmission Main	3951	P-682	WW	Washington St.	12	Cast Iron	66	133	1.86 out of 5	\$442	29,122
Transmission Main	3952	P-684	WW	Washington St.	12	Cast Iron	177	133	1.86 out of 5	\$442	78,343
Transmission Main	3953	P-1381	WW	Washington St.	12	Cast Iron	57	133	1.86 out of 5	\$442	25,336
Transmission Main	3954	P-1381	WW	Washington St.	12	Cast Iron	116	133	1.86 out of 5	\$442	51,207
Transmission Main	3955	P-686	WW	Washington St.	12	Cast Iron	249	133	1.86 out of 5	\$442	110,026

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	3956	P-686	WW	Washington St.	12	Cast Iron	727	133	1.86 out of 5	\$442	321,191
Distribution Main	10000	P-1974	WW	Washington St.	8	Cast Iron	15	88	1.72 out of 5	\$442	6,643
Distribution Main	10117	P-729	WW	Washington St.	6	Ductile Iron	10	UNK	0.71 out of 5	\$442	4,530
Distribution Main	11093	P-1681	WW	Washington St.	8	Cast Iron	14	134	1.86 out of 5	\$442	6,255
Distribution Main	11224	P-1681	WW	Washington St.	8	Cast Iron	22	134	1.86 out of 5	\$442	9,833
Distribution Main	11228	P-724	WW	Washington St.	8	Cast Iron	29	134	1.86 out of 5	\$442	12,610
Distribution Main	11229	P-668	WW	Washington St.	8	Cast Iron	22	88	1.72 out of 5	\$442	9,935
Distribution Main	10001	P-729	WW	Washington Street	6	Ductile Iron	6	12	0.71 out of 5	N/A	\$0
Distribution Main	10300	P-268	WW	Water St	8	Ductile Iron	12	5	0 out of 5	N/A	\$0
Distribution Main	10302	P-268	WW	Water St	8	Ductile Iron	502	5	0 out of 5	N/A	\$0
Distribution Main	10303	P-268	WW	Water St	8	Ductile Iron	178	5	0 out of 5	N/A	\$0
Distribution Main	10416	P-267	WW	Water St	8	Ductile Iron	172	5	0 out of 5	N/A	\$0
Distribution Main	4122	P-183	WW	Watervalley Rd.	8	PVC	430	35	0.43 out of 5	\$442	190,011
Distribution Main	4123	P-183	WW	Watervalley Rd.	8	PVC	4	35	0.43 out of 5	\$442	1,618
Distribution Main	10294	P-184	WW	Watervalley Rd.	8	PVC	39	35	0.43 out of 5	\$442	17,453
Distribution Main	486	P-960	WW	Waverly St.	8	Asbestos Cement	417	54	1.14 out of 5	\$442	184,440
Distribution Main	1008	P-960	WW	Waverly St.	8	Asbestos Cement	115	54	1.14 out of 5	\$442	51,001
Distribution Main	9995	P-1053	WW	Weaver St	8	Ductile Iron	13	8	0 out of 5	N/A	\$0
Distribution Main	9996	P-1053	WW	Weaver St	8	Ductile Iron	49	8	0 out of 5	N/A	\$0
Distribution Main	2847	P-1060	WW	Weaver St.	6	Cast Iron	225	129	2.57 out of 5	\$442	99,546
Distribution Main	3132	P-1048	WW	Weaver St.	6	Cast Iron	251	129	2.57 out of 5	\$442	111,136
Distribution Main	3133	P-1061	WW	Weaver St.	4	Cast Iron	241	129	3.29 out of 5	\$442	106,350
Distribution Main	3205	P-1339	WW	Weaver St.	4	Cast Iron	161	129	3.29 out of 5	\$442	71,380
Distribution Main	3206	P-1339	WW	Weaver St.	4	Cast Iron	92	129	3.29 out of 5	\$442	40,739
Distribution Main	214	P-341	WW	Webster Knight Dr.	6	Asbestos Cement	521	48	1.85 out of 5	\$442	230,432
Distribution Main	215	P-341	WW	Webster Knight Dr.	6	Asbestos Cement	36	48	1.85 out of 5	\$442	15,950
Distribution Main	4339		WW	Webster Knight Dr.	6	Asbestos Cement	476	48	1.85 out of 5	\$442	210,229
Distribution Main	4340		WW	Webster Knight Dr.	6	Asbestos Cement	69	48	1.85 out of 5	\$442	30,535
Distribution Main	3107	P-1366	WW	Webster St.	4	Cast Iron	296	109	3.29 out of 5	\$442	130,751
Distribution Main	10648		WW	Wells St	8	Ductile Iron	112	2	0 out of 5	N/A	\$0
Distribution Main	10649	P-384	WW	Wells St	8	Ductile Iron	183	2	0 out of 5	N/A	\$0
Distribution Main	10650	P-376	WW	Wells St.	8	Ductile Iron	42	2	0 out of 5	N/A	\$0
Distribution Main	10651	P-375	WW	Wells St.	8	Ductile Iron	263	2	0 out of 5	N/A	\$0
Distribution Main	11699	P-376	WW	Wells St.	8	Ductile Iron	220	2	0 out of 5	N/A	\$0
Distribution Main	3117	P-1147	WW	Wendy Way	6	Asbestos Cement	899	48	1.85 out of 5	\$442	397,230
Distribution Main	4820	P-1147	WW	Wendy Way	6	Asbestos Cement	18	48	1.85 out of 5	\$442	7,900
Distribution Main	9985	P-1583	WW	West Glen Lane	8	Ductile Iron	618	6	0 out of 5	N/A	\$0
Distribution Main	9986	P-1583	WW	West Glen Lane	8	Ductile Iron	228	6	0 out of 5	N/A	\$0
Distribution Main	130	P-697	WW	West St.	6	Cast Iron	232	131	2.57 out of 5	\$442	102,569
Transmission Main	2856	P-769	WW	West St.	12	Asbestos Cement	7	75	1.29 out of 5	\$442	3,249
Transmission Main	2857	P-765	WW	West St.	12	Cast Iron	296	89	1.72 out of 5	\$442	130,645
Transmission Main	2858	P-761	WW	West St.	12	Cast Iron	71	89	1.72 out of 5	\$442	31,493
Transmission Main	2859	P-761	WW	West St.	12	Cast Iron	308	89	1.72 out of 5	\$442	136,345
Transmission Main	2860	P-759	WW	West St.	12	Cast Iron	168	89	1.72 out of 5	\$442	74,101

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Transmission Main	2861	P-1289	WW	West St.	12	Cast Iron	282	89	1.72 out of 5	\$442	124,796
Transmission Main	3209	P-769	WW	West St.	16	Asbestos Cement	335	75	1.29 out of 5	\$442	148,144
Distribution Main	3212	P-708	WW	West St.	2	Galvanized Iron	797	79	3.28 out of 5	\$442	352,183
Distribution Main	3261	P-703	WW	West St.	4	Cast Iron	297	130	3.29 out of 5	\$442	131,452
Distribution Main	3262	P-706	WW	West St.	6	Cast Iron	133	79	2.28 out of 5	\$442	58,576
Distribution Main	3762	P-697	WW	West St.	6	Cast Iron	3	131	2.57 out of 5	\$442	1,442
Distribution Main	3777	P-1952	WW	West St.	6	Cast Iron	471	131	2.57 out of 5	\$442	208,087
Distribution Main	3778	P-1952	WW	West St.	6	Cast Iron	168	131	2.57 out of 5	\$442	74,374
Distribution Main	8836	P-696	WW	West St.	6	Cast Iron	56	130	2.57 out of 5	\$442	24,563
Distribution Main	8837	P-705	WW	West St.	4	Cast Iron	269	130	3.29 out of 5	\$442	118,708
Distribution Main	8838	P-705	WW	West St.	4	Cast Iron	13	130	3.29 out of 5	\$442	5,657
Distribution Main	10687	P-708	WW	West St.	6	Cast Iron	151	79	2.28 out of 5	\$442	66,561
Distribution Main	10688	P-708	WW	West St.	1	Copper	18	1	1.99 out of 5	N/A	\$0
Transmission Main	11205	P-769	WW	West St.	16	Asbestos Cement	6	75	1.29 out of 5	\$442	2,559
Distribution Main	11518	P-705	WW	West St.	4	Cast Iron	4	130	3.29 out of 5	\$442	1,574
Distribution Main	11707	P-708	WW	West St.	6	Cast Iron	3	79	2.28 out of 5	\$442	1,349
Transmission Main	2390		WW	West St. Tank	12	Cast Iron	9	89	1.72 out of 5	\$442	3,954
Transmission Main	2485		WW	West St. Tank	12	Ductile Iron	11	17	0 out of 5	N/A	\$0
Transmission Main	2486		WW	West St. Tank	12	Cast Iron	14	89	1.72 out of 5	\$442	6,051
Transmission Main	2496		WW	West St. Tank	12	Cast Iron	5	89	1.72 out of 5	\$442	2,220
Transmission Main	3208		WW	West St. Tank	16	Ductile Iron	4	17	0 out of 5	N/A	\$0
Distribution Main	3210		WW	West St. Tank	8	Cast Iron	40	89	1.72 out of 5	\$442	17,476
Transmission Main	3211		WW	West St. Tank	12	Ductile Iron	2	17	0 out of 5	N/A	\$0
Transmission Main	3213	P-769	WW	West St. Tank	12	Ductile Iron	4	17	0 out of 5	N/A	\$0
Transmission Main	3604		WW	West St. Tank	12	Cast Iron	4	89	1.72 out of 5	\$442	1,781
Transmission Main	3671		WW	West St. Tank	12	Ductile Iron	10	17	0 out of 5	N/A	\$0
Distribution Main	9709	P-1846	WW	West Warwick	10	Ductile Iron	29	13	0 out of 5	N/A	\$0
Distribution Main	140	P-550	WW	West Warwick Ave.	6	Cast Iron	90	134	2.57 out of 5	\$442	39,592
Distribution Main	141	P-550	WW	West Warwick Ave.	6	Cast Iron	129	134	2.57 out of 5	\$442	56,929
Distribution Main	1720	P-1949	WW	West Warwick Ave.	6	Cast Iron	158	134	2.57 out of 5	\$442	69,989
Distribution Main	1728	P-690	WW	West Warwick Ave.	6	Cast Iron	257	129	2.57 out of 5	\$442	113,793
Distribution Main	2890	P-639	WW	West Warwick Ave.	6	Cast Iron	415	134	2.57 out of 5	\$442	183,503
Distribution Main	2891	P-639	WW	West Warwick Ave.	6	Cast Iron	9	134	2.57 out of 5	\$442	4,108
Distribution Main	2895	P-550	WW	West Warwick Ave.	6	Cast Iron	3	134	2.57 out of 5	\$442	1,520
Distribution Main	3990	P-1969	WW	West Warwick Ave.	6	Cast Iron	203	134	2.57 out of 5	\$442	89,587
Distribution Main	3991	P-569	WW	West Warwick Ave.	6	Cast Iron	163	134	2.57 out of 5	\$442	71,860
Distribution Main	3992	P-566	WW	West Warwick Ave.	6	Cast Iron	119	134	2.57 out of 5	\$442	52,566
Distribution Main	3993	P-565	WW	West Warwick Ave.	6	Cast Iron	180	134	2.57 out of 5	\$442	79,625
Distribution Main	3994	P-565	WW	West Warwick Ave.	6	Cast Iron	22	134	2.57 out of 5	\$442	9,783
Distribution Main	3995	P-560	WW	West Warwick Ave.	6	Cast Iron	244	134	2.57 out of 5	\$442	107,654
Distribution Main	3996	P-559	WW	West Warwick Ave.	6	Cast Iron	204	134	2.57 out of 5	\$442	90,355
Distribution Main	3997	P-552	WW	West Warwick Ave.	6	Cast Iron	97	134	2.57 out of 5	\$442	42,983
Distribution Main	4004	P-639	WW	West Warwick Ave.	6	Cast Iron	33	134	2.57 out of 5	\$442	14,619
Distribution Main	4005	P-639	WW	West Warwick Ave.	6	Cast Iron	145	134	2.57 out of 5	\$442	64,217

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4317	P-640	WW	West Warwick Ave.	6	Cast Iron	111	134	2.57 out of 5	\$442	49,012
Distribution Main	4320	P-639	WW	West Warwick Ave.	6	Cast Iron	12	134	2.57 out of 5	\$442	5,249
Transmission Main	8021	P-557	WW	West Warwick Ave.	12	Ductile Iron	5	14	0 out of 5	N/A	\$0
Distribution Main	8022	P-557	WW	West Warwick Ave.	6	Cast Iron	6	134	2.57 out of 5	\$442	2,563
Distribution Main	8023	P-557	WW	West Warwick Ave.	6	Cast Iron	20	134	2.57 out of 5	\$442	8,793
Distribution Main	8024	P-555	WW	West Warwick Ave.	6	Cast Iron	234	134	2.57 out of 5	\$442	103,570
Transmission Main	8025	P-557	WW	West Warwick Ave.	12	Ductile Iron	6	14	0 out of 5	N/A	\$0
Distribution Main	9371	P-557	WW	West Warwick Ave.	6	Ductile Iron	2	14	0.71 out of 5	N/A	\$0
Distribution Main	9372	P-557	WW	West Warwick Ave.	6	Ductile Iron	2	14	0.71 out of 5	N/A	\$0
Distribution Main	11238	P-560	WW	West Warwick Ave.	6	Cast Iron	28	134	2.57 out of 5	\$442	12,361
Distribution Main	8548	P-923	WW	Westly St	8	Ductile Iron	25	13	0 out of 5	N/A	\$0
Distribution Main	8574	P-923	WW	Westly St	6	Ductile Iron	2	13	0.71 out of 5	N/A	\$0
Transmission Main	8575	P-924	WW	Westly St	20	Ductile Iron	179	13	0 out of 5	N/A	\$0
Transmission Main	11482	P-924	WW	Westly St	20	Ductile Iron	3	13	0 out of 5	N/A	\$0
Distribution Main	1519	P-923	WW	Westly St.	6	Cast Iron	57	134	2.57 out of 5	\$442	24,983
Distribution Main	1520	P-923	WW	Westly St.	6	Cast Iron	269	134	2.57 out of 5	\$442	119,106
Distribution Main	3739	P-922	WW	Westly St.	6	Cast Iron	182	134	2.57 out of 5	\$442	80,660
Transmission Main	9328	P-1689	WW	Whisper Ct	12	Ductile Iron	448	10	0 out of 5	N/A	\$0
Transmission Main	9329	P-1689	WW	Whisper Ct	12	Ductile Iron	143	10	0 out of 5	N/A	\$0
Transmission Main	9330	P-1691	WW	Whisper Ct	12	Ductile Iron	139	10	0 out of 5	N/A	\$0
Transmission Main	9331	P-1692	WW	Whisper Ct	12	Ductile Iron	448	10	0 out of 5	N/A	\$0
Transmission Main	11576		WW	Whisper Ct	12	Ductile Iron	1	10	0 out of 5	N/A	\$0
Distribution Main	2440	P-3	WW	Whispering Pines Ct.	8	Ductile Iron	236	28	0.14 out of 5	\$442	104,135
Distribution Main	4661	P-175	WW	Whitebirch Ln.	8	Asbestos Cement	379	42	1.14 out of 5	\$442	167,387
Distribution Main	4662	P-175	WW	Whitebirch Ln.	8	Asbestos Cement	38	42	1.14 out of 5	\$442	16,745
Transmission Main	2277	P-1356	WW	Wightman St.	12	PVC	10	31	0.43 out of 5	\$442	4,512
Transmission Main	3512	P-1356	WW	Wightman St.	12	PVC	433	31	0.43 out of 5	\$442	191,519
Transmission Main	3513	P-1357	WW	Wightman St.	12	PVC	335	31	0.43 out of 5	\$442	147,962
Transmission Main	3514	P-1357	WW	Wightman St.	12	PVC	296	31	1.14 out of 5	\$442	130,907
Transmission Main	3515	P-835	WW	Wightman St.	12	PVC	363	31	1.14 out of 5	\$442	160,525
Distribution Main	8843	P-8033	WW	Willow St.	6	Cast Iron	342	124	2.57 out of 5	\$442	151,365
Distribution Main	8844	P-694	WW	Willow St.	6	Cast Iron	177	129	2.57 out of 5	\$442	78,253
Distribution Main	8845	P-694	WW	Willow St.	6	Cast Iron	36	129	2.57 out of 5	\$442	15,716
Distribution Main	8846	P-695	WW	Willow St.	6	Cast Iron	407	129	2.57 out of 5	\$442	180,032
Transmission Main	10045	P-1704	WW	Wilson St	12	Ductile Iron	384	6	0 out of 5	N/A	\$0
Transmission Main	10046	P-256	WW	Wilson St	12	Ductile Iron	237	6	0 out of 5	N/A	\$0
Transmission Main	10047	P-1767	WW	Wilson St	12	Ductile Iron	138	6	0 out of 5	N/A	\$0
Transmission Main	10048	P-1767	WW	Wilson St	12	Ductile Iron	809	6	0 out of 5	N/A	\$0
Transmission Main	11635	P-1704	WW	Wilson St	12	Ductile Iron	79	6	0 out of 5	N/A	\$0
Distribution Main	10410	P-603	WW	Windsor Park Dr	8	Ductile Iron	145	14	0 out of 5	N/A	\$0
Distribution Main	9732	P-603	WW	Windsor Park Dr.	8	Ductile Iron	11	14	0 out of 5	N/A	\$0
Distribution Main	3109	P-544	WW	Winthrop Ave.	2	Galvanized Iron	380	109	4.28 out of 5	\$442	168,031
Distribution Main	3969	P-544	WW	Winthrop Ave.	2	Galvanized Iron	37	109	3.57 out of 5	\$442	16,332
Distribution Main	4314	P-545	WW	Winthrop Ave.	4	Cast Iron	50	109	3.29 out of 5	\$442	22,153

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	4315	P-545	WW	Winthrop Ave.	4	Cast Iron	643	109	3.29 out of 5	\$442	284,221
Distribution Main	8839	P-707	WW	Wood St.	6	Asbestos Cement	252	69	2 out of 5	\$442	111,171
Transmission Main	8409	P-1679	WW	Woodbine St	12	Ductile Iron	17	10	0 out of 5	N/A	\$0
Transmission Main	8410	P-1679	WW	Woodbine St	12	Ductile Iron	79	10	0 out of 5	N/A	\$0
Transmission Main	8411	P-967	WW	Woodbine St	12	Ductile Iron	435	10	0 out of 5	N/A	\$0
Transmission Main	8481	P-1679	WW	Woodbine St	12	Ductile Iron	242	10	0 out of 5	N/A	\$0
Distribution Main	8935		WW	Woodland Dr	8	Ductile Iron	35	9	0 out of 5	N/A	\$0
Distribution Main	8938	P-180	WW	Woodland Dr	8	Ductile Iron	14	9	0 out of 5	N/A	\$0
Distribution Main	8946	P-180	WW	Woodland Dr	6	Ductile Iron	2	9	0.71 out of 5	N/A	\$0
Distribution Main	4524	P-180	WW	Woodland Dr.	6	Asbestos Cement	223	69	2 out of 5	\$442	98,638
Distribution Main	5299	P-189	WW	Woodland Dr.	6	Asbestos Cement	506	69	2 out of 5	\$442	223,857
Distribution Main	5300	P-189	WW	Woodland Dr.	6	Asbestos Cement	19	69	2 out of 5	\$442	8,530
Distribution Main	6549	P-189	WW	Woodland Dr.	6	Asbestos Cement	2	69	2 out of 5	\$442	833
Distribution Main	333	P-818	WW	Woodside Ave.	6	Cast Iron	180	134	2.57 out of 5	\$442	79,724
Distribution Main	334	P-818	WW	Woodside Ave.	6	Cast Iron	347	134	2.57 out of 5	\$442	153,544
Distribution Main	1508	P-803	WW	Woodside Ave.	6	Cast Iron	575	81	2.43 out of 5	\$442	254,334
Distribution Main	3386	P-815	WW	Woodside Ave.	6	Cast Iron	48	134	2.57 out of 5	\$442	21,079
Distribution Main	3387	P-815	WW	Woodside Ave.	6	Cast Iron	154	134	2.57 out of 5	\$442	68,036
Distribution Main	3388	P-814	WW	Woodside Ave.	6	Cast Iron	718	134	2.57 out of 5	\$442	317,285
Distribution Main	3389	P-814	WW	Woodside Ave.	6	Cast Iron	327	134	2.57 out of 5	\$442	144,644
Distribution Main	3699	P-808	WW	Woodside Ave.	6	Cast Iron	607	81	2.43 out of 5	\$442	268,120
Distribution Main	3700	P-808	WW	Woodside Ave.	6	Cast Iron	12	81	2.43 out of 5	\$442	5,301
Distribution Main	8739	P-805	WW	Woodside Ave.	6	Cast Iron	177	81	2.43 out of 5	\$442	78,068
Distribution Main	3864	P-1483	WW	Wyman St.	6	Cast Iron	240	134	2.57 out of 5	\$442	106,255
Distribution Main	4212	P-1483	WW	Wyman St.	6	Cast Iron	11	134	2.57 out of 5	\$442	4,748
Distribution Main	5090	P-1485	WW	Wyman St.	6	Ductile Iron	50	14	0.71 out of 5	N/A	\$0
Distribution Main	204	P-782	WW	Youngs Ave.	8	Ductile Iron	49	18	0 out of 5	N/A	\$0
Distribution Main	205	P-782	WW	Youngs Ave.	8	Ductile Iron	151	18	0 out of 5	N/A	\$0
Distribution Main	291	P-787	WW	Youngs Ave.	6	Cast Iron	514	134	2.57 out of 5	\$442	227,252
Distribution Main	292	P-787	WW	Youngs Ave.	6	Cast Iron	213	134	2.57 out of 5	\$442	94,159
Distribution Main	1565	P-780	WW	Youngs Ave.	6	Asbestos Cement	246	63	2 out of 5	\$442	108,696
Distribution Main	1602	P-1038	WW	Youngs Ave.	2	Galvanized Iron	14	134	3.57 out of 5	\$442	6,400
Distribution Main	1603	P-1038	WW	Youngs Ave.	2	Galvanized Iron	909	134	3.57 out of 5	\$442	401,711
Distribution Main	2940	P-8050	WW	Youngs Ave.	8	Asbestos Cement	289	63	1.29 out of 5	\$442	127,717
Distribution Main	2941	P-8050	WW	Youngs Ave.	8	Asbestos Cement	333	63	1.29 out of 5	\$442	146,988
Distribution Main	3464	P-797	WW	Youngs Ave.	8	Ductile Iron	304	18	0 out of 5	N/A	\$0
Distribution Main	3467	P-782	WW	Youngs Ave.	8	Ductile Iron	297	18	0 out of 5	N/A	\$0
Distribution Main	3751	P-787	WW	Youngs Ave.	6	Cast Iron	62	134	2.57 out of 5	\$442	27,510
Distribution Main	3752	P-787	WW	Youngs Ave.	6	Cast Iron	137	134	2.57 out of 5	\$442	60,679
Distribution Main	3753	P-785	WW	Youngs Ave.	6	Cast Iron	337	134	2.57 out of 5	\$442	149,116
Distribution Main	8746	P-785	WW	Youngs Ave.	6	Cast Iron	35	134	2.57 out of 5	\$442	15,602
Distribution Main	8748	P-780	WW	Youngs Ave.	8	Ductile Iron	12	18	0 out of 5	N/A	\$0
Distribution Main	8750		WW	Youngs Ave.	6	Asbestos Cement	12	63	2 out of 5	\$442	5,224
Distribution Main	8751	P-8050	WW	Youngs Ave.	8	Asbestos Cement	10	63	1.29 out of 5	\$442	4,570

Infrastructure Subtype	Pipe ID (NEW)	Pipe ID (OLD)	Town	Street Name	Pipe Diameter	Pipe Material	Length (Linear Feet)	Age (in years)	Condition Assessment (Need for Rehabilitation)	Replacement Cost Per LF (+ 15% for Engineering/Construction Services)	Replacement Cost
Distribution Main	11049	P-787	WW	Youngs Ave.	6	Cast Iron	18	134	2.57 out of 5	\$442	7,794
Distribution Main	12010	P-787	WW	Youngs Ave.	6	Cast Iron	348	134	2.57 out of 5	\$442	154,002
Distribution Main	12011	P-787	WW	Youngs Ave.	6	Cast Iron	277	134	2.57 out of 5	\$442	122,340

Total Infrastructure Rehabilitation and Replacement Costs Kent County Water Authority		
Infrastructure Type	5-year Costs	Total Costs Over 20 Years
Source	\$1,000,000	\$1,000,000
Treatment	\$1,500,000	\$1,500,000
Disinfection	\$0	\$0
Transmission_Distribution**	\$32,450,000	\$135,550,000
Storage	\$0	\$1,800,000
Other	\$50,000	\$150,000
TOTAL*	\$35,000,000	\$140,000,000

*Totals are based on proposed annual restricted replacement fund of \$7,000,000.

**Remaining cost to replace transmission and distribution infrastructure is estimated at \$744,838,860

Financial Component	Questions	Brief Description
Infrastructure Replacement Fund	Does the water system have an Infrastructure Replacement Fund?	Yes, the system is approved by the RIPUC to collect rates to finance an annual restricted replacement fund of \$7,000,000.
Planning for Replacements (Impact on Rate Structure)	Did the plan incorporate proposed rate structure impacts, a schedule of proposed rate changes, and schedule for fully funding the replacement projects based on the schedule included in the plan?	Determined by RIPUC